


MS. MEARS

10-30-85

✓

DATA SHEET FROM
MEN SOUTHEASTERN, INC.

1 Hank



Rick

SECTION I

MANUFACTURER'S NAME National Chemsearch; Div. of NCH Corporation		EMERGENCY TELEPHONE NUMBER 214-438-4144 Ext. 013
ADDRESS (NUMBER, STREET, CITY, STATE & ZIP CODE) 2730 Chemsearch Blvd.; Irving, Texas 75062		
CHEMICAL NAME & SYNONYMS	TRADE NAME & SYNONYMS ND-150	
CHEMICAL FAMILY	FORMULA	

SECTION II - HAZARDOUS INGREDIENTS

PAINTS, PRESERVATIVES & SOLVENTS	%	TLV (UNITS)	ALLOYS AND METALLIC COATINGS	%	TLV (UNITS)
PIGMENTS			BASE METAL		
CATALYST			ALLOYS		
VEHICLE			METALLIC COATINGS		
SOLVENTS			FILLER METAL PLUS COATING OR CORE FLUX		
ADDITIVES			OTHERS		
OTHERS					

HAZARDOUS MIXTURES OF OTHER LIQUIDS, SOLIDS OR GASES

	%	TLV (UNITS)
Sodium silicate	5-10	
2-butoxyethanol	1-7	(SKIN) 50 ppm

SECTION III - PHYSICAL DATA

BOILING POINT (°F)	210	SPECIFIC GRAVITY (H ₂ O=1)	1.050
VAPOR PRESSURE (mm Hg.)	17	PERCENT, VOLATILE BY VOLUME (%)	95
VAPOR DENSITY (AIR=1)	0.6	EVAPORATION RATE (Bu Ac = 1)	0.10
SOLUBILITY IN WATER	Soluble	pH: 12.2	
APPEARANCE AND ODOR	Flourescent liquid - odor 2-butoxvethanol		

SECTION IV - FIRE AND EXPLOSION HAZARD DATA

FLASH POINT (METHOD USED) None	FLAMMABLE LIMITS	LEL	UEL
EXTINGUISHING MEDIA N/A			
SPECIAL FIRE FIGHTING PROCEDURES			
UNUSUAL FIRE & EXPLOSION HAZARDS			

SECTION V - HEALTH HAZARD DATA

THRESHOLD LIMIT VALUE

EFFECTS OF OVEREXPOSURE

May cause skin or eye irritation.

EMERGENCY & FIRST AID PROCEDURES

EYES: Flush with water for 5-10 minutes. If irritation persists, see a physician.

INGESTION: Give copious amounts of water. See a physician.

SKIN: Wash with water and apply emollient.

SECTION VI - REACTIVITY DATA

CONDITIONS TO AVOID

STABILITY

☒ STABLE☐ UNSTABLE

COMPATIBILITY (MATERIALS TO AVOID)

Anodized aluminum, glass

HAZARDOUS DECOMPOSITION PRODUCTS

HAZARDOUS

POLYMERIZATION

☒ WILL NOT
OCCUR☐ MAY OCCUR

CONDITIONS TO AVOID

SECTION VII - SPILL OR LEAK PROCEDURES

STEPS TAKEN IN CASE MATERIAL IS RELEASED OR SPILLED

Mop up or flush down floor drain.

SITE DISPOSAL METHOD

May be disposed of in a sewer drain, after oil water separation.

SECTION VIII - SPECIAL PROTECTION INFORMATION

RESPIRATORY PROTECTION (SPECIFY TYPE)

VENTILATION

LOCAL EXHAUST

Usually adequate

MECHANICAL (GENERAL)

SPECIAL

OTHER

PROTECTIVE GLOVES

Rubber or polyethylene

OTHER PROTECTIVE EQUIPMENT

EYE PROTECTION

Goggles

SECTION IX - SPECIAL PRECAUTIONS

PRECAUTIONS TO BE TAKEN IN HANDLING & STORING

KEEP OUT OF REACH OF CHILDREN. Keep from freezing.

Keep out of eyes. Avoid repeated or prolonged skin contact.

OTHER PRECAUTIONS