

Nichols, Danielle

From: Casey Stephens [Casey.Stephens@bocc.citrus.fl.us]
Sent: Friday, January 15, 2010 1:00 PM
To: Nichols, Danielle
Cc: Carmen Bruno
Subject: Fwd: Material used in Oil area
Attachments: CCCL-OilTanks&Containment 027.jpg

Danielle,

I apologize for not getting this to you sooner. It slipped through the cracks. Attached is a photo showing the new coating and a new double lined used oil tanks. The old tanks in the background have been emptied and are waiting proper paperwork so that we can scrap them.

The system used is approved by FDEP it is a multi product application. It is listed on the FDEP web site as EQ512

Sealer

1 Coat: Corobond 100 Epoxy Primer/Sealer
4.0-6.0 mils wet 4.0-6.0 mils dry

Cracks and Joints:
Corobond Flexible Joint Sealant

Kem Cati-Coat:

1 coat: Kem Cati-Coat @ 14.0 - 28.0 mils wet, 10.0 - 20.0 mils D.F.T

Shelcote II Coat:

1st coat: Shelcote II @ 9.0 - 11.0 mils Wet, 5.0 - 6.0 mils D.F.T
2nd coat: Shelcote II @ 9.0 - 11.0 mils Wet, 5.0 - 6.0 mils D.F.T

If you have any questions please do not hesitate to contact me.

Casey



