## 520 2Å6

## RÉCEIPT FOR CERTIFIED MAIL

NO INSURANCE COVERAGE PROVIDED NOT FOR INTERNATIONAL MAIL

(See Reverse)			
234-55	Mr. Jim Oliveros		
⇔U.S.G.P.O. 1989-234-555	Street and No Mobro Marine, Inc.		
G.P.O.	P.O., State and ZIP Code		
⇔U.S	Postage	S	
	Certified Fee		
	Special Delivery Fee		
,	Restricted Delivery Fee		
PS Form 3800, June 1985	Return Receipt showing to whom and Date Delivered		
	Return Receipt showing to whom, Date, and Address of Delivery		
June	TOTAL Postage and Fees	S	
3800,	Postmark or Date		
orm.			
SF	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		

SEN	DER
-----	-----

- Complete items 1 and/or 2 for additional services. Complete items 3, and 4a & b. Print your name and address on the reverse of this form so that we can
- return this card to you.

  Attach this form to the front of the mailpiece, or on the back if space
- Write "Return Receipt Requested" on the mailpiece below the article number.
- The Return Receipt Fee will provide you the signature of the person delivered to and the date of delivery.
- 3. Article Addressed to: Mr. Jim Oliveros, P.G.

- Missimer & Associates, Inc.
- Suite 104 🐣

- 8130 Baymeadows Way West Jacksonville, FL
- 7. Date of Delivery
  - 28-Addressee's Address (Only if requested

and fee is paid)

4a. Article Number P 520 286 468

4b. Service Type

Express Mail

☐ Registered

Certified

fee):

Signature (Agent)

5. Signature (Addressee)

Navember 1990 ± U.S. GPO: 1991DOMESTIC RETURN RECEIPT

I also wish to receive the following services (for an extra

1. Addressee's Address

2. Restricted Delivery

Consult postmaster for fee.

☐ Insured


☐ Return Receipt for

Merchandise

□ COD



Official Business



Print your name, address and ZIP Code here

STATE OF FLORIDA

DEPARTMENT OF ENVIRONMENTAL REGULATION

NORTHEAST DISTRICT

7825 BAYMEADOWS WAY, SUITE B-200

JACKSONVILLE, FLORIDA 32256-7577



## Florida Department of Environmental Regulation

Northeast District • Suite B200, 7825 Baymeadows Way • Jacksonville, Florida 32256-7577

Lawton Chiles, Governor Carol M. Browner, Secretary

May 27, 1992

CERTIFIED - RETURN RECEIPT

Mr. Jim Oliveros, P.G. Missimer & Associates, Inc. Suite 104 8130 Baymeadows Way West Jacksonville, Florida 32256

Dear Mr. Oliveros:

Mobro Marine, Inc. FLD 081 946 105 OGC Consent Order #90-1662 Clay County - Hazardous Waste

The Department has reviewed the Preliminary Contamination Assessment Plan (PCAP) for the referenced facility and has the following comments:

- 1) A brief site history, including the length of time the areas being assessed were used and how they were used, should be included.
- 2) Documents certifying that the laboratory performing the sampling and analysis has a Department approved Comprehensive Quality Assurance Plan (ComPQAP).
- 3. Piezometers should be utilized to determine site specific groundwater flow directions and well locations for each area then be proposed to be downgradient of any potential release. Proposed well locations should take into affect the proximity of a tidally influenced water body.
- 4. Details of the construction and condition of the production wells on-site should be included in the Preliminary Contamination Assessment.
- The well locations proposed for Area 7 appear to assume a northwesterly groundwater flow direction. While this flow direction is a strong possibility, it needs to be confirmed or additional wells proposed further to the northeast of Area 7.

Recycled Pape

Mr. Jim Oliveros, P.G. Mobro Marine, Inc. May 27, 1992
Page Two

- 6) Based on the figure provided, two of the wells proposed appear to be in an upgradient position upgradient of the fuel tanks assuming groundwater flow direction is towards the St. Johns River. The majority of wells should be placed on the downgradient side of the potential release.
- 7) Groundwater samples should be collected from each of the monitoring wells and laboratory analysis for each sample collected be performed.
- 8) Soil and water samples should also be analyzed for total recoverable petroleum hydrocarbons (TRPH).

Responses to the above comments need to be included in the submittal of a revised PCAP within 14 days of receipt of this letter.

If you have any questions, please contact me at the letterhead address or telephone (904) 448-4320 ext. 359.

Sincerely,

Jane W. Mears

Environmental Specialist Hazardous Waste Section

M) Mim:ps