

STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL REGULATION



SOUTHWEST DISTRICT

7601 HIGHWAY 301 NORTH
TAMPA, FLORIDA 33610

813-985-7402
SunCom - 570-8000

BOB GRAHAM
GOVERNOR

VICTORIA J. TSCHINKEL
SECRETARY

DR. RICHARD D. GARRITY
DISTRICT MANAGER

June 16, 1986

Mr. Stanley Walczynski
Environmental Engineer
Safety-Kleen Corporation
777 Big Timber Road
Elgin, Illinois 60120

RECEIVED
JUN 20 1986
Hazardous Waste

Re: Safety-Kleen Corp. FLD 980 847 214
Operating and Construction Permit Application
HO29-118985 and HC29-118986
First Notice of Deficiencies


Dear Mr. Walczynski:

We have reviewed your application and found it incomplete due to the lack of some information, and because amendments are required in some parts of the application. The required information and amendments necessary to complete your application are itemized in attached sheets.

When a permit application is incomplete, all processing of the application is suspended. Pursuant to Section 120.60, Florida Statutes, the Department may deny a permit application if the applicant, after receiving timely notice, fails to correct errors, omissions, or supply additional information within a reasonable period of time.

We expect to receive your submittal addressing the information requested in this notice within thirty days from this date.

Sincerely,


Armando Gonzalez
Permitting Engineer
Hazardous Waste Section

AG/dsh
Enclosure

cc: Satish Kastury

Deficiencies -
Part I - General

A. General Information

- Is Mr. Gordon Burman the actual site owner? or the purported future buyer? If Mr. Burman is not the actual site owner, page two (2) of the application form will have to be amended.

- A.18 of General Information in Part I of the application form needs to be filled out.

B. Site Information

- A 1":2000' scale map is required containing the following information [270.13(L)]:

- a. Surrounding land uses
- b. Injection wells used by facility (1 mile).
- c. Drinking water wells (1/4 mile).
- d. Intake and discharge structures (1 mile).

- A 1":200' scale topographic map is required containing the following information [270.14(b)(19)]:

- a. Map scale and date.
- b. Orientation of map.
- c. Existence of fire fighting installation on or near the facility.

C. Land Use Information

- A statement should be made in C.2 and C.3 of Part I in the application form. Resubmit corresponding form page.

D. Operation Information

- Site plan must clearly define loading and unloading areas, and normal and limited access entrances at the facility.

- Approximate amounts of wastes received and shipped in a period of time should be included in the application.

- Concerning the facility structures the following information is required:

- a. Present and future structures [270.13(g)].
- b. Traffic patterns, volume and control. Access roads and load bearing capacity [270.14(b)(LL)(i)].

- To comply with 264.12(b), notices to the generators are required to inform them that your facility is permitted to accept hazardous wastes.

- To comply with 264.12(c), a proof that the purported site buyer has been notified of the requirements of Part 264 and 270 should be included in the application, in case the purported buyer is different from the facility owner.

- A more thorough explanation of procedures and forms used to manifest, report discrepancies and unmanifested wastes, keeping operating records, availability, retention and disposition of records, and biennial reports, are required as per Part 264 Subpart E.

E. Facility Security Information

- To conform 40 CFR Part 264.14, a fence should surround the facility, and means to control entry through gates or entrances at all times should be provided.

- The Contingency Plan should include a list of the emergency response requirements available to comply with 264.52(e).

- To comply with 264.194(c)(1), proper considerations should be given to tank spills.

- A more complete evacuation plan should be provided to comply with 264.52(f).

- An internal alarm with several actuators properly located is required to comply with 264.32(a).

- To complete the personnel training plan, the employee names have to be submitted to comply with 264.16(d)(i).

Part II - Containers.

- Capacity calculation of the containment system should be submitted.

- Calculation showing relation between free liquid in waste stored, how partially the containers are filled, the number of containers and total amount of waste is required.

- If storage area described as UNIT 1 in ID. 5 - 2b will contain ignitable wastes, 50' or more from property boundary is required to comply with 264.176.

- A timetable for scheduled closure activities need to be submitted to comply with 264.112(a)(4).

- If means to control fire with water exist, it should be mentioned in the corresponding parts of your application to comply with 264.32(d).