

UNIVERSAL WASTE & TRANSIT
ISSUED PERMIT HC29-141782

For Routing To	
To:	
To:	
From:	

State of Florida
DEPARTMENT OF ENVIRONMENTAL REGULATION

Interoffice Memorandum

TO: Rick Garrity

THRU: Clabe Polk *CP 2-6-90*
Victor San Agustin, P.E.
Bill Crawford *BC*

FROM: Lynne R. Milanian *LRM 2/6*

DATE: February 6, 1990

SUBJECT: Universal Waste & Transit, Inc., FLD 981 932 494 *LC*
Modification of Construction Permit File No.: ~~HC29-141782~~
3002 N. Orient Road, Tampa, Hillsborough County

Universal Waste participated in a meeting with DER officials on November 22, 1989. During the course of the meeting Universal requested that modifications be made to their existing construction permit such that operation of the newly constructed facility could begin prior to issuance of their operation permit. The operation permit application is currently under Department review. Certain specific conditions allow operation of new facilities under an issued construction permit, however, these conditions are not present in Universal's existing permit. As such, the Department has agreed to modify the construction permit (as Universal requested) to incorporate the specific conditions authorizing facility operation during the term of the construction permit. This change in permit conditions is considered a major modification and it will be necessary for Universal to publish and broadcast the Department's intended action.

The facility will operate a hazardous waste storage and treatment operation. Universal Waste will handle a variety of wastes generally characterized as: flammable liquids, poisonous materials, oxidizer/reactives, flammable solids, waste corrosive materials, and hazardous waste liquids and solids.

Essentially, Universal Waste will accumulate each waste type and periodically transport the wastes to other treatment facilities. Universal will have on-site a filter press that will further treat semi-solid wastes to facilitate liquid removal. These dewatered wastes will then be transported to an appropriate disposal facility as will the waste liquids generated during the dewatering process.

Memo to Rick Garrity

SUBJECT: Universal Waste & Transit, Inc., FLD 981 932 494
Modification of Construction Permit File No.: HO29-141782
3002 N. Orient Road, Tampa, Hillsborough County

Page Two

The applicant has provided information verifying that each storage area has been designed to prevent releasement of stored wastes.

The forty-five day public notice period was over February 5, 1990, and no petitions concerning the intended permit have been filed. The facility is in compliance with financial requirements, and no unresolved enforcement actions exist. Issuance of this permit modification is recommended.

LRM/ab
Attachment



Florida Department of Environmental Regulation

Southwest District • 4520 Oak Fair Boulevard • Tampa, Florida 33610-7347 • 813-623-5561

Bob Martinez, Governor

Dale Twachtmann, Secretary

John Shearer, Assistant Secretary

Dr. Richard Garrity, Deputy Assistant Secretary

FEB - 7 1990

Universal Waste & Transit, Inc.
2002 N. Orient Road
Tampa, Florida 33619

Attn: Robert J. Bedore
Vice President

Re: Permit Modification
Construction Permit HC29-141782


Dear Mr. Bedore:

The Department has reviewed your request for modification of Permit No. HC29-141782. The modifications have been approved by the Department as follows:

<u>Specific Condition</u>	<u>From</u>	<u>To</u>
1.	as issued	as attached
5.	as issued	as attached
20.	Not present in original permit	as attached

This letter must be attached to your permit and becomes a part of that permit, henceforth referred to as Permit No. HC29-141782A and having the same date of expiration.

Sincerely,



for Richard D. Garrity, Ph. D.
Deputy Assistant Secretary
Southwest District

RDG/lrmb
Attachment

ATTACHMENT

SPECIFIC CONDITIONS

1. In accordance with Section 17-730.250(2), Florida Administrative Code (FAC), the permittee shall be authorized to begin operation of the physical treatment unit and drum storage area upon achieving compliance with the following items.
 - a. Submission of certification that the facility shall be operated and is adhering to Title 40 Chapter 264 Code of Federal Regulation (CFR) requirements; and
 - b. Conduction of an FDER inspection and receipt from this office a letter of verification that the facility has been constructed in accordance with the permit application.
5. Upon completion of construction and prior to actual operation, the permittee shall submit a certification of completion of construction certifying that the herein permitted unit has been constructed as specified in the application, this permit and approved modifications as described in specific condition #3. This certification shall comply with Section 17-730.220(5), FAC. The permittee shall also submit to the Department "as built" drawings, including location of all safety equipment, security devices, communication devices, water for fire control, spill control equipment, etc.
20. The permittee shall satisfy the requirements of the following specific conditions prior to commencing operation of the treatment unit and drum storage area: 1, 5, 6, 9, 11, 12, and 13.



Florida Department of Environmental Regulation

Southwest District • 4520 Oak Fair Boulevard • Tampa, Florida 33610-7347 • 813-623-5561

Bob Martinez, Governor

Dale Twachtmann, Secretary

John Shearer, Assistant Secretary

Dr. Richard Garrity, Deputy Assistant Secretary

JUN 16 1989

Robert J. Bedore, Vice President
Universal Waste & Transit, Inc.
2501 North Orient Road, Suite A
Tampa, Florida 33619

Permit Modification
Construction Permit HC29-141782

RDG *1-6*

Dear Mr. Bedore:

We are in receipt of your request for a modification of the permit conditions. The conditions are changed as follows:

<u>CONDITION</u>	<u>FROM</u>	<u>TO</u>
Expiration Date	November 23, 1989	November 23, 1990


This letter must be attached to your permit and becomes a part of that permit.

Sincerely,

Richard Garrity, Ph.D.
Deputy Assistant Secretary
Southwest District

RDG/pjpb

cc: James Scarbrough - EPA/Atlanta
Satish Kastury - DER/Tallahassee



State of Florida
DEPARTMENT OF ENVIRONMENTAL REGULATION

For Routing To Other Than The Addressee	
To: _____	Location: _____
To: _____	Location: _____
To: _____	Location: _____
From: _____	Date: _____

Interoffice Memorandum


TO: Richard Garrity
THRU: Clabe Polk *DT Bc CRP*
FROM: Armando Gonzalez *AG*
DATE: November 23, 1988
SUBJECT: Universal Waste & Transit, Inc.
Construction Permit Application HC29-141782

This permit will allow for the construction of a commercial hazardous waste storage and physical treatment facility. The facility will store a large variety of hazardous waste in containers in three bays specifically designed to cope with hazards posed by each type, and to segregate the most incompatibles. Physical treatment will consist of solidification of amendable waste via filtration. No wastewater resulting from treatment will be allowed to be disposed of on site, or be discharged into the sewer.

The City of Tampa has been very much interested in the process of this permit as well as Senator Malcolm. In a meeting held with the City of Tampa, I explained to them the permitting process and addressed their concerns. Senator Malcolm inquired on the time period for the issuance of the permit. In order to speed up the review process of this voluminous application (5 volumes plus drawings) I held twelve meetings with the applicant and its consultant to review and address deficiencies contained in it.

This facility has aroused some controversy due to its location on Orient Road. Petitions filed by Chapman Contracting Company and National Fisheries, Inc., a Florida Corporation were resolved by the applicant and petitioners without a hearing. The District was notified by Richard Donelan to proceed with permit issuance.

AG/ab
Attachments



Florida Department of Environmental Regulation

Southwest District • 4520 Oak Fair Boulevard • Tampa, Florida 33610-7347 • 813-623-5561

Bob Martinez, Governor

Dale Twachtmann, Secretary

John Shearer, Assistant Secretary
Richard Garrity, Deputy Assistant Secretary

AI, 1-a

NOTICE OF PERMIT

Mr. Robert Bedore
Universal Waste and Transit Company
7217 Gulf Boulevard
Suite 7
Clearwater, Florida 33706


Dear Mr. Bedore:

Enclosed is Permit Number HC29-141782 to construct a hazardous waste treatment and storage facility at 2002 Orient Road, Tampa, Hillsborough, Florida, pursuant to Section 403.722, Florida Statutes.

Any party to this permit has the right to seek judicial review of the permit pursuant to Section 120.68, Florida Statutes, by the filing of a Notice of Appeal pursuant to Rule 9.110, Florida Rules of Appellate Procedure, with the Clerk of the Department in the Office of General Counsel, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400 and by filing a copy of the Notice of Appeal accompanied by the applicable filing fees with the appropriate District Court of Appeal. The Notice of Appeal must be filed within 30 days from the date the Notice is filed with the Clerk of the Department.

Executed in Tampa, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL REGULATION


Armando Gonzalez
Permitting Engineer
Hazardous Waste Section
Division of Waste Management

AG/ab

cc: James H. Scarbrough - EPA/Atlanta w/attachment
Satish Kastury - DER/Tallahassee w/attachment
Melanie Curren - Hillsborough County/EPC
Nancy McCann - City of Tampa


CERTIFICATE OF SERVICES

This undersigned duly designated deputy clerk hereby certifies that this NOTICE OF PERMIT and all copies were mailed before the close of business on November 23, 1988 to the listed persons.

FILING AND ACKNOWLEDGEMENT
FILED, on this date, pursuant
the designated Department
Clerk, receipt of which is
hereby acknowledged.

Anna Black
Clerk

11/23/88
Date



Florida Department of Environmental Regulation

Southwest District • 4520 Oak Fair Boulevard • Tampa, Florida 33610-7347 • 813-623-5561

Bob Martinez, Governor

Dale Twachtmann, Secretary

John Shearer, Assistant Secretary

Richard Garrity, Deputy Assistant Secretary

PERMITTEE:

Universal Waste & Transit, Inc.
7217 Gulf Boulevard
Suite 7
St. Petersburg, Florida 33706

PERMIT/CERTIFICATION:

EPA I.D. Number: FLD 981 932 494
Permit No.: HC29-141782
County: Hillsborough
Issuance Date: November 23, 1988
Expiration Date: November 23, 1989
Latitude / Longitude:
27°57'49"N / 82°22'23"W
Section / Township / Range:
14 / 29S / 19E
Project: Construction of a
Hazardous Waste Treatment and
Storage Facility

Attention: Mr. Robert Bedore
President

This permit is issued under the provisions of Chapter 403.722, Florida Statutes, and Florida Administrative Code Rules 17-30. The above named permittee is hereby authorized to construct the facility shown on the application and approved drawings, plans, and other documents, attached hereto or on file with the Department and made a part hereof and specifically described as follows:

The construction of a drum storage and a physical treatment facility for hazardous waste on a vacant lot having a total area of 1.4 acres located at 2002 Orient Road, Tampa, Hillsborough County, Florida 33615.

The drum storage unit consists of three (3) sub-areas separated by a four hour reinforced masonry fire wall extended to eight inches above the roof. Two similar sub-areas approximately forty eight feet by fifty feet are located at opposite ends of the building, and the smaller one, approximately twenty one and one third feet by fifty feet is located in the middle. The smaller sub-area will store flammable wastes.

The exterior walls of the storage unit will be made of masonry to four feet above the finished floor with "CECO" metal panel above to roof. The roof will be made of "CECO" metal panel. The floor slab will be five inches of 4,000 PSI reinforced concrete sloped to two sumps in the large sub-areas, and to one sump in the small sub-area; each sump is capable of holding seven hundred (700) gallons. Interior side of the walls and floor will receive one coat of sealant and two coats of epoxy urethane.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

Physical treatment for solidification will be carried out by a filter press which is an eight hundred (800) millimeter device approximately one hundred twenty three (123) inches long and forty three and half (43-1/2) inches wide, with center fed polypropylene recessed chamber plates and four cornered discharge type.

The estimated maximum capacity of the storage unit is 33,660 gallons and the estimated capacity for solidification via physical treatment is 2,000 pounds per day. The table below shows the hazardous waste codes, their corresponding waste type and estimated annual quantity for storage and treatment:

<u>EPA Hazardous Waste Number</u>	<u>Waste Type</u>	<u>Estimated Annual Quantity</u>
D001	Ignitable	100,000 gallons
D002	Corrosive	25,000 gallons
D003	Reactive	5,000 gallons
D004 thru D017	E.P. Toxic	60,000 gallons
F001 & F002	Halogenated Solvents	100,000 gallons
F003 & F005	Non-Halogenated Solvents	Included in D001
F004	Non-Halogenated Solvents	10,000 gallons
F006	Electroplating Sludges	Included in D003 thru D017
F007 thru F012	Electroplating Wastes	Included in D003
F020 thru F024	HCL Manufacturing	1,000 gallons
K001	Wood Preservative	1,000 gallons
K002 thru K008	Inorganic Pigments	3,000 gallons
K009 thru K011 K013 thru K030 K093 thru K096 K083 & K085 K103 thru K105	Organic Chemicals	3,500 gallons

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

<u>EPA Hazardous Waste Number</u>	<u>Waste Type</u>	<u>Estimated Annual Quantity</u>
K071; K073; K106	Inorganic Chemicals	600 gallons
K031 thru K043 K097 thru K099	Pesticides	1,500 gallons
K048 thru K052	Petroleum Refining	8,000 gallons
K061 & K062	Iron & Steel	10,000 gallons
K069 & K100	Secondary Lead	1,500 gallons
K084; K101; K102	Veterinary Pharmaceuticals	1,500 gallons
K086	Ink Formulation	20,000 gallons
K060 & K087	Coking	1,500 gallons
"P" listed waste	Acute Hazardous Waste	4,000 gallons
"U" listed waste	Toxic Wastes	20,000 gallons

The following submittals were utilized in the preparation of this permit, and are considered a part thereof:

- Application For A Hazardous Waste Facility Permit, DER Form 17-30.401(2) and related attachments received November 12, 1987.
- Modifications and additions to the above application received on March 1, March 3, March 9, March 14, March 17, March 29, April 1, April 5, April 7, and April 14, 1988.
- Set of drawings sealed and signed by a Florida Registered Professional Engineer submitted on May 2, 1988.
- A letter dated June 14, 1988 providing new address for the same location and documents to support the change received on June 15, 1988.
- Letter dated July 15, 1988 and submitted on July 18, 1988
Replaces Permit: No permit history.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

GENERAL CONDITIONS:

1. The terms, conditions, requirements, limitations, and restrictions set forth herein are "Permit Conditions" and as such are binding upon the permittee and enforceable pursuant to the authority of Sections 403.161, 403.727, or 403.859 through 403.861, Florida Statutes. The permittee is hereby placed on notice that the Department will review this permit periodically and may initiate enforcement action for any violation of the "Permit Conditions" by the permittee, its agents, employees, servants or representatives.
2. This permit is valid only for the specific processes and operations applied for and indicated in the approved drawings or exhibits. Any unauthorized deviation from the approved drawings, exhibits, specifications, or conditions of this permit may constitute grounds for revocation and enforcement action by the Department.
3. As provided in Subsections 403.087(6) and 403.722(5), Florida Statutes, the issuance of this permit does not convey any vested rights or any exclusive privileges. Nor does it authorize any injury to public or private property or any invasion of personal rights, nor infringement of federal, state or local laws or regulations. This permit does not constitute a waiver of or approval of any other Department permit that may be required for other aspects of the total project which are not addressed in the permit.
4. This permit conveys no title to land or water, does not constitute state recognition or acknowledgement of title, and does not constitute authority for the use of submerged lands unless herein provided and the necessary title or leasehold interests have been obtained from the state. Only the Trustees of the Internal Improvement Trust Fund may express state opinion as to title.
5. This permit does not relieve the permittee from liability for harm or injury to human health or welfare, animal, plant or aquatic life or property and penalties therefore caused by the construction or operation of this permitted source, nor does it allow the permittee to cause pollution in contravention of Florida Statutes and Department rules, unless specifically authorized by any order from the Department.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HF53-138993
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

GENERAL CONDITIONS: (cont'd)

6. The permittee shall at all times properly operate and maintain the facility and systems of treatment and control (and related appurtenances) that are installed or used by the permittee to achieve compliance with the conditions of this permit, as required by Department rules. This provision includes the operation of backup or auxiliary facilities or similar systems when necessary to achieve compliance with the conditions of the permit and when required by Department rules.

7. The permittee, by accepting this permit, specifically agrees to allow authorized Department personnel, upon presentation of credentials or other documents as may be required by law, access to the premises, at reasonable times, where the permitted activity is located or conducted for the purposes of:

a. Having access to and copying any records that must be kept under the conditions of the permit;

b. Inspecting the facility, equipment, practices, or operations regulated or required under this permit; and

c. Sampling or monitoring any substances or parameters at any location reasonably necessary to assure compliance with this permit or Department rules.

Reasonable time may depend on the nature of the concern being investigated.

8. If, for any reason, the permittee does not comply with or will be unable to comply with any condition or limitation specified in this permit, the permittee shall immediately notify and provide the Department with the following information:

(a) a description of and cause of non-compliance; and

(b) the period of non-compliance, including exact dates and times; or, if not corrected, the anticipated time the non-compliance is expected to continue, and steps being taken to reduce, eliminate, and prevent recurrence of the non-compliance.

The permittee shall be responsible for any and all damages which may result and may be subject to enforcement action by the Department for penalties or revocation of this permit.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

GENERAL CONDITIONS: (cont'd)

9. In accepting this permit, the permittee understands and agrees that all records, notes, monitoring data and other information relating to the construction or operation of this permitted source, which are submitted to the Department, may be used by the Department as evidence in any enforcement case arising under the Florida Statutes or Department rules, except where such use is proscribed by Section 403.73 and 403.111, Florida Statutes.

10. The permittee agrees to comply with changes in Department rules and Florida Statutes after a reasonable time for compliance, provided, however, the permittee does not waive any other rights granted by Florida Statutes or Department rules.

11. This permit is transferable only upon Department approval in accordance with Florida Administrative Code Rules 17-4.12 and 17-30.300, as applicable. The permittee shall be liable for any non-compliance of the permitted activity until the transfer is approved by the Department.

12. This permit is required to be kept at the work site of the permitted activity during the entire period of construction or operation.

13. This permit also constitutes:

- () Determination of Best Available Control Technology (BACT)
- () Determination of Prevention of Significant Deterioration (PSD)
- () Certification of Compliance with State Water Quality Standards (Section 401, PL 92-500)
- () Compliance with New Source Performance Standards

14. The permittee shall comply with the following monitoring and record keeping requirements:

a. Upon request, the permittee shall furnish all records and plans required under Department rules. The retention period for all records will be extended automatically, unless otherwise stipulated by the Department, during the course of any unresolved enforcement action.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

GENERAL CONDITIONS: (cont'd)
14. (con't)

b. The permittee shall retain at the facility or other location designated by this permit records of all monitoring information (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation), copies of all reports required by this permit, and records of all data used to complete the application for this permit. The time period of retention shall be at least three years from the date of the sample, measurement, report or application unless otherwise specified by Department rule.

c. Records of monitoring information shall include:

- the date, exact place, and time of sampling or measurements;
- the person responsible for performing the sampling or measurements;
- the date(s) analyses were performed;
- the person responsible for performing the analyses;
- the analytical techniques or methods used; and
- the results of such analyses.

15. When requested by the Department, the permittee shall within a reasonable time furnish any information required by law which is needed to determine compliance with the permit. If the permittee becomes aware that relevant facts were not submitted or were incorrect in the permit application or in any report to the Department, such facts or information shall be submitted or corrected promptly.

16. In the case of a hazardous waste facility permit, the following permit conditions shall also apply:

a. The permittee will submit the following reports to the Department:

- (1) Manifest discrepancy report: If a significant discrepancy in a manifest is discovered, the permittee must attempt to reconcile the discrepancy. If not resolved within 15 days after receiving the waste, the permittee shall immediately submit a letter report including a copy of the manifest to the Department.
- (2) Unmanifested waste report: The permittee shall submit an unmanifested waste report to the Department within 15 days of receipt of unmanifested waste.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

GENERAL CONDITIONS: (cont'd)

16.a. (cont'd)

- (3) Annual report: An annual report covering facility activities during the previous calendar year must be submitted in accordance with Florida Administrative Code Rule 17-30.

b. Notification of any non-compliance which may endanger public drinking water supplies, or the occurrence of a fire or explosion from the facility which could threaten the environment or human health outside the facility, shall be verbally submitted to the Department within 24 hours and a written submission provided within 5 days. The verbal submission within 24 hours shall contain the name, address, I.D. number and telephone number of the facility and owner or operator, the name and quantity of materials involved, the extent of injuries (if any), an assessment of actual or potential hazards, and the estimated quantity and disposition of recovered material. The written submission shall contain the following:

- (1) a description of any cause of non-compliance; and
- (2) if not corrected, the anticipated time the non-compliance is expected to continue and steps being taken to reduce, eliminate, and prevent recurrence of the non-compliance.

c. Reports of compliance or non-compliance with, or any progress reports on, requirements contained in any compliance schedule of this permit shall be submitted no later than 14 days following each schedule date.

d. All reports or information required to be submitted to the Department by a hazardous waste permittee shall be signed by a person authorized to sign a permit application.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

SPECIFIC CONDITIONS

1. The permittee shall not begin operation of the waste treatment and storage facility until he has applied for and received an operation permit from the Department in accordance with the provisions of Chapter 17-30, Part IV, Florida Administrative Code (F.A.C.).
2. The permittee shall apply for an operation permit for this facility at least one hundred thirty five (135) days prior to the expiration of this construction permit. The complete application shall include the following:
 - a. All of the information approved in the construction permit application;
 - b. Additional information requested in this permit;
 - c. Changes required in the personnel training plan, the inspection schedule, the contingency plan, etc., which may be required as a result of any modification.
3. The facility shall be constructed as specified in the complete construction permit application. Any major changes to drawings and specifications of the approved construction permit application shall be submitted to and approved by the Department.
4. The facility shall be constructed to comply with all applicable standards contained in 40 CFR Part 264 as adopted in Section 17-30.180, F.A.C.
5. Upon completion of construction, the permittee shall submit a certification of completion of construction certifying that the herein permitted unit has been constructed as specified in the application, this permit and approved modifications as described in specific condition #3. This certification shall comply with Section 17-30.220(5), F.A.C. The permittee shall also submit to the Department an "as built" drawings, including location of all safety equipment, security devices, communication devices, water for fire control, spill control equipment, etc.

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

SPECIFIC CONDITIONS (cont'd)

6. At least sixty (60) days before the date on which hazardous waste is first received for treatment or storage, the permittee shall establish financial assurance for closure (40 CFR Part 264.143) and demonstrate financial responsibility for sudden accidental occurrences (40 CFR Part 264.147(a)).

7. The Department may modify this permit in accordance with the provisions of Section 17-30.290(1)(b), F.A.C.

8. Prior to issuance of the operation permit the permittee shall obtain an EPA Identification Number and a hazardous waste transporter license in accordance with 40 CFR Part 262.12 and Section 17-30.170, F.A.C. respectively.

9. The permittee shall provide the institutions, agencies and individuals shown in Volume 2, page 14 of the construction permit application with a copy of the contingency plan amended to address the requirements of this permit, and other changes that may be applicable. Proof of compliance shall be submitted prior to issuance of the operation permit.

10. The permittee shall submit with the operation permit application a "stand alone" document containing the contingency plan. This document shall comply with the requirement of 40 CFR Part 264, Subpart D.

11. Prior to issuance of the operation permit the permittee shall submit to the Department a copy of the emergency maintenance contract mentioned in Volume 1, page 45 of the construction permit application.

12. The permittee shall submit with the operation permit application a drawing showing location, aisle space, number and size of drums, and stacking practice for each row of drums in the storage unit.

13. The permittee shall specify in the operation permit application areas within the storage unit where incompatible waste groups will be stored.

14. The permittee shall provide in the operation permit application job titles and descriptions for each position in accordance with 40 CFR Part 264.16(d)(1) and (2).

PERMITTEE:
Universal Waste &
Transit, Inc.

PERMIT/CERTIFICATION NO: HC29-141782
Project: Construction of a Hazardous
Waste Treatment and Storage
Facility

SPECIFIC CONDITIONS (cont'd)

15. The permittee shall submit with the operation permit application a table or method to cross reference the identification number assigned to hazardous materials in 49 CFR Part 172, Subpart B, the EPA hazardous waste numbers in 40 CFR Part 261, Subparts C and D, and the requirements for packaging in 49 CFR Part 173.

16. The permittee shall include in the operation permit application a log to be filled out before a new type of waste is introduced in the filter press to prevent contact of the incoming waste with incompatible waste previously treated.

17. All submittals modifying major engineering features of the hazardous waste storage unit shall be worded, signed and certified by a qualified, independent professional engineer registered in the State of Florida in accordance with DER Form 17-30.401(2), Certification Section, page 49 and 50, item 4.


18. All documents submitted pursuant to the conditions of this permit shall be accompanied by a cover letter stating the name and date of document submitted, the number(s) of the specific condition(s) affected, and number and project name of the permit involved.

19. All submittals in response to the specific conditions of this permit shall be submitted in triplicate to:

District Manager
Department of Environmental Regulation
4520 Oak Fair Boulevard
Tampa, Florida 33610-7347

Issued this 23 day of Nov
1987.

STATE OF FLORIDA DEPARTMENT OF
ENVIRONMENTAL REGULATION



Richard D. Garrity, Ph.D.
District Manager