STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 1	EXTEND PIPE THRU BERM	---	---	268.00 (21" W)
S 2	MOD. FDOT TYPE 'E' INLET (DETAIL A)	145.70	142.96 (S)	141.13 (21" E) 139.46 (36" W)
S 3	4:1 MITERED END SECTION	---	---	139.46 (36" E)
S 4	EXTEND PIPE THRU BERM	---	---	268.00 (18" W)
S 5	MOD. FDOT TYPE 'E' INLET (DETAIL A)	145.70	142.96 (S)	141.13 (18" E) 139.46 (36" W)
S 6	4:1 MITERED END SECTION	---	---	139.46 (36" E)
S 7	FDOT TYPE 'E' INLET	145.70	142.96 (S)	141.86 (24" N)
S 8	CONST. MITERED END INTO CONC. PAVING	---	---	141.86 (24" S)
S 9	EXTEND PIPE THRU BERM	---	---	268.00 (18" N)
S 10	MOD. FDOT TYPE 'E' INLET (DETAIL A)	140.00	137.26 (W)	135.26 (18" S) 135.26 (36" N)
S 11	CONST. MITERED END INTO CONC. PAVING	---	---	135.26 (36" S)
S 12	EXTEND PIPE THRU BERM	---	---	268.00 (21" N)
S 13	MOD. FDOT TYPE 'E' INLET (DETAIL A)	135.25	132.51 (W)	130.51 (21" S) 130.51 (42" N)
S 14	CONST. MITERED END INTO CONC. PAVING	---	---	130.51 (42" S)
S 15	EXTEND PIPE THRU BERM	---	---	268.00 (21" N)
S 16	MOD. FDOT TYPE 'E' INLET (DETAIL A)	131.65	128.91 (W)	126.91 (21" S) 126.91 (42" N)
S 17	CONST. MITERED END INTO CONC. PAVING	---	---	126.91 (42" S)
S 18	EXTEND PIPE THRU BERM	---	---	268.00 (18" N)
S 19	MOD. FDOT TYPE 'E' INLET (DETAIL A)	126.80	124.06 (W)	122.06 (18" S) 122.06 (36" N)
S 20	CONST. MITERED END INTO CONC. PAVING	---	---	122.06 (36" S)
S 21	FDOT TYPE 'E' INLET	121.65	118.91 (NW)	115.65 (24" NE)
S 22	CONST. MITERED END INTO CONC. PAVING	---	---	115.65 (24" SW)
S 23	FDOT TYPE 'E' INLET	119.60	116.86 (S)	114.86 (24" E)
S 24	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	119.60	116.86 (S)	114.86 (24" W) 109.56 (42" S) 109.06 (48" N)
S 25	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	119.60	116.86 (S)	114.86 (24" NW) 107.66 (48" S) 107.66 (48" NE)
S 26	EXTEND PIPE THRU BERM	---	---	268.00 (21" E)
S 27	MOD. FDOT TYPE 'E' INLET (DETAIL B)	119.60	116.86 (S)	114.86 (21" W) 114.86 (42" E)
S 28	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	119.60	116.86 (S)	114.86 (42" W) 111.86 (42" N)
S 29	EXTEND PIPE THRU BERM	---	---	268.00 (21" E)
S 30	MOD. FDOT TYPE 'E' INLET (DETAIL A)	119.60	116.86 (N)	114.86 (21" W) 114.86 (42" E)
S 31	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	119.60	116.86 (N)	114.86 (42" W) 111.86 (42" S)
S 32	EXTEND PIPE THRU BERM	---	---	268.00 (18" E)
S 33	MOD. FDOT TYPE 'E' INLET (DETAIL B)	119.60	116.86 (SW)	114.86 (18" NW) 112.00 (36" SE)
S 34	CONST. MITERED END INTO CONC. PAVING	---	---	112.00 (36" NW)
S 35	FDOT TYPE 'E' INLET	122.40	119.66 (SW)	117.25 (24" SE)
S 36	CONST. MITERED END INTO CONC. PAVING	---	---	117.25 (24" NW)
S 37	EXTEND PIPE THRU BERM	---	---	268.00 (18" S)
S 38	MOD. FDOT TYPE 'E' INLET (DETAIL B)	127.20	124.46 (W)	122.46 (18" N) 122.46 (36" S)
S 39	CONST. MITERED END INTO CONC. PAVING	---	---	122.46 (36" N)
S 40	EXTEND PIPE THRU BERM	---	---	268.00 (21" S)
S 41	MOD. FDOT TYPE 'E' INLET (DETAIL B)	131.75	129.01 (W)	127.01 (21" N) 127.01 (42" S)
S 42	CONST. MITERED END INTO CONC. PAVING	---	---	127.01 (42" N)
S 43	EXTEND PIPE THRU BERM	---	---	268.00 (21" S)
S 44	MOD. FDOT TYPE 'E' INLET (DETAIL B)	135.40	132.66 (W)	130.66 (21" N) 130.66 (42" S)
S 45	CONST. MITERED END INTO CONC. PAVING	---	---	130.66 (42" N)
S 46	EXTEND PIPE THRU BERM	---	---	268.00 (18" S)
S 47	MOD. FDOT TYPE 'E' INLET (DETAIL B)	140.15	137.41 (W)	135.41 (18" N) 135.41 (36" S)
S 48	CONST. MITERED END INTO CONC. PAVING	---	---	135.41 (36" N)
S 49	FDOT TYPE 'E' INLET	145.70	142.96 (N)	141.91 (24" S)
S 50	CONST. MITERED END INTO CONC. PAVING	---	---	141.91 (24" N)
S 51	EXTEND PIPE THRU BERM	---	---	268.00 (18" W)
S 52	MOD. FDOT TYPE 'E' INLET (DETAIL B)	145.70	142.96 (N)	141.13 (18" E) 139.46 (36" W)
S 53	4:1 MITERED END SECTION	---	---	139.46 (36" E)
S 54	EXTEND PIPE THRU BERM	---	---	268.00 (21" W)
S 55	MOD. FDOT TYPE 'E' INLET (DETAIL B)	145.70	142.96 (N)	141.13 (21" E) 139.46 (36" W)
S 56	4:1 MITERED END SECTION	---	---	139.46 (36" E)
S 57	FDOT TYPE 'E' INLET	134.50	131.76 (W)	130.76 (30" N)
S 58	CONST. MITERED END INTO CONC. PAVING	---	---	130.76 (30" S)
S 59	FDOT TYPE 'E' INLET	130.27	127.53 (NW)	126.53 (30" NE)
S 60	CONST. MITERED END INTO CONC. PAVING	---	---	126.53 (30" SW)
S 61	FDOT TYPE 'E' INLET	128.15	125.41 (NW)	124.41 (30" NE)
S 62	CONST. MITERED END INTO CONC. PAVING	---	---	124.41 (30" SW)
S 63	FDOT TYPE 'E' INLET	124.50	121.76 (NW)	120.00 (24" NE)
S 64	CONST. MITERED END INTO CONC. PAVING	---	---	120.00 (24" SW)
S 65	FDOT TYPE 'E' INLET	123.50	120.76 (NW) 120.76 (SE)	117.41 (30" NE)
S 66	CONST. MITERED END INTO CONC. PAVING	---	---	117.41 (30" SW)
S 67	FDOT TYPE 'E' INLET	129.09	126.35 (SW)	125.35 (30" NW)
S 68	CONST. MITERED END INTO CONC. PAVING	---	---	125.35 (30" NW)
S 69	FDOT TYPE 'E' INLET	135.72	132.98 (NW)	131.98 (30" SW)
S 70	CONST. MITERED END INTO CONC. PAVING	---	---	131.98 (30" NE)
S 71	FDOT TYPE 'E' INLET	139.91	137.17 (NW)	136.17 (30" SW)
S 72	CONST. MITERED END INTO CONC. PAVING	---	---	136.17 (30" NE)
S 73	CONCRETE ENDWALL DOUBLE 48" RCP	---	---	118.00 (DBL. 48" E)
S 74	CONCRETE ENDWALL DOUBLE 48" RCP	---	---	117.30 (DBL. 48" W)
S 75	INLET STRUCTURE	116.90	111.90 (NW)	105.00 (DBL. 48" S)
S 76	JUNCTION BOX	120.00	---	102.30 (DBL 48" N & S) 106.66 (48" SW)
S 77	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	106.40 (DBL. 48" E)
S 78	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	105.48 (DBL. 48" W)
S 79	CONCRETE ENDWALL 48" CMP	---	---	115.80 (48" NE)
S 80	CONST. MITERED END INTO CONC. PAVING	---	---	114.60 (48" SW)
S 81	4:1 MITERED END SECTION	---	---	101.65 (QUAD 24" NE)
S 82	4:1 MITERED END SECTION	---	---	101.00 (QUAD 24" SW)
S 83	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	119.60	116.86 (N) 116.86 (S)	114.86 (24" W) 109.16 (42" N) 108.66 (48" S)
S 84	INLET STRUCTURE	115.00	110.10 (SW)	107.56 (48" NW) 102.83 (DBL. 48" SE)
S 85	4:1 MITERED END SECTION	---	---	101.33 (DBL. 48" SW)
S 86	4:1 MITERED END SECTION	---	---	101.00 (DBL. 48" NW)
S 87	FDOT TYPE 'E' INLET	116.65	115.90 (N) 115.90 (S)	114.44 (15" E)
S 88	FDOT TYPE 'E' INLET	116.65	115.90 (N) 115.90 (S)	114.16 (15" W) 114.16 (15" NE)
S 89	FDOT TYPE 'E' INLET	114.65	113.90 (N) 113.90 (S)	112.96 (15" NE)
S 90	FDOT TYPE 'E' INLET	114.65	113.90 (N) 113.90 (S)	112.68 (15" SW) 112.68 (15" N)
S 91	CONST. MITERED END INTO CONC. PAVING	---	---	111.77 (15" S)
S 92	4:1 MITERED END SECTION	---	---	105.49 (TRIP. 54" NE)
S 93	4:1 MITERED END SECTION	---	---	105.49 (TRIP. 54" SW)
S 94	4:1 MITERED END SECTION	---	---	114.00 (15" SW)
S 95	FDOT TYPE 'E' INLET	116.00	114.70 (W)	111.50 (15" E)
S 96	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	112.80 (DBL. 48" E)
S 97	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	112.25 (DBL. 48" W)
S 98	FDOT TYPE 'E' INLET	120.40	---	118.05 (15" SE)
S 99	CONST. MITERED END INTO CONC. PAVING	---	---	117.41 (15" NW)
S 100	CONST. MITERED END INTO CONC. PAVING	---	---	117.41 (36" NE)
S 101	CONST. MITERED END INTO CONC. PAVING	---	---	112.30 (36" SW)
S 102	4:1 MITERED END SECTION	---	---	111.00 (15" W)
S 103	FDOT TYPE 'E' INLET	119.60	116.86 (N) 116.86 (S)	114.86 (24" SE)
S 104	FDOT TYPE 'E' INLET	119.60	116.86 (N) 116.86 (S)	114.86 (24" SE)

10-11-90

REVISIONS

ENG PROJ. NO. 89-113-8
DRAWN BY: BWH
CHECKED BY: SAW
DATE: JUNE 11, 1990

SCHEDULE OF DRAINAGE STRUCTURES

TRAIL RIDGE LANDFILL

England-Thims & Miller, Inc.
Consulting & Design Engineers
JACKSONVILLE, FLORIDA

DRAWING NO.
35

SIGNED FOR CONSTRUCTION BY