



REFERENCE POINT FOR END OF
ENTRANCE ROAD PLAN & PROFILE
STATIONING; SEE SHEET 34.

CURVE	RADIUS	LENGTH	TANGENT	CHORD	BEARING	DELTA
01	403.00'	127.39'	64.74'	127.85'	S 53°10' W	18°50'33"
02	2068.45'	387.25'	184.53'	387.35'	N 60°59'10" W	10°44'43"
03	403.00'	368.87'	188.48'	369.13'	N 45°38'33" W	5°28'13"
04	227.25'	154.88'	78.88'	155.25'	N 38°38'12" W	3°22'53"
05	714.25'	198.71'	100.00'	199.87'	N 81°38'28" E	15°55'39"
06	441.46'	196.68'	100.00'	198.06'	N 12°39'06" E	25°31'52"
07	227.25'	154.88'	78.88'	155.25'	N 38°38'12" E	3°22'53"
08	403.00'	127.39'	64.74'	127.85'	N 53°10' W	18°50'33"
09	430.68'	139.44'	70.00'	139.57'	N 71°08'24" E	11°00'00"
10	20730.10'	119.23'	60.00'	119.60'	N 86°48'00" E	08°23'46"
11	2155.9'	379.22'	190.00'	379.23'	N 54°22'23" W	10°00'12"
12	1383.76'	397.22'	200.00'	398.89'	N 52°43'22" W	16°26'54"
13	2703.67'	159.81'	100.00'	159.86'	N 72°22'56" E	04°47'01"
14	848.08'	179.46'	90.00'	179.19'	N 64°50'23" W	10°50'44"
15	711.58'	139.53'	70.00'	139.57'	N 34°44'02" E	11°41'46"
16	60.00'	34.22'	60.00'	64.85'	N 45°08'42" E	06°00'00"
17	72.18'	113.38'	22.18'	122.07'	N 40°36'54" W	70°30'00"
18	226.39'	278.27'	160.00'	278.27'	N 40°36'54" W	70°30'00"
19	1701.24'	690.37'	370.00'	685.84'	N 77°14'24" E	43°45'00"
20	884.94'	242.73'	180.00'	244.45'	N 72°44'16" W	34°44'48"
21	180.00'	252.74'	180.00'	254.26'	N 45°06'42" E	06°00'00"
22	224.65'	271.11'	150.00'	258.49'	N 59°23'16" E	61°00'00"
23	218.68'	480.13'	275.00'	372.43'	N 88°38'16" W	11°45'00"
24	271.09'	381.33'	180.00'	336.37'	N 53°29'13" E	41°45'00"
25	274.79'	258.96'	140.00'	248.49'	N 45°21'46" W	53°58'48"
26	185.63'	169.19'	80.00'	163.97'	N 78°36'07" E	49°00'00"
27	204.35'	129.32'	66.91'	127.12'	N 18°01'05" W	36°15'35"
28	105.00'	157.38'	100.00'	141.42'	N 44°53'18" W	86°00'00"

REVISIONS

FILE NO. 10	DATE	BY	REVISION
8/1/11	8/1/11	EE	
8/1/11	8/1/11	EE	
8/1/11	8/1/11	EE	
8/1/11	8/1/11	EE	

GEOMETRY PLAN

TRAIL RIDGE LANDFILL

England-Thimby & Miller, Inc.

Civil & Design Engineers

JACKSONVILLE, FLORIDA

7

7-17-10