813 621-0080 FAX 813 623-6757

SCS ENGINEERS

May 31, 2005 File No. 09200020.15

Ms. Susan J. Pelz, P.E.
Florida Department of Environmental Protection
Southwest District
3804 Coconut Palm Drive
Tampa, Florida 33619



Subject:

Southeast County Landfill Phosphatic Clay Annual Evaluation

Hillsborough County, Florida - Permit No. 35435-006-SO

Dear Mr. Ford:

On behalf of the Hillsborough County Solid Waste Department, SCS Engineers (SCS) is submitting the attached report regarding the evaluation of the performance of the waste phosphatic clays at the Southeast County Landfill (SCLF) as required by the above referenced permit, specifically Specific Condition No. 16.f. As stated in the attached report by Ardaman and Associates, Inc. (Ardaman), the piezocone soundings show that, under existing conditions, an upward gradient exists at the locations PC-1K, PC-1L, and PC-4F.

At the location of PC-3E, a slight downward potentiometric head 0.4 feet was measured (measured from the head on top of the clay versus the excess pore pressure in the middle of the clay). SCS concurs with Ardaman's assessment that this condition is not significant considering that the phosphatic clay layer has a permeability of less than 1×10^{-8} cm/sec and the pore pressures within the clays will increase upon placement of the next lift of waste in this area.

Based on the data obtained by Ardaman, the performance of the waste phosphatic clays are consolidating and strengthening in general accordance with the original design assumptions. SCS recommends that no further action be taken at this time and that the annual evaluation as required by Specific Condition No. 16.f be continued.

Please call should you have any questions or require additional information.

Sincerely.

Joseph H. O'Neill, P.E.

Project Manager SCS ENGINEERS Raymond J. Dever, P.E., DEE

Vice President SCS ENGINEERS

Say of Ewa

JHO/RJD:jho

cc: Patricia V. Berry, SWMD

Ron Cope, EPCHC

Contembo


Hillsborough County Files in SCS Library


Double D	Groundwater Montoring Plan Blenhald Evolustion SE Cty Class I LET Plass I Environmental Site Assessment Proposed Middle School "Fish Hawk Rainch Develop. Northwest I assider Festilix Hillisborough County, Tourido Operation Permit Renewal Application. Leschitals Management Plan Societiesa County, Landial Hillisborough County, Florida Operation Permit Renewal Application. Leschitals Management Plan Societiesa County, Landial Hillisborough County, Florida Operations and Contingency Plan for Excavation of Landial Waste Materials Young Manage Middle Operations and Contingency Plan for Excavation of Landial Waste Materials Young Manage Middle Operations and Contingency Plan for Excavation of Landial Waste Materials Young Managed Middle Operations and Contingency Plan for Excavation of Landial Waste Materials Young Managed Touring Continued Area Additional Information to FDEP researched and Sci.L. Plases V and VI Operations Hot, Pendida Na. \$5435-003. Operations Permit Medications of Southeast County, Landial Hillisborough County, Florida Responses to the FPGEP Report of Construction Hillisborough Heights Landial Hillisborough County, Florida Responses to the FPGEP Report of Construction Hillisborough Heights Landial Hillisborough County, Florida System Improvements Hillisborough County Landial Hillisborough County, Florida Landial Gas System Improvements Hillisborough Landial Geolup Installation for Phases V & VI Phase V Activation Hillis City contract No. PC-339-88	All classistics in returns or circular to Erins Locumentation Expension. All Emissions inventory & Production to Erins Locumentation ESELF Proposed Class I Behavior Medical Continuation Regord SELF Proposed Class I Behavior Medical Proposed Phase I Behavior Medical Proposed Phase I Behavior Medical Proposed Phase I Reditions Local Form Case Permit Reneral Application. HYTRUE Pollution Providers of Best Management Practices is SELF Evaluation of Etiling Schedutes & Stability Analyses for SELF Permit Page Station B Construction Permit Application Responses to the EPDEP Clusure Permit Responses Contamination Assessment Plan Contamination Assessment Plan Contamination Assessment Plan Technical Specifications Phase II Uralinsad Improvements Technical Specifications Phase II Uralinsad Inprovements Technical Specifications Phase II Uralinsad Individual Providers Technical Specifications Phase II Uralinsad Individual Providers Technical Specifications Phase II Uralinsad Individual Providers Technical Specifications Phase I Uralinsad Individual Phase III Providers Technical Specifications Phase II Uralinsad Individual Phase III Providers Technical Specifications Phase II Providers Technical Specifications Phase III Providers Technical Phase III Providers Technical Specifications Phase III Providers Technical Specifi	Leschise Managemani Report Leschise Managemani Report Leschise Managemani Report Leschise Managemani Report Geotochnical Ecoloration, Proposed Leschale Treatment Plant Southeast Landfill Deadfon Permit Rentwest Responses Operation Permit Rentwest Responses - SELF Proposed Final Feasibility Study Taylor Read Landfill Site Proposed Final Feasibility Study Taylor Read Landfill Site Proposed Final Feasibility Study Taylor Read Landfill Site Phase II Mechanic Gas Migration Investigation Operation Heights Landfill Draft Remedial Investigation Fresponses Class I. Expansion Final Remedial Treasted Species Report to the Southeast County Feasibly Proposed Class I. Expansion Endeavourd and Treasted Species Report of the Southeast County Feasibly Proposed Class I. Expansion Site Endeavourd and Treasted Species Report of the Southeast County Feasibly Proposed Class I. Expansion Site Endeavourd and Treasted Species Report of the Southeast County Feasibly Proposed Class I. Expansion Site Inflied Operational Period Evaluation Report of the Southeast County Landfill Hydracerological Minestigation Southeast County Landfill Contract Operations Special Southeast County Landfill Lorients in Newfort & Period Evaluation Report of the Migration Control System Air Emissions Inventory & System Security Landfill Air Emissions Inventory & Proposed Site Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventory & Proposed Class I. Expansion Control System Air Emissions Inventor	Description Title V-Mr Permit Application, Southeast County Landfill Permanent Permit Application, Southeast County Landfill Permanent Permit Registering Phasest V and Vintervenments Southeast County LE Permanent Remit Registering Phasest V and Vintervenments Southeast County LE Conduction Remit Received Reports Barry Road Landfill Contamination Assessment Plan Berefort of Genetication, Southeast Landfill Sites Selected for Detailed Investigation Department of the Received Received Residents for Constitution and Operation Permit Received
美速接收品店等国际的工程,但是不是一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一个一	County County County Florids County	Journy Servici Journy Dept of Solid Weste County Dept of Solid Weste County Dest of Solid Weste County Dept of Solid Weste County	County Deat of Soid Waste County Soid Waste County Soid Waste County Soid Waste Marin Deat. County Soid Waste Marin Deat. County County County County County County County County County County County County County County County County Deat of Soid Waste County County Soid Waste County Soid Waste County County Soid Waste County Soid Waste County Soid Waste County County County Soid Waste County	Darle Darly SMAIO Darly Cept of Said Waste Darly Dest of Said Waste

Contract Countering Land Counter Counter Instantial Industry County Landill Big No. PC-339-98 C.I.P. No.:NIA Contract Counterin & Specifications for Taylor Road/Hillshorough Heights Landill Cast Control System Improvements (Rebid) Operation and Maintenance Measual - LFG Migration and Oxfor Control Facilities	Operations Plan Southeast County Landfill Hillspensyal Doubly, Rodds Grunnfurst Hundelfor Blen Southeast Frontia and ill Hillspensores Drushite, Horida	Operation Permit Renewal Application Southeast County Landial Historoping County, Florida Artechment L-2 (Groundwater, Montgoring Hein Leachteit Kanagement Plata Southeast County, Landial Historoping County, Florida	Responses to FDEP Operation Permit Renewal Application Southeast County Landfill, Hillsbergugh County, Florida	Operation / etrmit Renewa Application, Southeast County (abnet Histobrough County, Fioriga Artaschment X-) - Upgrations verial recommendation of the County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application Southeast County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application (2-) County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application (2-) County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application (2-) County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application (2-) County Landill Histobrough County Fioriga Artaschment (2-) Groupsdyself Application (2-) County Landill Histobrough County Fioriga Artaschment (2-) County Landill Histobrough (2-) County Lan	Operation Permit Renewal Application Southeast County Landfill Hillsborough County, Florida	Progress Report for Generality in Devil 1-year Light Novike Construction Progress Report for Generality Statistical Anniel Service Construction Cons	Request for Proposals for the Configuing Construction and Operation of the Histoprough County Southeast Landfill Reculation Assessment Report J. Land Libral Exhaust Closed I.E. Reculation Configuration Assessment Report J. Land Libral Land Closed I.E. Reculation Configuration Assessment Report J. Land Libral Land Closed I.E. Reculation Configuration Configurat	Preliminary Contamination Assessment Report - Leto High School Closed Landill, Tampa FL	Lecthiat Management (Pas Southeast County Landiii Hillsborough County, Fforida	Draft Landfill Gas Investigations Hillsborough Heights Landfill Closed Landfill Construction Processor (TC IIB).	Contamination Assessment Report Pleasant Grove Landfff Hillsborough County, Florida - Volume II	Hillsborough CN, SE CN, Sanitery, Landfill Application for Permit to Construct & Operatie e SW Resource Recovery & Marrit Facility.	Construction Permit Application Effluent/Leachate Storage Pond Southeast County Landfill Hillsborough County, Floridg	Contract Document But On C-1946 for Operation of the Southeast County Landil Leachast Freatment and Reciamation Facility for Solid Waste Department	Oseration and Maintenance Manual Hillsborough Heights Landill Leachate Tank Containment Area	Melhane Gas investigation Plan - Gunn Hidrway Laudfill	Gibundwater Monitoning Plan Phases I-VI and Section 7 and 8, Southeast County Landini Onescript plans Dessen I-VIA and Section 7 and 8, Townsteen County Landini	Operation Permit Application, Capacity, Expansion, Section 8, Southeast County, Landfil	Capacity Expansion Section 9 Expansion Area Southeast County Landfill, Volume 2 of 2 Engineering Support Calculations	18/or, Road Landell Superfuld Site Groundwater Chainff Statistical Englishment of 27 Engineering Support Chainff Statistical Englishment Chainff Statistical Chainff S	Long-Term Case Permit Renewal Application Hillsburguigh Heights and Taylor Read Class I Landfills	Technical Evaluation for Cyanide Reduction at the Leachate Treatment and Rectamation Facility	ত্রপার্থনে এইটোল্ডার ১ সুহন্তান্থেরতার তা' স্থলান্তর্গ তেলাপু Latoni হেনুপ্রান্থান সহয়ত্ত্ব ও Long-Term Jenne Renewa Abolisation Hillistonuuch Heights and Taylor Road Class i Landfüls	Application for Construction Permit to Renovate the Landfil Gas Collection & Control System Hillsborough Heights Landfil	Long-Term Care Permit Renewal Application Nathwest Class III Landfill, Hillsborough County Florida	HIIISBOYDURI HEIGHIS LANDIN GAS SYREM REINVARDA I ENTIRE I SEPERIZATIONS GROUND-MEH MONITOR I PAIN E EVALUATION SOUTHEAST I SCHOOL AND AND THE CONTROL OF THE SEPERICATION SOUTHEAST CONTROL AND THE SEPERICATION SOUTHEAST CONTROL OF THE SEPERICATION OF THE SEPERICATIO	Groundwater Quality Statistical Evaluation Taylor Road Landfill - Superfund Site Hillsborough County, Florida January 1995-January 2004 (2 copies)	Vested for Processing Facility Pennis Renewal Application Southeast County Landfill	Construction Permit Application, Capacity Expansion and and Responses for Section 8, Southeast County, Landfill Historiough County, Florida-Draft Readsed Turde Board is noted State Industry Market Marie State Readsed Turde Board is noted State Industry Market Marie Marie Readsed Turde Board is noted State Industry Market Marie Marie Readsed Turde Board is noted State Industry Market Marie Marie Readsed Turde Board is Noted State Industry Marie Mar	Responses to Request for Additional Information Hillstorough County, Northewest Transfer Station Feeding Petral No. 126750-002-50	Certification of Construction Completion Report Sectional Volume Control of Control of Construction Completion Report Sectional Control of Construction Completion Report Sectional Control of Construction Completion Completion Control of Control of Control of Construction Control of Construction Control of C	Certification of Constitution Completion Regard Southeast County Landiii Capacity Espansion Section 7 Constitution Volume 1 of 3 Certification of Constitution Completion Regard Southeast County Landiii Capacity Espansion Section 7 Constitution Volume 2 of 3 Certification Constitution Expondition Regard Southeast County Landiii Capacity Espansion 3 Constitution Volume 2 of 3	Minar Permit Modification Southeast County Landfill Stormwater Basin "A" Permit No. 35435-006-SO	Appfiesten for Title VA (operation Pennit Renews) Pennit No. 0570854-001-AV Southeast County, Futura Appfiesten for Title VA (operation Pennit Renews) Pennit No. 0570854-001-AV Southeast County, Lenditll Historough County, FL	Construction Certification Report Histogrouph Heights & Taylor Read & Landfills Sciencings Utility International Construction Certification Report Histogrouph Heights & Taylor Read & Landfills Sciencing Williams (Annahur State Heights) and Construction Heights (Annahur State Height	Leachate Management Plan Southeast County Landfill (Phases I-IV) Hillsburguigh County, Florida	Operation Plan Southeast County Landill, Phasss HV and Section 7 Capacity Expansion, Hillsborough County, Florida	<u>Upterations rean soutness (Unity) Landini Prases I-VI misborough Compt. Fibrida</u> Leachaite Management Pan Southessa (Courty Landidi Hisborough County. Fibrida	Clased Landill Investigation Program Pabruary 2003	Responses to Request for Additional Information Capacity Expansion, Section 1 Southers (County Landfill Histoprough County, Florida	Cpesigos, Permi, Appisation, Capacity Expansion, Section 7, Southeast County, Landill Hillsborough County, Honda New Source Performance Standards (NEPS) Tipr 2 Sempling and Non-Methane Chronic Commount Emissions Estimate Five-Year Refest Southeast County Landill Hillsborough County New Source Performance Standards (NEPS) Tipr 2 Sempling and Non-Methane Chronic Commount Emissions Estimate Five-Year Refest Southeast County Landill Hillsborough County New Source Performance Standards (NEPS) Tipr 2 Sempling and Non-Methane Chronic County Fine Programme (New York County Landill Hillsborough County Landill Hillsborou	Operations Permit Application - Capacity Expansion, Section 7 Southeast County Landfill Hillsborough County, Florida Attachment L-1 - Operations Plan	Cantinashari Catinashari (1894) Tibibottuga Figuria dari 1990 Toda Landinis, kangini Sasa Cutino Sasari (1892) Sas	Groundwater Quality Statistical Evaluation Taylor Road Landfill - Superfued Site Histologough County, Florida January, 1995-April 2001. Construction Conferentia Common Histologough County and Conference of Confe	Contract Documents & Specifications for Capacity Expansion Section 1 Southeast County Landill, by Hillsborough County	Certification of Constitution Ceropition Report Pleasant Grow Landfill Department of Solid Weste Management Hillsborguph County, Florida Vol. 182	Hitsporough Heights and Taylor Road Landfill Sas Control System Improvements Construction Jearchite Manaverance Team East Counts Landfill Sas Control System Improvements Construction	Taylor Road Landfil Superlund Site Groundwater Quality Statistical Evaluations Hilisborough County, Florida	Remedial Action Plan Pleasant Grove Landill Histoprough County, Florida	Contract Documents 8: Sepecifications for Histologogia Heights Landial Gast Control System Improvements Contract Documents 8: Sepecifications for Gestars for Phases IV V and VI Southeast Countrol Landial Gast Countrol System Improvements Contract Documents 8: Sepecifications for Gestars for Phases IV V and VI Southeast Country Landial Contract Documents 8: Sepecifications for Gestars for Phases IV V and VI Southeast Country Landial Contract Country Landia Co	Long-term Care Permit Renewel Application Northwest Class III Landill Hillsborough County, Florida	Long-Term A come A representative professional responses and a representative professional and a representat	Welland Delination Report Southeast County Facility Proposed Class I Expension Site Long-Term Crans Demit Benesed Analysis and Taylor Report Class I Londfile Milithorough County Facility Proposed Class I Londfile Milithorough County Facility Proposed Class I Londfile Milithorough County Florids	Waste Tire Processing Fernity Operation Permit Renewal	Northwest Class III Landfill Long Term Renewal Application	Contamination Assessment Report Pleasant Grove Lendill Hillsborough County, Florida - Volume I	Contamination Assessment Report Fleasant Grove Landfil Hillsborough County, Florida Volume II Appendices (2 copies)	Description	
County County County Dept of Solid Waste		County	County	County	County	Н	County Solid Waste Mont Dent	Solid Waste Management Dept.	County	Hillsborough County	County	Hillsborough County	County		County	Dept of Solid Waste		County	h County	County		County		n County	County	County		Hillsborough County	County	n County	Hillsborough County		Hillsborough County	Hillsborough County		Hillsborough County	Hillsberough County	Hillsborough	Hillsborough	Hillsborough County	Hillsbaroug	Hillsborough County	Hillsborough County	Hillsborough County	Hillsborough County	Hillsbarough County	Hillsborough County	Ηilisborough County	Hillsborough County (2 capies)	Hillsborough County Hillsborough County	1	Hillsberough County			Hilsborough County	Hillsborough County	Hilsborough County	Count	
October 30, 1998 0996029.24 Preconstruction/Notice to Proceed Meeting August 30, 2000 09199024 12 0985027	May 2001 Revised March 2002, 09200020,11 May 2001 Revised April 2002, 09200020,11	May 2001 (Revised July 16, 2001) 09200020.11 May 2001 (Revised July 16, 2001) 09200020.21	May 2001 (Revised July 16, 2001), 09200020.11	May 2001 05200020 11	May 2001 09200020.11	May 1995 0990018.34	May 1989 09960027.11 May 1994 0996028.32	Mar 97 0995028.00	July 2001 Revised March 2002 09200020.11	January 1990 0985027.13	Jan-March 1999 0998005.00	February 1983 0985027.11 Hillsborough County 09195029.23	December 2000 09195029.25	December 1995, 0990018,43	1995 0995028.13	13-Jan-95 0993010	3. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0. 0.	17-Aug-2005, 09200020.35	05-Aug-2005 09200020.55	22-Jul-2005 09200021.77 05-Aug-2005 09200020.53	27-May-2005 09204021.11	31-Mar-2005 09200020.45	14-Mar-2005 09204021.11	30-Aug-2004 09199024 15	17-Aug-2004 09199024.25	21-Jul-2004 0928028, 15 21-Jul-2004 0928028, 14	30-Jun-2004 09199024.35	23-Jun-2004 09200020,14	19-Jan-2004 09200020-34	15-Dec-2003 09199024.25	21-0et-2003 09200020.34	21-Oct-2003 09200020.34 21-Oct-2003 09200020.34	10-Sep-2003 09200020:13	01-Aug-2003 69200020.13	77. Har 2003 09199024 14	12-May-2003 09200020 23	12-May-2003 09200020.13	15-Apr-2003 09200020.13	01-Feb-2003 09199024.34	10-Dec-2002, 99200020, 33	07-Oct-2002 09200020.12	13-Sep-2002 09200020.32	05-Aug-2002 09200020.22	31-Aug-2001 0999024.32	19-Jul-2001 09200020.32	25-May-2001 09198005.00	08-Dec-2000 09199024.12	09-Jun-2000 09198024.11	21-Feb-2000 081898005.00	02-Dec-99 0995028.73 02-Dec-99 0995029.13	16-Nov-98 0985028.24	28-Oct-99 0998024,11	26-Oct-99 0990018,55	15-Oct-99 09195029 15	29-Sep-99 0990018.64	07.4May-99 0998005.00	07-May-99 0998005.00	Project No.	

Saptemb^{*}

Ġ,







Ardaman & Associates, Inc.

Geotechnical Study Associated with 2005 Annual Monitoring of Phosphatic Clay Liner Beneath the Southeast Landfill in Hillsborough County

May 27, 2005



Ardaman & Associates, Inc.

OFFICES

Orlando, 8008 S. Orange Avenue, Orlando, Florida 32809, Phone (407) 855-3860

Bartow, 1525 Centennial Drive, Bartow, Florida 33830, Phone (863) 533-0858

Cocoa, 1300 N. Cocoa Blvd., Cocoa, Florida 32922, Phone (321) 632-2503

Fort Myers, 9970 Bayaria Road, Fort Myers, Florida 33913, Phone (239) 768-6600

Miami, 2608 W. 84th Street, Hialeah, Florida 33016, Phone (305) 825-2683

Port Charlotte, 740 Tamiami Trail, Unit 3, Port Charlotte, Florida 33954, Phone (941) 624-3393

Port St. Lucie, 460 Concourse Place NW, Unit 1, Port St. Lucie, Florida 34986, Phone (772) 878-0072

Sarasota, 2500 Bee Ridge Road, Sarasota, Florida 34239, Phone (941) 922-3526

Tallahassee, 3175 West Tharpe Street, Tallahassee, Florida 32303, Phone (850) 576-6131

Tampa, 3925 Coconut Palm Drive, Suite 115, Tampa, Florida 33619, Phone (813) 620-3389

**Yest Palm Beach, 2200 North Florida Mango Road, Suite 101, West Palm Beach, Florida 33409, Phone (561) 687-8200

MEMBERS:
A.S.F.E.
American Concrete Institute
American Society for Testing and Materials
Florida Institute of Consulting Engineers



May 27, 2005 File Number 05-010

SCS Engineers 3012 US Highway 301 North Suite 700 Tampa, FL 33619

Attention:

Mr. Joe O'Neill, P.E.

Subject:

Geotechnical Study Associated with 2005 Annual Monitoring of Phosphatic Clay Liner

Beneath the Southeast Landfill in Hillsborough County

Gentlemen:

As requested by SCS Engineers (SCS), Ardaman & Associates, Inc., (Ardaman) has completed a geotechnical study associated with annual monitoring of the phosphatic clay liner beneath the Southeast Landfill in Hillsborough County. The annual monitoring program was mandated by the Florida Department of Environmental Protection (FDEP) under Specific Condition No. 16f of the Landfill Operation Permit No. 35435-006-SO issued on June 25, 2002, which requires performance of piezocone soundings and measurements of pore water pressures in the vicinity of the following four test sites where a number of piezocone soundings and pore pressure measurements had previously been performed by Ardaman and Madrid Engineering Group, Inc., (Madrid) in 2001/2002: (i) PC-1B in the Phase I area; (ii) PC-4B/PC-4C in the Phase IV area; (iii) PC-3/PC-3B in the Phase III area; and (iv) PC-1F in the Phase I area. Specifically, the permit condition required documentation and interpretation of the following data:

- Piezometric elevations in the drainage sand layer above the phosphatic clay.
- Top and bottom elevations of the phosphatic clay layer.
- Pore water pressures near the top, middle, and bottom of the phosphatic clay layer.
- Piezometric elevations in the natural soils below the phosphatic clay.

Evaluations of the phosphatic clay liner in 2003 and 2004 were documented in two Ardaman reports dated April 12, 2003 and April 15, 2004. This report contains the results of the piezocone soundings and pore pressure measurements obtained by Ardaman in March and April 2005, and presents our interpretation of the test data.

For this year, in addition to the four test sites in the Phase I, III, and IV areas required by the FDEP permit, SCS requested Ardaman to perform an electric Dutch cone sounding at a test site in the Phase VI area for the sole purpose of determining the top elevation of the phosphatic clay.

Site Location

The Southeast Landfill is located within Sections 14, 15, 22, and 23 of Township 31 South, Range 21 East, in Hillsborough County, Florida. More specifically, the landfill site is located between

Picnic and Pinecrest, about 2 miles west of State Road 39 and about 0.5 miles north of County Road 672. The approximate site location, as superimposed on a reproduction of the United States Geological Survey (USGS) quadrangle map of Lithia, Florida (1955, photorevised 1987), is shown in Figure 1.

Project History

The Southeast Landfill is constructed directly above a waste clay settling area at a former phosphate mine known as Lonesome Phosphate Mine or Boyette Mine. The settling area, also known as Settling Area No. 1, was built on natural ground within a perimeter dike constructed of sand borrowed from surrounding areas. Waste phosphatic clay was deposited within the settling area for a number of years during the mining operation.

A comprehensive geotechnical study was conducted by Ardaman between 1981 and 1983 to characterize the phosphatic clay deposit and to evaluate the feasibility of constructing a landfill within the waste clay settling area. Results from that study were documented in an Ardaman report titled "Hydrogeological Investigation, Southeast County Landfill, Hillsborough County, Florida", dated February 22, 1983. Based on the data and analyses documented in that report, Ardaman concluded that a landfill could be constructed directly on top of the phosphatic clay. However, to maintain an adequate factor of safety against slope failure, the waste disposal area was divided into different phases, and each phase had to be filled in lifts such that filling above a previous lift would occur only when the underlying phosphatic clay had consolidated under the weight of the previous refuse lift and experienced sufficient increase in shear strength to support the additional load. In areas where the clay thickness was greater than 14 feet, it was recommended that the clay should be pre-loaded prior to placement of the first lift of refuse. A diagram that shows the original thickness of the phosphatic clay within the settling area, as reproduced from the 1983 Ardaman report, is shown in Figure 2. As shown, the phosphatic clay deposit had an original thickness that varied between 4 and 18 feet.

Another comprehensive geotechnical study was completed by Ardaman in 1994 in association with operation permit renewal for the Southeast Landfill. Results from that study were documented in an Ardaman report titled "Geotechnical Investigation at Southeast Landfill, Hillsborough County, Florida", dated March 7, 1994. The strength and consolidation properties of the phosphatic clay obtained from that study were in good agreement with those used in the original stability analyses and affirmed the recommended filling schedule.

In support of the last operation permit renewal application in 2002, SCS retained Madrid and Ardaman to perform supplemental studies to confirm the engineering properties of the phosphatic clay, and to determine whether the material had been consolidating and gaining strength as predicted and whether the 7-year waiting period for placements of successive refuse lifts in the landfill should be modified. Results from the latest study were presented in an Ardaman report titled "Geotechnical Study Associated with Operation Permit Renewal for Hillsborough County Southeast Landfill", dated March 4, 2002.

The original geotechnical investigation completed in 1983 and the follow-up studies completed in 1994 and 2002 recommended that each lift of refuse should have a thickness no greater than 20 feet and that a minimum waiting period of 7 years should be provided between placements of successive refuse lifts. These requirements were derived based on stability analyses using an undrained shear strength to effective vertical stress ratio of 0.21 and a coefficient of consolidation

of 1.5x10⁻⁴ cm²/sec for the waste phosphatic clay. The undrained shear strength to effective vertical stress ratio determines the magnitude of strength increase in the phosphatic clay, whereas the coefficient of consolidation governs the rate of strength increase.

Field Test Program

Current operation at the Southeast Landfill divides the waste disposal area into six phases designated Phases I through VI, as shown on a topographic site plan in Figure 3. The topographic site plan was generated from survey data obtained on January 18, 2005. As part of our scope of work for the annual monitoring program stipulated in Specific Condition No. 16f of the FDEP Permit No. 35435-006-SO issued on June 25, 2002, Ardaman performed piezocone soundings and pore water pressure measurements at four test sites within the Phase I, III, and IV areas where a number of field tests and measurements had previously been performed by Madrid and Ardaman in 2001/2002.

Four test sites, designated PC-1K, PC-1L, PC-3E, and PC-4F, were selected by SCS for performance of piezocone soundings and installation of piezoprobes. The approximate locations of these test sites are shown in Figure 3 along with the test site locations selected in the 2001/2002 studies performed by Madrid and Ardaman as well as the test site locations selected for the 2003 and 2004 annual monitoring programs. As shown in Figure 3, two of the four test sites were located in the Phase I area (i.e., PC-1K and PC-1L), one test site was located within the Phase III area (i.e., PC-3E), and the remaining test site was located within the Phase IV area (i.e., PC-4F). PC-1K was located in close proximity to the previous PC-1B, PC-1H, and PC-1J test site locations, and PC-1L was selected adjacent to the previous PC-3B, and PC-3D test site locations. PC-4F was selected adjacent to the PC-4E test site location used in the 2004 annual monitoring program. The current field work and testing were undertaken by Ardaman in March and April 2005.

For this year, in addition to performance of piezocone soundings and installation of piezoprobes at the above four test sites, SCS also requested the performance of an electric Dutch Cone sounding at a test site designated PC-6F in the Phase VI area for the sole purpose of determining the top elevation of the phosphatic clay layer.

The surveyed coordinates and ground surface elevations at the current test site locations, as provided by Pickett & Associates, Inc., are summarized in Table 1. The elevations were surveyed using both the NGVD29 and NGVD88 datums. Although Hillsborough County mostly uses the NGVD88 datum for elevation data, the elevation data used in the previous geotechnical studies were based on the NGVD29 datum. For ease of data comparisons, the elevations based on the NGVD29 datum are used in this report.

Piezocone Penetration Tests

The piezocone consists of a conical point attached to a steel rod and a friction sleeve. The test is performed by pushing the assembly into the soil at a constant rate of penetration. Resistance to penetration at the cone tip and on the friction sleeve are measured by load cells placed within the assembly, and the pore pressure in the soil is measured using a pressure transducer connected to the porous element placed near the cone tip. Prior to pushing of the piezocone through the waste phosphatic clay, a hollow stem auger was used to create a borehole through the refuse.

Results of the four piezocone penetration tests (i.e., PC-1K, PC-1L, PC-3E, and PC-4F) performed at the four test site locations are presented in Figures 4 through 7, respectively. As shown in the figures, results are presented in the form of tip resistance (i.e., the resistance to penetration at the cone tip), sleeve resistance (i.e., the resistance to penetration of the friction sleeve), pore pressure (i.e., the total pore water pressure including the pore pressure generated due to penetration of the cone), friction ratio (i.e., the ratio of sleeve resistance to tip resistance), soil type (i.e., soil classification), and approximate standard penetration test blow count values (i.e., SPT N values) versus depth.

Since sandy soils typically exist above and below the phosphatic clay, the depth and thickness of the phosphatic clay layer could be inferred by examining the variations of tip resistance and pore pressure with depth. The tip resistance and the pore pressure in a clayey soil are expected to be lower and higher, respectively, than those in a sandy soil. Higher friction ratios are generally indicative of clayey soil types, whereas lower ratios generally indicate the presence of silty and sandy soils. Sudden changes in tip resistance, pore pressure, and friction ratio are expected to occur at the interface between the drainage sand layer and the underlying phosphatic clay as well as the interface between the phosphatic clay and the underlying natural sandy soils.

Thickness of Refuse

Based on results of the auger borings and piezocone soundings, the refuse thicknesses at the four test sites (i.e., PC-1K, PC-1L, PC-3E, and PC-4F) in March 2005 ranged from approximately 35 feet at PC-3E to 65 feet at PC-1L.

PC-1K was located in the western portion of the Phase I area. The refuse thickness at PC-1K in March 2005 was estimated to be 50 feet, compared to a refuse thickness of 65 feet at PC-1J in March 2004 and a refuse thickness of 50 to 55 feet at PC-1H in March 2003. The reason for the variation in refuse thickness was because the test sites were not at identical locations. PC-1K was located approximately 110 feet northwest of PC-1J and at the toe of slope between the Phase I and IV areas. The land surface elevation at PC-1K was approximately 14 feet lower than the land surface elevation at PC-1J, but was very close to the land surface elevation at PC-1H.

PC-1L was located in the eastern portion of the Phase I area. The refuse thickness at PC-1L in March 2005 was estimated to be 65 feet, compared to a refuse thickness of 50 feet at the nearby PC-1I in March 2004 and a refuse thickness of 50 to 55 feet at the nearby PC-1G in March 2003.

The refuse thickness at PC-3E in March 2005 was approximately 35 feet. We understand that the refuse thickness in the Phase III area has remained approximately the same since 2001/2002.

The refuse thickness at PC-4F in March 2005 was slightly greater than 60 feet, compared to a refuse thickness of slightly greater than 50 feet at PC-4E in March 2004 and at PC-4D in March 2003. We understand that refuse was last placed near these test site locations in the Phase IV area in March/April 2003.

Filling Schedule

In March 2005, refuse was being placed in the Phase II area. The filling originated in the Phase I area that began in March 2003 and progressed from west to east towards the Phase II area. Filling occurred in the vicinity of PC-1K around June 2003 and in the vicinity of PC-1L around July

2004. A comparison of the surveyed data in the Phase I area indicated that the thickness of the refuse lift was approximately 16 to 17 feet. The previous refuse lift in the Phase I area was completed in August 1997.

Filling of the Phase III area began in December 1990 and ended in June 1994. In the Phase IV area, approximately 13 feet of refuse was placed in the vicinity of PC-4F in March/April 2003 (i.e., just prior to filling of the Phase I area).

Elevations and Thicknesses of Phosphatic Clay

Prior to landfill construction, the surface of the waste phosphatic clay within the former settling area was documented to have typical elevations in the range of +121 to +123 feet (NGVD), and the bottom of the phosphatic clay reportedly occurred at typical elevations ranging from +103 to +117 feet (NGVD). As indicated previously, the original thickness of the phosphatic clay ranged from 4 to 18 feet.

Based on results of the piezocone soundings, the top and bottom elevations of the phosphatic clay as well as the phosphatic clay thickness encountered at the four test sites are summarized in Table 2. As shown, the top elevations of the phosphatic clay ranged from a low of +110.7 feet (NGVD) at PC-1K to a high of +118.7 feet (NGVD) at PC-3E. The bottom elevations of the phosphatic clay layer ranged from a low of +103.3 feet (NGVD) at PC-1K to a high of +112.9 feet (NGVD) at PC-1L.

At the location of PC-1K, the top and bottom of the phosphatic clay layer were encountered at approximately +110.7 and +103.3 feet (NGVD), respectively, for a clay thickness of about 7.4 feet. This thickness was approximately 1.2 feet greater than the clay thickness (6.2 feet) documented at PC-1J in March 2004. As indicated previously, approximately 17 feet of refuse was placed in the vicinity of PC-1K in June 2003. Because the PC-1K test site in 2005 was located about 110 feet from the PC-1J test site in 2004, the apparent difference could be a result of variation of phosphate clay thickness between the two test sites.

Based on the piezocone sounding performed at the location of PC-1L, the phosphatic clay had top and bottom elevations of +116.9 and +112.9 feet (NGVD), respectively, for a phosphatic clay thickness of 4.0 feet, which is close to the thickness (3.6 feet) documented at the nearby PC-1I in 2004. As indicated previously, approximately 17 feet of refuse was placed in the vicinity of PC-1L in July 2004.

The piezocone sounding performed at the location of PC-3E revealed the top elevation of the phosphatic clay at +118.7 feet (NGVD) and the bottom elevation at +110.3 feet (NGVD), for a clay thickness of 8.3 feet, which is very close to the thickness (8.0 feet) documented at the nearby PC-3D test site in 2004. As indicated previously, no refuse has been placed in the Phase III area since June 1994.

Based on the piezocone sounding performed at the location of PC-4F, the top and bottom elevations of the phosphatic clay were documented at +113.7 and +106.8 feet (NGVD), for a clay thickness of 6.9 feet, which is 2.9 feet less than the thickness (9.8 feet) documented at the nearby PC-4E test site in 2004. As noted previously, approximately 13 feet of refuse was added at this location in April 2003.

In summary, the phosphatic clay elevations and thicknesses documented at the four test sites in 2005 (i.e., PC-1K, PC-1L, PC-3E, and PC-4F) indicated that there were minimal changes in clay thickness from March 2004 to March 2005 at the locations of PC-1L and PC-3E. The apparent increase in clay thickness at PC-1K from 2004 to 2005 could be attributed to variation of clay thickness between the 2004 and 2005 test sites. The observed decrease in phosphatic clay layer thickness at PC-4F from March 2004 to March 2005 (about 3 feet) could be attributed to compression of the phosphatic clay layer by refuse loading. However, it could also be a result of variation of phosphatic clay thickness between the test sites in 2004 and 2005.

Piezometric Elevations on Top of Phosphatic Clay

The piezometric heads in the drainage sand layer on top of the phosphatic clay could be inferred from the piezocone penetration test results. As the piezocone was pushed through the drainage sand layer on top of the phosphatic clay, it was held stationary at selected depths to allow the excess pore water pressure generated as a result of pushing of the piezocone to stabilize. Because of the relatively high permeability of the sand, any excess pore pressure should dissipate in a short duration. The pore pressures were monitored for several minutes to make sure that the final readings represented the stabilized pore pressures at the selected depths.

Based on the piezocone soundings performed at the four test sites, the piezometric heads in the drainage sand layer on top of the phosphatic clay are summarized in Table 3 and are further displayed in Figure 8. Piezometric heads documented from previous studies are also shown on the same figure for comparisons.

As shown in Table 3 and Figure 8, results of the piezocone soundings indicated that the piezometric heads on top of the phosphatic clay at the four test site locations ranged from 6.6 to 8.8 feet. The highest piezometric elevation of +125.3 feet (NGVD) was observed at PC-3E (i.e., 6.6 feet above the top of the phosphatic clay). The piezometric heads in the drainage sand on top of the phosphatic clay at PC-1K, PC-1L, and PC-4F were measured to be 8.8, 7.2 and 6.9 feet above the top of the phosphatic clay, respectively. On the average, the piezometric heads in the drainage sand layer in March 2005 were approximately 3 feet higher than the previous readings obtained in March 2004 and March 2003.

Piezometric Elevations Below Phosphatic Clay

Based on the piezocone sounding results, the piezometric elevations in the natural soils below the phosphatic clay are summarized in Table 4. As shown, the piezometric elevations at the test site locations were documented at approximately +118 to +122 feet (NGVD). These piezometric elevations were generally in good agreement with those obtained in March 2004 and March 2003.

Piezoprobe Tests Within Phosphatic Clay

The piezoprobe tests were performed by installing piezoprobes to pre-selected depths and holding them stationary until the excess pore pressure generated from probe penetration completely dissipated, and the measured pore pressure reached the actual pore pressure before probe penetration.

The dissipation of excess pore pressures generated due to probe penetrations are presented in Figures 9 to 12 in the form of normalized excess pore pressure (i.e., the ratio of excess pore water

pressure at any time to the initial excess pore water pressure immediately after piezoprobe penetration) versus time. As shown in the figures, all pore pressures reached equilibrium conditions at the end of the monitoring periods. The rate of dissipation of excess pore pressure generated by probe penetration can be used to estimate the *in situ* coefficient of consolidation of the phosphatic clay.

At the locations of PC-1K, PC-3E, and PC-4F with approximately 7 to 8 feet of phosphatic clay, piezoprobe tests were performed at three different depths to measure the pore pressures near the top, middle, and bottom of the phosphatic clay layer. Because of the limited phosphatic clay thickness at PC-1L (4 feet), only one piezoprobe was installed. Results from the piezoprobe tests are summarized in Table 5.

At the location of PC-1K, the equilibrium piezometric elevations for the three piezoprobes installed with tip elevations at +109.3, +107.2 and +105.2 feet (NGVD) were documented to be approximately +130.4, +135.4 and +132.0 feet (NGVD), respectively. The excess pore water pressures within the phosphatic clay layer at the tip elevations were estimated to be 10.4, 14.9 and 10.8 feet of water, respectively. As indicated previously, approximately 17 feet of refuse was placed in the vicinity of PC-1K in June 2003.

At the location of PC-1L, one piezoprobe test was performed with the piezoprobe tip elevation at +115.7 feet (NGVD). The piezometric elevation at that depth was documented to be +129.5 feet (NGVD), corresponding to an excess pore water pressure that is equivalent to approximately 7.1 feet of water. As indicated previously, approximately 17 feet of refuse was placed in the vicinity of PC-1L in July 2004. Because the phosphatic clay thickness at PC-1L (4.0 feet) was less than that at PC-1K (7.4 feet), the excess pore water pressure from refuse loading would have dissipated at a faster rate.

At the location of PC-3E, three piezoprobe tests were performed within the phosphatic clay layer with the piezoprobe tip elevations at +116.7, +114.7 and +112.7 feet (NGVD). The excess pore water pressures documented by the piezoprobes were equivalent to only 0.2 to 1.8 feet of water. This is not unexpected since there has been no refuse placed in the Phase III area since July 1994.

At the location of PC-4F, three piezoprobe tests were performed within the phosphatic clay layer with the piezoprobe tip elevations at +111.9, +110.2 and +108.4 feet (NGVD) with the equilibrium piezometric elevations at +124.7, +124.9 and +124.5 feet (NGVD), respectively. The excess pore water pressures near the top, middle, and bottom of the phosphatic clay were equivalent to 19.4, 29.0 and 31.9 feet of water, respectively. High excess pore water pressures were also observed in the Phase IV area in previous piezoprobe measurements in 2003 and 2004. The high excess pore water pressures could be attributed to refuse loading in the Phase IV area. As noted previously, approximately 13 feet of refuse was added in the vicinity of PC-4F in April 2003.

Coefficient of Consolidation

The coefficient of consolidation governs the rate of strength increase in the phosphatic clay upon loading from a refuse lift and thus the waiting period between placement of successive refuse lifts in an area. The filling schedule at the Southeast Landfill was originally based on a design vertical coefficient of consolidation, c_v , of 1.5×10^{-4} cm²/sec.

Based on the rates of excess pore pressure dissipation shown in Figures 9 through 12, the horizontal coefficients of consolidation, c_h , of the phosphatic clay obtained from the piezoprobe tests were calculated and are presented in Table 6. The *in situ* vertical coefficients of consolidation, c_v , can be estimated from the horizontal coefficients of consolidation, c_h , based on the following empirical relationship proposed by Baligh, M. et al (ASCE Journal of Geotechnical Engineering, Vol. 112, No. 7, July, 1986): $c_v = 0.05 \times c_h$, and are also presented in Table 6.

The *in situ* vertical coefficients of consolidation from the piezoprobe measurement at PC-1L and the piezoprobe measurements at the top of the phosphatic clay layer at PC-1K and PC-3E indicated an average c_v value of 1.7x10⁻⁴ cm²/sec, which is close to the design vertical coefficient of consolidation. However, the *in situ* vertical coefficients of consolidation from the piezoprobe measurements at mid-depth and bottom of the phosphatic clay layer at PC-1K and PC-3E had an average c_v value of 3.1x10⁻⁵ cm²/sec. The c_v values of the phosphatic clay layer at PC-4F averaged 2.8x10⁻⁵ cm²/sec for the three measurements at different depths.

Although the vertical coefficients of consolidation documented at the middle and bottom of PC-1K and PC-3E were lower than the original design value of 1.5×10^{-4} cm/sec, the piezoprobe measurements in 2003 and 2004 at nearby test sites had vertical coefficients of consolidation that were consistent with the design value. Because the Phase I area has just been recently loaded and no significant excess pore water pressure was observed in the phosphatic clay within the Phase III area, the lower vertical coefficients of consolidation documented in 2005 should not be an issue at this time. At PC-4F, because low vertical coefficients of consolidation were also documented at the nearby test site in 2004, Ardaman recommends performance of additional field tests to measure the undrained shear strength of the clay or any excess pore water pressure in the phosphatic clay prior to placement of the next lift of refuse in the Phase IV area.

Settlement plate data at the location of Pump Station B in the Phase VI area, as provided by Hillsborough County, are plotted in Figure 13. At this location, the initial thickness of the phosphatic clay was approximately 13 feet. As shown in Figure 13, the phosphatic clay has undergone a settlement of about 4 feet over a period of 5 years. Assuming that an average degree of consolidation of 95% has been reached under double drainage condition with an average consolidating thickness of 11 feet, the backalculated c_v from the settlement observations is 2.0x10⁻⁴ cm²/sec, which is consistent with the design value.

Comparisons of Piezometric Heads

The piezometric elevations in the materials directly above and below the phosphatic clay layer, as documented from the piezocone soundings, are summarized in Table 7. The piezometric heads within the phosphatic clay layer are also shown on the same table for comparison.

The piezometric head within the phosphatic clay will be highest after loading of a new refuse lift and will decrease gradually as excess pore water pressure dissipates. If the piezometric head within the phosphatic clay is higher than the piezometric head on top of the phosphatic clay, there will be no downward migration of leachate. Once the excess pore water pressure from landfill loading dissipates, the flow direction through the phosphatic clay will be a function of the piezometric head difference across the phosphatic clay. If the piezometric elevation in the natural soils below the phosphatic clay is higher than the piezometric elevation on top of the phosphatic clay, upward flow will occur. Conversely, if the piezometric elevation in the natural soils is lower than the piezometric elevation on top of the phosphatic clay, leachate will migrate downward, at a rate governed by the

piezometric head difference, and the hydraulic conductivity and thickness of the phosphatic clay deposit.

As shown in Table 7, the existing maximum piezometric heads within the phosphatic clay layer are higher than the piezometric heads in the materials above and below the phosphatic clay at the PC-1K, PC-1L, and PC-4F test site locations. Accordingly, under existing condition, there should be no downward leachate migration or upward groundwater flow through the phosphatic clay layer at these locations. At the PC-3E test site location, the piezometric elevation on top of the phosphatic clay layer is slightly higher than the maximum piezometric head within the phosphatic clay and the piezometric head in the material below the phosphatic clay. This condition will result in downward leachate flow. However, the flow is not expected to be significant considering the thickness of the phosphatic clay layer (8 feet), the relatively small hydraulic head (< 4 feet), and the low hydraulic conductivity of the phosphatic clay material (< 1x10-8 cm/sec).

Electric Dutch Cone Sounding in Phase VI Area

For this year, SCS requested Ardaman to perform an electric Dutch cone sounding at a test site designated PC-6F in the Phase VI area for the sole purpose of determining the elevation at the top of the phosphatic clay. Results of the Dutch cone sounding test are presented in Figure 14. As shown in the figure, results are presented in the form of tip resistance (i.e., the resistance to penetration at the cone tip), sleeve resistance (i.e., the resistance to penetration of the friction sleeve), friction ratio (i.e., the ratio of sleeve resistance to tip resistance), soil type (i.e., soil classification), and approximate standard penetration test blow count values (i.e., SPT N values) versus depth. As shown in Table 2, the top of the phosphatic clay was encountered at a depth of 52.0 feet. The elevation of ground surface at the test location was at +167.31 feet (NGVD), and the top of the phosphatic clay was at elevation +115.3 feet (NGVD).

Summary of Observations

The following key observations were made from the 2005 annual monitoring data based on the field work completed:

- The refuse surface elevations increased by 17 and 13 feet compared to March 2004 at test locations PC-1L and PC-4F, respectively. At test location PC-3E, the existing grade remained unchanged. At test location PC-1K, the refuse elevation was about the same as test location PC-1H in 2003.
- The top elevations of the phosphatic clay were as expected and generally consistent with the data obtained in 2004.
- The thicknesses of the phosphatic clay were also generally consistent with the data obtained in 2004. The phosphatic clay thickness at PC-1K, PC-1L, and PC-3E were found to be higher by 1.2, 0.4 and 0.3 feet, respectively, compared to the thicknesses estimated in 2004. At PC-4F, the clay thickness was 2.9 feet less than that observed in PC-4E in 2004. The observed decrease in phosphatic clay layer thickness at PC-4F from March 2004 to March 2005 could be attributed to compression of the phosphatic clay layer by refuse loading. However, it could also be a result of variation of phosphatic clay thickness between the test sites in 2004 and 2005.

- A considerable amount of excess pore pressure was documented within the phosphatic clay layer at PC-1L, PC-1K, and especially PC-4F. Because these areas have been loaded recently, the excess pore pressure was not unexpected. There were minimal excess pore pressure documented within the phosphatic clay at PC-3E.
- The piezometric heads above the phosphatic clay at the PC-1K, PC-1L, PC-3E, and PC-4F test site locations were measured to be 8.8, 7.2, 6.6 and 6.9 feet, respectively. On the average, these measurements were about 3 feet higher than the readings obtained in 2004.
- The piezometric elevations below the phosphatic clay were observed to be at approximately +118 to +122 feet (NGVD). These elevations are similar to those observed in 2003 and 2004.

Recommendation

High excess pore water pressures at PC-4F were recorded but are not unexpected due to recent refuse placement in this area. However, because of the lower than expected coefficients of consolidation documented at different depths of the phosphatic clay layer at PC-4F, additional field tests should be performed to measure the undrained shear strength of the clay or any excess pore water pressure in the clay prior to placement of the next lift of refuse. For all other areas, the 7-year waiting period between placement of successive refuse lifts remain valid.

Closure

This report has been prepared for the exclusive use of SCS and the Hillsborough County Solid Waste Department for specific application to annual monitoring of the phosphatic clay liner at the Southeast Landfill in accordance with generally accepted geotechnical engineering practice. No other warranty, expressed or implied, is made.

Ardaman appreciates the opportunity to assist you on this project. Please contact us if you have any questions concerning this report or need additional information.

Very truly yours,

ARDAMAN & ASSOCIATES, INC.

Shawkat Ke' Shawkat Ali, Ph.D., P.E.

Project Engineer

Francis K. Cheung, P.E.

Senior Project Manager

Florida License No. 36382

Enclosures




Table 1

Test Site Locations and Elevations

Test		State Plan C	Coordinates	Approx Ground Surf	face Elevations (feet)
Site	Area	Northing	Easting	NGVD29	NGVD88
PC-1K	Phase I	1,250,443.55	595,886.47	+163.53	+162.62
PC-1L	Phase I	1,249,916.34	597,283.83	+188.66	+187.75
PC-3E	Phase III	1,251,089.80	597,409.63	+154.67	+153.76
PC-4F	Phase IV	1,250,656.68	596,423.09	+178.15	+177.24
PC-6F	Phase VI	1,250,983.97	596,262.97	+167.31	+166.40

Table 2

Top and Bottom Elevations of Phosphatic Clay

			Approx Ground	Тор	of Clay	Bottom	of Clay	Clay
Area	Test Site	Date	Surface Elevation (ft, NGVD)	Depth (ft, BLS)	Elevation (ft, NGVD)	Depth (ft, BLS)	Elevation (ft, NGVD)	Thickness (ft)
	PC-1K	03/14/05	+163.53	52.8	+110.7	60.2	+103.3	7.4
Phase I	PC-1L	03/16/05	+188.66	71.8	+116.9	75.8	+112.9	4.0
Phase III	PC-3E	03/11/05	+154.67	36.0	+118.7	44.3	+110.3	8.3
Phase IV	PC-4F	03/09/05	+178.15	64.5	+113.7	71.4	+106.8	6.9
Phase VI	PC-6F	03/03/05	+167.31	52.0	+115.3			

Table 3

Piezometric Levels on Top of Phosphatic Clay

Area	Test Site	Date	Ground Surface Elevation (ft, NGVD)	Piezometric Elevation on Top of Phosphatic Clay (ft, NGVD)	Top of Clay Elevation (ft, NGVD)	Piezometric Head on Top of Phosphatic Clay (ft)
	PC-1K	04/14/05	+163.53	+119.5	+110.73	8.8
Phase I	PC-1L	04/12/05	+188.66	+124.2	+116.9	7.2
Phase III	PC-3E	04/14/05	+154.67	+125.3	+118.7	6.6
Phase IV	PC-4F	04/14/05	+178.15	+119.5	+113.7	6.9

Table 4

Piezometric Elevations Below Phosphatic Clay

Area	Test Site	Date	Ground Surface Elevation (ft. NGVD)	Piezometric Elevation Below Phosphatic Clay (ft, NGVD)
	PC-1K	03/14/05	+163.53	+121.7
Phase I	PC-1L	04/18/05	+188.66	+118.3
Phase III	PC-3E	04/25/05	+154.67	+121.8
Phase IV	PC-4F	03/09/05	+178.15	+118.4

Table 5

Pore Pressures Within Phosphatic Clay

Area	Test Site	Ground Surface Elevation (ft, NGVD)	Top of Clay Elevation (ft, NGVD)	Bottom of Clay Elevation (ft, NGVD)	Piezoprobe Designation	Piezoprobe Tip Below Ground Surface (ft)	Elevation of Piezoprobe Tip (ft, NGVD)	Stabilized Pore Pressure at Piezoprobe Tip After Dissipation (ft of H ₂ O)	Piezometric Elevation at Piezoprobe Tip Level (ff, NGVD)	Piezometric Elevation on Top of Clay (ft, NGVD)	Piezometric Elevation Below Clay (ft, NGVD)	Excess Pore Pressure at Piezoprobe Tip Level (ft of H ₂ O)
Phase I	PC-1K	+163.53	+110.7	+103.3	PC-1K	54.2 56.3 58.3	+109.3 +107.2 +105.2	21.1 28.2 26.7	+130.4 +135.4 +132.0	+119.5	+121.7	10.4 14.9 10.8
	PC-1L	+188.66	+116.9	+112.9	PC-1L	73.0	+115.7	13.8	+129.5	+124.2*	+118.2	7.1
Phase III	PC-3E	+154.67	+118.7	+121.2	PC-3E	38.0 40.0 42.0	+116.7 +114.7 +112.7	8.0 10.2 11.87	+124.7 +124.9 +124.5	+125.3	+121.8	0.2
Phase IV	PC-4F	+1178.15	+113.7	+106.8	PC-4E	66.3 68.0 69.8	+111.9 +110.2 +108.4	26.7 37.8 42.2	+138.6 +148.0 +150.6	+119.5	+118.5	19.4 29.0 31.9

Table 6


Computed Coefficients of Consolidation from Piezoprobe Tests


Area	Test Site	Piezoprobe Designation	Piezoprobe Tip Depth Below Ground Surface (ft)	Elevation of Piezoprobe Tip (ft, NGVD)	Horizontal Coefficient of Consolidation, c _h (cm²/sec)	Vertical Coefficient of Consolidation, c _v * (cm²/sec)
Phase I	PC-1K	PC-1K	54.2 56.3 58.3	+109.3 +107.2 +105.2	3.0x10 ⁻³ 6.6x10 ⁻⁴ 5.8x10 ⁻⁴	1.5x10 ⁻⁴ 3.2x10 ⁻⁵ 2.9x10 ⁻⁵
	PC-1L	PC-1L	73.0	+115.7	2.6x10 ⁻³	1.3x10 ⁻⁴
Phase III	PC-3E	PC-3E	38.0 400 42.0	+116.7 +114.7 +112.7	4.9x10 ⁻³ 7.8x10 ⁻⁴ 4.8x10 ⁻⁴	2.4x10 ⁻⁴ 3.8x10 ⁻⁵ 2.3x10 ⁻⁵
Phase IV	PC-4F	PC-4F	66.3 68.0 69.8	+111.9 +110.2 +108.4	9.2x10 ⁻⁴ 3.4x10 ⁻⁴ 4.5x10 ⁻⁴	4.5x10 ⁻⁵ 1.7x10 ⁻⁵ 2.2x10 ⁻⁵
* c, using	empirical re	lationship recom	mended by Baligh	n et al., 1986.		


Table 7

Comparisons of Piezometric Elevations

Area	Test Site	Date	Ground Surface Elevation (ft, NGVD)	Piezometric Elevation on Top of Phosphatic Clay (ft, NGVD)	Existing Maximum Piezometric Elevation Within Clay (ft, NGVD)	Piezometric Elevation Below Phosphatic Clay (ft, NGVD)	Location of Existing Maximum Head
Dhace 1	PC-1K	04/14/05	+163.53	+119.5	+135.5	+121.7	Within Clay
11436	PC-1[04/12/05	+188.66	+124.2	+129.5	+118.3	Within Clay
Phase III	PC-3E	04/14/05	+154.67	+125.3	+124.9	+121.8	Above Clay
Phase IV	PC-4F	04/14/05	+178.15	+119.5	+150.6	+118.4	Within Clay








THICKNESS OF PHOSPHATIC CLAY BEFORE LANDFILL CONSTRUCTION




Ardaman & Associates, inc Geotechnical, Environmental and Materials Consultants

GEOTECHNICAL STUDY ASSOCIATED WITH ANNUAL MONITORING SOUTHEAST LANDFILL HILLSBOROUGH COUNTY, FLORIDA

DRAWN BY: BT	Ŵ	CHECKED	SY:	5A-	DATE	05/16/05	_
FILE NO.	AP.	PROVED E	/ 1	tarc.		FICURE:	





Soil I.D. #	Soil Description	ucs
1	Sensitive Fine Grained	OH/CH
2	Organic Material	ОН
3	Clay	СН
4	Silty Clay to Clay	CL/MH
5	Clayey Silt to Silty Clay	MH/CL
6	Silty Sand to Sandy Silt	SC

Soil I.D. #	Soil Description	ucs
7	Sand to Sandy Silt	SP/SC
8	Sand to Silty Sand	SP
9	Sand	SP/SW
10	Gravelly Sand to Sand	SP/GW
11	Very Stiff Fine Grained	OC Clay
12	Sand to Clayey Sand	Cemented

TEST SITE: PC-1K

SOUNDING DATE

3/14/05

SURFACE ELEVATION (FT, NGVD) 163.53

COORDINATE LOCATION (FT)

N 1,250,443.55

E 595,886.47

Ardaman & Associates, Inc.
Piezocone Test Results


GEOTECHNICAL STUDY ASSOCIATED
WITH ANNUAL MONITORING

SOUTHEAST LANDFILL
HILLSBOROUGH COUNTY, FL

DRAWN BY: SA CHECKED BY: SA DATE: 05-16-05

FILE NO.: 05-010 APPROVED BY: FICE FIGURE: 4

Soil Classification by Robertson et al., 1986



Sail I.D. #	Soil Description	ucs
1	Sensitive Fine Grained	OH/CH
2	Organic Material	ОН
3	Clay	сн
4	Silty Clay to Clay	CL/MH
5	Clayey Silt to Silty Clay	MH/CL
6	Silty Sand to Sandy Silt	sc

Soil I.D. #	Soil Description	ucs
7	Sand to Sandy Sift	SP/SC
8	Sand to Silty Sand	SP
9	Sand	SP/SW
10	Gravelly Sand to Sand	SP/GW
11	Very Stiff Fine Grained	OC Clay
12	Sand to Clayey Sand	Cemented

TEST SITE: PC-1L

SOUNDING DATE 3/16/05

SURFACE ELEVATION (FT, NGVD) 188.66

COORDINATE LOCATION (FT) N 1,249,916.34


E 597,283.83




Ardaman & Associates, Inc. Piezocone Test Results

GEOTECHNICAL STUDY ASSOCIATED WITH ANNUAL MONITORING

Soil Classification by Robertson et al., 1986





Silty Sand to Sandy Silt


Soil Classification by Robertson et al., 1986


Sand to Clayey Sand

Cemented

DRAWN BY: SA CHECKEO BY: SA DATE: 05-16-05
FILE NO: 05-010 APPROVED BY: FIGURE: 7

E 596,423.09






EXCESS PORE PRESSURE DISSIPATION PIEZOPROBE AT TEST LOCATION PC-1K


Ardaman & Associates, Inc.
Geotechnical, Environmental and
Materials Consultants GEOTECHNICAL STUDY ASSOCIATED


WITH ANNUAL MONITORING SOUTHEAST LANDFILL HILLSBOROUGH COUNTY, FLORIDA

DRAWN BY: S	Ą	CHECKED BY:	SA	DATE	05-16-03
FLE NO.: 05-010	APPI	ROVED BY:	teco		FIOURE: 9



EXCESS PORE PRESSURE DISSIPATION PIEZOPROBE AT TEST LOCATION PC-1L






EXCESS PORE PRESSURE DISSIPATION PIEZOPROBE AT TEST LOCATION PC-3E




Ardaman & Associates, Inc.
Geotechnical, Environmental and
Materials Consultants

GEOTECHNICAL STUDY ASSOCIATED WITH ANNUAL MONITORING SOUTHEAST LANDFILL HILLSBOROUGH COUNTY, FLORIDA


DRAWNBY: S	A	CHECKED BY:	SA	DATE	05-16-03
FILE NO.: 05-010	APPI	POVED BY: F	w		FIGURE: 11



EXCESS PORE PRESSURE DISSIPATION PIEZOPROBE AT TEST LOCATION PC-4F




Fills, day




SETTLEMENT VERSUS TIME

SETTLEMENT OF TOP OF PHOSPHATIC CLAY AT PUMP STATION B SUMP



05-010



Soil I.D. #	Soil Description	ucs
1	Sensitive Fine Grained	OH/CH
2	Organic Material	он
3	Clay	СН
4	Silty Clay to Clay	CUMH
5	Clayey Silt to Silty Clay	MH/CL
6	Silty Sand to Sandy Silt	sc

Soil l.D.#	Soil Description	ucs	
7	7 Sand to Sandy Silt		
8	Sand to Silty Sand	SP	
9	Sand	SP/SW	
10	Gravelly Sand to Sand	SP/GW	
11	Very Stiff Fine Grained	OC Clay	
12	Sand to Clayey Sand	Cemented	

TEST SITE: PC-6F

SOUNDING DATE

3/3/05

SURFACE ELEVATION (FT, NGVD) 167.31

COORDINATE LOCATION (FT)

N 1,250,983.97

E 96,262.97



Ardaman & Associates, Inc.
Piezocone Test Results

GEOTECHNICAL STUDY ASSOCIATED
WITH ANNUAL MONITORING

SOUTHEAST LANDFILL

HILLSBOROUGH COUNTY, FL

DRAWN BY: SA CHECKED BY: SA DATE: 05-16-05

FILE NO.: 05-010 APPROVED 8Y: FIGURE 14

Soil Classification by Robertson et al., 1986