


**Request for Approval of Alternate Procedure  
Landfill Sideslope Subbase Design and  
Horizontal Separation to Property Line  
Citrus County Central Landfill Phase 2 Expansion**



**SCS ENGINEERS**

**Prepared for:**


Citrus County  
Board of County Commissioners  
P.O. Box 340  
Lecanto, Florida 34460



**Prepared by:**

SCS Engineers  
3012 U.S. Highway 301 N., Suite 700  
Tampa, Florida 33619  
(813) 621-0080

File No. 09199056.02  
August 14, 2002

**SCS ENGINEERS**August 14, 2002  
File No. 09199056.02Mr. John Ruddell  
Director of the Division of Waste Management  
Florida Department of Environmental Protection (FDEP)  
2600 Blair Stone Road  
Twin Tower Office Building  
Tallahassee, Florida 32399-2400**RECEIVED**

AUG 15 2002

Solid Waste Section

Subject: Request for Approval of Alternate Procedure  
Landfill Sideslope Subbase Design and Horizontal Separation to Property Line  
Citrus County Central Landfill Phase 2 Expansion

Dear Mr. Ruddell:

On behalf of Citrus County, SCS Engineers (SCS) is preparing to submit to FDEP a permit application to construct the Citrus County Central Landfill Phase 2 Expansion. This letter was prepared in order to request approval of two alternate procedures: 1) landfill sideslope subbase design, and 2) horizontal separation between the toe of the final cover and the eastern property line, in accordance with the criteria set forth in Rule 62-701.310(2), Florida Administrative Code, FAC. A fee of \$2,000 in accordance with Rule 62-701.310(6), FAC, is also attached.

**SIDESLOPE SUBBASE DESIGN REQUIREMENT**

The criteria set forth in Rule 62-701.310(2), FAC, for approval of an alternate design is summarized in the following table and addressed in more detail in subsequent sections.

| Rule                  | Criteria  | Response  |
|-----------------------|---|---|
| 62-701.310(2)(a), FAC | Specific facility for which an exception is sought.   | Citrus County Central Landfill Phase 2 Expansion  |
| 62-701.310(2)(b), FAC | Specific provisions from which an exception is sought | Requirement to place lower geomembrane on a sub-base which is minimum 6-inches thick and has saturated hydraulic conductivity of less than or equal to $1 \times 10^{-5}$ cm/sec<br>Rule 62-701.400(3)(c)(1), FAC |
| 62-701.310(2)(c), FAC | Basis for the exception                               | The required lining subbase is not practical due to benefit comparisons and construction issues.  |



| Rule                  | Criteria  | Response  |
|-----------------------|---|---|
| 62-701.310(2)(d), FAC | Alternate procedure sought and demonstration that the alternate procedure provides an equal degree of protection for the public and environment | Construction of lower geomembrane liner on sideslopes of prepared, in-place, naturally occurring, subgrade soils.<br>Alternative provides an equal or greater degree of protection. |
| 62-701.310(2)(e), FAC | Demonstration of effectiveness of proposed alternate procedure  | Estimated leachate flow through sideslopes of Phase 2 Expansion is negligible.  |

Prior to addressing the criteria in detail for an alternate sideslope subbase design for Phase 2 at the Citrus County Central Landfill, SCS would like to note that on February 13, 1996, CH2M HILL submitted a letter report to FDEP requesting an alternate sideslope subbase design for the Phase 1A Expansion at the Citrus County Central Landfill, which was subsequently approved by FDEP. For the purpose of our report, SCS intends to show that the data gathered and the calculations presented by CH2M HILL are also valid for the alternate sideslope subbase design proposed for Phase 2. For citation purposes, a copy of this letter report is included in Attachment A to this letter.

**Rule 62-701.310(2)(a), FAC – Facility for Which Exception is Sought**

This exception is sought for the Citrus County Central Landfill Phase 2 Expansion in Lecanto, Florida.

**Rule 62-701.310(2)(b), FAC – Provisions for Which Exception is Sought**

The proposed lining system base plan and typical cross-sections for the Citrus County Central Landfill Phase 2 Expansion are shown on construction drawings included in the pending permit application. A detail for both the sideslopes and bottom liner systems of the Phase 2 Expansion are also shown on the enclosed Figure 1.

In accordance with Rule 62-701.400(3)(c), FAC, a double liner system consisting of upper and lower 60-mil geomembranes is proposed for this expansion. The exception is being sought for the lining subbase criteria set forth in Rule 62-701.400 (3)(c)(1), FAC for the sideslope liner portion only. This rule states that the lower geomembrane shall be placed directly on a subbase which is a minimum of 6-inches thick, is free of sharp materials or any material larger than one-half inch, and has a saturated hydraulic conductivity of less than or equal to  $1 \times 10^{-5}$  cm/sec. SCS' proposed design does not include preparing a six-inch subbase on the sideslopes of the Phase 2 Expansion. Rather, the sideslope lower liner will be placed on prepared, in-place naturally occurring, subgrade soils as shown in the lining detail on Figure 1.

**Rule 62-701.310(2)(c), FAC – Basis for the Exception**

The exception is based on whether it is practical to prepare a 6-inch thick lining subbase on the sideslopes for the proposed Phase 2 Expansion. In SCS' opinion, both from constructability and benefit considerations, the six-inch thick lining subbase is not practical.

**Constructability**

SCS designed the sides of the proposed Phase 2 Expansion to have a slope of 2 horizontal to 1 vertical, in order to stay within the site constraints and safety considerations of the landfill, but still maximize the amount of highly desirable air space. With this consideration in mind, it is not practical to prepare a 6-inch thick lining subbase in accordance with Rule 62-701.400(3)(c)(1), FAC. Due to slope considerations, it is unlikely, even if attempted, that the required lining subbase would be stable enough to support the overlying bottom liner, and consequently, the liner itself could become unstable.

Alternatively, Rule 62-701.400(3)(c)(1), FAC, states that a geosynthetic clay liner can be substituted for the 6-inch thick lining subbase. Due to the sideslope length of more than 175 feet, placement of a geosynthetic clay liner would require the use of an anchor bench in the middle of the slope. Preparing the sideslope for construction of an anchor trench would require placement of soil fill on the bottom portion of the sideslope up to the level of the anchor bench, thereby diminishing air space and possibly creating interface instability between the existing subgrade soil and the new fill soil. Therefore, this approach is also not practical.

**Benefit Considerations**

The provisions for a 6-inch thick lining subbase set forth in Rule 62-701.400(3)(c)(1), FAC, are intended to help in containing leaks through the secondary liner that could cause pollution of underlying groundwater aquifers by the leaking leachate. Typically in Florida, underlying aquifers are within a few feet of landfill bottoms. For the purposes of the proposed Phase 2 Expansion, the increased protection provided by a prepared lining subbase does not give a practical added benefit. The following site-specific conditions support this conclusion:

- The proposed leachate collection design includes a tri-planar geocomposite drainage net for the primary leachate collection layer and a tri-planar geocomposite for the secondary leachate collection layer. This design, in conjunction with a side slope of 2 horizontal to 1 vertical, allows leachate that encounters the collection layers to drain to the landfill sump very quickly. The efficient transmission of leachate down the slope results in a minimal residence time and hydraulic head on the liner. With these two components, the incidence of significant leakage into the soil, induced through liner perforations, are

substantially reduced.

- According to the geotechnical investigation conducted on November 15, 2001 by Universal Engineering Sciences, the groundwater elevation at the site is approximately 5 feet NGVD and approximately 120 feet below ground surface. (See Attachment B). These measurements put the groundwater at approximately 35 feet below the lowest point of the Phase 2 Expansion sideslopes. In addition, the geotechnical investigation describes the soil profile found in the proposed footprint of Phase 2. When the soil profile of the Phase 2 Expansion is compared with the soil profile at the Phase 1A Expansion, they are essentially the same.

With this in mind, the average hydraulic conductivity of  $3.0 \times 10^{-5}$  cm/sec for the soil presented in CH2M HILL's alternate procedure letter for the Phase 1A Expansion is appropriate to use for the Phase 2 Expansion. When the depth to groundwater, relative to the proposed liner elevation, is coupled with the low permeability of the natural soils, installing a liner subbase has no practical benefit.

**Rule 62-701.310(2)(d), FAC – Alternate Procedure for Which the Approval is Sought and Demonstration that the Alternate Procedure Provides an Equal Degree of Protection for the Public and Environment**

The alternate procedure being sought is to place the lower geomembrane sideslope liner of the Phase 2 Expansion on prepared in-place, naturally occurring subgrade soils instead of on a 6-inch thick prepared liner subbase with a saturated hydraulic conductivity of less than or equal to  $1 \times 10^{-5}$  cm/sec. In reality, the degree of protection afforded by placing the lower geomembrane sideslope liner on the naturally occurring soils is equal to or greater than if it was placed on a 6-inch thick prepared subbase.

For support of this conclusion, the amount of leachate that could flow through the lining subbase and alternatively, through naturally occurring soils is considered. The calculations provided in CH2M HILL's letter report in Attachment A to this letter are directly applicable for the proposed Phase 2 Expansion design. The calculations demonstrate that the potential flow through the alternative proposed is up to approximately 40% less than the flow through a 6-inch thick lining subbase by itself. In the calculations, CH2M HILL used a minimum thickness of 25 feet for the naturally occurring soil but, for the proposed Phase 2 Expansion design, the minimum thickness is 35 feet, which results in an even lower flow compared to the prescribed subbase.

**Rule 62-701.310(2)(e), FAC – Demonstration of the Effectiveness of the Proposed Alternate Procedure**

The effectiveness of the proposed alternate procedure is demonstrated by the ability of the proposed Phase 2 Expansion sideslopes to contain leachate. Since the proposed Phase 2

Mr. John Ruddell  
August 14, 2002  
Page 5

Expansion double liner system is essentially the same as the Phase 1A Expansion system, the calculations found in CH<sub>2</sub>M Hill's letter report in Attachment A to this letter are valid in application to the proposed Phase 2 Expansion.

The calculation of the maximum flow of leachate through the soil underlying the proposed Phase 2 Expansion sideslopes, as provided by CH<sub>2</sub>M Hill, is estimated to be  $8 \times 10^{-7}$  gal/day. This flow is negligible as it relates to a potential impact to groundwater, thereby demonstrating the effectiveness of the proposed alternative procedure for the lining subbase.

#### **HORIZONTAL SEPARATION TO PROPERTY LINE REQUIREMENT**

Rule 62-701.340(4)(c), Florida Administrative Code (FAC) requires a minimum 100-foot horizontal separation between the toe of the proposed cover slope and the landfill property boundary. The following is a request for approval of an alternate horizontal separation of 75 feet along the eastern property boundary in accordance with Rule 62-701.310, FAC.

##### **Rule 62-701.310(2)(a), FAC – Facility for Which Exception is Sought**

This exception is sought for the Citrus County Central Landfill Phase 2 Expansion in Lecanto, Florida.

##### **Rule 62-701.310(2)(b), FAC – Provisions for Which Exception is Sought**

Requirement to maintain a minimum horizontal separation between the toe of the proposed cover slope and the landfill property boundary of 100 feet in Rule 62-701.340(4)(c), FAC.

##### **Rule 62-701.310(2)(c), FAC – Basis for the Exception**

A 75-foot horizontal separation between the toe of the final cover and the eastern property boundary will be consistent with the existing cover slope of Phase 1A. Maintaining a consistent cover slope along the edge eliminates the likelihood of operational problems. The adjacent property is State forest lands and will not be occupied in perpetuity. The ability to maintain the same horizontal separation for Phase 2 expansion will minimize confusions related to the location of the edge of the liner.

A consistent slope along the eastern edge of the landfill will also eliminate the need to provide a severe jog in the liner alignment that could cause stress built up on the liner.

Mr. John Ruddell  
August 14, 2002  
Page 6

**Rule 62-701.310(2)(d), FAC – Alternate Procedure for Which the Approval is Sought and Demonstration that the Alternate Procedure Provides an Equal Degree of Protection for the Public and Environment**


Maintain the existing 75-foot horizontal separation between the toe of the final cover slope and the eastern property boundary. The proposed alternate setback does not compromise the degree of protection for the public or the environment.

**Rule 62-701.310(2)(e), FAC – Demonstration of the Effectiveness of the Proposed Alternate Procedure**

The proposed alternate minimum setback will provide an equal or greater degree of protection for the public and the environment as evidenced from the operation of the existing Phase IA.

SCS appreciates the opportunity to request an alternate procedure for the Citrus County Central Landfill Phase 2 Expansion. We look forward to your comments. Please contact us if you have any questions or need additional information to assist in the review process.

Sincerely,



8-14-02

John A. Banks, P.E.  
Project Manager  
SCS ENGINEERS



Raymond J. Dever, P.E., DEE  
Vice President  
SCS ENGINEERS

BJC:eac

cc: Susan Metcalfe, P.G. – Citrus County

Attachments

Application Fee


Figure 1 Liner System Details

Attachment A CH<sub>2</sub>M Hill Landfill Sideslope Subbase Design, Request for Alternate Procedure, dated Feb. 13, 1996

Attachment B Geotechnical Investigation For Citrus County Landfill, New Disposal Cell, Universal Engineering Services, Dated November 15, 2001



**FIGURE 1. LINER SYSTEM DETAILS**






### BOTTOM LINING SYSTEM

NOT TO SCALE



### SIDESLOPE LINING SYSTEM

NOT TO SCALE



G:\PROJECT\09199056.02\FinalConstruction\cover.dwg Aug 13, 2002 - 3:04pm Layout Name: Layout1.Bx 2205k/in

SCS ENGINEERS

Figure 1. Liner System Details

**ATTACHMENT A**

**CH<sub>2</sub>M HILL LANDFILL SIDESLOPE SUBBASE DESIGN, REQUEST FOR  
ALTERNATE PROCEDURE, DATED FEB. 13, 1996**



February 13, 1996

117956.28

Mr. John Ruddell  
Director of the Division of Waste Management  
Florida Department of Environmental Protection  
2600 Blair Stone Road  
Twin Tower Office Building  
Tallahassee, Florida 32399-2400

Dear Mr. Ruddell:

Subject: Landfill Sideslope Subbase Design  
Request for Alternate Procedure  
Citrus County Central Landfill Phase 1A Expansion

CH2M HILL has prepared and submitted to the FDEP Tampa District office a permit application to construct the Citrus County Central Landfill Phase 1A Expansion on behalf of Citrus County. The purpose of this correspondence is to request approval of an alternate landfill sideslope subbase design in accordance with Rule 62-701.310, Florida Administrative Code (FAC). All of the criteria for this request included in Rule 62-701.310(2), FAC are summarized in the following table. A more detailed discussion of each of the criteria is provided under the headings which follow the summary table. A fee of \$2000 in accordance with Rule 62-701.310(6), FAC is also attached.

Mr. John Ruddell  
Page 2  
February 13, 1996  
117956.28

| Rule                  | Criteria   | Response  |
|-----------------------|--|---|
| 62-701.310(2)(a), FAC | Facility.  | Citrus County Central Landfill Phase 1A Expansion.  |
| 62-701.310(2)(b), FAC | Specific provisions for which an exception is sought.                  | 6-inch-thick lining subbase for a double geomembrane lining (Rule 62-701.400(3)(c)(1), FAC.   |
| 62-701.310(2)(c), FAC | Basis for the exception.   | A lining subbase is not practical based on constructability and benefit considerations.   |
| 62-701.310(2)(d), FAC | Alternative procedure and demonstration of equal degree of protection. | Placement of the lower geomembrane of the sideslopes on prepared, in place naturally occurring subgrade soils. Alternative provides for a greater degree of protection. |
| 62-701.310(2)(e), FAC | Demonstration of effectiveness   | Estimated leachate flow through the Phase 1A Expansion sideslopes is negligible.  |

**Rule 62-701.310(2)(a), FAC The specific facility for which an exception is sought:**

This exception is being sought for the Citrus County Central Landfill Phase 1A Expansion in Lecanto, Florida.

**Rule 62-701.310(2)(b), FAC The specific provisions from which an exception is sought:**

The lining base grade plan for the Citrus County Central Landfill Phase 1A Expansion is shown on Drawing No. C-4 in Attachment A. The boundary of the east and west

Mr. John Ruddell  
Page 3  
February 13, 1996  
117956.28

sideslopes of the proposed expansion are indicated with a heavy dashed line on the drawing. A detail of the proposed lining for both the sideslopes and bottom of the landfill expansion is shown in Detail 18 on Drawing No. C-14 (Attachment A). A double geomembrane lining in general accordance with Rule 62-701.400(3)(c), FAC is proposed for the expansion. An exception is being sought for the lining subbase provisions of the referenced rule. Rule 62-701.400(3)(c)(1), FAC includes provisions for at least a 6-inch-thick lining subbase with a maximum hydraulic conductivity of  $1 \times 10^{-5}$  centimeters per second (cm/sec). As shown in Detail 18 on Drawing No. C-14 (Attachment A), a lining subbase is proposed for the bottom lining in the Phase 1A Expansion; however, a lining subbase is not proposed for the sideslopes of the expansion. Placement of the lower geomembrane on prepared, in place, naturally occurring subgrade soils is planned.

**Rule 62-701.310(2)(c), FAC The basis for the exception:**

This exception is based on the practicality, from both constructability and benefit considerations, of a lining subbase beneath the sideslopes of the proposed Phase 1A Expansion.

During Phase 1 construction of the facility, the sideslopes in the area of the Phase 1A expansion were excavated to approximately the proposed lining base grade elevations shown in Drawing No. C-4 (Attachment A). At that time, provisions for subbases were not part of the regulations and the Phase 1 lining and excavation for the future Phase 1A expansion were constructed in accordance with existing standards and permit provisions. Placement of a low-permeability, 6-inch lining subbase on the already excavated sideslopes is not practical with available construction technology. If attempted, it is unlikely that the subbase would be effective and support for the overlying lining system may even be compromised. The length of the slope, which is over 200 feet, precludes the use of geocomposite clay lining without an intermediate anchor trench in the middle of a slope. Both flattening the slope and providing for an intermediate anchor trench would require the placement of fill on the bottom portion of the slope since site boundaries prevent widening the limits of the excavation at the top. However, placement of soil fill on the bottom portion of the sideslope is undesirable because a weakened foundation support zone could be developed between the interface of the soil fill and in place soils below the landfill.

Mr. John Ruddell  
Page 4  
February 13, 1996  
117956.28

The lining subbase provisions are intended to inhibit lining leakage and contain leachate below the bottom of landfills to protect the public and environment. This protection usually applies to groundwater resources, which are typically within several feet of landfill bottoms in Florida. The use of a low permeable, 6-inch-thick sideslope lining subbase for this protection does not provide practicable benefits for the Phase 1A Expansion because of the following site specific conditions:

- The lining sideslopes will be at approximately 2 horizontal to 1 vertical slopes and composite drainage nets will be used for both the primary and secondary leachate collection layers. Therefore, leachate in the collection layers of the lining will be drained away to the landfill bottom quickly. As a result, there will be negligible head on the lower geomembrane lining which could contribute to leakage and make a lining subbase beneficial.
- The groundwater elevation at the site is at elevation 7 feet NGVD and approximately 113 feet below ground surface. This groundwater level is 25 feet from the bottom of the Phase 1A sideslopes. Hydraulic conductivity test results on soils adjacent to and below the sideslopes are summarized on Figure 1 in Attachment B. Tests results range from  $1.3 \times 10^{-7}$  to  $2.0 \times 10^{-4}$  cm/sec, with an average of  $3.0 \times 10^{-5}$  cm/sec. Considering the distance between the bottom of the sideslopes and groundwater, as well as the low permeability of natural soils at the site, placement of a lining subbase will have no practical benefit.

**Rule 62-701.310(2)(d), FAC The alternate procedure or requirement for which approval is sought and a demonstration that the alternate procedure or requirement provides an equal degree of protection for the public and the environment:**

The alternate procedure being sought is to place the lower geomembrane of the sideslopes at the Phase 1A Expansion on prepared, in place naturally occurring subgrade soils in lieu of a lining subbase. The degree of protection of the sought after alternate procedure and the required lining subbase can be evaluated by considering the amount of leachate that could flow through the lining subbase and, alternatively, in place soils. This flow is characterized using Darcy's law in the calculations in Attachment C. The

Mr. John Ruddell  
Page 5  
February 13, 1996  
117956.28

results are summarized below:

- The expected flow per cross-sectional area through a 6-inch-thick subbase layer in accordance with Rule 62-701.400(3)(c)(1), FAC is  $6.6 \times 10^{-7}$  times the head on the subbase, per second.
- The in place subgrade soils alternative is characterized by a thickness of 25 to 113 feet between the lining and the groundwater level, and ranges in hydraulic conductivity from  $1.3 \times 10^{-7}$  to  $2.0 \times 10^{-4}$  cm/sec. Based on a conservative thickness equal to 25 feet for the subgrade and the greatest measured hydraulic conductivity value of  $2.0 \times 10^{-4}$  cm/sec, the expected flow per cross-sectional area through the in place subgrade alternative is also  $2.6 \times 10^{-7}$  times the head on the subbase, per second.

Therefore, potential flow through the alternative is expected to be less than 40 percent of the flow through a 6-inch-thick lining subbase. The proposed alternative provides a greater degree of protection to the public and the environment.

**Rule 62-701.310(2)(e), FAC** A demonstration of the effectiveness of the proposed alternative procedure:

The effectiveness of the proposed alternative is evaluated in Attachment D by characterizing the proposed Phase 1A Expansion sideslopes' ability to contain landfill leachate. The methodology used in this evaluation is identified in the calculations and based on standard design equations developed by J. P. Giroud. Results are summarized below:

- Based on the slope of the lining, properties of the primary leachate collection layer, and a leachate impingement rate typical of Florida; the maximum expected head on the primary lining is  $1 \times 10^{-4}$  meters (m).
- Using this head, the expected size of potential lining defects, and the properties of the underlying leachate secondary collection layer; the maximum expected flow through the primary lining into the secondary leachate collection layer at each potential lining defect is expected to be 2 gallons per day (gal/day).

Mr. John Ruddell

Page 6

February 13, 1996

117956.28

- Based on the typical size and frequency of lining defects when determining lining effectiveness, a maximum impingement rate through the primary lining and on the secondary lining of  $2 \times 10^{-11}$  meters per second (m/s) is expected.
- Based on the slope of the lining, properties of the secondary leachate collection layer, and this estimated impingement rate; the maximum expected head on the secondary lining is  $1 \times 10^{-8}$  m.

Using this head, the size and frequency of potential lining defects, and the properties of the underlying soils; the maximum expected flow through the secondary lining can be estimated. As shown on Figure 1 in Attachment B, the hydraulic conductivity of soils at the site which will underlie the secondary lining as the proposed alternative ranges from  $1.3 \times 10^{-7}$  to  $2.0 \times 10^{-4}$  cm/sec. The frequency of different ranges in hydraulic conductivity from this data was used to calculate a total maximum flow of approximately  $8 \times 10^{-7}$  gal/day through the proposed Phase 1A Expansion sideslopes. This flow is negligible, which demonstrates the effectiveness of the proposed alternative procedure for the lining subbase.


As requested by your office, we are submitting seven additional copies of this correspondence. We look forward to receiving your comments on our requested alternative procedure. Please do not hesitate to contact me if you have any questions or need additional information to assist in your review process.

Sincerely,

CH2M HILL



Gary L. Panozzo, P.E.  
Project Manager




ILET015.DOC



cc: Kim Ford - FDEP Tampa District  
Susan Metcalfe, P.G. - Citrus County



**Attachment A**  
**Drawings**



- NOTES:
1. SCREENED LINES ARE APPROXIMATE EXISTING GRADES. HEAVY LINES ARE PROPOSED LINING BASE GRADES.
  2. PROVIDE SIDE SLOPE LINING SYSTEM IN ACCORDANCE WITH DETAIL 18 FROM EL 120.00 AT THE TOP OF THE LANDFILL EXCAVATION TO THE LIMITS SHOWN. PROVIDE BOTTOM LINING SYSTEM IN ACCORDANCE WITH DETAIL 18 IN THE BOTTOM OF THE LANDFILL EXCAVATION TO THE LIMITS SHOWN.
  3. SEE DETAILS 20 AND 21 FOR LINING FIELD WELDS.
  4. SEE SHEET 8 FOR FINAL SURFACE TREATMENTS AND EROSION CONTROL.



BASELINE PROFILE

by  
**CHM HILL**  
 DSGN L. FIELD  
 G.L. PANOZZO  
 OR B.J. MCCORKLE  
 CK G.L. PANOZZO  
 APVD JOHN WOOD

NO. DATE REVISION BY APVD

REUSE OF DOCUMENTS

THIS DOCUMENT, AND THE IDEAS AND DESIGNS INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF CHM HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CHM HILL.

SCALE: 1" = 40' HORIZ. 1" = 10' VERT.  
 IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY.

CITRUS COUNTY  
 CENTRAL LANDFILL  
 PHASE 1A EXPANSION  
 CITRUS COUNTY, FLORIDA


LINING BASE GRADE PLAN

SHEET 6  
 DWG NO. C-4  
 DATE 12-29-95  
 PROJ NO. 130786.78.03



**Attachment B**  
**Figures**

Figure 1



**Attachment C**  
**Equal Degree of Protection Calculations**



SUBJECT SOIL USE 1A EXPANSION  
ALTERNATE SIDE SLOPE LINING  
SUBBASE

BY PAWORTO DATE 2/6/95  
 SHEET NO. 1 OF 1  
 PROJECT NO. 117956.28

## I. DETERMINE FLOW THROUGH REQUIRED

LINING SUBBASES

USING DARCY'S LAW

$$Q_{REQ} = K I A$$

$I = \text{HYDRAULIC GRADIENT}$

$$= \frac{\text{CHANGE IN HEAD}}{L} = \frac{15.24 \text{ ft}}{6 \text{ in}} = 15.24 \text{ ft/in}$$

$$Q_{REQ} = \left( \frac{1 \times 10^{-5} \text{ cm}}{\text{sec}} \right) \left( \frac{\Delta H}{15.24 \text{ cm}} \right) A \quad K = 1 \times 10^{-5} \text{ cm/sec}$$

$$Q_{REQ} = \frac{6.6 \times 10^{-7} \Delta H \cdot A}{\text{sec}}$$

## II. DETERMINE FLOW THROUGH IN PLACE SUBGRADE SOIL ALTERNATIVES

USING DARCY'S LAW

$$Q_{ALT} = K I A$$

$I = \text{HYDRAULIC GRADIENT}$

$$= \frac{\text{CHANGE IN HEAD } (\Delta H)}{L}$$

$$Q_{ALT} = \left( \frac{2.0 \times 10^{-4} \text{ cm}}{\text{sec}} \right) \left( \frac{\Delta H}{25 \text{ FT} - 12.25 \text{ FT}} \right) A \quad L = (\text{RANGES FROM } 25 \text{ FT TO } 12.25 \text{ FT}) = \text{ASSUM}$$

$$K = \text{RANGES FROM } 1.3 \times 10^{-7} \text{ cm/sec}$$

$$\text{to } 2.0 \times 10^{-4} \text{ cm/sec}$$

$$= \text{ASSUME } 2.0 \times 10^{-4} \text{ cm/sec}$$

$$\rightarrow \text{VERY CONSERVATIVE}$$

$$Q_{ALT} = \frac{2.6 \times 10^{-7} \Delta H \cdot A}{\text{sec}}$$

SUBJECT Crus County LandfillBY T. Oloro DATE 2/7/96SHEET NO. 1 OF 1  
PROJECT NO. 11795628

Determine the head on top of the primary liner on the side slopes:

$$T_{max} = L \left[ \sqrt{4(e/k) + \tan^2 \beta} - \tan \beta \right] / (2 \cos \beta)$$

$T_{max}$  = maximum thickness of leachate in leachate collection layer (meters)

$L$  = length of horizontal projection of the leachate collection layer, from top to collector (meters)

$e$  = impingement rate (or leachate generation rate) (meters/sec)

$k$  = hydraulic conductivity of drainage layer (meters/sec)

$\beta$  = slope angle (degrees)

$e$  = 25% of the 7-day storm w/ a recurrence period of 100 years

For Florida the 100-year 7-day precipitation is 21 inch or .53 m

$$e = \frac{.25(.53)}{(7 \times 24 \times 60 \times 60)} = 2.2 \times 10^{-7} \text{ m/s}$$

For a 2:1 slope  $\beta = 26.6^\circ$

For a 2.5:1 slope  $\beta = 21.8^\circ$

$L$  = 190 feet or 58 m

transmissivity of composite drainage net = 10 gal/min,  
(from technical specifications) or  $2.1 \times 10^{-3} \frac{\text{m}^2}{\text{sec}}$





SUBJECT Civil & County Landfill

BY T. Olore DATE 2/7/96

SHEET NO. 2 OF       

PROJECT NO. 47956-28

$$k = \frac{\text{transm. coeff.}}{\text{thickness of composite drainage net}}$$

$$\text{thickness CDN} = 0.26 \text{ inches or } .0066 \text{ m}$$

$$k = \frac{2.1 \times 10^{-3} \text{ m}^2/\text{sec}}{.0066 \text{ m}} = 0.3182 \text{ m/s}$$

For 2:1 slope:

$$T_{\max} = \frac{58 \left[ \sqrt{4 \left( \frac{2.2 \times 10^{-7}}{0.3182} \right) + \tan^2 26.6^\circ} - \tan 26.6^\circ \right]}{2 \cos 26.6^\circ}$$

$$T_{\max} = .0001 \text{ m}$$

For 2.5:1 slope:

$$T_{\max} = \frac{58 \left[ \sqrt{4 \left( \frac{2.2 \times 10^{-7}}{0.3182} \right) + \tan^2 21.8^\circ} - \tan 21.8^\circ \right]}{2 \cos 21.8^\circ}$$

$$T_{\max} = .0001 \text{ m}$$

use leachate head = .0001 m

Reference:

Design Example 2, "Leachate Collection System", J. P. Giroud

SUBJECT Crus County LandfillBY T. Obire DATE 2/7/96SHEET NO. 3 OF       PROJECT NO. 11795628

Determine rate of leakage through primary lining

From J.P. Giroud's, Design Example 3  
"Leakage Evaluation"

Rate of leakage through holes in geomembrane  
overlain and underlain by high-permeability  
materials =

$$Q = 0.6 a \sqrt{2gh}$$

where  $a$  = area of geomembrane hole ( $m^2$ )  
 $g$  = acceleration of gravity ( $m/s^2$ )  
 $h$  = head of leakage on top of  
geomembrane (m)

Equation valid if

$$k_{CDN} > 10^4 a \text{ (m}^2\text{)}$$

check  $k_{CDN} = 0.3182 \text{ m/s}$

For  $a = 3 \times 10^{-6} \text{ m}^2$  Hole size from Giroud  
typical size hole when evaluating performance  
of lining systems

$$k_{min} = (1 \times 10^4)(3 \times 10^{-6}) = 0.03 \text{ m/s}$$

$0.3182 \text{ m/s} > 0.03 \text{ m/s}$  okay to  
use equation



SUBJECT

Cus County landfill

BY

T. Olbre DATE 2/7/96

SHEET NO.

OF

PROJECT NO. 117956.28

$$g = 9.81 \text{ m/s}^2$$

$$a = 3 \times 10^{-6} \text{ m}^2$$

$$h = .0001 \text{ m}$$

$$Q = 0.6 (3 \times 10^{-6}) \sqrt{2(9.81)(.0001)}$$

$$Q = 9.4 \times 10^{-8} \text{ m}^3/\text{s} \quad \text{or} \quad \underline{2 \text{ gal/day (for one acre)}}$$

Determine rate of leakage through secondary lining.

The impingement rate (e) through the primary liner is:

$$e = 9.4 \times 10^{-8} \text{ m}^3/\text{s/acre} \quad \text{or} \quad 2.3 \times 10^{-11} \text{ m/s}$$

Thickness of leachate on top of secondary liner is:

For 2:5:1 slope:

$$\beta = 21.8^\circ$$

$$L = 190 \text{ ft} \quad \text{or} \quad 58 \text{ m}$$

$$K = .0318 \text{ m/s}$$

$$T_{\max} = 58 \left[ \frac{\sqrt{4 \left( \frac{2.3 \times 10^{-11}}{0.3182} \right) + \tan^2 21.8} - \tan 21.8}{2 \cos 21.8} \right]$$

$$T_{\max} = 1.25 \times 10^{-8} \text{ m}$$



SUBJECT C-15 Canby Land C. II

BY T. Obire DATE 2/7/9  
SHEET NO. 5 OF         
PROJECT NO. H 7956-28

From Giroud's Leakage Evaluation, Design Example 3

Rate of leakage through a composite liner

$$Q = 0.21 a^{1/3} h^{0.9} k_s^{0.74} \text{ for good contact}$$

Where:

$Q$  = rate of leakage through one hole in

the geomembrane component of a composite liner

$a$  = area of the hole in the geomembrane ( $m^2$ )

$h$  = head of leachate on top of geomembrane (m)

$k_s$  = hydraulic conductivity of the low-permeability soil underlying the geomembrane

$$a = 3 \times 10^{-6} m^2$$

$$h = 1.0 \times 10^{-8} m$$

- To determine  $Q$  through a composite liner, the frequency of permeability values was determined based on the number of permeability tests conducted on on-site soils and the results of the tests.

For each permeability value,  $Q$  ( $m^3/s/acre$ ) determined using the above equation.

The  $Q$  was then multiplied by the percent frequency and the total leakage of the 2.5:1 side slope.



SUBJECT Citrus County Landfill

BY T. Olye DATE 2/7/96

SHEET NO. 6 OF 11  
PROJECT NO. 117956-28

The  $Q$ 's for each of the permeability values were used to determine the total amount of leakage through the composite liner system. The attached spreadsheet presents the results of the analysis.

As shown on the spreadsheet the amount of leakage through the composite liner is approximately  $7.8 \times 10^{-7}$  gal/day which is negligible.

## Rate of Leakage Through Secondary Liner

| $k_s$ (m/sec) | Data Range (cm/sec) | Number of Tests | Percent Frequency | $a$ (m <sup>2</sup> ) | $h$ (m)  | $Q$ (m <sup>3</sup> /sec/acre) | acres | $Q$ (m <sup>3</sup> /sec) | $Q$ (gal/day) |
|---------------|---------------------|-----------------|-------------------|-----------------------|----------|--------------------------------|-------|---------------------------|---------------|
| 1E-06         | 5E-5 to 4E-4        | 2               | 18%               | 3.00E-06              | 1.25E-08 | 1.65E-13                       | 0.15  | 2.52E-14                  | 5.75E-07      |
| 1E-07         | 5E-6 to 4E-5        | 3               | 27%               | 3.00E-06              | 1.25E-08 | 3.00E-14                       | 0.23  | 6.87E-15                  | 1.57E-07      |
| 1E-08         | 5E-7 to 4E-6        | 5               | 45%               | 3.00E-06              | 1.25E-08 | 5.46E-15                       | 0.38  | 2.08E-15                  | 4.76E-08      |
| 1E-09         | 5E-8 to 4E-7        | 1               | 9%                | 3.00E-06              | 1.25E-08 | 9.93E-16                       | 0.08  | 7.59E-17                  | 1.73E-09      |
|               |                     |                 |                   |                       |          |                                |       |                           |               |
| <b>Total</b>  |                     | 11              | 100%              |                       |          |                                | 0.84  | 3.42E-14                  | 7.81E-07      |

## DESIGN EXAMPLE 2

# LEACHATE COLLECTION SYSTEM

PREPARED BY J.P. GIROUD  
GEOSYNTEC CONSULTANTS

### 1. DESIGN

#### 1.1 Equation

*Leachate thickness in LCS*

The maximum thickness of leachate in the leachate collection layer is approximately given by the following equation (Figure 1) [Giroud et al., 1993]:

$$T_{\max} = L [\sqrt{4(e/k) + \tan^2 \beta} - \tan \beta] / (2 \cos \beta)$$

*this is revised Moore's equation and is accurate to within 10% or more conservative than Moore's*

where:  $T_{\max}$  = maximum thickness of leachate in leachate collection layer;  $L$  = length of horizontal projection of the leachate collection layer, from top to collector;  $e$  = impingement rate (or leachate generation rate);  $k$  = hydraulic conductivity (coefficient of permeability) of the drainage layer; and  $\beta$  = slope angle. Basic SI units are:  $T_{\max}$  (m),  $L$  (m),  $e$  (m/s),  $k$  (m/s), and  $\beta$  (degrees).

#### 1.2 Comment on the Impingement Rate

$e$  = precipitation - runoff - evaporation - waste and soil moisture storage

The impingement rate can be determined by performing a water balance model to represent the landfill in operating conditions. Suitable water balance models available are the USEPA water balance method [USEPA, 1975] and the Hydrologic Evaluation of Landfill Performance (HELP) model

[USEPA, 1984a and 1984b].

An alternative but conservative approach is to use an impingement rate equal to 25% of the 7-day storm with a recurrence period of 100 years. For example, in Florida the 100-year 7-day precipitation is 21 in. (0.53 m). This results in:

$$e = 0.25 \times 0.53 / (7 \times 24 \times 60 \times 60) = 2.2 \times 10^{-7} \text{ m/s}$$

$8.7 \times 10^{-6} \text{ in./sec}$

Assumptions

In the following design examples, it is assumed that the impingement rate was obtained from the HELP model. It is assumed that for the considered landfill, the HELP model indicated that approximately 40% of the average monthly rainfall will percolate through the proposed landfill as leachate. It is also assumed that the worst month is June, with a mean precipitation equal to 12.6 in. (0.32 m). This results in:

$$e = 0.40 \times 0.32 / (30 \times 24 \times 60 \times 60)$$

$$e = 5.0 \times 10^{-8} \text{ m/s} = 2.0 \times 10^{-6} \text{ in./s} = 4,620 \text{ gpad}$$

.(gpad = gallons/acre/day)

### 1.3 Comment on $T_{\max}$

To prevent pressure buildup in the leachate collection layer,  $T_{\max}$  should satisfy the following criterion:

$$T_{\max} < t$$

where:  $t$  = thickness of the leachate collection layer (m).

← meters

In addition, it is recommended that  $T_{\max}$  be smaller than 0.3 m (1 foot) to minimize leakage through the liner.



## 2. EXAMPLES

## 2.1 Sand Drainage Layer

Given:

$$\tan \beta = 2\% = 0.02$$

$$k = 1 \times 10^{-4} \text{ m/s}$$

$$e = 5 \times 10^{-8} \text{ m/s} = \text{impingement rate}$$

$$L = 30 \text{ m (100 ft)} = \text{distance from peak to pipe.}$$

$$t = 0.45 \text{ m (1.5 ft)}$$

Calculations:

Giroud's equation:

Can use any  
system of  
units if consistent

$$T_{\max} = 30 \left[ \sqrt{4(5 \times 10^{-8}) / (1 \times 10^{-4}) + (0.02)^2} - 0.02 \right] / (2 \times 0.9998)$$

$$= 0.435 \text{ m} \quad = 17 \text{ in.} \quad = 1.43 \text{ ft}$$

It appears that the leachate thickness does not exceed the thickness of the drainage layer, but exceeds the recommended maximum leachate thickness of 0.3 m (1 ft). In this case, the drainage length, L, may be reduced or the slope,  $\beta$ , increased to meet the requirements of 0.3 m (1 ft) maximum leachate thickness. Alternatively, a material with higher hydraulic conductivity may be used as the drainage medium. For example, if the drainage length is reduced to 21 m (69 ft), the calculated leachate thickness becomes 0.3 m (1 ft).

## 2.2 Geonet Drainage Layer

Given:

$$\tan \beta = 2\% = 0.02$$

$$L = 30 \text{ m (100 ft)}$$

Geonet hydraulic transmissivity measured under a compressive stress equal to the expected landfill overburden stress:

must do a test to determine this value.

2 values  
depending on  
how geonet  
is tested

$$\theta = \text{transmissivity}$$

$\theta = 2.0 \times 10^{-5} \text{ m}^2/\text{s}$  for the considered geonet between geotextile and geomembrane

$\theta = 2.0 \times 10^{-4} \text{ m}^2/\text{s}$  for the considered geonet between two geomembranes

geotextile restricts  
flow of geonet &  
reduces Transmissivity value

Geonet thickness:

$$t_g = 4 \text{ mm} = 0.004 \text{ m} \quad (\text{assumes one layer})$$

Leachate impingement rate:

$$e = 5 \times 10^{-8} \text{ m/s} \quad (\text{see section 1.2})$$

### Calculations:

Geonet hydraulic conductivity: *geonet thickness in meters*

$$k = \theta/t_g = 2 \times 10^{-5} / 0.004 = 5 \times 10^{-3} \text{ m/s} = 0.5 \frac{\text{cm}}{\text{sec}}$$

Giroud's equation:

$$T_{\max} = 30 \left[ \sqrt{4(5 \times 10^{-3}) / (5 \times 10^{-3}) + (0.02)^2} - 0.02 \right] / (2 \times 0.9998)$$

$$= 0.0146 \text{ m} = 14.6 \text{ mm} > 4 \text{ mm (thickness of geonet)}.$$

$$= 0.57 \text{ inches}$$

greater  
than  
drainage  
layer

This leachate thickness exceeds the geonet thickness, which is 4 mm; one layer of geonet is insufficient. Therefore, try two layers of geonet.

A hydraulic transmissivity  $\theta = 2 \times 10^{-4} \text{ m}^2/\text{s}$  should be used for the lower layer geonet, which is between a geomembrane and a geonet (compared to the upper geonet which is in contact with a geotextile, and for which a hydraulic transmissivity of  $2 \times 10^{-5} \text{ m}^2/\text{s}$  is used). The new value of hydraulic conductivity to consider is:

upper geonet  
keeps filter  
fabric out of  
geonet  
act.

$$k = \theta/t_g = 2 \times 10^{-4}/0.004 = 0.05 \text{ m/s}$$

Giroud's equation is then used for the lower geonet only, the transmissivity of the upper geonet being negligible compared to that of the lower geonet:

$$T_{\max} = 30 \left[ \sqrt{4(5 \times 10^{-5})/0.05 + (0.02)^2} - 0.02 \right] / (2 \times 0.9998)$$

$$= 1.5 \times 10^{-3} \text{ m} = 1.5 \text{ mm} < \text{thickness of 1 geonet.}$$

*This calculation assumes 2 geonets and filter fabric on top.*

This value being less than 4 mm, it is sufficient to have one layer of geonet not in contact with a geotextile. Therefore, two layers of geonets are needed, one geonet (the upper geonet) in contact with the geotextile filter, and the other between the upper geonet and the geomembrane.

*Note:  
2 geosynthetic  
in contact mean  
must check slope  
stability and bottom  
slip also. can get small  
friction  
angles.*

#### REFERENCES

USEPA, "Use of Water Balance Method for Predicting Leachate Generation from Solid Waste Disposal Sites", EPA/530/SW-169, U.S. Environmental Protection Agency, oct 1975, 40 p.

USEPA, "The Hydrologic Evaluation of Landfill Performance (HELP) Model, Vol. I, User's Guide for Version I, EPA/530-SW-84-009, U.S. Environmental Protection Agency, Washington, DC, Jun 1984a, 120 p.

USEPA, "The Hydrologic Evaluation of Landfill Performance (HELP) Model, Vol. II, Documentation for Version I, EPA/530-SW-84-010, U.S. Environmental Protection Agency, Washington, DC, Jun 1984b, 256 p.

Giroud, J.P., Gross, B.A., and Darrasse, J., "Flow in Leachate Collection Layers", to be published, 1993.

*IFAI will soon publish this book*

Depth of leachate  
Thickness of leachate  $\approx$  Head

$e = \text{Imperviousness}$




Figure 1. Leachate Thickness in the Leachate Collection System.

## DESIGN EXAMPLE 3

# LEAKAGE EVALUATION

PREPARED BY J.P. GIROUD

### 1. DESIGN METHOD

#### 1.1 Leakage Mechanisms

There are essentially two mechanisms of leakage through geomembranes [Giroud and Bonaparte, 1989]: fluid permeation through an intact geomembrane and flow through geomembrane holes. Leakage rates due to geomembrane permeation are generally negligible compared to leakage rates due to flow through geomembrane holes. Therefore, only leakage through geomembrane holes is considered in this design example.

With regard to leakage through geomembrane holes, three cases can be considered:

- The geomembrane is overlain and underlain by high-permeability materials (such as geonet or coarse gravel).
- The geomembrane is placed on a layer of low-permeability soil to form a composite liner.
- The geomembrane is placed on a high-permeability material, and is overlain by a sand or a fine gravel (i.e., a medium permeability material).

## 1.2 Rate of Leakage Through Holes in Geomembrane Overlain and Underlain by High-Permeability Materials

In this design example, a geomembrane "alone" is a geomembrane overlain and underlain by high-permeability materials (such as geonets or coarse gravel). According to Giroud [1984a, 1984b], the rate of leakage through a hole in such a geomembrane can be evaluated using Bernoulli's equation for free flow through an orifice, provided the underlying material has a hydraulic conductivity greater than  $k_{min}$  given by:

$$\begin{aligned}k_{min} \text{ (m/s)} &= 10^4 a \text{ (m}^2\text{)} \\k_{min} \text{ (cm/s)} &= 100 a \text{ (cm}^2\text{)}\end{aligned}$$

where  $a$  = area of geomembrane hole.

Bernoulli's equation is as follows [Giroud and Bonaparte, 1989a]:

$$Q = 0.6 a \sqrt{2gh}$$

where:  $Q$  = leakage rate through one geomembrane hole;  $a$  = area of geomembrane hole;  $g$  = acceleration of gravity; and  $h$  = head of liquid on top of the geomembrane. Basic SI units are:  $Q(\text{m}^3/\text{s})$ ,  $a(\text{m}^2)$ ,  $g(\text{m}/\text{s}^2)$ , and  $h(\text{m})$ .

## 1.3 Rate of Leakage Through a Composite Liner

The mechanism of leakage through a composite liner with a hole in the geomembrane is as follows: the liquid first migrates through the hole in the geomembrane; the liquid may then travel laterally some distance in the space, if any, between the geomembrane and the low-permeability soil; and finally, the liquid migrates into and eventually through the low-permeability soil. Therefore, the leakage rate depends on the quality of contact between the geomembrane and the low-permeability soil.

For the typical contact conditions encountered in the field, the leakage rate can be calculated from the following empirical equations [Giroud et al., 1989] based on work by Giroud and Bonaparte [1989b]:

$$Q = 0.21 a^{0.1} h^{0.9} k_s^{0.74} \quad \text{for good contact}$$

$$Q = 1.15 a^{0.1} h^{0.9} k_s^{0.74} \quad \text{for poor contact}$$

where:  $Q$  = rate of leakage through one hole in the geomembrane component of a composite liner;  $a$  = area of the hole in the geomembrane;  $h$  = head of liquid on top of the geomembrane; and  $k_s$  = hydraulic conductivity of the low-permeability soil underlying the geomembrane. The above equations are not dimensionally homogeneous; they can only be used with the following units:  $Q(\text{m}^3/\text{s})$ ,  $a(\text{m}^2)$ ,  $h(\text{m})$ , and  $k_s(\text{m}/\text{s})$ .

The above equations should be restricted to cases where:

- the hydraulic conductivity of the low-permeability soil is less than  $10^{-5}$  m/s ( $10^{-4}$  cm/s); and
- the head of liquid on top of the geomembrane is less than the thickness of the low-permeability soil layer underlying the geomembrane.

The material overlying the geomembrane has no influence on the rate of leakage as long as its hydraulic conductivity is greater than that of the low-permeability soil underlying the geomembrane.

The good and poor contact conditions are defined as follows [Bonaparte et al., 1989]:

- The good contact condition corresponds to a geomembrane installed with as few wrinkles as possible, on top of a low-permeability soil layer that has been adequately compacted and has a smooth surface.

- The poor contact condition corresponds to a geomembrane that has been installed with a certain number of wrinkles, and/or placed on a low-permeability soil that has not been well compacted and does not appear smooth.

These two contact conditions, which can be considered as typical field conditions, are between the two extremes defined as follows:

- *Best Conditions.* The low-permeability soil is well compacted, flat and smooth, has not been deformed by rutting during construction, and has no clods and cracks, and the geomembrane is flexible and has no wrinkles.
- *Worst Conditions.* The low-permeability soil is poorly compacted, has an irregular surface and is cracked, and the geomembrane is stiff and exhibits a pattern of large, connected wrinkles.

#### 1.4 Rate of Leakage Through a Geomembrane Overlain by a Medium-permeability Drainage Material

If a geomembrane resting on a high-permeability material (such as geonet or coarse gravel) is overlain by a medium-permeability drainage material (such as sand or fine gravel), the flow toward the geomembrane hole is impeded by the drainage material, and the flow rate is less than in the case of free flow (i.e., the case when the geomembrane is underlain and overlain by a high-permeability material). A typical field situation is a geomembrane primary liner overlain by a sand leachate collection layer and underlain by a geonet leakage detection and collection layer. An approximate empirical equation for the calculation of the leakage rate is as follows [Bonaparte et al., 1989]:

$$Q = 3 a^{0.75} h^{0.75} k_d^{0.5}$$

where:  $Q$  = rate of leakage through one geomembrane hole;  $a$  = area of the hole in the geomembrane;  $h$  = head of liquid on top of the geomembrane;  $k_d$



$$\frac{\pi}{4} D^2 = 1 \text{ cm}^2 = \dots$$

$$\Rightarrow D = \sqrt{\frac{4A}{\pi}}$$

$$= 1.13 \text{ cm} = .44 \text{ in}$$

Design Examples

GeoSyntec Consultants

= hydraulic conductivity of the drainage material overlying the geomembrane. This equation is not dimensionally homogeneous; it can only be used with the following units:  $Q(\text{m}^3/\text{s})$ ,  $a(\text{m}^2)$ ,  $h(\text{m})$ , and  $k_d(\text{m}/\text{s})$ .

This equation is applicable only when the hydraulic conductivity of the drainage layer material,  $k_d$ , is greater than  $10^{-6} \text{ m/s}$  ( $10^{-4} \text{ cm/s}$ ). Also, the equation should be limited to cases where the head of liquid on top of the geomembrane,  $h$ , is less than the thickness of the drainage layer. (This condition is usually fulfilled in the case of landfills.)

### 1.5 Hole Frequency

Typically one hole per 4000  $\text{m}^2$  (acre) is considered based on work by Giroud and Bonaparte [1989a]. However, any other frequency can be considered by the design engineer.

### 1.6 Hole Size

Two hole sizes are typically considered:

- $1 \text{ cm}^2 = 100 \text{ mm}^2 = 10^{-4} \text{ m}^2$  ( $0.16 \text{ in.}^2$ ); and
- 2 mm (0.08 in.) in diameter, i.e.,  $0.031 \text{ cm}^2 = 3.14 \text{ mm}^2 = 3 \times 10^{-6} \text{ m}^2$  ( $4.9 \times 10^{-3} \text{ in.}^2$ ).

The large hole is typically considered for sizing the leakage collection system, and the small hole for evaluating the performance of lining systems constructed with adequate quality assurance. Any other hole size can be considered by the design engineer.

large hole  $\Rightarrow$  sizing LCS  
small hole  $\Rightarrow$  evaluating performance of liner system

## 2. DESIGN EXAMPLES

### 2.1 Example 1

- Size of landfill: 2 acres.
- Head on liner: 0.2 mm on slopes and 1.2 mm on the base, as obtained in the design of the leachate collection system (not given here).
- The liner is a geomembrane alone on the slopes and a composite liner at the base of the landfill.
- Hydraulic conductivity of the clay component of the composite liner:  $10^{-8}$  m/s ( $10^{-6}$  cm/s).
- The geomembrane is overlain by a geonet on the slopes and at the base of the landfill.
- Holes with a surface area of  $1 \text{ cm}^2$  ( $0.16 \text{ in.}^2$ ) are considered.

#### Calculations

##### - Leakage on side slopes

The liner is a geomembrane alone (i.e., overlain and underlain by a very permeable material) and Bernoulli's equation can be used with:

$$a = 1 \times 10^{-4} \text{ m}^2 (1 \text{ cm}^2)$$

$$h = 2 \times 10^{-4} \text{ m} (0.2 \text{ mm})$$

Hence:

$$Q = 0.6 \times 10^{-4} \sqrt{2 \times 9.81 \times 2 \times 10^{-4}}$$

$$Q = 3.76 \times 10^{-6} \text{ m}^3/\text{s}$$

$$Q = 0.325 \text{ m}^3/\text{day} = 86 \text{ gallons/day (for one hole)}$$

This is the leakage rate through one hole with a surface area of 1 cm<sup>2</sup>.

- Leakage on base

The liner is a composite liner. Assuming that the contact conditions between the geomembrane and the low-permeability soil layer are good, the following equation can be used:

$$Q = 0.21 a^{0.1} h^{0.9} k_s^{0.74}$$

with:

$$a = 1 \times 10^{-4} \text{ m}^2 = 1 \text{ cm}^2$$

$$k_s = 1 \times 10^{-8} \text{ m/s}$$

$$h = 1.2 \times 10^{-3} \text{ m (1.2 mm)}$$

The leakage rate is given by:

$$Q = 0.21 \times (10^{-4})^{0.1} \times (1.2 \times 10^{-3})^{0.9} (10^{-8})^{0.74}$$

$$Q = 2.36 \times 10^{-10} \text{ m}^3/\text{s}$$

$$Q = 2.0 \times 10^{-5} \text{ m}^3/\text{day} = 5.4 \times 10^{-3} \text{ gallons/day (for one hole)}$$

It appears that one hole in the slope generates 16,000 times more leakage than one hole through the base. This is because the liner on the slope is a geomembrane alone, while the liner on the base is a composite liner. The effect of the composite liner is to significantly reduce the

rate of leakage through a hole in the geomembrane. (Note that neither of the above calculations take into account any additional head caused by liquid ponding which may be due to geomembrane wrinkles.)

- Leakage through the entire liner

Assuming a frequency of one hole per acre, since the lining system surface area is two acres, there are two holes. Assuming conservatively that the two holes are on the slope, the leakage through the top liner is:

$$Q = 2 \times 3.76 \times 10^{-6} \text{ m}^3/\text{s}$$

$$Q = 7.5 \times 10^{-6} \text{ m}^3/\text{s} = 0.64 \text{ m}^3/\text{day} = 640 \text{ liters/day}$$

$$Q = 170 \text{ gallons/day}$$

The leakage rate per unit area is obtained by dividing the above leakage rate by the landfill surface area,  $8,000 \text{ m}^2 = 0.8 \text{ hectare}$  (2 acres):

$$Q = 800 \text{ lphd} = 85 \text{ gpad}$$

(lphd = liters/hectare/day; gpad = gallon/acre/day)

## 2.2 Example 2

- Size of landfill: 5 acres
- The primary liner of a double liner is a geomembrane alone on the slopes and at the base.
- The geomembrane is underlain by a geonet on the slopes and the base. (The geonet is the leakage collection layer for the double liner.)

- The geomembrane is overlain by a geonet on the slopes and by sand at the base. (The geonet and sand constitute the leachate collection layer material for the double liner.)
- The hydraulic conductivity of the sand is  $10^{-5}$  m/s ( $10^{-3}$  cm/s).
- Head on the primary liner: 0.2 mm on slopes and 120 mm on the base.
- A hole size of  $10 \text{ mm}^2$  ( $0.016 \text{ in.}^2$ ) is considered.

### Calculations

#### - Leakage on side slopes

The primary liner is a geomembrane alone overlain and underlain by high-permeability materials. Therefore, Bernoulli's equation can be used. The values of the parameters to be used in Bernoulli's equation are:

$$a = 1 \times 10^{-5} \text{ m}^2 (10 \text{ mm}^2), \text{ i.e., average case}$$

$$h = 2 \times 10^{-4} \text{ m} (0.2 \text{ mm})$$

$$Q = 0.6 \times 10^{-5} \sqrt{2 \times 9.81 \times 2 \times 10^{-4}}$$

$$Q = 3.76 \times 10^{-7} \text{ m}^3/\text{s}$$

$$Q = 8.6 \text{ gallons/day (for one hole)}$$

This is the leakage rate through one hole with a surface area of  $10 \text{ mm}^2$ .

#### - Leakage on base

The primary liner is a geomembrane alone which is overlain by a

medium-permeability drainage material (sand) and underlain by a high-permeability material (geonet). The leakage rate through one hole in the geomembrane can be calculated using the following equation:

$$Q = 3 a^{0.75} h^{0.75} k_d^{0.5}$$

with:

$$a = 1 \times 10^{-5} \text{ m}^2 = 10 \text{ mm}^2$$

$$k_d = 1 \times 10^{-5} \text{ m/s}$$

$$h = 0.12 \text{ (120 mm)}$$

The leakage rate is given by:

$$Q = 3 \times (10^{-5})^{0.75} \times (0.12)^{0.75} \times (10^{-5})^{0.5}$$

$$Q = 3.44 \times 10^{-7} \text{ m}^3/\text{s}$$

$$Q = 7.85 \text{ gallons/day (for one hole)}$$

- Leakage through the entire liner

Assuming a frequency of one hole per acre, since the lining system surface area is five acres, there are five holes. Assuming that two holes are on the slope and three holes are at the base, the rate of leakage through the top liner is:

$$Q = 2 \times 3.76 \times 10^{-7} + 3 \times 3.44 \times 10^{-7}$$

$$Q = 1.78 \times 10^{-6} \text{ m}^3/\text{s} = 154 \text{ liters/day}$$

$$Q = 40.7 \text{ gallons/day}$$

The leakage rate per unit area is obtained by dividing the above leakage rate by the landfill surface area,  $20,000 \text{ m}^2 = 2 \text{ hectares (5 acres)}$ :

$$Q = 77 \text{ lphd} = 8.1 \text{ gpad}$$

(lphd = liters/hectare/day; gpad = gallon/acre/day)

## REFERENCES

Giroud, J.P., "Impermeability: The Myth and a Rational Approach", *Proceedings of the International Conference on Geomembranes*, Vol. 1, Denver, CO, Jun 1984, pp. 157-162. [1984a]

Giroud, J.P., "Geotextiles and Geomembranes. Definitions, Properties and Design", IFAI Publishers, 1984, 325 p. [1984b]

Bonaparte, R., Giroud, J.P., and Gross, B.A., "Rates of Leakage Through Landfill Liners", *Proceedings of Geosynthetics '89 Conference*, San Diego, CA, Vol. 1, 1989, pp. 18-28.

Giroud, J.P. and Bonaparte, R., "Leakage through Liners Constructed with Geomembranes, Part I: Geomembrane Liners", *Geotextiles and Geomembranes*, Vol. 8, No. 1, 1989, pp. 27-67. [1989a]

Giroud, J.P. and Bonaparte, R., "Leakage through Liners Constructed with Geomembranes, Part II: Composite Liners", *Geotextiles and Geomembranes*, Vol. 8, No. 2, 1989, pp. 71-111. [1989b]

Giroud, J.P., Khatami, A., and Badu-Tweneboah, K., "Evaluation of the Rate of Leakage through Composite Liners", *Geotextiles and Geomembranes*, Vol. 8, No. 4, 1989, pp. 337-340. [1989]



## DESIGN EXAMPLE 4

## LEAKAGE COLLECTION LAYER

PREPARED BY J.P. GIROUD  
GEOSYNTEC CONSULTANTS

## 1. DESIGN METHOD

The purpose of this design example is to size the leakage collection and detection layer located between the two liners of a double liner. The rate of leakage through a hole of the primary liner is assumed to be known. Assume that the collected leakage will flow over a width B of the leakage detection layer. This width B can be arbitrarily chosen between 1 and 5 m (3 and 16 ft.). Then, calculate the flow thickness as follows:

$$D = \frac{Q/B}{k \sin \beta}$$

liquid flow thickness (Equation 1)

where: D = flow thickness; Q = flow rate; B = flow width; k = hydraulic conductivity of the drainage medium; and  $\beta$  = slope. Basic SI units are: D (m); Q ( $\text{m}^3/\text{s}$ ), B (m), k (m/s), and  $\beta$  (degrees).

It is then necessary to verify that the flow thickness, D, is less than the thickness of the leakage detection layer or 0.3 m (1 ft), whichever is smaller, to ensure a small head on the secondary liner.

If the leakage detection layer is characterized by its hydraulic transmissivity, the above equation becomes:

$$\frac{D}{T} = \frac{Q/B}{k \sin \beta} \quad (\text{Equation 2})$$

where: D = flow thickness; T = thickness of the drainage layer; Q = flow

rate;  $B$  = flow width;  $\theta$  = hydraulic transmissivity of the drainage layer; and  $\beta$  = slope. Basic SI units are:  $D$  (m),  $T$  (m),  $Q$  ( $\text{m}^3/\text{s}$ ),  $B$  (m),  $\theta$  ( $\text{m}^2/\text{s}$ ), and  $\beta$  (degrees).

~~A~~ The above equation is particularly useful for geonets. It is used to verify that  $D/T < 1$  or  $D < 0.3$  m, whichever value of  $D$  is smaller.

Leak detection time is the time leakage takes to travel from the leak to the nearest collection sump. In this design example, it is assumed that steady-state conditions exist in the leakage detection layer. The steady-state leakage detection time is given by Giroud and Bonaparte [1992]:

$$t_{sl} = n_L L_L / (k_L \sin \beta_L) \quad (\text{Equation 3})$$

where:  $t_{sl}$  = steady-state leakage travel time in a leakage detection layer;  $n_L$  = porosity of the leakage detection layer;  $L_L$  = length of the leakage path in the leakage detection layer;  $k_L$  = hydraulic conductivity of the leakage detection layer material; and  $\beta_L$  = slope of the leakage detection layer along the leakage path. Basic SI units are:  $t_{sl}$  (s),  $L_L$  (m);  $k_L$  (m/s), and  $\beta_L$  (degrees);  $n_L$  and  $\beta_L$  are dimensionless.

The above equation considers only the time during which leakage flows in the leakage collection layer. The time spent by leakage in pipes is not included. A maximum steady-state leak detection time of 24 hours is typically required.

Since the location of leaks is not known, it is conservative to use for  $L_L$  the maximum distance between a leak and a collection sump.

## 2. DESIGN EXAMPLE

### Given

The top liner has two holes located near the toe of the side slopes. The leakage rate through each hole is  $3.76 \times 10^{-6} \text{ m}^3/\text{s}$  (85 gallons/day). The base slope is 3%. A geonet with a hydraulic transmissivity of  $5 \times 10^{-4} \text{ m}^2/\text{s}$  is considered. For leak detection time calculations, a maximum

distance of 30 m (100 ft) between hole and collector pipe is considered.

### Calculations

Assume a flow width  $B = 1.5$  m (5 ft) and conservatively assume that the two holes are next to each other.

$$\frac{D}{T} = \frac{2 \times 3.76 \times 10^{-6} / 1.5}{5 \times 10^{-4} \times 0.03}$$

$$\frac{D}{T} = 0.33$$

The flow thickness is one third of the geonet thickness; in other words, the factor of safety is 3.

To calculate the leak detection time, it is necessary to know the porosity and the hydraulic conductivity of the geonet. A value of 0.8 can be assumed for the porosity. The hydraulic conductivity can be obtained by dividing the hydraulic transmissivity by an assumed thickness of 4 mm as follows:

$$k = \theta / t_g$$

$$k = 5 \times 10^{-4} / 4 \times 10^{-3}$$

$$k = 0.125 \text{ m/s}$$

The leak detection time is then given by Equation 3 as follows:

$$\begin{aligned} t_{SL} &= 0.8 \times 30 / (0.125 \times 0.03) \\ &= \frac{6400}{9600} \text{ s} = \frac{1.8}{2.7} \text{ hours} \end{aligned}$$

This time is less than 24 hours and is, therefore, acceptable.

## REFERENCES

Giroud, J.P. and Bonaparte, R., "*Design and Performance of Geosynthetic Lining System for Waste Conatinment*", book to be published by IFAI, 1992.

**ATTACHMENT B**

**GEOTECHNICAL INVESTIGATION**  
**FOR**  
**CITRUS COUNTY LANDFILL, NEW DISPOSAL CELL,**  
**UNIVERSAL ENGINEERING SERVICES,**  
**DATED NOVEMBER 15, 2001**



# **UNIVERSAL**

## **ENGINEERING SCIENCES**

**GEOTECHNICAL INVESTIGATION  
FOR  
CITRUS COUNTY CENTRAL LANDFILL  
NEW DISPOSAL CELL  
S.R. 44  
CITRUS COUNTY, FL**


**ORDER NO. 26081-001-01  
REPORT NO. 21607**

**Prepared by:**

**Universal Engineering Sciences, Inc.  
4475 SW 35<sup>th</sup> Terrace  
Gainesville, FL 32608  
(352) 372-3392**

**November 15, 2001**

**Consultants in: Geotechnical Engineering • Environmental Sciences • Construction Materials Testing  
Offices in: Orlando • Gainesville • Ocala • Fort Myers • Merritt Island • Daytona Beach • West Palm Beach**



# UNIVERSAL ENGINEERING SCIENCES

Consultants in: Geotechnical Engineering • Threshold Inspection  
Environmental Sciences • Construction Materials Testing

OFFICES IN:  
• Orlando  
• Gainesville  
• Fort Myers  
• Rockledge  
• St. Augustine  
• Daytona Beach  
• West Palm Beach  
• Jacksonville  
• Ocala  
• Tampa  
• Debary

November 15, 2001

SCS Engineers  
3012 U.S. Highway 301 North, Suite 700  
Tampa, FL 33619-2242

Attention: Mr. Bruce Clark, P.E., D.E.F.

Reference: Citrus County Central Landfill  
New 9.5 Acre Waste Disposal Cell  
S.R. 44  
Citrus County, FL  
Order No. 26081-001-01 Report No. 21607

Dear Mr. Clark:

Universal Engineering Sciences, Inc., has completed the subsurface investigation and engineering evaluation for the proposed construction at the above referenced location. Our investigation was performed in accordance with our proposal No. 21447, which was authorized by Raymond J. Dever, P.E., D.E.F. with SCS Engineers on October 9, 2001.

This report contains the results of our investigations, an engineering interpretation of these with respect to the project characteristics described to us, and recommendations for side slopes excavations and filling, foundation design and site preparation.

We appreciate the opportunity to have worked with you on this project and look forward to a continued association. If you have any questions concerning this report or if we may further assist you as your plans proceed, please contact us.

Respectfully submitted,

UNIVERSAL ENGINEERING SCIENCES, INC.

Eduardo Suarez  
Project Engineer

Thomas A. Boatman, P.E.  
Senior Project Engineer  
Florida P.E. No: 56030

Jack W. Ray  
Regional Manager

ES/TAB/JWR:es (2)

**TABLE OF CONTENTS**

|   |   |
|---|---|
| 1.0 <b><u>INTRODUCTION</u></b>                            | 1 |
| 1.1 <b>GENERAL</b>  | 1 |
| 2.0 <b><u>SCOPE OF SERVICES</u></b>                       | 1 |
| 2.1 <b>PROJECT DESCRIPTION</b>                            | 1 |
| 2.2 <b>PURPOSE</b>  | 1 |
| 2.3 <b>USDA SOIL SURVEY DATA AND USGS SITE TOPOGRAPHY</b> | 2 |
| 2.4 <b>FIELD INVESTIGATION</b>                            | 2 |
| 2.5 <b>LABORATORY INVESTIGATION</b>                       | 3 |
| 3.0 <b><u>FINDINGS</u></b>                                | 3 |
| 3.1 <b>SURFACE CONDITIONS</b>                             | 3 |
| 3.2 <b>GENERAL GEOLOGY</b>                                | 3 |
| 3.3 <b>SUBSURFACE CONDITIONS</b>                          | 4 |
| 4.0 <b><u>RECOMMENDATIONS</u></b>                         | 4 |
| 4.1 <b>GENERAL</b>  | 4 |
| 4.2 <b>LANDFILL</b>                                       | 5 |
| 4.2.1 <b>Foundation Bearing Capacity</b>                  | 5 |
| 4.2.2 <b>Settlement Estimates</b>                         | 5 |
| 4.2.3 <b>Landfill Slope Stability</b>                     | 5 |
| 4.2.4 <b>Subgrade Slope Stability</b>                     | 6 |
| 4.3 <b>FILL SUITABILITY</b>                               | 6 |
| 4.4 <b>CONSTRUCTION RELATED SERVICES</b>                  | 6 |
| 5.0 <b><u>LIMITATIONS</u></b>                             | 6 |
| 6.0 <b><u>SUMMARY</u></b>                                 | 7 |



**TABLE OF CONTENTS CONTINUED**

**APPENDIX A**

|   |     |
|---|-----|
| SOIL CONSERVATION SERVICE SURVEY- DETAILED SOIL MAP ..... | A-1 |
| USGS-TOPOGRAPHICAL MAP .....                              | A-2 |

**APPENDIX B**

|                            |            |
|----------------------------|------------|
| BORING LOCATION PLAN ..... | B-1        |
| BORING LOGS .....          | B-2 - B-17 |

**APPENDIX C**

|   |           |
|---|-----------|
| SUMMARY OF LABORATORY TESTS RESULTS .....                   | C-1 - C-3 |
| SUMMARY OF LIMEROCK BEARING RATIO (LBR) TESTS RESULTS ..... | C-4       |
| DESCRIPTION OF LABORATORY TESTING PROCEDURES .....          | C-5       |

**APPENDIX D**

|                                |   |
|--------------------------------|---|
| SLOPE STABILITY ANALYSIS ..... | D |
|--------------------------------|---|

**APPENDIX E**

|   |   |
|---|---|
| IMPORTANT INFORMATION ABOUT YOUR GEOTECHNICAL<br>ENGINEERING REPORT, CONSTRAINTS AND RESTRICTIONS ..... | E |
|---|---|