

BOARD OF COUNTY COMMISSIONERS

Kevin Beckner
Victor D. Crist
Ken Hagan
Al Higginbotham
Lesley "Les" Miller, Jr.
Sandra L. Murman
Mark Sharpe



Office of the County Administrator
Michael S. Merrill

CHIEF ADMINISTRATIVE OFFICER
Helene Marks

CHIEF FINANCIAL ADMINISTRATOR
Bonnie M. Wise

DEPUTY COUNTY ADMINISTRATORS
Lucia E. Garsys
Sharon D. Subadan

June 26, 2014

Mr. John Morris, P.G.
Florida Department of Environmental Protection
Waste Permitting Section
13051 Telecom Parkway
Temple Terrace, FL 33637

**RE: Southeast County Landfill
Laboratory Analytical Results
Initial Assessment Monitoring Plan
Report No. 45 – May 2014**

Dear Mr. Morris:

The Hillsborough County Public Utilities Department (County) is pleased to provide the analytical results from the May 2014 sampling event conducted as part of the continuation of the Initial Assessment Monitoring Plan (IAMP). The IAMP was developed to address the potential impacts to groundwater from the sinkhole on the edge of Phase VI at the Southeast County Landfill (SCLF), which was discovered on December 14, 2010.

As part of the agreement between the County and Florida Department of Environmental Protection Southwest District Office (Department), three (3) upper Floridan/Limestone aquifer monitoring wells, designated as TH-72, TH-76 and TH-77 are sampled on a monthly schedule and three (3) surficial aquifer monitoring wells, designated as TH-73, TH-74, and TH-75 are sampled on a quarterly schedule. Representative samples were collected from each of these six (6) monitoring wells on May 6-7, 2014 and analyzed for total dissolved solids (TDS), chloride, total ammonia, arsenic, iron, sodium, and five (5) field parameters. Each sample collected was analyzed by our contracted laboratory, Test America, Inc. The following paragraphs summarize the parameter specific results pertinent to the evaluation of potential water quality impacts from the sinkhole at the SCLF.

Turbidity

Turbidity values in the surficial aquifer monitoring wells TH-73, TH-74, and TH-75 were recorded at 4.01, 3.93, 3.01 Nephelometric Turbidity Units (NTUs). Turbidity values in upper Floridan / Limestone aquifer monitoring wells TH-72, TH-76, and TH-77 were recorded at 1.22, 12.7, and 1.01 NTUs, respectively. No significant changes in turbidity values were noted in the data set from this sampling event.

Conductivity

The conductivity values in TH-73, TH-74, and TH-75 were recorded at 340, 549, and 341 micromhos per centimeter (umhos/cm), and the values in TH-72, TH-76, and TH-77 were recorded at 2247, 427, and 414 umhos/cm, respectively. Monitoring well TH-72 is the closest UFA monitoring well to the sinkhole, and it continues to exhibit groundwater impacts similar to those observed over the past year. The elevated conductivity observed is likely attributable to the waste in the throat and bottom voids of the sinkhole and the large amounts of grout materials and fluids injected into the subsurface as part of the sinkhole stabilization process. Conductivity values in TH-76 and TH-77 are relatively low and appear to be consistent with the unaffected deep wells across the site.

Total Dissolved Solids (TDS)

The TDS in TH-73, TH-74, and TH-75 were all within the Secondary Drinking Water Standard (SDWS) of 500 mg/l. However, TDS in TH-72 was observed at 1,400 mg/l and continues to be above the SDWS. The two down gradient monitoring wells, TH-76 and TH-77 both exhibited a TDS value of 220 mg/l, which is consistent with the water quality historically observed in the unaffected deep wells across the site.

Chloride

Chloride concentrations in the surficial aquifer wells were all below 100 mg/l. A concentration of 590 mg/l was observed in TH-72, which is well above the SDWS of 250 mg/l. Chloride values in TH-76 and TH-77 were observed at 12 mg/l and 9.7 mg/l, which is consistent with the unaffected deep wells across the site.

Iron

Iron concentrations in TH-73, TH-74, and TH-75 were observed at 4, 29, and 6.1 mg/l, respectively. Concentrations in TH-72, TH-76, and TH-77 were observed at 0.64, 0.65, and 0.19 mg/l, respectively. The elevated iron concentrations observed at specific locations across the site are consistent with background water quality, and are likely naturally occurring and/or the result of past strip mining activities at the site.

Sodium

Sodium was observed at a concentration of 230 mg/l in TH-72, which is above the PDWS of 160 mg/l. The elevated sodium value is likely attributable to the waste in the sinkhole and/or the grouting activities. Sodium values in TH-76 and TH-77 were observed at 21 and 17 mg/l, which is consistent with the unaffected deep wells across the site.

Groundwater Elevations and Direction of Flow

On May 5, 2014, the County collected groundwater and surface water elevation data at sixty-five (65) points across the site, including twenty eight (28) surficial aquifer wells, seven (7) upper Floridan (limestone) aquifer wells, twenty three (23) piezometers, and six (6) surface water sites. No significant changes to the patterns of flow in the surficial aquifer were noted in the data set, and the flow diagram provided is consistent with the observations over the extensive period of record. The elevations observed within the wells closest to the sinkhole indicate that flow patterns continue to be affected in that area, which has not be unexpected. However, the overall direction of flow within the surficial aquifer remains toward the west/northwest across the site.

A contour diagram of the upper Floridan / Limestone aquifer has been prepared for the general area around the sinkhole and is included with this submittal. This diagram was generated manually in AutoCad TM utilizing only the three data points closest to the sinkhole. During this sampling event, the change in elevation between TH-72 and TH-76 is - 0.05 ft., and the change between TH-72 and TH-77 is + 0.12 ft. The diagram indicates that flow within the UFA in the area of the former sinkhole continues to be in a north/northwest direction, but at what appears to be a very slow rate. Based on the consistency of the direction of flow, the County has installed an additional upper Floridan / Limestone aquifer groundwater monitoring well down gradient of the sinkhole. This monitoring well, designated as TH-78, shall be completed in June, and sampled during the July IAMP sampling event and each month thereafter.

Conclusions

The water quality observed in the May 2014 IAMP sampling event indicates that the upper Floridan / Limestone well TH-72, which is closest to the sinkhole, continues to exhibit impacts to water quality. The impacts observed in TH-72 include elevated conductivity, TDS, chloride, iron and sodium. These impacts are not unexpected within the upper Floridan / Limestone aquifer in the immediate vicinity of the sinkhole feature. Upper Floridan / Limestone aquifer monitoring wells, TH-76 and TH-77 continue to exhibit good water quality with no evidence of impact from the sinkhole. Conductivity values, TDS, and chloride are all very low and consistent with the historical data set for the unaffected upper Floridan aquifer groundwater monitoring wells at the SCLF, which supports the position that the impacts from the sinkhole are limited in extent and do not appear to be migrating beyond the area close to the feature.

Recommendations

The County continues to move forward with implementation of the IAMP, which includes the monthly sampling of the three upper Floridan / Limestone aquifer groundwater monitoring wells, TH-72, TH-76, and TH-77, and the quarterly sampling of the three surficial aquifer monitoring wells, TH-73, TH-74, and TH-75. Additionally, the County will also begin monthly monitoring of upper Floridan / Limestone aquifer groundwater monitoring well TH-78. We will continue to evaluate any water quality changes in both the surficial and upper Floridan aquifer wells, and present the findings in the monthly IAMP reports. The monitoring activities have been conducted for over three years and the consistency of the data set supports a significant reduction

Mr. John Morris, P.G.
June 26, 2014
Page 4 of 4

in the frequency. The County intends to propose this reduction in the number of monitoring wells sampled and the frequency of sampling and reporting in a separate correspondence. If the Department has any specific concerns with this position, we would welcome any guidance.

Enclosed for your review please find a site location map depicting the location of the monitoring wells sampled, the water quality data summary table for this sampling event, a groundwater elevation data table, groundwater contour and flow diagrams for the surficial and upper Floridan / Limestone aquifers, the historical data summary tables for the wells sampled this month, and the complete analytical data report from our contracted laboratory, Test America, Inc.

Should you have any questions or require any additional information please feel free to call me at (813) 663-3221.

Respectfully submitted,

David S. Adams 6/26/2014

David S. Adams, P.G.
Environmental Manager
Public Utilities Department
Environmental Services




xc: John Lyons, Director, Public Works Department
Kim Byer, Public Works Department, Solid Waste Division
Larry Ruiz, Public Works Department, Solid Waste Division
Jeff Greenwell, Public Utilities Department
Richard Tedder, FDEP Tallahassee
Clark Moore, FDEP Tallahassee
Steve Morgan, FDEP, Southwest District
Andy Schipfer, EPC
Ernest Ely, WMI
Brian Miller, DOH
Rich Siemering, HDR
Joe O'Neill, CDS

**Southeast County Landfill
Laboratory Analytical Data
Surficial and Upper Floridan Aquifer Groundwater Monitoring Wells
May 6-7, 2014**


GENERAL (mg/l)	Surficial Aquifer Wells			Upper Floridan Wells				(MCL) STANDARD
PARAMETERS	TH-73	TH-74	TH-75	TH-72	TH-76	TH-77	Duplicate	
conductivity (umhos/cm) (field)	340	549	341	2247	427	414	NA	NS
dissolved oxygen (mg/l) (field)	1.13	0.57	0.37	0.46	0.24	0.34	NA	NS
pH (field)	5.05	5.56	5.67	6.81	7.56	7.52	NA	(6.5 - 8.5)**
temperature (°C) (field)	25.59	22.06	22.61	23.50	22.85	23.47	NA	NS
turbidity (NTU) (field)	4.01	3.93	3.01	1.22	12.7	1.01	NA	NS
total dissolved solids (mg/l)	210	310	200	1400	220	220	220	500**
chloride (mg/l)	90	92	27	590	12	9.7	9.8	250**
ammonia nitrogen (mg/l as N)	3.3	3.1	1.8	24	0.38	0.59	0.63	NS
								(MCL) STANDARD
Metals: (mg/l)	TH-73	TH-74	TH-75	TH-72	TH-76	TH-77	Duplicate	
arsenic	0.004 u	0.004 u	0.0066 i	0.004 u	0.004 u	0.004 u	0.004 u	0.01*
iron	4	31	6.1 j3	0.64	0.65	0.19 i	0.18 i	0.3**
sodium	31	40	18	230	21	17	17	160*
MCL=Maximum Contaminant Level								
NA =Not Analyzed								
NS=No Standard								
NTU = Nephelometric Turbidity Units								
i = reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.								
u = parameter was analyzed but not detected.								
j3 = estimated value, value may not be accurate. Spike recovery or RPD outside of criteria.								
*=Denotes Primary Drinking Water Standard as per Chapter 62-550.310, F.A.C.								
**=Denotes Secondary Drinking Water Standard as per Chapter 62-550.320, F.A.C.								
*** = Denotes Groundwater Cleanup Target Levels as per Chapter 62,777, F.A.C.								
5.05	Exceeds Standard							
mg/l=milligrams per liter								
ug/l = Micrograms per liter								

Southeast County Landfill
Groundwater and Surface Water Elevations
May 5, 2014

Measuring Point	T.O.C. Elevations	W.L.	W.L.	Time
I.D.	(NGVD)	B.T.O.C.	(NGVD)	
P-4D	140.78	22.67	118.11	12:49 PM
P-4S	140.95	9.52	131.43	12:48 PM
P-5D	151.94	Dry	151.94	11:08 AM
P-6D-A	148.01	26.52	121.49	11:18 AM
P-7D	138.92	17.96	120.96	11:51 AM
P-8D	138.34	18.19	120.15	12:14 PM
P-11D	138.02	17.97	120.05	12:34 PM
P-12S	134.97	14.50	120.47	12:16 PM
P-13S	140.21	18.16	122.05	12:01 PM
P-14S	138.56	17.34	121.22	11:57 AM
P-15S	139.19	18.50	120.69	11:54 AM
P-16S	143.38	15.80	127.58	11:27 AM
P-16I	144.15	23.87	120.28	11:27 AM
P-16D	143.84	23.61	120.23	11:28 AM
P-17S	137.35	14.80	122.55	11:34 AM
P-17I	137.32	15.95	121.37	11:34 AM
P-17D	137.22	16.09	121.13	11:35 AM
P-18S	129.86	18.49	111.37	10:36 AM
P-19	133.36	13.51	119.85	11:15 AM
P-20	132.38	12.11	120.27	11:22 AM
P-21	122.79	2.95	119.84	1:06 PM
P-22	128.35	8.33	120.02	1:07 PM
P-23	143.13	23.49	119.64	1:11 PM
TH-19*	130.27	101.69	28.58	11:44 AM
TH-20A	131.86	9.01	122.85	12:26 PM
TH-20B	132.57	10.02	122.55	12:25 PM
TH-22	128.82	4.51	124.31	9:39 AM
TH-22A	129.27	5.13	124.14	9:40 AM
TH-24A	128.23	4.02	124.21	9:43 AM
TH-28A	131.10	27.74	103.36	10:47 AM
TH-30	128.88	23.88	105.00	10:40 AM
TH-32	129.90	15.08	114.82	10:32 AM
TH-35	145.98	28.34	117.64	11:12 AM
TH-36A	152.70	32.71	119.99	11:48 AM
TH-38A	130.68	10.15	120.53	12:29 PM
TH-38B	131.81	12.67	119.14	12:30 PM
TH-40*	124.99	96.80	28.19	9:53 AM
TH-41*	125.00	102.89	22.11	9:52 AM
TH-42*	116.74	75.39	41.35	10:29 AM
TH-57	128.36	18.90	109.46	10:50 AM
TH-58	127.88	27.98	99.90	10:42 AM
TH-61	138.73	17.30	121.43	12:10 PM
TH-61A	139.45	18.10	121.35	12:11 PM
TH-64	139.64	17.42	122.22	11:59 AM
TH-65	135.40	14.70	120.70	12:19 PM
TH-66	130.58	8.70	121.88	12:22 PM
TH-66A	130.66	9.04	121.62	12:21 PM
TH-67	129.51	5.49	124.02	12:23 PM
TH-68	140.01	18.78	121.23	11:53 AM
TH-69A	144.97	25.89	119.08	12:39 PM
TH-70A	146.63	26.89	119.74	12:46 PM
TH-71A	146.95	27.42	119.53	1:00 PM
TH-72*	130.96	100.22	30.74	10:52 AM
TH-73	131.07	30.66	100.41	10:51 AM
TH-74	109.08	9.22	99.86	10:53 AM
TH-75	106.92	7.63	99.29	10:58 AM
TH-76*	111.21	80.52	30.69	10:03 AM
TH-77*	119.88	89.02	30.86	9:59 AM
SW-3A	3.0'=125.53'	0.74	123.27	9:28 AM
SW-3B2B	3.0'=97.97'	1.80	96.77	10:12 AM
SW-3C2	6.0'=92.33'	1.66	87.99	10:18 AM
Mine Cut #1	4.0'=122.14'	2.56	120.70	12:05 PM
Mine Cut #2	6.0'=123.47'	2.79	120.26	11:13 AM
Mine Cut #3	4.0'=112.27'	2.45	110.72	10:26 AM
Mine Cut #4	5.0'=97.54'	1.88	94.42	10:24 AM
NGVD = National Geodetic Vertical Datum				
T.O.C. = Top of Casing				
B.T.O.C. = Below Top of Casing				
* = Floridan Well				
ND = No Data - Sampling Location Dry				
W.L. = Water Level				



Southeast County Landfill
 Groundwater Elevation Contour Diagram – May 5, 2014



MAY 2014
 UPPER FLORIDAN / LIMESTONE AQUIFER CONTOUR DIAGRAM
 IN THE VICINITY OF THE FORMER SINKHOLE
 SOUTHEAST COUNTY LANDFILL
 HILLSBOROUGH COUNTY, FLORIDA

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-72

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
01/27/2011	115.69	15.27	551	0.39	7.43	22.88	3.2	320	32	0.22	0.004 u	0.52	32
02/03/2011	112.18	18.78	565	1.09	7.38	22.95	9.9	300	32	0.21	0.004 u	0.62	27
02/10/2011	109.80	21.16	514	1.58	7.34	22.65	3.2	340	31	0.28	0.004 u	0.54	31
02/14/2011	108.18	22.78	483	1.15	7.36	22.7	3.5	320	32	0.24	0.0013 u	0.58	32
02/24/2011	111.71	19.25	513	0.19	7.34	22.85	1	350	32	0.22	0.004 u	0.53	31
03/03/2011	111.88	19.08	579	0.77	7.35	22.8	0.8	330	31	0.23	0.004 u	0.43	32
03/10/2011	113.65	17.31	551	1.26	7.41	22.73	0.9	320	30	0.18	0.004 u	0.35	31
03/17/2011	112.85	18.11	388	1.05	7.34	22.9	0.9	330	30	0.31	0.004 u	0.25	31
03/24/2011	114.33	16.63	1192	1.5	7.58	23.1	1.5	1,100	350	9	0.004 u	0.64	130
04/01/2011	115.70	15.26	928	0.16	7.41	22.8	3.6	520	110	2	0.004 u	0.24	59
04/08/2011	112.10	18.86	810	0.92	7.35	23.13	6.1	420	87	1.9	0.004 u	0.22	51
05/05/2011	116.21	14.75	609	0.71	7.67	23.01	6.6	320	33	0.3	0.004 u	0.27	37
06/08/2011	119.19	11.77	607	0.71	7.65	23.35	4.51	340	32	0.57	0.004 u	0.2	34
07/07/2011	113.30	17.66	606	0.72	7.4	23.25	3.94	150	64	2.1	0.004 u	7.9	27
08/04/2011	103.31	27.65	564	0.33	7.29	23.18	0.4	360	33	0.21	0.004 u	0.18 i	34
09/08/2011	97.99	32.97	536	1.11	7.29	23.2	0.6	340	34	0.41	0.004 u	0.18 i	36
10/04/2011	99.45	31.51	471	1.69	7.31	23.13	1.1	290	31	0.3	0.004 u	0.14 i	34
11/03/2011	103.37	27.59	550	1.8	7.28	23.04	1.51	290	32	0.29	0.004 u	0.15 i	34
12/08/2011	106.80	24.16	528	1.92	7.31	22.9	0.73	320	29	0.32	0.004 u	0.13 i	33
01/05/2012	113.08	17.88	535	0.2	7.23	22.74	0.44	330	32	0.29	0.004 u	0.097 i	31
02/10/2012	113.86	17.10	511	0.94	7.3	22.89	1.39	310	28	0.28	0.004 u	0.13 i	30
03/07/2012	121.00	9.96	575	0.27	7.15	23.23	0.5	310	25	0.22	0.004 u	0.11 i	31
04/05/2012	124.96	6.00	522	1.09	7.08	23.18	0.65	280	28	0.41	0.004 u	0.11 i	29
05/03/2012	126.55	4.41	746	1.6	6.9	23.46	0.81	380	72	2.3	0.004 u	0.54	49
06/07/2012	120.46	10.50	641	0.72	7.07	23.4	0.26	370	46	1	0.004 u	0.23	37
07/05/2012	104.95	26.01	900	0.23	6.54	23.52	0.4	650	190	2.9 j3	0.004 u	0.39	70
08/03/2012	98.26	32.70	843	0.69	6.77	23.6	2.23	730	210	3	0.004 u	0.48	78
09/06/2012	91.18	39.66	2,357	0.2	6.51	23.62	1.05	1,300	570	12	0.004 u	1.1	170
10/04/2012	90.19	40.77	1,654	0.6	6.43	23.22	0.46	1,500	650	25	0.004 u	1.9	210
11/07/2012	99.29	31.67	2,488	0.76	6.58	23.03	0.74	1,400	540	15	0.004 u	1.4	180
12/05/2012	101.82	29.14	2,416	0.23	6.49	23.18	0.45	1,300	540	13	0.004 u	1.3	180 j3
01/03/2013	100.65	30.31	2,430	1.1	6.44	23.09	0.42	1,400	500	15	0.004 u	1.3	170 j3
02/07/2013	105.58	25.38	2,206	0.6	6.5	23.1	0.22	1,100	470	13	0.004 u	1.1	160
03/07/2013	110.00	20.96	1,234	0.3	6.61	22.85	0.41	770	290	11	0.004 u	1.1	110
04/04/2013	111.35	19.61	1,252	0.33	6.74	23.15	9.9	870	260	10	0.004 u	1	100
05/02/2013	109.56	21.40	1,615	0.18	6.83	23.16	0.45	810	300	8.6	0.004 u	0.87	110
06/04/2013	109.62	21.34	1,440	0.31	7.13	23.3	0.27	850	290	8.4	0.004 u	0.82	120
07/03/2013	98.72	32.24	1,450	0.18	7.03	23.5	0.41	820	280	8.8	0.004 u	0.79	120
08/02/2013	ND	ND	1,256	0.46	6.88	23.43	0.2	800	290	6.8	0.004 u	0.72	120
09/05/2013	87.92	43.04	1,001	0.61	6.98	23.45	1.17	760	290	7.6	0.004 u	0.71	110
10/02/2013	87.39	43.57	1,566	0.32	6.86	23.53	12.6	1,000	350	7.4 j3	0.004 u	0.79	120
11/06/2013	97.90	33.06	2,145	0.16	6.69	23.36	0.8	1,200	450	12	0.004 u	0.64	170
12/05/2013	98.50	32.46	2,615	0.39	6.74	23.45	0.58	1,200	580	16	0.004 u	0.65	200
01/03/2014	99.02	31.94	2,220	0.84	6.83	22.88	1.64	1,200	580	25	0.004 u	0.67	230 j3
02/06/2014	99.50	31.46	2,452	0.13	6.69	23.13	2.07	1,300	580	23 j3	0.004 u	0.71	210
03/04/2014	97.91	33.05	2,173	0.24	6.67	23.4	1.33	1,500	580	22	0.004 u	0.74	220
04/03/2014	96.22	34.74	1,992	0.22	6.74	23.35	1.33	1,400	590	27	0.0013 u	0.71	220

New survey data beginning with 10/4/2012.
u = parameter was analyzed but not detected
i = reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.
j3 = estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
ND = No Data - water levels collected during quarterly ADR.

1,100

EXCEEDS STANDARD

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-73

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
01/27/2011	30.99	100.08	440	1.7	5.53	25.01	22.2	180	69	2.3	0.004 u	15	38
02/03/2011	30.85	100.22	400	1.78	5.62	26.12	17.6	140	56	1.9	0.004 u	31	26
02/10/2011	30.76	100.31	336	1.44	5.62	25.86	12	160	56	2	0.004 u	26	27
02/14/2011	30.82	100.25	312	0.56	5.54	26	15.5	190	55	2.6	0.004 u	34	24
02/24/2011	30.78	100.29	340	0.38	5.62	26.15	16.4	170	61	3	0.004 u	17	28
03/03/2011	30.87	100.20	382	0.53	5.56	26	19.4	200	61	2.1	0.004 u	21	29
03/10/2011	30.87	100.20	371	0.66	5.56	25.97	8.3	170	60	1.7	0.004 u	21	27
03/17/2011	30.76	100.31	266	1.22	5.35	26	14.3	150	69	2.1	0.004 u	12	33
03/24/2011	30.78	100.29	346	0.61	5.47	26.02	8	140	63	2	0.004 u	13	27
04/01/2011	31.11	99.96	366	0.78	5.53	25.89	19.8	160	68	1.7	0.004 u	14	29
04/08/2011	30.65	100.42	331	0.62	5.35	25.97	18	140	66	2.1	0.004 u	11	30
05/05/2011	31.70	99.37	361	0.4	5.34	25.64	12.2	150	66	2	0.004 u	20	28
06/08/2011	32.54	98.53	391	0.7	5.41	25.69	14	150	63	2.2	0.004 u	14	27
07/07/2011	31.55	99.52	306	0.35	5.13	25.34	19.2	350	33	0.52	0.004 u	0.22	31
08/04/2011	31.40	99.67	262	0.89	5.12	25.44	19.9	140	60	1.2	0.004 u	8.2	24
09/08/2011	30.66	100.41	259	0.49	5.24	25.41	28.1	170	62	1.9	0.004 u	8.5	27
10/04/2011	31.16	99.91	345	0.89	5.2	25.48	12	220	96	1.8	0.004 u	9.1	33
11/03/2011	31.27	99.80	1273	0.3	5.21	25.55	8.16	720	360	7.3	0.004 u	22	97
12/08/2011	31.96	99.11	1499	0.62	5.3	25.24	2.64	820	500	3	0.004 u	26	110
01/05/2012	32.31	98.76	1188	0.71	5.16	25.18	2.05	750	350	3.3	0.004 u	19	80
02/10/2012	32.25	98.82	304	0.55	5.28	25.24	3.31	190	67	1.6	0.004 u	4.9	23
03/07/2012	32.42	98.65	312	1.08	5.22	25.24	3.3	150	56	1.2	0.004 u	4.7	22
04/05/2012	32.63	98.44	231	0.79	5.06	24.94	4.39	120	50	1.1	0.004 u	4.1	20
05/03/2012	32.74	98.33	283	0.99	4.8	24.88	6.47	160	63	1.9	0.004 u	4.5	22
06/07/2012	32.40	98.67	224	0.87	4.82	24.64	5.6	140	48	1.6	0.004 u	3.3	18
07/05/2012	31.51	99.56	232	0.31	4.77	24.63	9	140	50	1.7	0.004 u	4	18
08/03/2012	32.09	98.98	201	0.71	5.02	24.63	5.13	160	52	1.7	0.004 u	3.8	19
09/06/2012	31.22	99.76	242	0.5	5.06	24.67	7.39	140	47	1.3	0.004 u	3.6	18
10/04/2012	31.46	99.61	222	0.18	4.86	24.68	7.56	130	43	1.2	0.004 u	3.4	16
11/07/2012	31.84	99.23	231	0.39	5.06	24.75	5.54	130	45	0.94	0.004 u	3.6	16
12/05/2012	32.14	98.93	237	0.2	5.03	24.9	3.26	110	46	0.84	0.004 u	3.5	17
01/03/2013	31.91	99.16	237	0.49	4.95	24.84	2.47	130	45	1.1	0.004 u	3.2	16
02/07/2013	32.11	98.96	221	0.69	4.84	24.79	4.8	120	47	0.84	0.004 u	3	15
03/07/2013	32.41	98.66	179	0.23	4.78	24.46	2.64	110	45	1.2	0.004 u	3.1	17
04/04/2013	32.41	98.66	191	0.2	4.73	24.42	2.49	140	53	1.1	0.004 u	3.4	20
05/02/2013	31.40	99.67	240	0.24	5.12	24.43	8.82	120	52	0.99	0.004 u	3.4	16
08/02/2013	ND	ND	395	0.23	5.13	24.85	10.4	270	130	2.3	0.004 u	7.8	38
11/06/2013	30.36	100.71	319	0.62	5.01	25.54	6.35	200	76	2.2	0.004 u	3.8	25
03/04/2014	30.78	100.29	381	0.39	4.92	25.11	6.23	230	96	1.9	0.004 u	4.6	31

New survey data beginning with 10/4/2012.

u = parameter was analyzed but not detected

NS = No Sample Collected (Surficial wells are now sampled quarterly)

ND = No Data - water levels collected during quarterly ADR.

5.53 EXCEEDS STANDARD

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-74

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
11/03/2011	9.65	ND	485	0.51	5.56	23.62	5.45	280	48	2.9	0.004 u	26	20
12/08/2011	10.11	98.97	445	0.89	5.64	22.9	14.7	270	40	2.3	0.0042 i	27	21
01/05/2012	10.30	98.78	474	0.66	5.66	21.97	16.8	240	59	1.8	0.004 u	30	26
02/10/2012	10.22	98.86	501	0.6	5.42	21.48	9.99	350	95	2.5	0.004 u	34	22
03/07/2012	10.40	98.68	618	0.53	5.24	21.57	8.7	210	120	2.3	0.004 u	38	22
04/05/2012	10.53	98.55	592	0.79	5.13	21.74	13.7	270	120	2.8	0.004 u	40	24
05/03/2012	10.71	98.37	602	0.86	5.15	21.93	12.5	330	110	2.8	0.004 u	38	25
06/07/2012	10.45	98.63	334	0.75	5.35	22.48	6.92	210	37	3	0.004 u	20	16
07/05/2012	9.45	99.63	495	0.32	4.99	23.09	5.33	240	73	2.1	0.004 u	11	27
08/03/2012	9.99	99.09	261	0.37	5.18	23.63	6.12	210	47	3	0.004 u	19	15
09/06/2012	9.36	99.66	578	0.24	5.33	24.08	2.37	330	110	2.8	0.012	21	36
10/04/2012	9.53	99.55	369	0.25	5.36	24.12	3.98	260	76	3.5	0.0055 i	19	22
11/07/2012	9.91	99.17	385	0.36	5.47	23.53	3.21	240	60	1.9	0.0045 i	18	20
12/05/2012	10.14	98.94	398	0.34	5.44	22.82	3.08	230	59	2.7	0.004 u	21	19
01/03/2013	9.96	99.12	418	0.31	5.43	22.03	3.03	280	59	2.7	0.004 u	20	20
02/07/2013	10.16	98.92	394	0.34	5.43	21.66	1.95	200	45	1.9	0.004 u	20	16
03/07/2013	10.23	98.85	363	0.35	5.38	21.06	1.24	180	47	3	0.004 u	20	17
04/04/2013	10.52	98.56	273	0.38	5.34	20.75	5.85	210	43	1.9	0.004 u	20	16
05/02/2013	9.94	99.14	357	0.39	5.61	21.28	2.62	190	37	2.8	0.004 u	21	14
08/02/2013	ND	ND	508	0.29	5.55	23.26	1.3	240	63	3.2	0.004 u	31	20
11/06/2013	9.37	99.71	1,348	1.41	5.43	23.98	9.71	890	370	3.2	0.004 u	60	78
03/04/2014	9.52	99.56	570	0.58	5.55	21.83	2.26	370	95	3.5	0.004 u	29	44

New survey data beginning with 10/4/2012.
u = parameter was analyzed but not detected
i = reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.
NS = No Sample Collected (Surficial wells are now sampled quarterly)
ND = No Data - water levels collected during quarterly ADR.

5.56 EXCEEDS STANDARD

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-75

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
11/03/2011	7.68	ND	396	0.25	5.65	23.63	11.6	220	49	1.4	0.0085 i	11	14
12/08/2011	7.90	99.02	301	0.46	5.57	22.9	20.1	150	23	1.1	0.011	8.9	11
01/05/2012	8.01	98.91	300	0.92	5.58	21.69	18.9	180	25	1.1	0.0071 i	8.6	10
02/10/2012	8.00	98.92	422	0.51	5.48	21.5	17.9	280	81	1.1	0.0072 i	12	20
03/07/2012	8.14	98.78	495	0.26	5.39	21.5	19.6	220	79	0.96	0.0079 i	13	22
04/05/2012	8.15	98.77	584	0.33	5.37	21.76	4.94	300	130	1.3	0.0063 i	16	26
05/03/2012	8.27	98.65	588	0.28	5.32	22.06	0.0	350	120	1.9	0.0078 i	16	33
06/07/2012	8.14	98.78	702	0.39	5.61	22.87	5.69	480	140	1.5	0.0095 i	10	40
07/05/2012	7.36	99.56	344	0.22	5.35	23.52	6.48	180	37	2	0.01	9.8	15
08/03/2012	7.80	99.12	241	0.28	5.28	24.07	4.21	190	25	1.8	0.008 i	8.3	14
09/06/2012	7.42	99.50	360	0.18	5.41	24.5	4.41	200	40	2	0.01	9.1	15
10/04/2012	7.55	99.37	346	0.15	5.35	24.54	6.73	240	51	2.5	0.0084 i	9.2	15
11/07/2012	7.79	99.13	422	0.3	5.48	23.8	2.51	200	54	1.6	0.0086 i	9.8	17
12/05/2012	7.98	98.94	395	0.31	5.5	22.97	7.22	210	48	1.4	0.0067 i	9.2	16
01/03/2013	7.88	99.04	447	0.37	5.53	21.89	13.9	400	60	1.3	0.0065 i	8.1	21
02/07/2013	8.02	98.90	453	0.2	5.48	21.71	6.35	240	62	1.5	0.0076 i	9.8	19
03/07/2013	8.04	98.88	379	0.27	5.4	21.38	2.71	200	40	1.9	0.0061 i	8	17
04/04/2013	8.23	98.69	245	0.25	5.34	21.08	4.92	180	22	1.7	0.0068 i	7.3	14
05/02/2013	8.00	98.92	340	0.21	5.61	21.72	1.59	170	26	1.3	0.0071 i	7.6	13
08/02/2013	ND	ND	356	0.21	5.63	23.9	2.1	170	28	1.3	0.0096 i	7.6	18
11/06/2013	7.81	99.11	353	1.13	5.78	24.32	12.3	200	31	1.3	0.0046 i	6.5	14
03/04/2014	7.87	99.05	338	0.39	5.66	22.51	5.3	200	27	1.5	0.0067 i	6.1	16

New survey data beginning with 10/4/2012.
i = reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.
ND = No Data - water levels collected during quarterly ADR.

5.65 EXCEEDS STANDARD

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-76

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
05/02/2013	89.83	21.38	450	0.22	7.63	22.81	36.9	220	13	0.4	0.004 u	1.1	20
06/04/2013	89.91	21.30	401	0.27	7.86	22.9	16.2	240	13	0.4	0.004 u	0.66	22
07/03/2013	79.04	32.17	398	0.19	8	23	28.6	210	12	0.34	0.004 u	0.99	22
08/02/2013	ND	ND	343	0.22	7.57	23.02	42.2	230	13	0.26	0.004 u	1.6	21
09/05/2013	68.22	42.99	278	0.21	7.74	22.97	46	240	12	0.32	0.004 u	1.5	20
10/02/2013	67.69	43.46	399	0.22	7.61	22.99	61.9	120	13	0.38	0.004 u	1.7	20
11/06/2013	78.19	33.02	446	0.64	7.54	22.84	29	260	13	0.36	0.004 u	1.1	20
12/05/2013	78.80	32.41	478	0.48	7.45	22.9	19.2	240	12	0.35	0.004 u	0.96	20
01/03/2014	79.38	31.83	398	0.58	7.67	22.35	19.4	190	12	0.23 j3	0.004 u	1.1	20
02/06/2014	79.87	31.34	446	0.14	7.54	22.57	18.1	230	12	0.45	0.004 u	0.96	20
03/04/2014	78.20	33.01	434	0.18	7.36	22.7	26.2	230	12	0.33	0.004 u	0.69	20
04/03/2014	76.54	34.67	441	0.18	7.46	22.82	24.7	210	12	0.6	0.0013 u	0.34	19

u = parameter was analyzed but not detected
ND = No Data - water levels collected during quarterly ADR.

1.1	EXCEEDS STANDARD
-----	------------------

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-77

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
05/02/2013	98.31	21.57	440	0.57	7.39	23.39	59.4	190	9.4	0.39	0.004 u	1.2	17
06/04/2013	98.38	21.50	384	0.56	7.86	23.59	35.4	230	8.9	0.42	0.004 u	0.89	18
07/03/2013	87.48	32.40	388	0.41	7.8	23.7	38.4	210	8.9	0.4	0.004 u	1.1	17
08/02/2013	ND	ND	334	0.47	7.44	23.66	42.9	230	9.2	0.36	0.004 u	1.1	18
09/05/2013	76.66	43.22	269	0.83	7.61	23.68	47.1	230	8.9	0.35	0.004 u	0.96	16
10/02/2013	76.14	43.72	383	0.69	7.5	23.59	52.7	240	9.1	0.39	0.004 u	1.3	17
11/06/2013	86.68	33.20	423	0.74	7.43	23.51	25.1	230	9.7	0.36 j3	0.004 u	0.68	17
12/05/2013	87.29	32.59	451	0.9	7.44	23.6	16.4	220	9	0.36	0.004 u	0.58	17
01/03/2014	87.87	32.01	371	0.85	7.65	23.18	16.5	160	9.1	0.39	0.004 u	0.63	17
02/06/2014	88.30	31.58	424	0.09	7.53	23.39	4.62	250	9.2	0.27	0.004 u	0.26	16
03/04/2014	86.70	33.18	418	0.36	7.34	23.38	1.12	230	9.3	0.32	0.004 u	0.21	16
04/03/2014	85.02	34.86	430	0.28	7.45	23.47	1.97	220	9.4	0.61	0.0013 u	0.18	15

u = parameter was analyzed but not detected
j3 = estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
ND = No Data - water levels collected during quarterly ADR.

1.2 EXCEEDS STANDARD

TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Tampa
6712 Benjamin Road
Suite 100
Tampa, FL 33634
Tel: (813)885-7427

TestAmerica Job ID: 660-60510-1

Client Project/Site: SELF IAMP Monitoring Wells

For:

Hillsborough Co Public Utilities Dept
Environmental Services Group
Brandon Support Operations Complex
332 North Falkenburg Rd, 2nd Floor
Tampa, Florida 33619

Attn: David Adams



Authorized for release by:
5/16/2014 12:52:27 PM

Nancy Robertson, Project Manager II
(813)885-7427
nancy.robertson@testamericainc.com

LINKS

Review your project
results through
TotalAccess

Have a Question?



Visit us at:
www.testamericainc.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.

1
2
3
4
5
6
7
8
9
10
11
12
13
14



Table of Contents

Cover Page	1
Table of Contents	2
Sample Summary	3
Case Narrative	4
Definitions/Glossary	5
Detection Summary	6
Client Sample Results	9
QC Sample Results	17
QC Association Summary	23
Lab Chronicle	26
Method Summary	29
Certification Summary	30
Chain of Custody	32
Receipt Checklists	44

Sample Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
660-60510-1	DUPLICATE NOT BLANK	Ground Water	05/06/14 00:00	05/06/14 14:36
660-60510-2	BLANK FIELD	Ground Water	05/06/14 09:58	05/06/14 14:36
660-60510-3	TH-77	Ground Water	05/06/14 10:09	05/06/14 14:36
660-60510-4	TH-76	Ground Water	05/06/14 11:15	05/06/14 14:36
660-60510-5	TH-72	Ground Water	05/06/14 12:33	05/06/14 14:36
660-60541-1	TH-75	Water	05/07/14 12:07	05/07/14 14:12
660-60541-2	TH-74	Water	05/07/14 11:22	05/07/14 14:12
660-60541-3	TH-73	Water	05/07/14 10:39	05/07/14 14:12

Case Narrative

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Job ID: 660-60510-1

Laboratory: TestAmerica Tampa

Narrative

Job Narrative 660-60510-1

Comments

No additional comments.

Receipt

The samples were received on 5/6/2014 2:36 PM and 5/7/2014 2:12 PM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperatures of the 2 coolers at receipt time were 2.9° C and 5.1° C.

Metals

Method 6010B: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for batch 148192 were outside control limits for iron. Sample matrix interference and/or non-homogeneity are suspected because the associated laboratory control sample (LCS) recovery was within acceptance limits. The sample is flagged with J3.

No other analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

General Chemistry

Method 350.1: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for batch 328800 were outside control limits. Sample matrix interference and/or non-homogeneity are suspected because the associated laboratory control sample (LCS) recovery was within acceptance limits.

Method 350.1: The matrix spike / matrix spike duplicate (MS/MSD) recoveries for batch 328800 were outside control limits. Sample matrix interference and/or non-homogeneity are suspected because the associated laboratory control sample (LCS) recovery was within acceptance limits.

No other analytical or quality issues were noted, other than those described in the Definitions/Glossary page.

Definitions/Glossary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Qualifiers

HPLC/IC

Qualifier	Qualifier Description
U	Indicates that the compound was analyzed for but not detected.

Metals

Qualifier	Qualifier Description
U	Indicates that the compound was analyzed for but not detected.
I	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.
J3	Estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.

General Chemistry

Qualifier	Qualifier Description
J3	Estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
U	Indicates that the compound was analyzed for but not detected.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Detection Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: DUPLICATE NOT BLANK

Lab Sample ID: 660-60510-1

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	9.8		0.50	0.25	mg/L	1		300.0	Total/NA
Iron	180	I	200	50	ug/L	1		6010B	Total Recoverable
Sodium	17		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	0.63		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	220		10	10	mg/L	1		SM 2540C	Total/NA

Client Sample ID: BLANK FIELD

Lab Sample ID: 660-60510-2

No Detections.

Client Sample ID: TH-77

Lab Sample ID: 660-60510-3

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	9.7		0.50	0.25	mg/L	1		300.0	Total/NA
Iron	190	I	200	50	ug/L	1		6010B	Total Recoverable
Sodium	17		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	0.59		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	220		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	7.52				SU	1		Field Sampling	Total/NA
Field Temperature	23.47				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.34				mg/L	1		Field Sampling	Total/NA
Specific Conductance	414				uS/cm	1		Field Sampling	Total/NA
Turbidity	1.01				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-76

Lab Sample ID: 660-60510-4

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	12		0.50	0.25	mg/L	1		300.0	Total/NA
Iron	650		200	50	ug/L	1		6010B	Total Recoverable
Sodium	21		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	0.38		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	220		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	7.56				SU	1		Field Sampling	Total/NA
Field Temperature	22.85				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.24				mg/L	1		Field Sampling	Total/NA
Specific Conductance	427				uS/cm	1		Field Sampling	Total/NA
Turbidity	12.7				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-72

Lab Sample ID: 660-60510-5

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	590		10	5.0	mg/L	20		300.0	Total/NA
Iron	640		200	50	ug/L	1		6010B	Total Recoverable
Sodium	230		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	24		1.0	0.52	mg/L	20		350.1	Total/NA

This Detection Summary does not include radiochemical test results.

TestAmerica Tampa

Detection Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-72 (Continued)

Lab Sample ID: 660-60510-5

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Total Dissolved Solids	1400		25	25	mg/L	1		SM 2540C	Total/NA
Field pH	6.81				SU	1		Field Sampling	Total/NA
Field Temperature	23.50				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.46				mg/L	1		Field Sampling	Total/NA
Specific Conductance	2247				uS/cm	1		Field Sampling	Total/NA
Turbidity	1.22				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-75

Lab Sample ID: 660-60541-1

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	27		0.50	0.25	mg/L	1		300.0	Total/NA
Arsenic	6.6	I	10	4.0	ug/L	1		6010B	Total Recoverable
Iron	6100	J3	200	50	ug/L	1		6010B	Total Recoverable
Sodium	18		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	1.8		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	200		5.0	5.0	mg/L	1		SM 2540C	Total/NA
Field pH	5.67				SU	1		Field Sampling	Total/NA
Field Temperature	22.61				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.37				mg/L	1		Field Sampling	Total/NA
Specific Conductance	341				uS/cm	1		Field Sampling	Total/NA
Turbidity	3.01				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-74

Lab Sample ID: 660-60541-2

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	92		2.0	1.0	mg/L	4		300.0	Total/NA
Iron	31000		200	50	ug/L	1		6010B	Total Recoverable
Sodium	40		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	3.1		0.10	0.052	mg/L	2		350.1	Total/NA
Total Dissolved Solids	310		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	5.56				SU	1		Field Sampling	Total/NA
Field Temperature	22.06				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.57				mg/L	1		Field Sampling	Total/NA
Specific Conductance	549				uS/cm	1		Field Sampling	Total/NA
Turbidity	3.93				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-73

Lab Sample ID: 660-60541-3

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	90		2.0	1.0	mg/L	4		300.0	Total/NA
Iron	4000		200	50	ug/L	1		6010B	Total Recoverable
Sodium	31		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	3.3		0.10	0.052	mg/L	2		350.1	Total/NA
Total Dissolved Solids	210		5.0	5.0	mg/L	1		SM 2540C	Total/NA
Field pH	5.05				SU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

TestAmerica Tampa

Detection Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-73 (Continued)

Lab Sample ID: 660-60541-3

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Field Temperature	25.59				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	1.13				mg/L	1		Field Sampling	Total/NA
Specific Conductance	340				uS/cm	1		Field Sampling	Total/NA
Turbidity	4.01				NTU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: DUPLICATE NOT BLANK

Lab Sample ID: 660-60510-1

Date Collected: 05/06/14 00:00

Matrix: Ground Water

Date Received: 05/06/14 14:36

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	9.8		0.50	0.25	mg/L			05/13/14 15:38	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 09:10	1
Iron	180	I	200	50	ug/L		05/07/14 08:54	05/08/14 09:10	1
Sodium	17		0.50	0.31	mg/L		05/07/14 08:54	05/08/14 09:10	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.63		0.050	0.026	mg/L			05/08/14 08:37	1
Total Dissolved Solids	220		10	10	mg/L			05/07/14 10:15	1

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: BLANK FIELD

Lab Sample ID: 660-60510-2

Date Collected: 05/06/14 09:58

Matrix: Ground Water

Date Received: 05/06/14 14:36

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			05/13/14 15:53	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 09:14	1
Iron	50	U	200	50	ug/L		05/07/14 08:54	05/08/14 09:14	1
Sodium	0.31	U	0.50	0.31	mg/L		05/07/14 08:54	05/08/14 09:14	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.026	U	0.050	0.026	mg/L			05/13/14 08:45	1
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L			05/07/14 10:15	1

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-77

Date Collected: 05/06/14 10:09

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-3

Matrix: Ground Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	9.7		0.50	0.25	mg/L			05/13/14 16:08	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 09:17	1
Iron	190	I	200	50	ug/L		05/07/14 08:54	05/08/14 09:17	1
Sodium	17		0.50	0.31	mg/L		05/07/14 08:54	05/08/14 09:17	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.59		0.050	0.026	mg/L			05/07/14 16:44	1
Total Dissolved Solids	220		10	10	mg/L			05/07/14 10:15	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.52				SU			05/06/14 10:09	1
Field Temperature	23.47				Degrees C			05/06/14 10:09	1
Oxygen, Dissolved	0.34				mg/L			05/06/14 10:09	1
Specific Conductance	414				uS/cm			05/06/14 10:09	1
Turbidity	1.01				NTU			05/06/14 10:09	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-76

Date Collected: 05/06/14 11:15

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-4

Matrix: Ground Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	12		0.50	0.25	mg/L			05/13/14 16:24	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 09:20	1
Iron	650		200	50	ug/L		05/07/14 08:54	05/08/14 09:20	1
Sodium	21		0.50	0.31	mg/L		05/07/14 08:54	05/08/14 09:20	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.38		0.050	0.026	mg/L			05/07/14 16:44	1
Total Dissolved Solids	220		10	10	mg/L			05/07/14 10:15	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.56				SU			05/06/14 11:15	1
Field Temperature	22.85				Degrees C			05/06/14 11:15	1
Oxygen, Dissolved	0.24				mg/L			05/06/14 11:15	1
Specific Conductance	427				uS/cm			05/06/14 11:15	1
Turbidity	12.7				NTU			05/06/14 11:15	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-72

Date Collected: 05/06/14 12:33

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-5

Matrix: Ground Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	590		10	5.0	mg/L			05/13/14 16:39	20

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 09:24	1
Iron	640		200	50	ug/L		05/07/14 08:54	05/08/14 09:24	1
Sodium	230		0.50	0.31	mg/L		05/07/14 08:54	05/08/14 09:24	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	24		1.0	0.52	mg/L			05/08/14 08:46	20
Total Dissolved Solids	1400		25	25	mg/L			05/07/14 10:15	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	6.81				SU			05/06/14 12:33	1
Field Temperature	23.50				Degrees C			05/06/14 12:33	1
Oxygen, Dissolved	0.46				mg/L			05/06/14 12:33	1
Specific Conductance	2247				uS/cm			05/06/14 12:33	1
Turbidity	1.22				NTU			05/06/14 12:33	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-75

Date Collected: 05/07/14 12:07

Date Received: 05/07/14 14:12

Lab Sample ID: 660-60541-1

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	27		0.50	0.25	mg/L			05/13/14 19:58	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	6.6	I	10	4.0	ug/L		05/08/14 08:16	05/09/14 08:57	1
Iron	6100	J3	200	50	ug/L		05/08/14 08:16	05/09/14 08:57	1
Sodium	18		0.50	0.31	mg/L		05/08/14 08:16	05/09/14 08:57	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	1.8		0.050	0.026	mg/L			05/13/14 08:54	1
Total Dissolved Solids	200		5.0	5.0	mg/L			05/09/14 12:36	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	5.67				SU			05/07/14 12:07	1
Field Temperature	22.61				Degrees C			05/07/14 12:07	1
Oxygen, Dissolved	0.37				mg/L			05/07/14 12:07	1
Specific Conductance	341				uS/cm			05/07/14 12:07	1
Turbidity	3.01				NTU			05/07/14 12:07	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-74

Date Collected: 05/07/14 11:22

Date Received: 05/07/14 14:12

Lab Sample ID: 660-60541-2

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	92		2.0	1.0	mg/L			05/13/14 20:14	4

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/08/14 08:16	05/09/14 09:07	1
Iron	31000		200	50	ug/L		05/08/14 08:16	05/09/14 09:07	1
Sodium	40		0.50	0.31	mg/L		05/08/14 08:16	05/09/14 09:07	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	3.1		0.10	0.052	mg/L			05/13/14 10:03	2
Total Dissolved Solids	310		10	10	mg/L			05/09/14 12:36	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	5.56				SU			05/07/14 11:22	1
Field Temperature	22.06				Degrees C			05/07/14 11:22	1
Oxygen, Dissolved	0.57				mg/L			05/07/14 11:22	1
Specific Conductance	549				uS/cm			05/07/14 11:22	1
Turbidity	3.93				NTU			05/07/14 11:22	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-73

Date Collected: 05/07/14 10:39

Date Received: 05/07/14 14:12

Lab Sample ID: 660-60541-3

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	90		2.0	1.0	mg/L			05/13/14 21:30	4

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/08/14 08:16	05/09/14 09:10	1
Iron	4000		200	50	ug/L		05/08/14 08:16	05/09/14 09:10	1
Sodium	31		0.50	0.31	mg/L		05/08/14 08:16	05/09/14 09:10	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	3.3		0.10	0.052	mg/L			05/13/14 10:03	2
Total Dissolved Solids	210		5.0	5.0	mg/L			05/09/14 12:36	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	5.05				SU			05/07/14 10:39	1
Field Temperature	25.59				Degrees C			05/07/14 10:39	1
Oxygen, Dissolved	1.13				mg/L			05/07/14 10:39	1
Specific Conductance	340				uS/cm			05/07/14 10:39	1
Turbidity	4.01				NTU			05/07/14 10:39	1

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 680-328824/2

Matrix: Water

Analysis Batch: 328824

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			05/13/14 12:34	1

Lab Sample ID: LCS 680-328824/3

Matrix: Water

Analysis Batch: 328824

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	10.0	10.2		mg/L		102	90 - 110

Lab Sample ID: LCSD 680-328824/4

Matrix: Water

Analysis Batch: 328824

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	10.0	10.2		mg/L		102	90 - 110	0	30

Lab Sample ID: 660-60510-5 MS

Matrix: Ground Water

Analysis Batch: 328824

Client Sample ID: TH-72

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	590		200	790		mg/L		99	80 - 120

Lab Sample ID: 660-60510-5 MSD

Matrix: Ground Water

Analysis Batch: 328824

Client Sample ID: TH-72

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	590		200	792		mg/L		100	80 - 120	0	30

Lab Sample ID: MB 680-328853/24

Matrix: Water

Analysis Batch: 328853

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			05/13/14 17:40	1

Lab Sample ID: LCS 680-328853/25

Matrix: Water

Analysis Batch: 328853

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	10.0	10.3		mg/L		103	90 - 110

Lab Sample ID: LCSD 680-328853/26

Matrix: Water

Analysis Batch: 328853

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	10.0	10.2		mg/L		102	90 - 110	0	30

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Lab Sample ID: 660-60541-2 MS

Matrix: Water

Analysis Batch: 328853

Client Sample ID: TH-74

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	92		40.0	133		mg/L		101	80 - 120

Lab Sample ID: 660-60541-2 MSD

Matrix: Water

Analysis Batch: 328853

Client Sample ID: TH-74

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	92		40.0	133		mg/L		103	80 - 120	1	30

Method: 6010B - Metals (ICP)

Lab Sample ID: MB 660-148116/1-A

Matrix: Water

Analysis Batch: 148159

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 148116

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/07/14 08:54	05/08/14 08:24	1
Iron	50	U	200	50	ug/L		05/07/14 08:54	05/08/14 08:24	1
Sodium	0.31	U	0.50	0.31	mg/L		05/07/14 08:54	05/08/14 08:24	1

Lab Sample ID: LCS 660-148116/2-A

Matrix: Water

Analysis Batch: 148159

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 148116

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	1000	1030		ug/L		103	80 - 120
Iron	1000	1060		ug/L		106	80 - 120
Sodium	10.0	10.4		mg/L		104	80 - 120

Lab Sample ID: 640-47760-A-1-B MS

Matrix: Water

Analysis Batch: 148159

Client Sample ID: Matrix Spike

Prep Type: Total Recoverable

Prep Batch: 148116

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	4.0	U	1000	1040		ug/L		104	80 - 120
Iron	970		1000	2040		ug/L		108	80 - 120
Sodium	0.86		10.0	11.1		mg/L		103	80 - 120

Lab Sample ID: 640-47760-A-1-C MSD

Matrix: Water

Analysis Batch: 148159

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total Recoverable

Prep Batch: 148116

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Arsenic	4.0	U	1000	1030		ug/L		103	80 - 120	1	20
Iron	970		1000	2050		ug/L		108	80 - 120	0	20
Sodium	0.86		10.0	11.0		mg/L		101	80 - 120	1	20

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Method: 6010B - Metals (ICP) (Continued)

Lab Sample ID: MB 660-148149/1-A

Matrix: Water

Analysis Batch: 148192

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 148149

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		05/08/14 08:16	05/09/14 08:08	1
Iron	50	U	200	50	ug/L		05/08/14 08:16	05/09/14 08:08	1
Sodium	0.31	U	0.50	0.31	mg/L		05/08/14 08:16	05/09/14 08:08	1

Lab Sample ID: LCS 660-148149/2-A

Matrix: Water

Analysis Batch: 148192

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 148149

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	1000	1040		ug/L		104	80 - 120
Iron	1000	1070		ug/L		107	80 - 120
Sodium	10.0	10.4		mg/L		104	80 - 120

Lab Sample ID: 660-60541-1 MS

Matrix: Water

Analysis Batch: 148192

Client Sample ID: TH-75

Prep Type: Total Recoverable

Prep Batch: 148149

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	6.6	I	1000	1070		ug/L		106	80 - 120
Iron	6100	J3	1000	7190		ug/L		110	80 - 120
Sodium	18		10.0	28.7		mg/L		109	80 - 120

Lab Sample ID: 660-60541-1 MSD

Matrix: Water

Analysis Batch: 148192

Client Sample ID: TH-75

Prep Type: Total Recoverable

Prep Batch: 148149

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Arsenic	6.6	I	1000	1080		ug/L		108	80 - 120	1	20
Iron	6100	J3	1000	7300	J3	ug/L		121	80 - 120	2	20
Sodium	18		10.0	28.8		mg/L		110	80 - 120	0	20

Method: 350.1 - Nitrogen, Ammonia

Lab Sample ID: MB 680-328075/2

Matrix: Water

Analysis Batch: 328075

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.026	U	0.050	0.026	mg/L			05/07/14 16:44	1

Lab Sample ID: LCS 680-328075/1

Matrix: Water

Analysis Batch: 328075

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	1.00	0.948		mg/L		95	90 - 110

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Method: 350.1 - Nitrogen, Ammonia (Continued)

Lab Sample ID: 660-60510-4 MS

Matrix: Ground Water

Analysis Batch: 328075

Client Sample ID: TH-76

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	0.38		1.00	1.38		mg/L		100	90 - 110

Lab Sample ID: 660-60510-4 MSD

Matrix: Ground Water

Analysis Batch: 328075

Client Sample ID: TH-76

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	0.38		1.00	1.38		mg/L		100	90 - 110	0	30

Lab Sample ID: 660-60510-3 DU

Matrix: Ground Water

Analysis Batch: 328075

Client Sample ID: TH-77

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Ammonia as N	0.59		0.569		mg/L		3	30

Lab Sample ID: MB 680-328799/50

Matrix: Water

Analysis Batch: 328799

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.026	U	0.050	0.026	mg/L			05/13/14 10:32	1

Lab Sample ID: LCS 680-328799/32

Matrix: Water

Analysis Batch: 328799

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	1.00	0.943		mg/L		94	90 - 110

Lab Sample ID: 640-47821-F-2 MS

Matrix: Water

Analysis Batch: 328799

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	11	J3	1.00	12.0	J3	mg/L		64	90 - 110

Lab Sample ID: 640-47821-F-2 MSD

Matrix: Water

Analysis Batch: 328799

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	11	J3	1.00	11.8	J3	mg/L		48	90 - 110	1	30

Lab Sample ID: 640-47821-F-3 DU

Matrix: Water

Analysis Batch: 328799

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Ammonia as N	11		10.7		mg/L		1	30

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Lab Sample ID: MB 680-328800/18

Matrix: Water

Analysis Batch: 328800

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.026	U	0.050	0.026	mg/L	-		05/13/14 09:03	1

Lab Sample ID: LCS 680-328800/24

Matrix: Water

Analysis Batch: 328800

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	1.00	0.943		mg/L	-	94	90 - 110

Lab Sample ID: 680-101050-C-1 MS

Matrix: Water

Analysis Batch: 328800

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as N	0.65	J3	1.00	0.713	J3	mg/L	-	6	90 - 110

Lab Sample ID: 680-101050-C-1 MSD

Matrix: Water

Analysis Batch: 328800

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as N	0.65	J3	1.00	0.725	J3	mg/L	-	7	90 - 110	2	30

Lab Sample ID: 660-60541-1 DU

Matrix: Water

Analysis Batch: 328800

Client Sample ID: TH-75

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Ammonia as N	1.8		1.82		mg/L	-	4	30

Method: SM 2540C - Solids, Total Dissolved (TDS)

Lab Sample ID: MB 660-148122/1

Matrix: Water

Analysis Batch: 148122

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L	-		05/07/14 10:15	1

Lab Sample ID: LCS 660-148122/2

Matrix: Water

Analysis Batch: 148122

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Dissolved Solids	10000	9880		mg/L	-	99	80 - 120

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Method: SM 2540C - Solids, Total Dissolved (TDS) (Continued)

Lab Sample ID: 660-60510-5 DU
Matrix: Ground Water
Analysis Batch: 148122

Client Sample ID: TH-72
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	Limit
Total Dissolved Solids	1400		1340		mg/L		3	20

Lab Sample ID: MB 660-148198/1
Matrix: Water
Analysis Batch: 148198

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L			05/09/14 12:36	1

Lab Sample ID: LCS 660-148198/2
Matrix: Water
Analysis Batch: 148198

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Dissolved Solids	10000	9970		mg/L		100	80 - 120

Lab Sample ID: 660-60541-2 DU
Matrix: Water
Analysis Batch: 148198

Client Sample ID: TH-74
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	Limit
Total Dissolved Solids	310		328		mg/L		5	20

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

HPLC/IC

Analysis Batch: 328824

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60510-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	300.0	
660-60510-2	BLANK FIELD	Total/NA	Ground Water	300.0	
660-60510-3	TH-77	Total/NA	Ground Water	300.0	
660-60510-4	TH-76	Total/NA	Ground Water	300.0	
660-60510-5	TH-72	Total/NA	Ground Water	300.0	
660-60510-5 MS	TH-72	Total/NA	Ground Water	300.0	
660-60510-5 MSD	TH-72	Total/NA	Ground Water	300.0	
LCS 680-328824/3	Lab Control Sample	Total/NA	Water	300.0	
LCSD 680-328824/4	Lab Control Sample Dup	Total/NA	Water	300.0	
MB 680-328824/2	Method Blank	Total/NA	Water	300.0	

Analysis Batch: 328853

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total/NA	Water	300.0	
660-60541-2	TH-74	Total/NA	Water	300.0	
660-60541-2 MS	TH-74	Total/NA	Water	300.0	
660-60541-2 MSD	TH-74	Total/NA	Water	300.0	
660-60541-3	TH-73	Total/NA	Water	300.0	
LCS 680-328853/25	Lab Control Sample	Total/NA	Water	300.0	
LCSD 680-328853/26	Lab Control Sample Dup	Total/NA	Water	300.0	
MB 680-328853/24	Method Blank	Total/NA	Water	300.0	

Metals

Prep Batch: 148116

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-47760-A-1-B MS	Matrix Spike	Total Recoverable	Water	3005A	
640-47760-A-1-C MSD	Matrix Spike Duplicate	Total Recoverable	Water	3005A	
660-60510-1	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	3005A	
660-60510-2	BLANK FIELD	Total Recoverable	Ground Water	3005A	
660-60510-3	TH-77	Total Recoverable	Ground Water	3005A	
660-60510-4	TH-76	Total Recoverable	Ground Water	3005A	
660-60510-5	TH-72	Total Recoverable	Ground Water	3005A	
LCS 660-148116/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
MB 660-148116/1-A	Method Blank	Total Recoverable	Water	3005A	

Prep Batch: 148149

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total Recoverable	Water	3005A	
660-60541-1 MS	TH-75	Total Recoverable	Water	3005A	
660-60541-1 MSD	TH-75	Total Recoverable	Water	3005A	
660-60541-2	TH-74	Total Recoverable	Water	3005A	
660-60541-3	TH-73	Total Recoverable	Water	3005A	
LCS 660-148149/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
MB 660-148149/1-A	Method Blank	Total Recoverable	Water	3005A	

Analysis Batch: 148159

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-47760-A-1-B MS	Matrix Spike	Total Recoverable	Water	6010B	148116
640-47760-A-1-C MSD	Matrix Spike Duplicate	Total Recoverable	Water	6010B	148116

TestAmerica Tampa

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Metals (Continued)

Analysis Batch: 148159 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60510-1	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	6010B	148116
660-60510-2	BLANK FIELD	Total Recoverable	Ground Water	6010B	148116
660-60510-3	TH-77	Total Recoverable	Ground Water	6010B	148116
660-60510-4	TH-76	Total Recoverable	Ground Water	6010B	148116
660-60510-5	TH-72	Total Recoverable	Ground Water	6010B	148116
LCS 660-148116/2-A	Lab Control Sample	Total Recoverable	Water	6010B	148116
MB 660-148116/1-A	Method Blank	Total Recoverable	Water	6010B	148116

Analysis Batch: 148192

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total Recoverable	Water	6010B	148149
660-60541-1 MS	TH-75	Total Recoverable	Water	6010B	148149
660-60541-1 MSD	TH-75	Total Recoverable	Water	6010B	148149
660-60541-2	TH-74	Total Recoverable	Water	6010B	148149
660-60541-3	TH-73	Total Recoverable	Water	6010B	148149
LCS 660-148149/2-A	Lab Control Sample	Total Recoverable	Water	6010B	148149
MB 660-148149/1-A	Method Blank	Total Recoverable	Water	6010B	148149

General Chemistry

Analysis Batch: 148122

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60510-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	SM 2540C	
660-60510-2	BLANK FIELD	Total/NA	Ground Water	SM 2540C	
660-60510-3	TH-77	Total/NA	Ground Water	SM 2540C	
660-60510-4	TH-76	Total/NA	Ground Water	SM 2540C	
660-60510-5	TH-72	Total/NA	Ground Water	SM 2540C	
660-60510-5 DU	TH-72	Total/NA	Ground Water	SM 2540C	
LCS 660-148122/2	Lab Control Sample	Total/NA	Water	SM 2540C	
MB 660-148122/1	Method Blank	Total/NA	Water	SM 2540C	

Analysis Batch: 148198

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total/NA	Water	SM 2540C	
660-60541-2	TH-74	Total/NA	Water	SM 2540C	
660-60541-2 DU	TH-74	Total/NA	Water	SM 2540C	
660-60541-3	TH-73	Total/NA	Water	SM 2540C	
LCS 660-148198/2	Lab Control Sample	Total/NA	Water	SM 2540C	
MB 660-148198/1	Method Blank	Total/NA	Water	SM 2540C	

Analysis Batch: 328075

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60510-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	350.1	
660-60510-3	TH-77	Total/NA	Ground Water	350.1	
660-60510-3 DU	TH-77	Total/NA	Ground Water	350.1	
660-60510-4	TH-76	Total/NA	Ground Water	350.1	
660-60510-4 MS	TH-76	Total/NA	Ground Water	350.1	
660-60510-4 MSD	TH-76	Total/NA	Ground Water	350.1	
660-60510-5	TH-72	Total/NA	Ground Water	350.1	
LCS 680-328075/1	Lab Control Sample	Total/NA	Water	350.1	

TestAmerica Tampa

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

General Chemistry (Continued)

Analysis Batch: 328075 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
MB 680-328075/2	Method Blank	Total/NA	Water	350.1	

Analysis Batch: 328799

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-47821-F-2 MS	Matrix Spike	Total/NA	Water	350.1	
640-47821-F-2 MSD	Matrix Spike Duplicate	Total/NA	Water	350.1	
640-47821-F-3 DU	Duplicate	Total/NA	Water	350.1	
660-60510-2	BLANK FIELD	Total/NA	Ground Water	350.1	
LCS 680-328799/32	Lab Control Sample	Total/NA	Water	350.1	
MB 680-328799/50	Method Blank	Total/NA	Water	350.1	

Analysis Batch: 328800

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total/NA	Water	350.1	
660-60541-1 DU	TH-75	Total/NA	Water	350.1	
660-60541-2	TH-74	Total/NA	Water	350.1	
660-60541-3	TH-73	Total/NA	Water	350.1	
680-101050-C-1 MS	Matrix Spike	Total/NA	Water	350.1	
680-101050-C-1 MSD	Matrix Spike Duplicate	Total/NA	Water	350.1	
LCS 680-328800/24	Lab Control Sample	Total/NA	Water	350.1	
MB 680-328800/18	Method Blank	Total/NA	Water	350.1	

Field Service / Mobile Lab

Analysis Batch: 148132

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60510-3	TH-77	Total/NA	Ground Water	Field Sampling	
660-60510-4	TH-76	Total/NA	Ground Water	Field Sampling	
660-60510-5	TH-72	Total/NA	Ground Water	Field Sampling	

Analysis Batch: 148218

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-60541-1	TH-75	Total/NA	Water	Field Sampling	
660-60541-2	TH-74	Total/NA	Water	Field Sampling	
660-60541-3	TH-73	Total/NA	Water	Field Sampling	

Lab Chronicle

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: DUPLICATE NOT BLANK

Date Collected: 05/06/14 00:00

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-1

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	328824	05/13/14 15:38	DAS	TAL SAV
Total Recoverable	Prep	3005A			148116	05/07/14 08:54	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148159	05/08/14 09:10	GAF	TAL TAM
Total/NA	Analysis	350.1		1	328075	05/08/14 08:37	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148122	05/07/14 10:15	TKO	TAL TAM

Client Sample ID: BLANK FIELD

Date Collected: 05/06/14 09:58

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-2

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	328824	05/13/14 15:53	DAS	TAL SAV
Total Recoverable	Prep	3005A			148116	05/07/14 08:54	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148159	05/08/14 09:14	GAF	TAL TAM
Total/NA	Analysis	350.1		1	328799	05/13/14 08:45	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148122	05/07/14 10:15	TKO	TAL TAM

Client Sample ID: TH-77

Date Collected: 05/06/14 10:09

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-3

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	328824	05/13/14 16:08	DAS	TAL SAV
Total Recoverable	Prep	3005A			148116	05/07/14 08:54	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148159	05/08/14 09:17	GAF	TAL TAM
Total/NA	Analysis	350.1		1	328075	05/07/14 16:44	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148122	05/07/14 10:15	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	148132	05/06/14 10:09		TAL TAM

Client Sample ID: TH-76

Date Collected: 05/06/14 11:15

Date Received: 05/06/14 14:36

Lab Sample ID: 660-60510-4

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	328824	05/13/14 16:24	DAS	TAL SAV
Total Recoverable	Prep	3005A			148116	05/07/14 08:54	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148159	05/08/14 09:20	GAF	TAL TAM
Total/NA	Analysis	350.1		1	328075	05/07/14 16:44	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148122	05/07/14 10:15	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	148132	05/06/14 11:15		TAL TAM

TestAmerica Tampa

Lab Chronicle

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-72

Lab Sample ID: 660-60510-5

Date Collected: 05/06/14 12:33

Matrix: Ground Water

Date Received: 05/06/14 14:36

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		20	328824	05/13/14 16:39	DAS	TAL SAV
Total Recoverable	Prep	3005A			148116	05/07/14 08:54	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148159	05/08/14 09:24	GAF	TAL TAM
Total/NA	Analysis	350.1		20	328075	05/08/14 08:46	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148122	05/07/14 10:15	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	148132	05/06/14 12:33		TAL TAM

Client Sample ID: TH-75

Lab Sample ID: 660-60541-1

Date Collected: 05/07/14 12:07

Matrix: Water

Date Received: 05/07/14 14:12

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	328853	05/13/14 19:58	DAS	TAL SAV
Total Recoverable	Prep	3005A			148149	05/08/14 08:16	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148192	05/09/14 08:57	GAF	TAL TAM
Total/NA	Analysis	350.1		1	328800	05/13/14 08:54	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148198	05/09/14 12:36	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	148218	05/07/14 12:07		TAL TAM

Client Sample ID: TH-74

Lab Sample ID: 660-60541-2

Date Collected: 05/07/14 11:22

Matrix: Water

Date Received: 05/07/14 14:12

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		4	328853	05/13/14 20:14	DAS	TAL SAV
Total Recoverable	Prep	3005A			148149	05/08/14 08:16	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148192	05/09/14 09:07	GAF	TAL TAM
Total/NA	Analysis	350.1		2	328800	05/13/14 10:03	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148198	05/09/14 12:36	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	148218	05/07/14 11:22		TAL TAM

Client Sample ID: TH-73

Lab Sample ID: 660-60541-3

Date Collected: 05/07/14 10:39

Matrix: Water

Date Received: 05/07/14 14:12

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		4	328853	05/13/14 21:30	DAS	TAL SAV
Total Recoverable	Prep	3005A			148149	05/08/14 08:16	ALQ	TAL TAM
Total Recoverable	Analysis	6010B		1	148192	05/09/14 09:10	GAF	TAL TAM
Total/NA	Analysis	350.1		2	328800	05/13/14 10:03	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	148198	05/09/14 12:36	TKO	TAL TAM

TestAmerica Tampa

Lab Chronicle

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Client Sample ID: TH-73

Date Collected: 05/07/14 10:39

Date Received: 05/07/14 14:12

Lab Sample ID: 660-60541-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	Field Sampling		1	148218	05/07/14 10:39		TAL TAM

Laboratory References:

TAL SAV = TestAmerica Savannah, 5102 LaRoche Avenue, Savannah, GA 31404, TEL (912)354-7858

TAL TAM = TestAmerica Tampa, 6712 Benjamin Road, Suite 100, Tampa, FL 33634, TEL (813)885-7427

Method Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Method	Method Description	Protocol	Laboratory
300.0	Anions, Ion Chromatography	MCAWW	TAL SAV
6010B	Metals (ICP)	SW846	TAL TAM
350.1	Nitrogen, Ammonia	MCAWW	TAL SAV
SM 2540C	Solids, Total Dissolved (TDS)	SM	TAL TAM
Field Sampling	Field Sampling	EPA	TAL TAM

Protocol References:

EPA = US Environmental Protection Agency

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

SM = "Standard Methods For The Examination Of Water And Wastewater",

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL SAV = TestAmerica Savannah, 5102 LaRoche Avenue, Savannah, GA 31404, TEL (912)354-7858

TAL TAM = TestAmerica Tampa, 6712 Benjamin Road, Suite 100, Tampa, FL 33634, TEL (813)885-7427

Certification Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Laboratory: TestAmerica Tampa

The certifications listed below are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
Florida	NELAP	4	E84282	06-30-14

Laboratory: TestAmerica Savannah

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
	AFCEE		SAVLAB	
A2LA	DoD ELAP		399.01	02-28-15
A2LA	ISO/IEC 17025		399.01	02-28-15
Alabama	State Program	4	41450	06-30-14 *
Arkansas DEQ	State Program	6	88-0692	01-31-15
California	NELAP	9	3217CA	07-31-14
Colorado	State Program	8	N/A	12-31-14
Connecticut	State Program	1	PH-0161	03-31-15
Florida	NELAP	4	E87052	06-30-14 *
GA Dept. of Agriculture	State Program	4	N/A	06-30-14 *
Georgia	State Program	4	N/A	06-30-14 *
Georgia	State Program	4	803	06-30-14 *
Guam	State Program	9	09-005r	04-16-15
Hawaii	State Program	9	N/A	06-30-14 *
Illinois	NELAP	5	200022	11-30-14
Indiana	State Program	5	N/A	06-30-14 *
Iowa	State Program	7	353	07-01-15
Kentucky (DW)	State Program	4	90084	12-31-14
Kentucky (UST)	State Program	4	18	06-30-14 *
Louisiana	NELAP	6	LA100015	12-31-14
Maine	State Program	1	GA00006	08-16-14
Maryland	State Program	3	250	12-31-14
Massachusetts	State Program	1	M-GA006	06-30-14 *
Michigan	State Program	5	9925	06-30-14 *
Mississippi	State Program	4	N/A	06-30-14 *
Montana	State Program	8	CERT0081	01-01-15
Nebraska	State Program	7	TestAmerica-Savannah	06-30-14 *
New Jersey	NELAP	2	GA769	06-30-14 *
New Mexico	State Program	6	N/A	06-30-14 *
New York	NELAP	2	10842	03-31-15
North Carolina DENR	State Program	4	269	12-31-14
North Carolina DHHS	State Program	4	13701	07-31-14
Oklahoma	State Program	6	9984	08-31-14
Pennsylvania	NELAP	3	68-00474	06-30-14 *
Puerto Rico	State Program	2	GA00006	12-31-14
South Carolina	State Program	4	98001	06-30-14 *
Tennessee	State Program	4	TN02961	06-30-14 *
Texas	NELAP	6	T104704185-08-TX	11-30-14
USDA	Federal		SAV 3-04	04-07-14 *
Virginia	NELAP	3	460161	06-14-14 *
Washington	State Program	10	C805	06-10-14 *
West Virginia DEP	State Program	3	94	06-30-14 *
West Virginia DHHR	State Program	3	9950C	12-31-14
Wisconsin	State Program	5	999819810	08-31-14

* Expired certification is currently pending renewal and is considered valid.

TestAmerica Tampa

Certification Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF IAMP Monitoring Wells

TestAmerica Job ID: 660-60510-1

Laboratory: TestAmerica Savannah (Continued)

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
Wyoming	State Program	8	8TMS-L	06-30-14 *

* Expired certification is currently pending renewal and is considered valid.

TestAmerica Tampa

ANALYSIS REQUEST AND CHAIN OF CUSTODY RECORD										TestAmerica		www.testamericainc.com	
<div style="display: flex; justify-content: space-between;"> <div> <p>PROJECT REFERENCE SELF-IAMP Monitoring Wells</p> <p>TESTAMERICA (LAB) PROJECT MANAGER Nancy Robertson</p> <p>CLIENT (SITE) PM Michael Townsel</p> <p>CLIENT NAME Hills. County Public Utilities</p> <p>CLIENT ADDRESS 332 North Falkenburg Road</p> <p>COMPANY CONTRACTING THIS WORK</p> </div> <div> <p>PROJECT NO</p> <p>P.O. NUMBER</p> <p>CLIENT PHONE (813) 663-3222</p> <p>CLIENT FAX (813) 274-6801</p> <p>CLIENT EMAIL townselm@hillsboroughcounty.org</p> <p>SAMPLER'S SIGNATURE <i>[Signature]</i></p> </div> <div> <p>PROJECT LOCATION Lithia, FL</p> <p>CONTRACT NO</p> <p>CLIENT FAX (813) 274-6801</p> </div> </div>										<p>TestAmerica Tampa</p> <p>6712 Benjamin Rd, Suite 100</p> <p>Tampa, FL 33634</p> <p>Phone: (813) 885 7427</p> <p>Fax: (813) 885 7049</p>		<p>Alternate Laboratory Name/Location:</p> <p>Phone:</p> <p>Fax:</p>	
<p>STANDARD REPORT DELIVERY <input type="radio"/></p> <p>DATE DUE</p> <p>EXPEDITED REPORT DELIVERY (SURCHARGE) <input type="radio"/></p> <p>DATE DUE</p>										<p>NUMBER OF COOLERS SUBMITTED PER SHIPMENT</p>			
<p>COMPOSITE (C) OR GRAB (G) INDICATE</p> <p>AQUEOUS (WATER)</p> <p>SOLID OR SEMISOLID</p> <p>AIR</p> <p>NONAQUEOUS LIQUID (OIL, SOLVENT)</p>										<p>Ammonia-N</p> <p>TDS</p> <p>Chloride</p> <p>As, Fe, Na</p> <p>HNO3</p>			
<p>DATE</p> <p>TIME</p> <p>SAMPLE IDENTIFICATION</p>										<p>NUMBER OF CONTAINERS SUBMITTED</p>		<p>REMARKS</p>	
<p>5-6-14</p> <p>9:58</p> <p>10:09</p> <p>11:16</p> <p>12:33</p> <p>Duplicate</p> <p>FIELD BLANK</p> <p>TH-77</p> <p>TH-76</p> <p>TH-72</p>										<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>		<p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p> <p>X</p>	
<p>RELINQUISHED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p> <p>RELINQUISHED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p> <p>RELINQUISHED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p>										<p>660-60510 Chain of Custody</p>			
<p>RECEIVED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p> <p>RECEIVED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p> <p>RECEIVED BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p>										<p>LABORATORY USE ONLY</p>			
<p>RECEIVED FOR LABORATORY BY: (SIGNATURE)</p> <p>DATE</p> <p>TIME</p> <p>CUSTODY INTACT YES NO</p> <p>CUSTODY SEAL NO.</p> <p>STL LOG NO.</p> <p>LABORATORY REMARKS:</p>										<p>3.1°C/29°C cu-07</p>			

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: Southeast County Landfill IAMP		SITE LOCATION: Lithia, Florida	
WELL NO: TH-72	SAMPLE ID:	DATE: 5-6-14	

PURGING DATA

WELL DIAMETER (inches): 2	TUBING DIAMETER (inches): 0.5	WELL SCREEN INTERVAL DEPTH: 180 feet to 190 feet	STATIC DEPTH TO WATER (feet): 100.15	PURGE PUMP TYPE OR BAILER: DBP							
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable) = (190 feet - 100.15 feet) X .16 gallons/foot = 14.38 gallons											
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable) = gallons + (gallons/foot X feet) + gallons = gallons											
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): 189	FINAL PUMP OR TUBING DEPTH IN WELL (feet): 189	PURGING INITIATED AT: 11.48	PURGING ENDED AT: 12.33	TOTAL VOLUME PURGED (gallons): 22.5							
TIME	VOLUME PURGED (gallons)	CUMUL VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. µS/cm	DISSOLVED OXYGEN mg/L	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
12.17	14.5	14.5	.50	100.15	6.80	23.52	2223	.44	4.46	NONE	NONE
12.25	4.0	18.5	.50	100.15	6.81	23.55	2237	.76	1.79	↓	↓
12.33	4.0	22.5	.50	100.15	6.81	23.50	2247	.46	1.22	↓	↓
WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.10; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88 TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0006; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.008; 1/2" = 0.010; 5/8" = 0.018 PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)											

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: ANDREW BALLOON / ZACK PATTERSON				SAMPLER(S) SIGNATURE(S): <i>Zack Patterson</i>				SAMPLING INITIATED AT: 12.33		SAMPLING ENDED AT: 12.45	
PUMP OR TUBING DEPTH IN WELL (feet): 189				TUBING MATERIAL CODE: T				FIELD-FILTERED: Y <input checked="" type="radio"/> N <input type="radio"/>		FILTER SIZE: _____ µm	
FIELD DECONTAMINATION: PUMP Y <input type="radio"/> N <input checked="" type="radio"/> (Dedicated)				TUBING Y <input type="radio"/> N <input checked="" type="radio"/> (Dedicated)				DUPLICATE: Y <input type="radio"/> N <input checked="" type="radio"/> (N)			
SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION				INTENDED ANALYSIS AND/OR METHOD		SAMPLE PUMP FLOW RATE (mL per minute)	
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH					

SEE C.O.C. FOR SAMPLE ANALYSIS

DBP = Dedicated Bladder Pump

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)

SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: Southeast County Landfill IAMP	SITE LOCATION: Lithia, Florida
WELL NO: TH-76	DATE: 5-6-14

PURGING DATA

WELL DIAMETER (inches): 2	TUBING DIAMETER (inches): 0.5	WELL SCREEN INTERVAL DEPTH: 163.35 feet to 178.35 feet	STATIC DEPTH TO WATER (feet): 80.44	PURGE PUMP TYPE OR BAILER: DBP
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable) = (178.35 feet - 80.44 feet) X .16 gallons/foot = 15.67 gallons				
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable) = gallons + (gallons/foot X feet) + gallons = gallons				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): 177.35	FINAL PUMP OR TUBING DEPTH IN WELL (feet): 177.35	PURGING INITIATED AT: 10.29	PURGING ENDED AT: 11.15	TOTAL VOLUME PURGED (gallons): 24.38

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. µS/cm	DISSOLVED OXYGEN mg/L	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
10.59	15.90	15.90	.53	81.50	7.56	22.82	428	.28	12.8	Very light cloudy	None
11.07	4.24	20.14	.53	81.50	7.56	22.83	427	.26	12.8	↓	↓
11.15	4.24	24.38	.53	81.50	7.56	22.85	427	.24	12.7	↓	↓

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE D.I.A. CAPACITY (Gal./ft): 1/8" = 0.0006; 3/16" = 0.0014; 1/4" = 0.0028; 5/16" = 0.004; 3/8" = 0.006; 1/2" = 0.010; 5/8" = 0.016
PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: ANDREW BALLOON / ZACK PATTERSON		SAMPLER(S) SIGNATURE(S): <i>[Signature]</i>		SAMPLING INITIATED AT: 11.15	SAMPLING ENDED AT: 11.27
PUMP OR TUBING DEPTH IN WELL (feet): 177.35		TUBING MATERIAL CODE: T	FIELD-FILTERED: Y (N)	FILTER SIZE: _____ µm	
FIELD DECONTAMINATION: PUMP Y N (Dedicated)		TUBING Y N (Dedicated)	DUPLICATE: Y (N)		

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (mL per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH			

SEE C.O.C. FOR SAMPLE ANALYSIS DBP = Dedicated bladder pump

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)
SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

- NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.
2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)
pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

PURGING DATA

SAMPLING DATA

SEE C.O.C. FOR SAMPLE ANALYSIS

DBP= Dedicated bladder pump

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)

SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailor; BP = Bladder Pump; ESP = Electric Submersible Pump;
RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: $\pm 5\%$ Dissolved Oxygen: all readings $\leq 20\%$ saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or $\pm 10\%$ (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or $\pm 10\%$ (whichever is greater)

Revision Date: February 1, 2004
5/16/2014

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: <u>Southeast County Landfill IAMP</u>		SITE LOCATION: <u>LITHIA, FL</u>	
WELL NO: <u>Duplicate</u>	SAMPLE ID:	DATE: <u>5-6-14</u>	

PURGING DATA

WELL DIAMETER (inches): <u>N/A</u>	TUBING DIAMETER (inches): <u>N/A</u>	WELL SCREEN INTERVAL DEPTH: — feet to — feet	STATIC DEPTH TO WATER (feet): <u>N/A</u>	PURGE PUMP TYPE OR BAILER: <u>N/A</u>
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable)				
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable)				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>	FINAL PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>	PURGING INITIATED AT: <u>N/A</u>	PURGING ENDED AT: <u>N/A</u>	TOTAL VOLUME PURGED (gallons): <u>N/A</u>

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (circle units) μmhos/cm or μS/cm	DISSOLVED OXYGEN (circle units) mg/L or % saturation	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
DUPLICATE											

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0006; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.006; 1/2" = 0.010; 5/8" = 0.016

PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: <u>ANDREW BALLOON / ZACK PATTERSON</u>		SAMPLER(S) SIGNATURE: <u>[Signature]</u>		SAMPLING INITIATED AT: <u>N/A</u>	SAMPLING ENDED AT: <u>N/A</u>
PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>	TUBING MATERIAL CODE: <u>T</u>	FIELD-FILTERED: Y <u>(N)</u>		FILTER SIZE: — μm	
FIELD DECONTAMINATION: <u>PUMP</u> Y <u>N</u> Dedicated		TUBING Y <u>N</u> Dedicated		DUPLICATE: <u>(Y)</u> N	

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (mL per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH			

SEE COC FOR ANALYSIS

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)

SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: <u>Southeast County landfill IAMP</u>		SITE LOCATION: <u>Lithia, FL</u>	
WELL NO: <u>Field Blank</u>	SAMPLE ID:	DATE: <u>5-6-14</u>	

PURGING DATA

WELL DIAMETER (inches): <u>N/A</u>	TUBING DIAMETER (inches): <u>N/A</u>	WELL SCREEN INTERVAL DEPTH: - feet to - feet	STATIC DEPTH TO WATER (feet): <u>N/A</u>	PURGE PUMP TYPE OR BAILER: <u>N/A</u>
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable)				
EQUIPMENT VOLUME PURGE: EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable)				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>	FINAL PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>	PURGING INITIATED AT: <u>N/A</u>	PURGING ENDED AT: <u>N/A</u>	TOTAL VOLUME PURGED (gallons): <u>N/A</u>

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (circle units) <u>µmhos/cm or µS/cm</u>	DISSOLVED OXYGEN (circle units) <u>mg/L or % saturation</u>	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
FIELD BLANK											

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0008; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.008; 1/2" = 0.010; 5/8" = 0.016
PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: <u>ANDREW BALLOON / ZACK PATTERSON</u>		SAMPLER(S) SIGNATURE(S): <u>[Signature]</u>		SAMPLING INITIATED AT: <u>9:58</u>	SAMPLING ENDED AT: <u>10:10</u>
PUMP OR TUBING DEPTH IN WELL (feet): <u>N/A</u>		TUBING MATERIAL CODE: <u>T</u>		FIELD-FILTERED: Y <u>(N)</u>	FILTER SIZE: <u> </u> µm
FIELD DECONTAMINATION: PUMP Y <u>N</u> Dedicated		TUBING Y <u>N</u> Dedicated		DUPLICATE: Y <u>(N)</u>	

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (ml. per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL. ADDED IN FIELD (mL)	FINAL pH			
SEE COC FOR ANALYSIS									

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)
SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.

2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)

pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

FCU036:12.20.00:2

Original - Return to Laboratory with Sample(s)

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

THE LEADER IN ENVIRONMENTAL TESTING

[illegible]

THE LEADER IN ENVIRONMENTAL TESTING

[illegible]

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-60510-1

Login Number: 60510

List Source: TestAmerica Tampa

List Number: 1

Creator: Williams, Jennifer

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	False	Check done at department level as required.

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-60510-1

Login Number: 60510

List Number: 1

Creator: Banda, Christy S

List Source: TestAmerica Savannah

List Creation: 05/07/14 08:44 AM

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-60510-1

Login Number: 60541

List Source: TestAmerica Tampa

List Number: 1

Creator: McNulty, Carol

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-60510-1

Login Number: 60541

List Number: 1

Creator: West, Lauren H

List Source: TestAmerica Savannah

List Creation: 05/08/14 06:10 AM

Question	Answer	Comment
Radioactivity wasn't checked or is \leq background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	