



December 19, 2014

Richard B. Tedder, PE
Solid Waste Section
Florida Department of Environmental Protection
2600 Blair Stone Road, MS #4565
Tallahassee, Florida 32399

RE: Highlands County Solid Waste Agricultural Plastics Disposal Unit
Operations Permit Renewal Application
Permit No.: 0038570-023-SO/08
Jones Edmunds Project No.: 08345-015-01

Mr. Tedder:

On behalf of the Highlands County Solid Waste, Jones Edmunds & Associates, Inc. is pleased to provide the enclosed operations permit renewal application for the Agricultural Plastics Disposal Unit at the Highlands County Solid Waste Management Center in Sebring, Florida. The enclosed application includes Florida Department of Environmental Protection (FDEP) Form 62-701.900(1) and supporting information for the renewal of Permit No. 0038570-023-SO/08.

Jones Edmunds is providing one original hard copy and one electronic copy in PDF format on CD of the enclosed permit application. Jones Edmunds requests an application fee waiver and has included a copy of FDEP's approval for a Reduction or Waiver of Permit Processing Fees for calendar year 2015 under Section 218.075 of Florida Statutes 2008, dated November 12, 2014 (see Attachment D.5 of the permit application submittal).

If you or your staff have any questions, please feel free to contact me at (352) 377-5821 or hsboudreau@jonesedmunds.com.

Sincerely,

A handwritten signature in blue ink that reads "Harold S. Boudreau III".

Harold S. Boudreau, III, PE
Project Manager

\\gnv-projects\projects\08345-highlandscounty\015-01 ag plastic renewal\consult\permitting\coverletter.docx

Enclosures

xc: Ramon Gavarrete, Highlands County Solid Waste Division



**HIGHLANDS COUNTY AGRICULTURAL PLASTICS
DISPOSAL UNIT OPERATION PERMIT RENEWAL
APPLICATION**

Permit Number: 0038570-023-SO/08

Highlands County Board of County Commissioners | December 2014

**HIGHLANDS COUNTY
AGRICULTURAL PLASTICS DISPOSAL UNIT
OPERATION PERMIT
RENEWAL APPLICATION**

FDEP Permit No.: 0038570-023-SO/08

FDEP WACS No. 00074956

Prepared for:

HIGHLANDS COUNTY BOARD OF COUNTY COMMISSIONERS

600 S. Commerce Avenue

Sebring, Florida 33870

Prepared by:

JONES EDMUNDS & ASSOCIATES, INC.

730 NE Waldo Road

Gainesville, Florida 32641

Certificate of Authorization #1841

December 2014



TABLE OF CONTENTS

INTRODUCTION

PERMIT APPLICATION FORM 62-701.900(1)

SUPPORTING DOCUMENTATION

PART D SOLID WASTE MANAGEMENT FACILITY PERMIT REQUIREMENTS, GENERAL

ATTACHMENT D.5 FDEP'S APPROVAL OF THE REDUCTION OR WAIVER OF PERMIT PROCESSING FEES

PART E LANDFILL PERMIT REQUIREMENTS

ATTACHMENT E.1 AIRPORT LOCATION MAP AND AERIAL PHOTO

ATTACHMENT E.4 DESIGN LIFE CALCULATIONS

PART F GENERAL CRITERIA FOR LANDFILLS

PART G LANDFILL CONSTRUCTION REQUIREMENTS

PART H HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS

PART I GEOTECHNICAL INVESTIGATION REQUIREMENTS

PART J VERTICAL EXPANSION OF LANDFILLS

PART K LANDFILL OPERATION REQUIREMENTS

PART L WATER QUALITY MONITORING REQUIREMENTS

PART M SPECIAL WASTE HANDLING REQUIREMENTS

PART N GAS MANAGEMENT SYSTEM REQUIREMENTS

PART O LANDFILL FINAL CLOSURE REQUIREMENTS

PART P OTHER CLOSURE PROCEDURES

PART Q LONG-TERM CARE

PART R FINANCIAL ASSURANCE

ATTACHMENT R.1 FINANCIAL ASSURANCE COST ESTIMATE

APPENDICES

APPENDIX A OPERATION PLAN

Introduction

1 INTRODUCTION

Jones Edmunds prepared this permit renewal application and is submitting it to the Florida Department of Environmental Protection (FDEP) on behalf of the Highlands County Board of County Commissioners for the Highlands County Solid Waste Management Center (HCSWMC) Agricultural (Ag) Plastic Disposal Unit. This application is to renew the Ag Plastic permit No. 0038570-023-SO/08.

The HCSWMC AG Plastic operation permit expires on February 17, 2015. The permit requires that a permit renewal application be submitted at least 60 days before the permit expires. Therefore, the due date for submittal of the application package is December 19, 2014.

The 6-acre Ag Plastic Landfill is within the 147-acre HCSWMC on the northwest portion of the 987-acre HCSWMC property at 12700 Arbuckle Creek Road, near Sebring, Florida 33870, in Section 22, Township 34 South, and Range 30 East. The HCSWMC also operates a Class I Landfill (permit number: 0038570-030-SO/01), Construction and Demolition Debris Landfill (permit number: 0038570-029-SO/24), as shown in previously submitted 2014 Class I Application (reference below), Appendix B, Sheet C1. No expansions of the Ag Plastic Landfill are planned.

The permit application includes the *Application to Construct, Operate, Modify, or Close a Solid Waste Management Facility* (FDEP Form 62-701.900(1)) and the supporting information as required for permit renewal of an active Ag Plastic Landfill. Supporting documentation meets the requirements of Rule 62-701, FAC and includes an updated Operation Plan, and Engineering Plan. The Closure Plan and Long-Term Care Plan were submitted previously as part of the 2004 Ag Plastic Application (reference below). Information previously submitted to FDEP that is still valid was not resubmitted for this permit renewal, and the previous submittals are referenced. Previous submittals incorporated by reference in this application document are listed below:

- 2004 Ag Plastic Application – *Application and Engineering Report for Construction and Operation Permit for Agricultural Waste, Gas Plastic Film, Tubing, and Piping Disposal Facility*, dated May 28, 2004, submitted by Highlands County Department of Solid Waste Management, prepared by PBS&J.
- 2009 Ag Plastic Application – *Permit Application and Engineering Report For Agricultural Plastic Disposal Unit Operation Permit Renewal*, dated September 9, 2009, submitted by Highlands County Department of Solid Waste Management, prepared by PBS&J.
- 2014 Class I Application – *Highlands County Class I Landfill Operation Permit Renewal Application*, dated June 2014, prepared for Highlands County Board of County Commissioners, prepared by Jones Edmunds & Associates, Inc.

**Application to Construct, Operate, Modify, or
Close a Solid Waste Management Facility**

FDEP Form 62-701.900(1)



Florida Department of Environmental Protection

Bob Martinez Center
2600 Blair Stone Road
Tallahassee, Florida 32399-2400

DEP Form #: 62-701.900(1), F.A.C.
Form Title: Application to Construct, Operate, Modify, or
Close a Solid Waste Management Facility
Effective Date: August 12, 2012
Incorporated in Rule: 62-701.330(3), F.A.C.

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION

APPLICATION TO CONSTRUCT, OPERATE, MODIFY, OR CLOSE A SOLID WASTE MANAGEMENT FACILITY

APPLICATION INSTRUCTIONS AND FORMS

Northwest District
160 Governmental Center
Suite 308
Pensacola, FL 32502-5794
850-595-8300

Northeast District
7777 Baymeadows Way West
Suite 100
Jacksonville, FL 32266-7690
904-256-1700

Central District
3319 Maguire Boulevard
Suite 232
Orlando, FL 32803-3767
407-897-4100

Southwest District
13051 North Telecom Pkwy
Temple Terrace, FL 33637
813-632-7600

South District
2295 Victoria Ave, Suite 364
P.O. Box 2549
Fort Myers, FL 33901-3881
239-344-5600

Southeast District
400 North Congress Avenue
Suite 200
West Palm Beach, FL 33401
561-681-6600

INSTRUCTIONS TO APPLY FOR A SOLID WASTE MANAGEMENT FACILITY PERMIT

I. General

Solid Waste Management Facilities shall be permitted pursuant to Section 403.707, Florida Statutes (FS) and in accordance with Florida Administrative Code (FAC) Chapter 62-701. A minimum of four copies of the application shall be submitted to the appropriate Department office having jurisdiction over the facility. The appropriate fee in accordance with Rule 62-701.315, FAC, shall be submitted with the application by check made payable to the Department of Environmental Protection (DEP).

Complete appropriate sections for the type of facility for which application is made. Entries shall be typed or printed in ink. All blanks shall be filled in or marked "Not Applicable" or "No Substantial Change". Information provided in support of the application shall be marked "Submitted" and the location of this information in the application package indicated. The application shall include all information, drawings, and reports necessary to evaluate the facility. Information required to complete the application is listed on the attached pages of this form.

II. Application Parts Required for Construction and Operation Permits

- A. Landfills and Ash Monofills - Submit Parts A through S
- B. Asbestos Monofills - Submit Parts A, B, C, D, E, F, I, K, M, O through S
- C. Industrial Solid Waste Disposal Facilities - Submit Parts A through S

NOTE: Portions of some Parts may not be applicable.

NOTE: For facilities that have been satisfactorily constructed in accordance with their construction permit, the information required for A, B and C type facilities does not have to be resubmitted for an operation permit if the information has not substantially changed during the construction period. The appropriate portion of the form should be marked "no substantial change".

III. Application Parts Required for Closure Permits

- A. Landfills and Ash Monofills - Submit Parts A, B, L, N through S
- B. Asbestos Monofills - Submit Parts A, B, M, O through S
- C. Industrial Solid Waste Disposal Facilities - Submit Parts A, B, L through S

NOTE: Portions of some Parts may not be applicable.

IV. Permit Renewals

The above information shall be submitted at time of permit renewal in support of the new permit. However, facility information that was submitted to the Department to support the expiring permit, and which is still valid, does not need to be re-submitted for permit renewal. Portions of the application not re-submitted shall be marked "no substantial change" on the application form.

V. Application Codes

- S - Submitted
- LOCATION - Physical location of information in application
- N/A - Not Applicable
- N/C - No Substantial Change

VI. Listing of Application Parts

- PART A: GENERAL INFORMATION
- PART B: DISPOSAL FACILITY GENERAL INFORMATION
- PART C: PROHIBITIONS
- PART D: SOLID WASTE MANAGEMENT FACILITY PERMIT REQUIREMENTS, GENERAL
- PART E: LANDFILL PERMIT REQUIREMENTS
- PART F: GENERAL CRITERIA FOR LANDFILLS
- PART G: LANDFILL CONSTRUCTION REQUIREMENTS
- PART H: HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS
- PART I: GEOTECHNICAL INVESTIGATION REQUIREMENTS
- PART J: VERTICAL EXPANSION OF LANDFILLS
- PART K: LANDFILL OPERATION REQUIREMENTS
- PART L: WATER QUALITY AND LEACHATE MONITORING REQUIREMENTS
- PART M: SPECIAL WASTE HANDLING REQUIREMENTS
- PART N: GAS MANAGEMENT SYSTEM REQUIREMENTS
- PART O: LANDFILL CLOSURE REQUIREMENTS
- PART P: OTHER CLOSURE PROCEDURES
- PART Q: LONG-TERM CARE
- PART R: FINANCIAL ASSURANCE
- PART S: CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
APPLICATION FOR A PERMIT TO CONSTRUCT, OPERATE, MODIFY OR CLOSE A
SOLID WASTE MANAGEMENT FACILITY

Please Type or Print

PART A. GENERAL INFORMATION

1. Type of disposal facility (check all that apply):

- | | |
|---|--|
| <input type="checkbox"/> Class I Landfill | <input type="checkbox"/> Ash Monofill |
| <input type="checkbox"/> Class III Landfill | <input type="checkbox"/> Asbestos Monofill |
| <input type="checkbox"/> Industrial Solid Waste | |
| <input checked="" type="checkbox"/> Other (describe): | |

Disposal Unit for agricultural waste plastic film, plastic tubing, and plastic irrigation pipe.

NOTE: Waste Processing Facilities should apply on Form 62-701.900(4), FAC;
Yard Trash Disposal Facilities should notify on Form 62-701.900(3), FAC;
Compost Facilities should apply on Form 62-709.901(1), FAC; and
C&D Disposal Facilities should apply on Form 62-701.900(6), FAC

2. Type of application:

- | |
|---|
| <input type="checkbox"/> Construction |
| <input checked="" type="checkbox"/> Operation |
| <input type="checkbox"/> Construction/Operation |
| <input type="checkbox"/> Closure |
| <input type="checkbox"/> Long-term Care Only |

3. Classification of application:

- | | |
|---|--|
| <input type="checkbox"/> New | <input type="checkbox"/> Substantial Modification |
| <input checked="" type="checkbox"/> Renewal | <input type="checkbox"/> Intermediate Modification |
| | <input type="checkbox"/> Minor Modification |

4. Facility name: Highlands County Solid Waste Management Center

5. DEP ID number: 00074956 County: Highlands

6. Facility location (main entrance):

12700 Arbuckle Creek Road, Sebring, Florida, 33870

7. Location coordinates:

Section: 22 Township: 34S Range: 30E
Latitude: 27 ° 30 ' 14 " Longitude: 81 ° 19 ' 4 "
Datum: WGS 84 Coordinate method: Google Earth
Collected by: M. Pollman Company/Affiliation: Jones Edmunds & Associates, Inc.

8. Applicant name (operating authority): Highlands County Board of County Commissioners
Mailing address: 600 South Commerce Avenue Sebring Florida 33870
Street or P.O. Box City State Zip
Contact person: Ramon D. Gavarrete, PE Telephone: (863) 402-6877
Title: County Engineer
rgavarre@hcbcc.org
E-Mail address (if available)
9. Authorized agent/Consultant: Jones Edmunds & Associates, Inc.
Mailing address: 730 Northeast Waldo Road
Street or P.O. Box City State Zip
Contact person: Hal S. Boudreau, III, PE Telephone: (352) 377-5821
Title: Project Manager
hsboudreau@jonesedmunds.com
E-Mail address (if available)
10. Landowner (if different than applicant): Landowner same as applicant
Mailing address: _____
Street or P.O. Box City State Zip
Contact person: _____ Telephone: (____) _____

E-Mail address (if available)
11. Cities, towns, and areas to be served:
Highlands County

12. Population to be served:
Current: 101,600 (2015 BEBR Medium Projection) Five-Year Projection: 107,200 (2020 BEBR Medium Projection)
13. Date site will be ready to be inspected for completion: N/A
14. Expected life of the facility: 79 years
15. Estimated costs:
Total Construction: \$ 0 Closing Costs: \$ 466,461
16. Anticipated construction starting and completion dates:
From: N/A To: N/A
17. Expected volume or weight of waste to be received:
_____ yds³/day ~1,000 tons/year tons/day _____ gallons/day

PART B. DISPOSAL FACILITY GENERAL INFORMATION

1. Provide brief description of disposal facility design and operations planned under this application:
Operations permit will allow the continued disposal of agricultural plastic waste
in the Agricultural Plastic Disposal Unit. Waste disposal will be limited to agricultural
plastic film, plastic tubing, plastic irrigation pipe, and other plastic agricultural waste.
The waste is generally received twice per year in the spring and fall.

2. Facility site supervisor: Dick Gorman
Title: Landfill Operations Manager Telephone: (863) 402-7786
dgorman@hcbcc.org
E-Mail address (if available)

3. Disposal area: Total acres: 6 Used acres: 6 Available acres: 0

4. Weighing scales used: Yes No

5. Security to prevent unauthorized use: Yes No

6. Charge for waste received: N/A \$/yds³ 45 \$/ton

7. Surrounding land use, zoning:

- | | |
|--|--|
| <input type="checkbox"/> Residential | <input type="checkbox"/> Industrial |
| <input checked="" type="checkbox"/> Agricultural | <input type="checkbox"/> None |
| <input type="checkbox"/> Commercial | <input type="checkbox"/> Other (describe): |

8. Types of waste received:

- | | |
|---|---|
| <input type="checkbox"/> Household | <input type="checkbox"/> C & D debris |
| <input type="checkbox"/> Commercial | <input type="checkbox"/> Shredded/cut tires |
| <input type="checkbox"/> Incinerator/WTE ash | <input type="checkbox"/> Yard trash |
| <input type="checkbox"/> Treated biomedical | <input type="checkbox"/> Septic tank |
| <input type="checkbox"/> Water treatment sludge | <input type="checkbox"/> Industrial |
| <input type="checkbox"/> Air treatment sludge | <input type="checkbox"/> Industrial sludge |
| <input type="checkbox"/> Agricultural | <input type="checkbox"/> Domestic sludge |
| <input type="checkbox"/> Asbestos | <input checked="" type="checkbox"/> Other (describe): |

Waste plastic film, plastic irrigation tubing, and plastic irrigation pipe from
agricultural operations only.

9. Salvaging permitted: Yes No
10. Attendant: Yes No Trained operator: Yes No
11. Trained spotters: Yes No Number of spotters used: 1
12. Site located in: Floodplain Wetlands Other (describe):
Uplands
-
13. Days of operation: Monday through Saturday
14. Hours of operation: 7:30 am to 5:00 pm
15. Days working face covered: None required.
16. Elevation of water table: 62 ft. Datum Used: NGVD 1929
17. Number of monitoring wells: None for Ag Plastic - adjacent to Class I Landfill.
18. Number of surface monitoring points: None - adjacent to Class I Landfill
19. Gas controls used: Yes No Type controls: Active Passive
- Gas flaring: Yes No Gas recovery: Yes No
20. Landfill unit liner type:
- | | |
|---|--|
| <input type="checkbox"/> Natural soils | <input type="checkbox"/> Double geomembrane |
| <input type="checkbox"/> Single clay liner | <input type="checkbox"/> Geomembrane & composite |
| <input type="checkbox"/> Single geomembrane | <input type="checkbox"/> Double composite |
| <input type="checkbox"/> Single composite | <input checked="" type="checkbox"/> None |
| <input type="checkbox"/> Slurry wall | <input type="checkbox"/> Other (describe): |
-
21. Leachate collection method:
- | | |
|--|---|
| <input type="checkbox"/> Collection pipes | <input type="checkbox"/> Double geomembrane |
| <input type="checkbox"/> Geonets | <input type="checkbox"/> Gravel layer |
| <input type="checkbox"/> Well points | <input type="checkbox"/> Interceptor trench |
| <input type="checkbox"/> Perimeter ditch | <input checked="" type="checkbox"/> None |
| <input type="checkbox"/> Other (describe): | |
-

22. Leachate storage method:

Tanks

Surface impoundments

Other (describe):

No leachate collection or storage.

23. Leachate treatment method:

Oxidation

Chemical treatment

Secondary

Settling

Advanced

None

Other (describe):

No leachate collection or treatment.

24. Leachate disposal method:

Recirculated

Pumped to WWTP

Transported to WWTP

Discharged to surface water/wetland

Injection well

Percolation ponds

Evaporation

Spray irrigation

Other (describe):

No leachate collection or disposal.

25. For leachate discharged to surface waters:

Name and Class of receiving water:

N/A

26. Storm Water:

Collected: Yes No

Type of treatment:

Wetlands

Name and Class of receiving water:

Arbuckle Creek Class IV Agricultural Water Supply

27. Environmental Resources Permit (ERP) number or status:

Permit No. 28-00342-S, Active.

No modifications since last permit application.

PART C. PROHIBITIONS (62-701.300, FAC)

<u>LOCATION</u>		N/C indicates no change from the May 28, 2004 permit application document.	
S	<input type="checkbox"/> <u>C.1</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	1. Provide documentation that each of the siting criteria will be satisfied for the facility; (62-701.300(2), FAC)
S	<input type="checkbox"/> <u>C.2</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	2. If the facility qualifies for any of the exemptions contained in Rules 62-701.300(12) through (18), FAC, then document this qualification(s);
S	<input type="checkbox"/> <u>C.3</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	3. Provide documentation that the facility will be in compliance with the burning restrictions; (62-701.300(3), FAC)
S	<input type="checkbox"/> <u>C.4</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	4. Provide documentation that the facility will be in compliance with the hazardous waste restrictions; (62-701.300(4), FAC)
S	<input type="checkbox"/> <u>C.5</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	5. Provide documentation that the facility will be in compliance with the PCB disposal restrictions; (62-701.300(5), FAC)
S	<input type="checkbox"/> <u>C.6</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	6. Provide documentation that the facility will be in compliance with the biomedical waste restrictions; (62-701.300(6), FAC)
S	<input type="checkbox"/> <u>C.7</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	7. Provide documentation that the facility will be in compliance with the Class I surface water restrictions; (62-701.300(7), FAC)
S	<input type="checkbox"/> <u>C.8</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	8. Provide documentation that the facility will be in compliance with the special waste for landfills restrictions; (62-701.300(8), FAC)
S	<input type="checkbox"/> <u>C.9</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	9. Provide documentation that the facility will be in compliance with the liquid restrictions; (62-701.300(10), FAC)
S	<input type="checkbox"/> <u>C.10</u>	N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/>	10. Provide documentation that the facility will be in compliance with the used oil and oily waste restrictions; (62-701.300(11), FAC)

PART D. SOLID WASTE MANAGEMENT FACILITY PERMIT REQUIREMENTS, GENERAL (62-701.320, FAC)

<u>LOCATION</u>		N/C indicates no change from the May 28, 2004 permit application document or the 2014 Class I permit application document.	
S	<input checked="" type="checkbox"/> <u>D.1</u>	N/A <input type="checkbox"/> N/C <input type="checkbox"/>	1. Four copies, at minimum, of the completed application form, all supporting data and reports; (62-701.320(5)(a), FAC)
S	<input checked="" type="checkbox"/> <u>D.2</u>	N/A <input type="checkbox"/> N/C <input type="checkbox"/>	2. Engineering and/or professional certification (signature, date, and seal) provided on the applications and all engineering plans, reports, and supporting information for the application; (62-701.320(6), FAC)
S	<input checked="" type="checkbox"/> <u>D.3</u>	N/A <input type="checkbox"/> N/C <input type="checkbox"/>	3. A letter of transmittal to the Department; (62-701.320(7)(a), FAC)

LOCATION

PART D CONTINUED

S D.4 N/A N/C

4. A completed application form dated and signed by the applicant; (62-701.320(7)(b), FAC)

S D.5 N/A N/C

5. Permit fee specified in Rule 62-701.315, FAC in check or money order, payable to the Department; (62-701.320(7)(c), FAC)

S D.6 N/A N/C

6. An engineering report addressing the requirements of this rule and with the following format: a cover sheet, text printed on 8 ½ inch by 11 inch consecutively numbered pages, a table of contents or index, the body of the report and all appendices including an operation plan, contingency plan, illustrative charts and graphs, records or logs of tests and investigations, engineering calculations; (62-701.320(7)(d), FAC)

S D.7 N/A N/C

7. Operation Plan and Closure Plan; (62-701.320(7)(e)1, FAC)

S D.8 N/A N/C

8. Contingency Plan; (62-701.320(7)(e)2, FAC)

S D.9 N/A N/C

9. Plans or drawings for the solid waste management facilities in appropriate format (including sheet size restrictions, cover sheet, legends, north arrow, horizontal and vertical scales, elevations referenced to NGVD 1929) showing: (62-701.320(7)(f), FAC)

S D.9.a N/A N/C

a. A regional map or plan with the project location in relation to major roadways and population centers;

S D.9.b N/A N/C

b. A vicinity map or aerial photograph no more than one year old showing the facility site and relevant surface features located within 1000 feet of the facility;

S D.9.c N/A N/C

c. A site plan showing all property boundaries certified by a Florida Licensed Professional Surveyor and Mapper;

S D.9.d N/A N/C

d. Other necessary details to support the engineering report, including referencing elevations to a consistent, nationally recognized datum, and identifying the method used for collecting latitude and longitude data;

S D.10 N/A N/C

10. Documentation that the applicant either owns the property or has legal authority from the property owner to use the site; (62-701.320(7)(g), FAC)

S D.11 N/A N/C

11. For facilities owned or operated by a county, provide a description of how, if any, the facilities covered in this application will contribute to the county's achievement of the waste reduction and recycling goals contained in Section 403.706, FS; (62-701.320(7)(h), FAC)

LOCATION

PART D CONTINUED

S D.12 N/A N/C

12. Provide a history and description of any enforcement actions taken by the Department against the applicant for violations of applicable statutes, rules, orders, or permit conditions relating to the operation of any solid waste management facility in the state; (62-701.320(7)(i), FAC)

S D.13 N/A N/C

13. Proof of publication in a newspaper of general circulation of notice of application for a permit to construct or substantially modify a solid waste management facility; (62-701.320(8), FAC)

S D.14 N/A N/C

14. Provide a description of how the requirements for airport safety will be achieved, including proof of required notices if applicable. If exempt, explain how the exemption applies; (62-701.320(13), FAC)

S D.15 N/A N/C

15. Explain how the operator and spotter training requirements and special criteria will be satisfied for the facility; (62-701.320(15), FAC)

PART E. LANDFILL PERMIT REQUIREMENTS (62-701.330, FAC)

LOCATION

N/C indicates no change from the May 28, 2004 permit application document.

S E.1 N/A N/C

1. Regional map or aerial photograph no more than five years old showing all airports that are located within five miles of the proposed landfill; (62-701.330(3)(a), FAC)

S E.2 N/A N/C

2. Plot plan with a scale not greater than 200 feet to the inch showing: (62-701.330(3)(b), FAC)

S E.2.a N/A N/C

a. Dimensions;

S E.2.b N/A N/C

b. Locations of proposed and existing water quality monitoring wells;

S E.2.c N/A N/C

c. Locations of soil borings;

S E.2.d N/A N/C

d. Proposed plan of trenching or disposal areas;

S E.2.e N/A N/C

e. Cross sections showing original elevations and proposed final contours which shall be included either on the plot plan or on separate sheets;

S E.2.f N/A N/C

f. Any previously filled waste disposal areas;

S E.2.g N/A N/C

g. Fencing or other measures to restrict access;

LOCATION

PART E CONTINUED

S E.3 N/A N/C

3. Topographic maps with a scale not greater than 200 feet to the inch with five foot contour intervals showing: (62-701.330(3)(c), FAC)

S E.3.a N/A N/C

a. Proposed fill areas;

S E.3.b N/A N/C

b. Borrow areas;

S E.3.c N/A N/C

c. Access roads;

S E.3.d N/A N/C

d. Grades required for proper drainage;

S E.3.e N/A N/C

e. Cross sections of lifts;

S E.3.f N/A N/C

f. Special drainage devices if necessary;

S E.3.g N/A N/C

g. Fencing;

S E.3.h N/A N/C

h. Equipment facilities;

S E.4 N/A N/C

4. A report on the landfill describing the following: (62-701.330(3)(d), FAC)

S E.4.a N/A N/C

a. The current and projected population and area to be served by the proposed site;

S E.4.b N/A N/C

b. The anticipated type, annual quantity, and source of solid waste expressed in tons;

S E.4.c N/A N/C

c. Planned active life of the facility, the final design height of the facility, and the maximum height of the facility during its operation;

S E.4.d N/A N/C

d. The source and type of cover material used for the landfill;

S E.5 N/A N/C

5. Provide evidence that an approved laboratory shall conduct water quality monitoring for the facility in accordance with Chapter 62-160, FAC; (62-701.330(3)(g), FAC)

S E.6 N/A N/C

6. Provide a statement of how the applicant will demonstrate financial responsibility for the closing and long-term care of the landfill; (62-701.330(3)(h), FAC)

PART F. GENERAL CRITERIA FOR LANDFILLS (62-701.340, FAC)

- | | | | |
|--|-----------------|--|--|
| | LOCATION | N/C indicates no change from the May 28, 2004 permit application document or the 2014 Class I permit application document. | |
|--|-----------------|--|--|
- S F.1 N/A N/C 1. Describe (and show on a Federal Insurance Administration flood map, if available) how the landfill or solid waste disposal unit shall not be located in the 100 year floodplain where it will restrict the flow of the 100 year flood, reduce the temporary water storage capacity of the floodplain unless compensating storage is provided, or result in a washout of solid waste; (62-701.340(3)(b), FAC)
- S F.2 N/A N/C 2. Describe how the minimum horizontal separation between waste deposits in the landfill and the landfill property boundary shall be 100 feet, measured from the toe of the proposed final cover slope; (62-701.340(3)(c), FAC)

PART G. LANDFILL CONSTRUCTION REQUIREMENTS (62-701.400, FAC)

- | | | | |
|--|-----------------|--|--|
| | LOCATION | N/A indicates that this section is not applicable because no construction is proposed with this permit application document. | |
|--|-----------------|--|--|
- S _____ N/A N/C 1. Describe how the landfill shall be designed so the solid waste disposal units will be constructed and closed at planned intervals throughout the design period of the landfill, and shall be designed to achieve a minimum factor of safety of 1.5 using peak strength values to prevent failures of side slopes and deep-seated failures; (62-701.400(2), FAC)
- S _____ N/A N/C 2. Landfill liner requirements; (62-701.400(3), FAC)
- S _____ N/A N/C a. General construction requirements; (62-701.400(3)(a), FAC)
- S _____ N/A N/C (1) Provide test information and documentation to ensure the liner will be constructed of materials that have appropriate physical, chemical, and mechanical properties to prevent failure;
- S _____ N/A N/C (2) Document foundation is adequate to prevent liner failure;
- S _____ N/A N/C (3) Constructed so bottom liner will not be adversely impacted by fluctuations of the ground water;
- S _____ N/A N/C (4) Designed to resist hydrostatic uplift if bottom liner located below seasonal high ground water table;
- S _____ N/A N/C (5) Installed to cover all surrounding earth which could come into contact with the waste or leachate;

LOCATION

PART G CONTINUED

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

b. Composite liners; (62-701.400(3)(b), FAC)

- (1) Upper geomembrane thickness and properties;
- (2) Design leachate head for primary leachate collection and removal system (LCRS) including leachate recirculation if appropriate;
- (3) Design thickness in accordance with Table A and number of lifts planned for lower soil component;

c. Double liners; (62-701.400(3)(c), FAC)

- (1) Upper and lower geomembrane thickness and properties;
- (2) Design leachate head for primary LCRS to limit the head to one foot above the liner;
- (3) Lower geomembrane sub-base design;
- (4) Leak detection and secondary leachate collection system minimum design criteria ($k \geq 10$ cm/sec, head on lower liner ≤ 1 inch, head not to exceed thickness of drainage layer);

d. Standards for geosynthetic components; (62-701.400(3)(d), FAC)

- (1) Factory and field seam test methods to ensure all geomembrane seams achieve the minimum specifications;
- (2) Geomembranes to be used shall pass a continuous spark test by the manufacturer;
- (3) Design of 24-inch-thick protective layer above upper geomembrane liner;
- (4) Describe operational plans to protect the liner and leachate collection system when placing the first layer of waste above a 24-inch-thick protective layer;
- (5) HDPE geomembranes, if used, meet the specifications in GRI GM13, and LLDPE geomembranes, if used, meet the specifications in GRI GM17;
- (6) PVC geomembranes, if used, meet the specifications in PGI 1104;

LOCATION

PART G CONTINUED

S _____ N/A N/C

(7) Interface shear strength testing results of the actual components which will be used in the liner system;

S _____ N/A N/C

(8) Transmissivity testing results of geonets if they are used in the liner system;

S _____ N/A N/C

(9) Hydraulic conductivity testing results of geosynthetic clay liners if they are used in the liner system;

S _____ N/A N/C

e. Geosynthetic specification requirements; (62-701.400(3)(e), FAC)

S _____ N/A N/C

(1) Definition and qualifications of the designer, manufacturer, installer, QA consultant and laboratory, and QA program;

S _____ N/A N/C

(2) Material specifications for geomembranes, geocomposites, geotextiles, geogrids, and geonets;

S _____ N/A N/C

(3) Manufacturing and fabrication specifications including geomembrane raw material and roll QA, fabrication personnel qualifications, seaming equipment and procedures, overlaps, trial seams, destructive and non-destructive seam testing, seam testing location, frequency, procedure, sample size, and geomembrane repairs;

S _____ N/A N/C

(4) Geomembrane installation specifications including earthwork, conformance testing, geomembrane placement, installation personnel qualifications, field seaming and testing, overlapping and repairs, materials in contact with geomembranes, and procedures for lining system acceptance;

S _____ N/A N/C

(5) Geotextile and geogrids specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil materials and any overlying materials;

S _____ N/A N/C

(6) Geonet and geocomposites specifications including handling and placement, conformance testing, stacking and joining, repair, and placement of soil materials and any overlying materials;

S _____ N/A N/C

(7) Geosynthetic clay liner specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil materials and any overlying materials;

LOCATION

PART G CONTINUED

- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C

- f. Standards for soil liner components; (62-701.400(3)(f), FAC)
- (1) Description of construction procedures including over-excavation and backfilling to preclude structural inconsistencies and procedures for placing and compacting soil components in layers;
 - (2) Demonstration of compatibility of the soil component with actual or simulated leachate in accordance with EPA Test Method 9100, or an equivalent test method;
 - (3) Procedures for testing in situ soils to demonstrate they meet the specifications for soil liners;
 - (4) Specifications for soil component of liner including at a minimum:
 - (a) Allowable particle size distribution, and Atterberg limits including shrinkage limit;
 - (b) Placement moisture and dry density criteria;
 - (c) Maximum laboratory-determined saturated hydraulic conductivity using simulated leachate;
 - (d) Minimum thickness of soil liner;
 - (e) Lift thickness;
 - (f) Surface preparation (scarification);
 - (g) Type and percentage of clay mineral within the soil component;
 - (5) Procedures for constructing and using a field test section to document the desired saturated hydraulic conductivity and thickness can be achieved in the field;
- g. If a Class III landfill is to be constructed with a bottom liner system, provide a description of how the minimum requirements for the liner will be achieved;

LOCATION

PART G CONTINUED

- | | | | |
|----------------------------------|---|------------------------------|---|
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | 3. Leachate collection and removal system (LCRS); (62-701.400(4), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | a. The primary and secondary LCRS requirements; (62-701.400(4)(a), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (1) Constructed of materials chemically resistant to the waste and leachate; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (2) Have sufficient mechanical properties to prevent collapse under pressure; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (3) Have granular material or synthetic geotextile to prevent clogging; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (4) Have a method for testing and cleaning clogged pipes or contingent designs for reducing leachate around failed areas; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | b. Other LCRS requirements; (62-701.400(4)(b) and (c), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (1) Bottom 12 inches having hydraulic conductivity $\geq 1 \times 10^{-9}$ cm/sec; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (2) Total thickness of 24 inches of material chemically resistant to the waste and leachate; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (3) Bottom slope design to accommodate for predicted settlement and still meet minimum slope requirements; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | (4) Demonstration that synthetic drainage material, if used, is equivalent or better than granular material in chemical compatibility, flow under load, and protection of geomembranes liner; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | 4. Leachate recirculation; (62-701.400(5), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | a. Describe general procedures for recirculating leachate; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | b. Describe procedures for controlling leachate runoff and minimizing mixing of leachate runoff with storm water; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> | N/C <input type="checkbox"/> | c. Describe procedures for preventing perched water conditions and gas buildup; |

LOCATION

PART G CONTINUED

S _____ N/A N/C

d. Describe alternate methods for leachate management when it cannot be recirculated due to weather or runoff conditions, surface seeps, wind-blown spray, or elevated levels of leachate head on the liner;

S _____ N/A N/C

e. Describe methods of gas management in accordance with Rule 62-701.530, FAC;

S _____ N/A N/C

f. If leachate irrigation is proposed, describe treatment methods and standards for leachate treatment prior to irrigation over final cover, and provide documentation that irrigation does not contribute significantly to leachate generation;

S _____ N/A N/C

5. Leachate storage tanks and leachate surface impoundments; (62-701.400(6), FAC)

S _____ N/A N/C

a. Surface impoundment requirements; (62-701.400(6)(b), FAC)

S _____ N/A N/C

(1) Documentation that the design of the bottom liner will not be adversely impacted by fluctuations of the ground water;

S _____ N/A N/C

(2) Designed in segments to allow for inspection and repair, as needed, without interruption of service;

S _____ N/A N/C

(3) General design requirements;

S _____ N/A N/C

(a) Double liner system consisting of an upper and lower 60-mil minimum thickness geomembrane;

S _____ N/A N/C

(b) Leak detection and collection system with hydraulic conductivity ≥ 1 cm/sec;

S _____ N/A N/C

(c) Lower geomembrane place on subbase ≥ 6 inches thick with $k \leq 1 \times 10^{-5}$ cm/sec or on an approved geosynthetic clay liner with $k \leq 1 \times 10^{-7}$ cm/sec;

S _____ N/A N/C

(d) Design calculation to predict potential leakage through the upper liner;

S _____ N/A N/C

(e) Daily inspection requirements, and notification and corrective action requirements if leakage rates exceed that predicted by design calculations;

S _____ N/A N/C

(4) Description of procedures to prevent uplift, if applicable;

LOCATION

PART G CONTINUED

- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C
- S _____ N/A N/C

- (5) Design calculations to demonstrate minimum two feet of freeboard will be maintained;
- (6) Procedures for controlling vectors and off-site odors;
- b. Above-ground leachate storage tanks; (62-701.400(6)(c), FAC)
 - (1) Describe tank materials of construction and ensure foundation is sufficient to support tank;
 - (2) Describe procedures for cathodic protection for the tank, if needed;
 - (3) Describe exterior painting and interior lining of the tank to protect it from the weather and the leachate stored;
 - (4) Describe secondary containment design to ensure adequate capacity will be provided and compatibility of materials of construction;
 - (5) Describe design to remove and dispose of stormwater from the secondary containment system;
 - (6) Describe an overfill prevention system, such as level sensors, gauges, alarms, and shutoff controls to prevent overfilling;
 - (7) Inspections, corrective action, and reporting requirements;
 - (a) Weekly inspection of overfill prevention system;
 - (b) Weekly inspection of exposed tank exteriors;
 - (c) Inspection of tank interiors when tank is drained, or at least every three years;
 - (d) Procedures for immediate corrective action if failures detected;
 - (e) Inspection reports available for Department review;
- c. Underground leachate storage tanks; (62-701.400(6)(d), FAC)

LOCATION

PART G CONTINUED

S _____ N/A N/C

(1) Describe materials of construction;

S _____ N/A N/C

(2) A double-walled tank design system to be used with the following requirements:

S _____ N/A N/C

(a) Interstitial space monitoring at least weekly;

S _____ N/A N/C

(b) Corrosion protection provided for primary tank interior and external surface of outer shell;

S _____ N/A N/C

(c) Interior tank coatings compatible with stored leachate;

S _____ N/A N/C

(d) Cathodic protection inspected weekly and repaired as needed;

S _____ N/A N/C

(3) Describe an overflow prevention system, such as level sensors, gauges, alarms, and shutoff controls to prevent overflowing, and provide for weekly inspections;

S _____ N/A N/C

(4) Inspection reports available for Department review;

S _____ N/A N/C

d. Schedule provided for routine maintenance of LCRS; (62-701.400(6)(e), FAC)

S _____ N/A N/C

6. Liner systems construction quality assurance (CQA); (62-701.400(7), FAC)

S _____ N/A N/C

a. Provide CQA Plan including:

S _____ N/A N/C

(1) Specifications and construction requirements for liner system;

S _____ N/A N/C

(2) Detailed description of quality control testing procedures and frequencies;

S _____ N/A N/C

(3) Identification of supervising professional engineer;

S _____ N/A N/C

(4) Identify responsibility and authority of all appropriate organizations and key personnel involved in the construction project;

S _____ N/A N/C

(5) State qualifications of CQA professional engineer and support personnel;

LOCATION

PART G CONTINUED

S _____ N/A N/C

(6) Description of CQA reporting forms and documents;

S _____ N/A N/C

b. An independent laboratory experienced in the testing of geosynthetics to perform required testing;

S _____ N/A N/C

7. Soil liner CQA; (62-701.400(8), FAC)

S _____ N/A N/C

a. Documentation that an adequate borrow source has been located with test results, or description of the field exploration and laboratory testing program to define a suitable borrow source;

S _____ N/A N/C

b. Description of field test section construction and test methods to be implemented prior to liner installation;

S _____ N/A N/C

c. Description of field test methods, including rejection criteria and corrective measures to insure proper liner installation;

S _____ N/A N/C

8. For surface water management systems at aboveground disposal units, provide documentation showing the design of any features intended to convey stormwater to a permitted or exempted treatment system; (62-701.400(9), FAC)

S _____ N/A N/C

9. Gas control systems; (62-701.400(10), FAC)

S _____ N/A N/C

a. Provide documentation that if the landfill is receiving degradable wastes, it will have a gas control system complying with the requirements of Rule 62-701.530, FAC;

S _____ N/A N/C

10. For landfills designed in ground water, provide documentation that the landfill will provide a degree of protection equivalent to landfills designed with bottom liners not in contact with ground water; (62-701.400(11), FAC)

PART H. HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS (62-701.410(1), FAC)

LOCATION

N/A indicates that this section is not applicable because no construction and no new hydrogeological investigations are proposed with this permit application document.

S _____ N/A N/C

1. Submit a hydrogeological investigation and site report including at least the following information:

S _____ N/A N/C

a. Regional and site specific geology and hydrology;

S _____ N/A N/C

b. Direction and rate of ground water and surface water flow including seasonal variations;

LOCATION

PART H CONTINUED

S _____ N/A N/C

c. Background quality of ground water and surface water;

S _____ N/A N/C

d. Any on-site hydraulic connections between aquifers;

S _____ N/A N/C

e. Site stratigraphy and aquifer characteristics for confining layers, semi-confining layers, and all aquifers below the landfill site that may be affected by the landfill;

S _____ N/A N/C

f. Description of topography, soil types, and surface water drainage systems;

S _____ N/A N/C

g. Inventory of all public and private water wells within a one mile radius of the landfill including, where available, well top of casing and bottom elevations, name of owner, age and usage of each well, stratigraphic unit screened, well construction technique, and static water level;

S _____ N/A N/C

h. Identify and locate any existing contaminated areas on the site;

S _____ N/A N/C

i. Include a map showing the locations of all potable wells within 500 feet of the waste storage and disposal areas;

S _____ N/A N/C

2. Report signed, sealed, and dated by P.E. and/or P.G.;

PART I. GEOTECHNICAL INVESTIGATION REQUIREMENTS (62-701.410(2), FAC)

LOCATION

N/A indicates that this section is not applicable because no construction and no new geotechnical investigations are proposed with this permit application document.

S _____ N/A N/C

1. Submit a geotechnical site investigation report defining the engineering properties of the site including at least the following:

S _____ N/A N/C

a. Description of subsurface conditions including soil stratigraphy and ground water table conditions;

S _____ N/A N/C

b. Investigate for the presence of muck, previously filled areas, soft ground, lineaments, and sink holes;

S _____ N/A N/C

c. Estimates of average and maximum high water table across the site;

S _____ N/A N/C

d. Foundation analysis including:

S _____ N/A N/C

(1) Foundation bearing capacity analysis;

LOCATION

PART I CONTINUED

S _____ N/A N/C

(2) Total and differential subgrade settlement analysis;

S _____ N/A N/C

(3) Slope stability analysis;

S _____ N/A N/C

e. Description of methods used in the investigation, and includes soil boring logs, laboratory results, analytical calculations, cross sections, interpretations, and conclusions;

S _____ N/A N/C

f. An evaluation of fault areas, seismic impact zones, and unstable areas as described in 40 CFR 258.13, 40 CFR 258.14, and 40 CFR 258.15;

S _____ N/A N/C

2. Report signed, sealed, and dated by P.E. and/or P.G.;

PART J. VERTICAL EXPANSION OF LANDFILLS (62-701.430, FAC)

LOCATION

N/A indicates that this section is not applicable because no vertical expansion is proposed with this permit application document.

S _____ N/A N/C

1. Describe how the vertical expansion shall not cause or contribute to leachate leakage from the existing landfill, shall not cause objectionable odors, or adversely affect the closure design of the existing landfill;

S _____ N/A N/C

2. Describe how the vertical expansion over unlined landfills will meet the requirements of Rule 62-701.400, FAC with the exceptions of Rule 62-701.430(1)(c), FAC;

S _____ N/A N/C

3. Provide foundation and settlement analysis for the vertical expansion;

S _____ N/A N/C

4. Provide total settlement calculations demonstrating that the final elevations of the lining system, gravity drainage, and no other component of the design will be adversely affected;

S _____ N/A N/C

5. Minimum stability factor of safety of 1.5 for the lining system component interface stability and for deep stability;

S _____ N/A N/C

6. Provide documentation to show the surface water management system will not be adversely affected by the vertical expansion;

S _____ N/A N/C

7. Provide gas control designs to prevent accumulation of gas under the new liner for the vertical expansion;

PART K. LANDFILL OPERATION REQUIREMENTS (62-701.500, FAC)

LOCATION

- | | | | |
|---------------------------------------|--------------|---|---|
| S <input checked="" type="checkbox"/> | <u>K.1</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 1. Provide documentation that the landfill will have at least one trained operator during operation and at least one trained spotter at each working face; (62-701.500(1), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.2</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 2. Provide a landfill operation plan including procedures for: (62-701.500(2), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.2.a</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | a. Designating responsible operating and maintenance personnel; |
| S <input checked="" type="checkbox"/> | <u>K.2.b</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | b. Emergency preparedness and response, as required in subsection 62-701.320(16), FAC; |
| S <input checked="" type="checkbox"/> | <u>K.2.c</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | c. Controlling types of waste received at the landfill; |
| S <input checked="" type="checkbox"/> | <u>K.2.d</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | d. Weighing incoming waste; |
| S <input checked="" type="checkbox"/> | <u>K.2.e</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | e. Vehicle traffic control and unloading; |
| S <input checked="" type="checkbox"/> | <u>K.2.f</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | f. Method and sequence of filling waste; |
| S <input checked="" type="checkbox"/> | <u>K.2.g</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | g. Waste compaction and application of cover; |
| S <input checked="" type="checkbox"/> | <u>K.2.h</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | h. Operations of gas, leachate, and stormwater controls; |
| S <input checked="" type="checkbox"/> | <u>K.2.i</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | i. Water quality monitoring; |
| S <input checked="" type="checkbox"/> | <u>K.2.j</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | j. Maintaining and cleaning the leachate collection system; |
| S <input checked="" type="checkbox"/> | <u>K.3</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 3. Provide a description of the landfill operation record to be used at the landfill, details as to location of where various operational records will be kept (i.e. DEP permit, engineering drawings, water quality records, etc.); (62-701.500(3), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.4</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 4. Describe the waste records that will be compiled monthly and provided to the Department annually; (62-701.500(4), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.5</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 5. Describe methods of access control; (62-701.500(5), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.6</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 6. Describe load checking program to be implemented at the landfill to discourage disposal of unauthorized waste at the landfill; (62-701.500(6), FAC) |

LOCATION

PART K CONTINUED

S K.7 N/A N/C

7. Describe procedures for spreading and compacting waste at the landfill that include: (62-701.500(7), FAC)

S K.7.a N/A N/C

a. Waste layer thickness and compaction frequencies;

S K.7.b N/A N/C

b. Special considerations for first layer of waste placed above the liner and leachate collection system;

S K.7.c N/A N/C

c. Slopes of cell working face and side grades above land surface, and planned lift depths during operation;

S K.7.d N/A N/C

d. Maximum width of working face;

S K.7.e,K.7.f N/A N/C

e. Description of type of initial cover to be used at the facility that controls:

S K.7.e,K.7.f N/A N/C

(1) Vector breeding/animal attraction;

S K.7.e,K.7.f N/A N/C

(2) Fires;

S K.7.e,K.7.f N/A N/C

(3) Odors;

S K.7.e,K.7.f N/A N/C

(4) Blowing litter;

S K.7.e,K.7.f N/A N/C

(5) Moisture infiltration;

S K.7.f N/A N/C

f. Procedures for applying initial cover, including minimum cover frequencies;

S K.7.g N/A N/C

g. Procedures for applying intermediate cover;

S K.7.h N/A N/C

h. Time frames for applying final cover;

S K.7.i N/A N/C

i. Procedures for controlling scavenging and salvaging;

S K.7.j N/A N/C

j. Description of litter policing methods;

S K.7.k N/A N/C

k. Erosion control procedures;

N/A indicates that this section is not applicable because no leachate collection and no gas monitoring are specifically required for the Ag Plastic Landfill.

LOCATION

PART K CONTINUED

- | | | | |
|---------------------------------------|---------------|--|---|
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 8. Describe operational procedures for leachate management including: (62-701.500(8), FAC) |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | a. Leachate level monitoring; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | b. Operation and maintenance of leachate collection and removal system, and treatment as required; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | c. Procedures for managing leachate if it becomes regulated as a hazardous waste; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | d. Identification of treatment or disposal facilities that may be used for off-site discharge and treatment of leachate; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | e. Contingency plan for managing leachate during emergencies or equipment problems; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | f. Procedures for recording quantities of leachate generated in gal/day and including this in the operating record; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | g. Procedures for comparing precipitation experienced at the landfill with leachate generation rates and including this information in the operating record; |
| S <input type="checkbox"/> | <u>K.8</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | h. Procedures for water pressure cleaning or video inspecting leachate collection systems; |
| S <input type="checkbox"/> | <u>K.9</u> | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 9. Describe how the landfill receiving degradable wastes shall implement a gas management system meeting the requirements of Rule 62-701.530, FAC; (62-701.500(9), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.10</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 10. Describe procedures for operating and maintaining the landfill stormwater management system to comply with the requirements of Rule 62-701.400(9), FAC; (62-701.500(10), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.11</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | 11. Equipment and operation feature requirements; (62-701.500(11), FAC) |
| S <input checked="" type="checkbox"/> | <u>K.11.a</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | a. Sufficient equipment for excavating, spreading, compacting, and covering waste; |
| S <input checked="" type="checkbox"/> | <u>K.11.b</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | b. Reserve equipment or arrangements to obtain additional equipment within 24 hours of breakdown; |
| S <input checked="" type="checkbox"/> | <u>K.11.c</u> | N/A <input type="checkbox"/> N/C <input type="checkbox"/> | c. Communications equipment; |

LOCATION

PART K CONTINUED

S K.11.d N/A N/C

d. Dust control methods;

S K.11.e N/A N/C

e. Fire protection capabilities and procedures for notifying local fire department authorities in emergencies;

S K.11.f N/A N/C

f. Litter control devices;

S K.11.g N/A N/C

g. Signs indicating operating authority, traffic flow, hours of operation, and disposal restrictions;

S K.12 N/A N/C

12. Provide a description of all-weather access road, inside perimeter road, and other on-site roads necessary for access at the landfill; (62-701.500(12), FAC)

S K.13 N/A N/C

13. Additional record keeping and reporting requirements; (62-701.500(13), FAC)

S K.13.a N/A N/C

a. Records used for developing permit applications and supplemental information maintained for the design period of the landfill;

S K.13.b N/A N/C

b. Monitoring information, calibration and maintenance records, and copies of reports required by permit maintained for at least 10 years;

S K.13.c N/A N/C

c. Maintain annual estimates of the remaining life of constructed landfills, and of other permitted areas not yet constructed, and submit this estimate annually to the Department;

S K.13.d N/A N/C

d. Procedures for archiving and retrieving records which are more than five years old;

PART L. WATER QUALITY MONITORING REQUIREMENTS (62-701.510, FAC)

LOCATION

N/A indicates that this section is not applicable because the Ag Plastic Landfill has no water quality monitoring requirements and water quality monitoring is not proposed with this permit application document.

S _____ N/A N/C

1. A water quality monitoring plan shall be submitted describing the proposed ground water and surface water monitoring systems, and shall meet at least the following requirements:

S _____ N/A N/C

a. Based on the information obtained in the hydrogeological investigation and signed, dated, and sealed by the P.G. or P.E. who prepared it; (62-701.510(2)(a), FAC)

LOCATION

PART L CONTINUED

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

S _____ N/A N/C

b. All sampling and analysis performed in accordance with Chapter 62-160, FAC; (62-701.510(2)(b), FAC)

c. Ground water monitoring requirements; (62-701.510(3), FAC)

(1) Detection wells located downgradient from and within 50 feet of disposal units;

(2) Downgradient compliance wells as required;

(3) Background wells screened in all aquifers below the landfill that may be affected by the landfill;

(4) Location information for each monitoring well;

(5) Well spacing no greater than 500 feet apart for downgradient wells and no greater than 1500 feet apart for upgradient wells, unless site specific conditions justify alternate well spacings;

(6) Properly selected well screen locations;

(7) Monitoring wells constructed to provide representative ground water samples;

(8) Procedures for properly abandoning monitoring wells;

(9) Detailed description of detection sensors, if proposed;

d. Surface water monitoring requirements; (62-701.510(4), FAC)

(1) Location of and justification for all proposed surface water monitoring points;

(2) Each monitoring location to be marked and its position determined by a registered Florida land surveyor;

e. Initial and routine sampling frequency and requirements; (62-701.510(5), FAC)

(1) Initial background ground water and surface water sampling and analysis requirements;

LOCATION

PART L CONTINUED

- S _____ N/A N/C (2) Routine monitoring well sampling and analysis requirements;
- S _____ N/A N/C (3) Routine surface water sampling and analysis requirements;
- S _____ N/A N/C f. Describe procedures for implementing evaluation monitoring, prevention measures, and corrective action as required; (62-701.510(6), FAC)
- S _____ N/A N/C g. Water quality monitoring report requirements; (62-701.510(8), FAC)
- S _____ N/A N/C (1) Semi-annual report requirements; (see paragraphs 62-701.510(5)(c) and (d), FAC for sampling frequencies)
- S _____ N/A N/C (2) Documentation that the water quality data shall be provided to the Department in an electronic format consistent with requirements for importing into Department databases, unless an alternate form of submittal is specified in the permit;
- S _____ N/A N/C (3) Two and one-half year report requirements, or every five years if in long-term care, signed dated, and sealed by P.G. or P.E.;

PART M. SPECIAL WASTE HANDLING REQUIREMENTS (62-701.520, FAC)

LOCATION

N/A indicates that this section is not applicable because special waste is not accepted at the Ag Plastic Landfill and no special waste acceptance is proposed with this permit application document.

- S _____ N/A N/C 1. Describe procedures for managing motor vehicles; (62-701.520(1), FAC)
- S _____ N/A N/C 2. Describe procedures for landfilling shredded waste; (62-701.520(2), FAC)
- S _____ N/A N/C 3. Describe procedures for asbestos waste disposal; (62-701.520(3), FAC)
- S _____ N/A N/C 4. Describe procedures for disposal or management of contaminated soil; (62-701.520(4), FAC)
- S _____ N/A N/C 5. Describe procedures for disposal of biological wastes; (62-701.520(5), FAC)

PART N. GAS MANAGEMENT SYSTEM REQUIREMENTS (62-701.530, FAC)

N/A indicates that this section is not applicable because no putrescible waste is accepted at the Ag Plastic Landfill and no gas management systems are required or proposed with this permit application document.

- | <u>LOCATION</u> | | |
|----------------------------------|--|---|
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 1. Provide documentation for a gas management system that will: (62-701.530(1), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | a. Be designed to prevent concentrations of combustible gases from exceeding 25% the LEL in structures and 100% the LEL at the property boundary; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | b. Be designed for site specific conditions; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | c. Be designed to reduce gas pressure in the interior of the landfill; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | d. Be designed to not interfere with the liner, leachate control system, or final cover; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 2. Provide documentation that will describe locations, construction details, and procedures for monitoring gas at ambient monitoring points and with soil monitoring probes; (62-701.530(2), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 3. Provide documentation describing how the gas remediation plan and odor remediation plan will be implemented; (62-701.530(3), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | 4. Landfill gas recovery facilities; (62-701.530(5), FAC) |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | a. Provide information required in Rules 62-701.320(7) and 62-701.330(3), FAC; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | b. Provide information required in Rule 62-701.600(4), FAC, where relevant and practical; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | c. Provide estimates of current and expected gas generation rates and description of condensate disposal methods; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | d. Provide description of procedures for condensate sampling, analyzing, and data reporting; |
| S <input type="checkbox"/> _____ | N/A <input checked="" type="checkbox"/> N/C <input type="checkbox"/> | e. Provide closure plan describing methods to control gas after recovery facility ceases operation, and any other requirements contained in Rule 62-701.400(10), FAC; |

PART O. LANDFILL FINAL CLOSURE REQUIREMENTS (62-701.600, FAC)

LOCATION

N/C indicates no change from the May 28, 2004 permit application document.

- | | | | |
|----------------------------|------------|--|--|
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | 1. Closure permit requirements; (62-701.600(2), FAC) |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | a. Application submitted to the Department at least 90 days prior to final receipt of wastes; |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | b. Closure plan shall include the following: |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (1) Closure design plan; |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (2) Closure operation plan; |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (3) Plan for long-term care; |
| S <input type="checkbox"/> | <u>0.1</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (4) A demonstration that proof of financial assurance for long-term care will be provided; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | 2. Closure design plan including the following requirements: (62-701.600(3), FAC) |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | a. Plan sheet showing phases of site closing; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | b. Drawings showing existing topography and proposed final grades; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | c. Provisions to close units when they reach approved design dimensions; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | d. Final elevations before settlement; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | e. Side slope design including benches, terraces, down slope drainage ways, energy dissipaters, and description of expected precipitation effects; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | f. Final cover installation plans including: |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (1) CQA plan for installing and testing final cover; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (2) Schedule for installing final cover after final receipt of waste; |
| S <input type="checkbox"/> | <u>0.2</u> | N/A <input type="checkbox"/> N/C <input checked="" type="checkbox"/> | (3) Description of drought resistant species to be used in the vegetative cover; |

LOCATION

PART O CONTINUED

N/C indicates no change from the May 28, 2004 permit application document.

- S 0.2 N/A N/C (4) Top gradient design to maximize runoff and minimize erosion;
- S 0.2 N/A N/C (5) Provisions for cover material to be used for final cover maintenance;
- S 0.2 N/A N/C g. Final cover design requirements;
- S 0.2 N/A N/C (1) Protective soil layer design;
- S 0.2 N/A N/C (2) Barrier soil layer design;
- S 0.2 N/A N/C (3) Erosion control vegetation;
- S 0.2 N/A N/C (4) Geomembrane barrier layer design;
- S 0.2 N/A N/C (5) Geosynthetic clay liner design, if used;
- S 0.2 N/A N/C (6) Stability analysis of the cover system and the disposed waste;
- S 0.2 N/A N/C h. Proposed method of stormwater control;
- S 0.2 N/A N/C i. Proposed method of access control;
- S 0.2 N/A N/C j. Description of the proposed or existing gas management system which complies with Rule 62-701.530, FAC;
- S 0.3 N/A N/C 3. Closure operation plan shall include: (62-701.600(4), FAC)
- S 0.3 N/A N/C a. Detailed description of actions which will be taken to close the landfill;
- S 0.3 N/A N/C b. Time schedule for completion of closing and long-term care;
- S 0.3 N/A N/C c. Describe proposed method for demonstrating financial assurance for long-term care;
- S 0.3 N/A N/C d. Operation of the water quality monitoring plan required in Rule 62-701.510, FAC;
- S 0.3 N/A N/C e. Development and implementation of gas management system required in Rule 62-701.530, FAC;

LOCATION

PART O CONTINUED

- S O.4 N/A N/C 4. Certification of closure construction completion including: (62-701.600(6), FAC)
- S O.4 N/A N/C a. Survey monuments; (62-701.600(6)(a), FAC)
- S O.4 N/A N/C b. Final survey report; (62-701.600(6)(b), FAC)
- S O.5 N/A N/C 5. Declaration to the public; (62-701.600(7), FAC)
- S O.6 N/A N/C 6. Official date of closing; (62-701.600(8), FAC)
- S O.7 N/A N/C 7. Justification for and detailed description of procedures to be followed for temporary closure of the landfill, if desired; (62-701.600(9), FAC)

PART P. OTHER CLOSURE PROCEDURES (62-701.610, FAC)

N/A indicates that this section is not applicable because this application does not include landfill closure or other closure procedures.

LOCATION

- S P.1 N/A N/C 1. Describe how the requirements for use of closed solid waste disposal areas will be achieved; (62-701.610(1), FAC)
- S P.2 N/A N/C 2. Describe how the requirements for relocation of wastes will be achieved; (62-701.610(2), FAC)

PART Q. LONG-TERM CARE (62-701.620, FAC)

N/A indicates that this section is not applicable to the active Ag Plastic Landfill. The Long-Term-Care Plan included in the previously submitted 2004 Ag Plastic permit application has not changed.

LOCATION

- S Q.1 N/A N/C 1. Maintaining the gas collection and monitoring system; (62-701.620(5), FAC)
- S Q.2 N/A N/C 2. Stabilization report requirements; (62-701.620(6), FAC)
- S Q.3 N/A N/C 3. Right of access; (62-701.620(7), FAC)
- S Q.4 N/A N/C 4. Requirements for replacement of monitoring devices; (62-701.620(8), FAC)
- S Q.5 N/A N/C 5. Completion of long-term care signed and sealed by professional engineer; (62-701.620(9), FAC)

PART R. FINANCIAL ASSURANCE (62-701.630, FAC)

LOCATION

S R.1 N/A N/C

1. Provide cost estimates for closing, long-term care, and corrective action costs estimated by a P.E. for a third party performing the work, on a per unit basis, with the source of estimates indicated; (62-701.630(3) & (7), FAC)

S R.2 N/A N/C

2. Describe procedures for providing annual cost adjustments to the Department based on inflation and changes in the closing, long-term care, and corrective action plans; (62-701.630(4) & (8), FAC)

S R.3 N/A N/C

3. Describe funding mechanisms for providing proof of financial assurance and include appropriate financial assurance forms. (62-701.630(5), (6), & (9), FAC)

PART 5. CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

1. Applicant:

The undersigned applicant or authorized representative of Highlands Board of County Commissioners is aware that statements made in this form and attached information are an application for a Operation permit from the Florida Department of Environmental Protection, and certifies that the information in this application is true, correct, and complete to the best of his/her knowledge and belief. Further, the undersigned agrees to comply with the provisions of Chapter 403, Florida Statutes, and all rules and regulations of the Department. It is understood that the Permit is not transferable, and the Department will be notified prior to the sale or legal transfer of the permitted facility.



 Signature of Applicant or Agent
Ramon Gavarrete, PE, County Engineer
 Name and Title (please type)
rgavarre@hcbcc.org
 E-Mail Address (if available)

12700 Arbuckle Creek Road
 Mailing Address
Sebring, FL 33870
 City, State, Zip Code
(863) 402-7786
 Telephone Number
 Date: 12-19-2014

Attach letter of authorization if agent is not a government official, owner, or corporate officer.

2. Professional Engineer registered in Florida (or Public Officer if authorized under Sections 403.707 and 403.7075, Florida Statutes):

This is to certify that the engineering features of this solid waste management facility have been designed/examined by me and found to conform to engineering principles applicable to such facilities. In my professional judgment, this facility, when properly maintained and operated, will comply with all applicable statutes of the State of Florida and rules of the Department. It is agreed that the undersigned will provide the applicant with a set of instructions of proper maintenance and operation of the facility.


 Signature
Harold S. Boudreau, III, PE, Project Engineer
 Name and Title (please type)

730 NE Waldo Road
 Mailing Address
Gainesville, FL 32641
 City, State, Zip Code
hsboudreau@jonesedmunds.com
 E-Mail Address (if available)
(352) 377-5821
 Telephone Number
 Date: 12/19/2014

77030
 Florida Registration Number (please affix seal)



Supporting Documentation

PART D

SOLID WASTE MANAGEMENT FACILITY

PERMIT REQUIREMENTS, GENERAL

1 APPLICATION FORM AND ALL SUPPORTING DATA AND REPORTS

Rule 62-701.320(5)(a), FAC requires four copies of the application, engineering plans and reports, and all supporting information for the proposed construction, substantial modification, operation, or closure of a facility. However, recent guidance from FDEP requires applicants to submit one hard copy of the application, drawings, and supporting documentation and one electronic copy in Adobe Acrobat PDF file format of the application, drawings, and supporting documentation. FDEP is transitioning to a paperless process for permit applications; the electronic copy is easily duplicated and is considered satisfactory for the rule requirement.

2 ENGINEERING AND/OR PROFESSIONAL CERTIFICATION

Jones Edmunds & Associates, Inc. has prepared this application and is an authorized engineering firm in Florida (Certificate of Authorization #1841). This application plans, reports, and supporting information have been signed and sealed by Harold S. Boudreau, PE, a registered Professional Engineer in Florida (Florida Professional Engineer No. 77030), as the Engineer of Record.

3 LETTER OF TRANSMITTAL

A letter of transmittal is included with this permit application.

4 APPLICATION FORM

FDEP Form No. 62-701.900(1), effective date of August 12, 2012, has been completed and is dated and signed by the applicant.

5 PERMIT FEE

In lieu of the permit fee, a copy of FDEP's approval of the Reduction or Waiver of Permit Processing Fees for calendar year 2015 based on Florida Statute Section 218.075 is included as Attachment D.5.

6 ENGINEERING REPORT

This application and supporting documentation meet the requirements of an engineering report required by Rule 62-701.320(7)(d), FAC.

7 OPERATION PLAN AND CLOSURE PLAN

This application is for the operation of the Ag Plastic Landfill. The Operation Plan provided in Appendix A outlines the operations of the Ag Plastic Landfill and identifies the policies, procedures, and guidelines for operations.

A Closure Plan was submitted with the 2004 Ag Plastic Application. A detailed Closure and Long-Term-Care Plan will be provided at the time of closure.

8 CONTINGENCY PLAN

Contingency plans for operations at the Ag Plastic Landfill are provided in the Operation Plan provided in Appendix A.

9 PLANS OR DRAWINGS

The engineering plans and drawings for the Ag Plastic Landfill have not changed and are provided in the 2004 Ag Plastic Application, Part F.

a. Regional Map or Plan

The regional map or plan is provided in previously submitted 2004 Ag Plastic Application and the more recently submitted 2014 Class I Application, Appendix B, Sheet V1.

b. Vicinity Map or Aerial Photograph

The vicinity map with aerial photo is provided in previously submitted 2014 Class I Application Appendix B, Sheet C1. See also Attachment E.1.

c. Site Plan

The site plan showing all property boundaries is provided in previously submitted 2014 Class I Application Appendix B, Sheet C1. No changes to the facility's property boundary have occurred since it was previously certified by a Florida-Licensed Professional Surveyor and Mapper; therefore, a site plan with the boundaries certified is not provided with this application.

d. Supporting Details

Drawings previously submitted in the 2004 Ag Plastic Application and 2009 Ag Plastic Application provide other necessary details to support the engineering report including referencing elevations to a consistent, nationally recognized datum and identifying the method used for collecting latitude and longitude data.

10 DOCUMENTATION FROM PROPERTY OWNER

The entire property is owned by the Highlands County Board of County Commissioners Solid Waste Division. A copy of the Warranty Deed dated April 3, 1989, was submitted in the 2004 Ag Plastic Application, Part E.

11 COUNTY WASTE REDUCTION AND RECYCLING GOALS

No changes to the facility's waste reduction and recycling goals are proposed in this permit application.

The Highlands County recycling program consists of 24 drop-off locations around the County. At these locations, residents can recycle newspapers, magazines, plastic containers, cardboard, steel cans, aluminum cans, and glass. The Ag Plastic Landfill generally supports the components of the County's solid waste management system by providing disposal.

12 HISTORY AND DESCRIPTION OF ENFORCEMENT ACTIONS

FDEP took enforcement action against Highlands County with Consent Order 10-0884-28-TK. A fine of \$1,200 was submitted to FDEP May 19, 2010, and the HCSWMC is now in compliance.

13 PROOF OF PUBLICATION AND NOTIFICATION LETTERS

In accordance with Rule 62-701.320(8), FAC, a Notice of Application is not applicable for renewal permit applications and is not required to be submitted by Highlands County.

14 AIRPORT SAFETY

Attachment E.1 shows no change since the previous permit application. Sebring Regional Airport is the only airport within a 5-mile radius of the proposed Ag Plastic Landfill. In accordance with the requirements of 62-701.320(13), FAC, no waste is stored, disposed, or processed within 10,000 feet of the Sebring Regional Airport.

15 OPERATOR AND SPOTTER TRAINING REQUIREMENTS

Operators and spotters that work at the HCSWMC and Ag Plastic Landfill will be trained in accordance with Rule 62-701.320(15), FAC. Personnel are required to successfully complete FDEP-approved training courses. The training plan and records documenting successful completion of the courses will be kept at the HCSWMC at all times. The Operation Plan in Appendix A identifies the operators' training requirements for the Ag Plastic Landfill.

Attachment D.5

FDEP's Approval of the Reduction or Waiver of Permit Processing Fees



**FLORIDA DEPARTMENT OF
ENVIRONMENTAL PROTECTION**

South District Office
P.O. Box 2549
Fort Myers, FL 33902-2549
SouthDistrict@dep.state.fl.us

RICK SCOTT
GOVERNOR

CARLOS LOPEZ-CANTERA
LT. GOVERNOR

HERSCHEL T. VINYARD JR.
SECRETARY

November 12, 2014

SENT BY ELECTRONIC MAIL

Mr. Timothy R. Mechling
OMB Senior Manager
Highlands County
Email: tmechling@hcbcc.org

Re: Fee Waiver Request

Dear Mr. Mechling:

Thank you for your letter dated November 4, 2014, and supporting documentation sent to Albert McLaurin, (received via e-mail on November 10, 2014) requesting fee waivers based upon §218.075, F.S., on behalf of the Highlands County Board of County Commissioners.

Pursuant to §218.075, F.S., Department of Environmental Protection permit processing fees are hereby waived for the Highlands County Board of County Commissioners for calendar year 2015. This waiver is applicable when the permit applicant is the governing body of Highlands County or a third party under contract with the county and the project serves a public purpose. Please submit a copy of this letter along with any permit application for which the fee waiver is sought.

Please note that Mr. McLaurin has retired from this agency since October 5, 2014.

If you have any questions, please feel free to contact Abdul B. Ahmadi, P.E. at (239) 344-5614.

Sincerely,

Jon M. Iglehart
Director of District Management

JMI/ABA/se

Copies to:

Kimberly A. Middleton: kmiddleton@hcbcc.org
Megan Mills, DEP
Gary Maier, DEP
Mary Fitzgerald, DEP
Jeannie Gerhart, DEP
Maria Coleman, DEP

PART E

LANDFILL PERMIT REQUIREMENTS

1 REGIONAL MAP OR AERIAL PHOTOGRAPH SHOWING AIRPORTS

Attachment E.1 provides an aerial photograph showing all airports within 5 miles of the HCSWMC.

2 PLOT PLAN

The previously submitted drawings provided in 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4 and 2014 Class I Application, Appendix B meet the requirements of Rule 62-701.330(3)(b), FAC, and include a plot plan of the site showing dimensions, locations of proposed and existing water quality monitoring wells, locations of soil borings, proposed plan of disposal areas, original elevations, proposed final contours, previously filled waste areas, and fencing. The scale of the plot plan is not greater than 200 feet to the inch.

a. Dimensions

The Permit Drawings are drawn to scale. Dimensions of the Ag Plastic Landfill are shown on the 2004 Ag Plastic Application, Part F, Figure F-3.

b. Locations of Proposed and Existing Water Quality Monitoring Wells

Specific water quality monitoring for the Ag Plastic Landfill is not required. Water quality monitoring for the HCSWMC is performed as part of the Class I Landfill Permit Number 0038570-030-SO/01, Appendix 3. Locations of the existing water quality monitoring wells are shown on the 2014 Class I Application, Figure L.1.

c. Locations of Soil Borings

Soil borings are not applicable to this permit renewal application because no expansions are planned.

d. Proposed Plan of Trenching or Disposal Areas

The Ag Plastic Landfill disposal area is shown in the previously submitted 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4. No new disposal areas are proposed as a part of this permit application.

e. Cross Sections

Cross-sections are shown in the previously submitted 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4. No changes are proposed as a part of this permit application.

f. Previously Filled Waste Disposal Areas

The Ag Plastic Landfill has no previously filled waste disposal areas.

g. Fencing or Other Measures to Restrict Access

The project area is surrounded by a fence, and the entrance has a security gate, as discussed in the Operation Plan (Appendix A). The HCSWMC property is fenced and has a 6-foot-deep ditch and 5-foot-high berm running along the outside of the fence. The entrance gate along Arbuckle Creek Road is only open during operating hours. Signs indicating hours of operation, operating and permitting authorities, and directions for persons delivering waste are posted at the entrance.

3 TOPOGRAPHIC MAPS

The previously submitted drawings provided in 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4 and 2014 Class I Application, Appendix B meet the requirements of Rule 62-701.330(3)(c), FAC, and include topographic maps at a scale no greater than 200 feet to the inch with 5-foot contour intervals that show proposed fill area, access roads, grades required for proper drainage, special drainage devices, fencing, and equipment facilities.

a. Proposed Fill Areas

No construction or fill are proposed in this permit application.

b. Borrow Areas

Borrow areas are shown in 2014 Class I Application, Appendix B, Site Plan. No new borrow areas are proposed in this permit application.

c. Access Roads

Access roads are shown in 2014 Class I Application, Appendix B, Site Plan. No new access roads are proposed in this permit application.

d. Grades Required for Proper Drainage

Final build-out grades and drainage structures were previously submitted in the 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4. No changes are proposed as a part of this permit application.

e. Cross Sections of Lifts

Cross-sections were previously submitted in the 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4. No changes are proposed as a part of this permit application.

f. Special Drainage Devices

Drainage structures and details were previously submitted in the 2004 Ag Plastic Application, Part F and 2009 Ag Plastic Application, Section 4. No changes are proposed as a part of this permit application.

g. Fencing

See Part E.2.g.

h. Equipment Facilities

No changes to equipment facilities are proposed.

4 LANDFILL REPORT

a. Current and Projected Population

The Ag Plastic Landfill serves the populations of incorporated and unincorporated Highlands County. The current and projected population was obtained from the University of Florida's Bureau of Economic and Business Research (BEBR). The BEBR's population projection data used were released in March 2013 (*Projections of Florida Population by County, 2015–2040, with Estimates for 2012* in Volume 46, Bulletin 165 of *Florida Population Studies* – Attachment E.4).

b. Anticipated Type, Annual Quantity, and Source of Solid Waste

The Ag Plastic Landfill only accepts agricultural plastic waste, including film, tubing, and irrigation pipe. Data on the annual quantity of waste received in FY12/13 are provided in Attachment E.4.

Reports providing waste types and quantities disposed of in the HCSWMC are provided to FDEP as required by Chapter 62-701.500(4), FAC.

c. Planned Active Life, Final Design Height, and Maximum Operation Height of the Facility

The planned active life was calculated for the Ag Plastic Landfill, and the calculations are provided in Attachment E.4. The volume remaining was calculated based on the most recent topographic survey. The proposed final closure design was previously submitted and has not changed. The design life accounts for increased solid waste acceptance due to population increase. The Ag Plastic Landfill has approximately 79 years of active life for waste disposal. The maximum operation height of the solid waste (top of intermediate cover) is 102 feet NGVD, based on the 104 feet NGVD design height of the landfill.

d. Source and Type of Cover Material

Cover material will be obtained from the on-site borrow pit or off-site pits, if necessary. See Operation Plan (Appendix A) for information on the cover material.

5 WATER QUALITY MONITORING LABORATORY

Specific water quality monitoring for the Ag Plastic Landfill is not required. Water quality monitoring for the HCSWMC is performed as part of the Class I Landfill Permit Number 0038570-030-SO-01, Appendix 3. Water quality monitoring for the HCSWMC is performed by an FDEP-approved laboratory in accordance with Rule 62-160, FAC. Pace Analytic Services, Inc. is currently contracted. A copy of their certification is provided in the previously submitted 2014 Class I Application, Attachment E.5.

6 FINANCIAL RESPONSIBILITY



Please refer to Part R of this permit application for financial assurance documentation required by Rule 62-701.630, FAC.

Attachment E.1

Airport Location Map and Aerial Photo

Attachment E.1

Airport Location and Aerial Photo Map
Highlands County Solid Waste Management Center AG Plastic Landfill



Aerial Photo: 2014 FDOT



Attachment E.4
Design Life Calculations



Attachment 1 - Capacity and Design Life Analysis

PROJECT NUMBER: 08345-012-01
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/20/14
 CHECKED BY: H. Boudreau *H. Boudreau* Date: 12/19/24

Ag Plastic Landfill

Objective:

1. Calculate the annual BEBR Population Growth Rate Projections.
2. Calculate the volume remaining from survey date 9/26/2013
3. Calculate the remaining capacity and projected lifespan.

Data:

$V_T =$	Total Design Volume (based on Highlands County value) =	230,000	CY	(Reference 3 - Table 8)
$V_C =$	Current Disposal Volume =	25,519	CY	(Reference 1)
$W_A =$	Annual Tonnage Disposed (FY12-13 - rounded) =	440	Tons	(Reference 2)
$W_{A(11)} =$	Annual Tonnage Disposed (FY12-13) =	634	Tons	(Reference 3 - Table 8)
$V_{A(11)} =$	Annual Capacity Used (FY12-13) =	2,883	CY	(Reference 3 - Table 8)
$\sigma_a =$	$W_{A(11)} / V_{A(11)} =$ Waste to Volume Ratio (FY12-13) =	16	pcf	(Calculated)
	634 tons / 2883 CY =	0.22	tey	(Calculated)

Calculations:

1. Estimate the future annual growth rate based on BEBR medium population projections. (Reference 4)
2. Calculate the waste volume remaining based on 2013 survey.

$V_R = V_T - V_C$

Where:

$V_T =$	Total Design Volume	230,000	CY	(Reference 1)
$V_C =$	Current Volume based on 9/26/2013 Survey =	25,519	CY	(Reference 1)
$V_R =$	230000 CY - 25519 CY =	204,481	CY	(Calculated)

3. Calculate the tonnage projections and the anticipated lifespan for the Landfill.

Medium BEBR Population Projections Ag Plastic Landfill						
(4) Disposal Volume Remaining (V_R) =					204,481 CY	(Calculated)
Year	(1) Annual Waste Disposal Rate (Tons/year)	(2) Annual Growth Rate (Reference 4) (%/yr)	(3) Waste to Volume Ratio (T/CY)	[(1) x (3)] Volume of Waste Landfilled CY	(5) = Previous Volume Remaining - [(1)x(3)] Annual Volume Remaining (CY)	
2013	440				204,481	
2014	444	0.9%	0.22	2,018	202,463	
2015	448	0.9%	0.22	2,036	200,427	
2016	453	1.1%	0.22	2,058	198,370	
2017	458	1.1%	0.22	2,080	196,290	
2018	462	1.1%	0.22	2,102	194,188	
2019	467	1.1%	0.22	2,125	192,063	
2020	472	1.1%	0.22	2,148	189,915	
2021	477	0.9%	0.22	2,168	187,747	
2022	481	0.9%	0.22	2,188	185,559	
2023	486	0.9%	0.22	2,209	183,350	
2024	490	0.9%	0.22	2,229	181,121	
2025	495	0.9%	0.22	2,250	178,871	
2026	499	0.8%	0.22	2,267	176,603	
2027	503	0.8%	0.22	2,285	174,318	
2028	507	0.8%	0.22	2,303	172,016	
2029	510	0.8%	0.22	2,320	169,695	
2030	514	0.8%	0.22	2,338	167,357	
2031	518	0.6%	0.22	2,353	165,004	
2032	521	0.6%	0.22	2,368	162,637	
2033	524	0.6%	0.22	2,382	160,254	
2034	527	0.6%	0.22	2,397	157,857	
2035	531	0.6%	0.22	2,412	155,445	
2036	533	0.5%	0.22	2,425	153,019	
2037	536	0.5%	0.22	2,438	150,582	
2038	539	0.5%	0.22	2,451	148,131	
2039	542	0.5%	0.22	2,464	145,667	
2040	545	0.5%	0.22	2,476	143,191	
2041	548	0.5%	0.22	2,490	140,701	
2042	551	0.5%	0.22	2,503	138,199	



Attachment 1 - Capacity and Design Life Analysis

PROJECT NUMBER: 08345-012-01
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/20/14
 CHECKED BY: H. Boudreau Date: 12/19/14

Ag Plastic Landfill

Objective:

1. Calculate the annual BEBR Population Growth Rate Projections.
2. Calculate the volume remaining from survey date 9/26/2013
3. Calculate the remaining capacity and projected lifespan.

Data:

$V_T =$	Total Design Volume (based on Highlands County value) =	230,000	CY	(Reference 3 - Table 8)
$V_C =$	Current Disposal Volume =	25,519	CY	(Reference 1)
$W_A =$	Annual Tonnage Disposed (FY12-13 - rounded) =	440	Tons	(Reference 2)
$W_{A(11)} =$	Annual Tonnage Disposed (FY12-13) =	634	Tons	(Reference 3 - Table 8)
$V_{A(11)} =$	Annual Capacity Used (FY12-13) =	2,883	CY	(Reference 3 - Table 8)
$\sigma_a =$	$W_{A(11)} / V_{A(11)} =$ Waste to Volume Ratio (FY12-13) =	16	pcf	(Calculated)
	634 tons / 2883 CY =	0.22	tcy	(Calculated)

Calculations:

1. Estimate the future annual growth rate based on BEBR medium population projections. (Reference 4)
2. Calculate the waste volume remaining based on 2013 survey.

$V_R = V_T - V_C$

Where:

$V_T =$	Total Design Volume	230,000	CY	(Reference 1)
$V_C =$	Current Volume based on 9/26/2013 Survey =	25,519	CY	(Reference 1)
$V_R =$	230000 CY - 25519 CY =	204,481	CY	(Calculated)

3. Calculate the tonnage projections and the anticipated lifespan for the Landfill.

Medium BEBR Population Projections					
Ag Plastic Landfill					
(4) Disposal Volume Remaining (V_R) =					204,481 CY
Year	(1) Annual Waste Disposal Rate (Tons/year)	(2) Annual Growth Rate (Reference 4) (%/yr)	(3) Waste to Volume Ratio (T/CY)	[(1) x (3)] Volume of Waste Landfilled CY	(5) = Previous Volume Remaining - [(1)x(3)] Annual Volume Remaining (CY)
2043	553	0.5%	0.22	2,516	135,683
2044	556	0.5%	0.22	2,529	133,154
2045	559	0.5%	0.22	2,542	130,612
2046	562	0.5%	0.22	2,556	128,056
2047	565	0.5%	0.22	2,569	125,487
2048	568	0.5%	0.22	2,583	122,904
2049	571	0.5%	0.22	2,596	120,308
2050	574	0.5%	0.22	2,610	117,698
2051	577	0.5%	0.22	2,624	115,075
2052	580	0.5%	0.22	2,637	112,437
2053	583	0.5%	0.22	2,651	109,786
2054	586	0.5%	0.22	2,665	107,121
2055	589	0.5%	0.22	2,679	104,441
2056	592	0.5%	0.22	2,693	101,748
2057	596	0.5%	0.22	2,708	99,041
2058	599	0.5%	0.22	2,722	96,319
2059	602	0.5%	0.22	2,736	93,583
2060	605	0.5%	0.22	2,750	90,832
2061	608	0.5%	0.22	2,765	88,067
2062	611	0.5%	0.22	2,779	85,288
2063	615	0.5%	0.22	2,794	82,494
2064	618	0.5%	0.22	2,809	79,685
2065	621	0.5%	0.22	2,824	76,862
2066	624	0.5%	0.22	2,838	74,023
2067	628	0.5%	0.22	2,853	71,170
2068	631	0.5%	0.22	2,868	68,301
2069	634	0.5%	0.22	2,883	65,418
2070	638	0.5%	0.22	2,899	62,519
2071	641	0.5%	0.22	2,914	59,606
2072	644	0.5%	0.22	2,929	56,676
2073	648	0.5%	0.22	2,945	53,732

(Calculated)



Attachment 1 - Capacity and Design Life Analysis

PROJECT NUMBER: 08345-012-01
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/20/14
 CHECKED BY: H. Boudreau *[Signature]* Date: 12/19/14

Ag Plastic Landfill

Objective:

1. Calculate the annual BEBR Population Growth Rate Projections.
2. Calculate the volume remaining from survey date 9/26/2013
3. Calculate the remaining capacity and projected lifespan.

Data:

$V_T =$	Total Design Volume (based on Highlands County value) =	230,000	CY	<i>(Reference 3 - Table 8)</i>
$V_C =$	Current Disposal Volume =	25,519	CY	<i>(Reference 1)</i>
$W_A =$	Annual Tonnage Disposed (FY12-13 - rounded) =	440	Tons	<i>(Reference 2)</i>
$W_{A(11)} =$	Annual Tonnage Disposed (FY12-13) =	634	Tons	<i>(Reference 3 - Table 8)</i>
$V_{A(11)} =$	Annual Capacity Used (FY12-13) =	2,883	CY	<i>(Reference 3 - Table 8)</i>
$\sigma_a =$	$W_{A(11)} / V_{A(11)} =$ Waste to Volume Ratio (FY12-13) =	16	pcf	<i>(Calculated)</i>
	634 tons / 2883 CY =	0.22	tcy	<i>(Calculated)</i>

Calculations:

1. Estimate the future annual growth rate based on BEBR medium population projections. *(Reference 4)*
2. Calculate the waste volume remaining based on 2013 survey.

$V_R = V_T - V_C$

Where:

$V_T =$	Total Design Volume	230,000	CY	<i>(Reference 1)</i>
$V_C =$	Current Volume based on 9/26/2013 Survey =	25,519	CY	<i>(Reference 1)</i>
$V_R =$	230000 CY - 25519 CY =	204,481	CY	<i>(Calculated)</i>

3. Calculate the tonnage projections and the anticipated lifespan for the Landfill.

Medium BEBR Population Projections Ag Plastic Landfill					
(4) Disposal Volume Remaining (V_R) =					204,481 CY
Year	(1) Annual Waste Disposal Rate (Tons/year)	(2) Annual Growth Rate <i>(Reference 4)</i> (%/yr)	(3) Waste to Volume Ratio (T/CY)	[(1) x (3)] Volume of Waste Landfilled CY	(5) = Previous Volume Remaining - [(1)x(3)] Annual Volume Remaining (CY)
2074	651	0.5%	0.22	2,960	50,772
2075	655	0.5%	0.22	2,976	47,796
2076	658	0.5%	0.22	2,991	44,805
2077	661	0.5%	0.22	3,007	41,798
2078	665	0.5%	0.22	3,023	38,775
2079	668	0.5%	0.22	3,039	35,736
2080	672	0.5%	0.22	3,055	32,682
2081	676	0.5%	0.22	3,071	29,611
2082	679	0.5%	0.22	3,087	26,524
2083	683	0.5%	0.22	3,103	23,421
2084	686	0.5%	0.22	3,120	20,301
2085	690	0.5%	0.22	3,136	17,165
2086	693	0.5%	0.22	3,152	14,013
2087	697	0.5%	0.22	3,169	10,844
2088	701	0.5%	0.22	3,186	7,658
2089	704	0.5%	0.22	3,202	4,456
2090	704	0.5%	0.22	3,202	4,456
2091	708	0.5%	0.22	3,219	1,236
2092	712	0.5%	0.22	3,236	-2,000
(6) Total Years Remaining (from September 2013)					78.6
(7) Anticipated Closure Date					April 2092

Note: Numbering in parenthesis based on discussion items in text.

References:

1. AutoCAD Civil 3D Volume of 9-26-2013 survey.
AutoCAD Civil 3D Volume of conceptual final cover surface developed for this analysis.
2. 2013 Tonnage Data from Highlands County report for residential plus commercial.
3. FY11/12 Tonnage and Volume Data from Yearly Volume Consumption Report for Permit Specific Condition #22 dated October 25, 2012 prepared by Highlands County Solid Waste Management for Mr. Alber McLaurin, PE FDEP Fort Myers Regional Service Center.
4. University of Florida Bureau of Economic and Business Research (BEBR), Florida Population Studies, Bulletin 162 (Revised) March 2012, "Projections for Florida Populations by County, 2011 - 2040".



Attachment 1 - Capacity and Design Life Analysis

PROJECT NUMBER: 08345-012-01
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/20/14
 CHECKED BY: H. Boudreau *[Signature]* Date: 12/19/14

Ag Plastic Landfill

Objective:

1. Calculate the annual BEBR Population Growth Rate Projections.
2. Calculate the volume remaining from survey date 9/26/2013
3. Calculate the remaining capacity and projected lifespan.

Data:

$V_T =$	Total Design Volume (based on Highlands County value) =	230,000	CY	(Reference 3 - Table 8)
$V_C =$	Current Disposal Volume =	25,519	CY	(Reference 1)
$W_A =$	Annual Tonnage Disposed (FY12-13 - rounded) =	440	Tons	(Reference 2)
$W_{A(11)} =$	Annual Tonnage Disposed (FY12-13) =	634	Tons	(Reference 3 - Table 8)
$V_{A(11)} =$	Annual Capacity Used (FY12-13) =	2,883	CY	(Reference 3 - Table 8)
$\sigma_a =$	$W_{A(11)} / V_{A(11)} =$ Waste to Volume Ratio (FY12-13) =	16	pcf	(Calculated)
	634 tons / 2883 CY =	0.22	tcy	(Calculated)

Calculations:

1. Estimate the future annual growth rate based on BEBR medium population projections. (Reference 4)
2. Calculate the waste volume remaining based on 2013 survey.

$V_R = V_T - V_C$

Where:

$V_T =$	Total Design Volume	230,000	CY	(Reference 1)
$V_C =$	Current Volume based on 9/26/2013 Survey =	25,519	CY	(Reference 1)
$V_R =$	230000 CY - 25519 CY =	204,481	CY	(Calculated)

3. Calculate the tonnage projections and the anticipated lifespan for the Landfill.

Medium BEBR Population Projections Ag Plastic Landfill						
(4) Disposal Volume Remaining (V_R) =					204,481 CY	(Calculated)
Year	(1) Annual Waste Disposal Rate (Tons/year)	(2) Annual Growth Rate (Reference 4) (%/yr)	(3) Waste to Volume Ratio (T/CY)	[(1) x (3)] Volume of Waste Landfilled CY	(5) = Previous Volume Remaining - [(1)x(3)] Annual Volume Remaining (CY)	

Explanation of Calculations:

- 1 Estimated 2013/2014 Annual Waste Disposal Rate: The 2012/2013 waste disposal rate in tpy is estimated based on FY12-13 tonnage data provided by Highlands County (Attachment 1, Reference 2).
- 2 Annual Growth Rate: An annual growth rate is used in the design life calculation to model the annual increase in waste flow to the landfill due to increasing population. Using the population as the measure for the annual growth rate assumes that the average per capita waste production will remain constant. The annual growth rate calculations from 2012 to 2040 ranging from 0.5% to 1.1% (Attachment 1, Reference 4) are based on the University of Florida Bureau of Economic and Business Research (BEBR), Projections of Florida Population by County 2010-2040, Bulletin 162, March 2012.
- 3 Waste Weight-to-Volume Ratio: The waste weight-to-volume ratio (density) is used in the design life calculation to convert the waste tonnage landfilled into a volume for determining the volume remaining for each year of active landfilling. The density is calculated by dividing the total tonnage of waste placed between topographic surveys by the total volume of airspace used between topographic surveys.

The waste tonnage data and the annual volume consumed were provided by Highlands County (Attachment 1, Reference 3). The waste tonnage and yearly volume consumption report is dated October 25, 2012, and was retrieved from the FDEP OCULUS database.

The variation in waste densities shown is typical for changes in waste type and degree of compaction.
- 4 Disposal Volume Remaining: The volume remaining in the landfill is calculated using CADD software by estimating the volume between the 2013 topographic survey surface from the intermediate closure design surface (Attachment 1, Reference 1). The intermediate closure design was developed by Jones Edmunds based on permit conditions (minus 2 feet to account for the final cover thickness).
- 5 Annual Volume Remaining: The volume remaining for each year in the active life of the landfill is calculated for each year. The annual landfill volume remaining is calculated based on the estimated tonnage of waste landfilled (increased annually using the annual growth rate) converted to a volume by multiplying it by the waste density. The annual volume landfilled is then subtracted from the volume remaining in the previous year of the landfill's active lifespan.
- 6 Total Lifespan: The lifespan is the number of years calculated by iteratively subtracting the annual volume landfilled from the annual volume remaining until the volume remaining becomes zero or negative. If negative volume remains, the fraction of the year remaining is linearly interpolated.
- 7 Anticipated Closure Date: The closure date is determined based on the calculated lifespan starting from the survey date.



Attachment E4 - Reference 1

PROJECT NUMBER: 08345-012-01 SHEET: 1 OF 1
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: P. Upstill Date: 8/12/14
 CHECKED BY: M. Pollman *MP* Date: 12/19/14

08345-013-01 MC REPORTING Reference 1

CADD Volume Calculations:

Landfill	2D Area (acres)	Peak Elevation (feet)	Volume	Base Surface	Comparison Surface	Cut (CY)	Fill (CY)	Net (CY)
Class I*	31	128	Total	JE-SAND	intermediate-cover	34	3,146,262	3,146,228
Class I	31	130	Current	JE-SAND	Cell 1a and 1b	4	1,984,533	1,984,529

* Net Fill calculated based on the Jones Edmunds final cover surface is very close to the value reported by Highlands County. Highlands County value of used in the analysis.

Landfill	Area	Peak Elev	Volume	Base Surface	Comparison Surface	Cut (CY)	Fill (CY)	Net (CY)
C&DD	11	127.5	Total	je-bottom	je-cover-M2	41	554,243	554,201
C&DD	11		Current	je-bottom	C & D	0	222,443	222,443

Landfill	Area	Peak Elev	Landfill	Base Surface	Comparison Surface	Cut (CY)	Fill (CY)	Net (CY)
Ag Plastic	6	See 2004	Total	BASE	plastic-cover	0	See 2004 permit app.	
Ag Plastic	6		Current	BASE	Plastic avg top	0	25,519	25,519

Surface Notes

Class I

JE-SAND - Bottom surface derived from ARBUCKLE CREEK LANDFILL CELL 1A, 1B, 3A, 3B, & 3C VOLUME SUMMERY 9/26/13 drawings from Highlands County Engineering Department by merging 3 sand bottom surfaces.

Cell 1a and 1b - Top grades surface from ARBUCKLE CREEK LANDFILL CELL 1A, 1B, 3A, 3B, & 3C VOLUME SUMMERY 9/26/13 drawings from Highlands County Engineering Department.

Intermediate-cover - Intermediate Cover surface derived from sheet C-3 elevations shown in the Highlands County Solid Waste Management Center 2008 Permit Drawings.

C&DD

1. Je-cover-M2 – Cover Surface derived from Highlands County Construction and Demolition Waste Landfill Closure Permit Drawings dated May 27, 1999 Sheet 5 Stage 2 and added 25 foot wide benches at elevation 95.0, peak cover elevation 129.5, then lowered 2 feet.

Je-bottom – Bottom surface derived from ARBUCKLE CREEK LANDFILL CELL C & D VOLUME REPORT 9/26/13 drawings from Highlands County Engineering Department and extended into Phase II by interpolating 3d lines.

C & D - Top grades surface from ARBUCKLE CREEK LANDFILL CELL C & D VOLUME REPORT 9/26/13 drawings from Highlands County Engineering Department.

Ag Plastic

BASE - Base grades surface from Agricultural Plastic Disposal Unit Volume Report 9/26/13 drawings from Highlands County Engineering Department and added surrounding grades to top of existing berm.

Plastic avg top - Base grades surface from Agricultural Plastic Disposal Unit Volume Report 9/26/13 drawings from Highlands County Engineering Department.

Plastic-cover - Top grades surface 3:1 slopes from existing berm top to elevation 130.0 feet, designed by M Pollman at JE.

Drawings Used

- \\Gnv-projects\projects\08345-HighlandsCounty\012-01 economic eval\Evaluation\Task 2 Evaluate Remaining Capacity\Calculations\20141105-Capacity2013RevisedandUpdatedC&DDClass\FACE.xlsxRef1-CADD volume calcs
- \\eacad\Drafting\08345 Highlands County\Capacity Analysis\012 MC Reporting\20140702\C + D\08345012vol20140702.dwg
- \\eacad\Drafting\08345 Highlands County\Capacity Analysis\012 MC Reporting\20140702\Class I\08345012vol20140702.dwg
- \\eacad\Drafting\08345 Highlands County\Capacity Analysis\012 MC Reporting\20140702\Plastic\08345012vol20140702.dwg



PROJECT NUMBER: 08345-012-01 SHEET: 1 OF 1
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/12/14

Attachment E4 - Reference 2

Data provided by Highlands County

Reference 2

Data provided by Highlands County used for initial annual tonnage disposed (W_T).

**Monthly Tonnages Received at Highlands County Landfills
FY 12-13**

Highlands County Solid Waste Management Center	Residential Household Waste ¹	Commercial Waste ²	Yard Waste (Including Grass Clippings ³)	Tires ⁴	Miscellaneous ⁵ (Class I Only)	White Goods (Including Recycled White Goods)	Ag - Plastic	C&D ⁶	Sub-Totals	Road Base	Other Material & Transactions ⁶	Total Tons
FY 12/13	37,448.92	28,014.02	6,115.90	392.11	2,947.13	43.02	438.51	9,642.45	85,042.06	4,134.70	3,878.99	93,055.75
FY 11/12	38,394.04	27,956.30	6,717.29	350.74	2,931.11	30.73	634.09	9,468.32	86,482.62	3,613.38	5,637.54	95,733.54
Percent Change from FY 11/12	-2%	0.206%	-9%	12%	1%	40%	-31%	2%		14%		
Total Percent Change from FY 11-12:										-1.67%		-2.80%

- ¹ Modified Residential Household Waste in FY 2011/2012 to NOT include Community Cleanup. Community Cleanup was included in FY2010/2011.
- ² Modified Commercial Waste in FY 2011/2012 NOT to include daily Recycling Trash and small C & D material brought in on Saturdays. Recycling Trash was included in FY2010/2011.
- ³ Grass Clippings are received @ no charge according to adopted fee schedule.
- ⁴ Tires include loads by tonnage, individual tires (EA), and Community/legal Cleanups.
- ⁵ Miscellaneous = Garbage Arbuckle Creek, Seb Street Sweepings, Sewer Grit, Waste Water - R&B, Community Cleanup, Recycling Trash, Monitors (E-Waste), Animal Carcasses, Special Waste (Other), Contaminated Soil (Board Waived Fees), Contaminated Soil, Asbestos Containing Material, Waste Water Treatment Sludge, Septic Sludge, ASR.
- ⁶ Begun Including Granite Sand (Code 50) and C&D Wastes (Code 250) in FY 2011/2012.
- ⁷ Begun Including this category in FY 2011/2012 in order to account for 100% of tonnage & revenue as listed in the Transaction Daily Reports for each month.

Highlands County Solid Waste Management Center	Residential Household Waste ¹	Commercial Waste ²	Yard Waste (Including Grass Clippings ³)	Tires ⁴	Miscellaneous ⁵ (Class I Only)	White Goods (Including Recycled White Goods)	Ag - Plastic	C&D ⁶	Sub-Totals	Road Base	Other Material & Transactions ⁶	Total Revenue
FY 12/13	\$ 1,687,320.30	\$ 1,256,964.79	\$ 149,195.65	\$ 38,116.20	\$ 26,785.75	\$ 299.60	\$ 19,750.35	\$ 159,612.42	\$ 3,338,045.06	\$ -	\$ 8,706.55	\$ 3,346,751.61
FY 11/12	\$ 1,730,036.80	\$ 1,259,209.10	\$ 151,464.50	\$ 34,549.70	\$ 25,448.10	\$ 182.20	\$ 28,542.35	\$ 148,960.30	\$ 3,378,393.05	\$ -	\$ 4,792.55	\$ 3,383,185.60
Percent Change from FY 11/12	-2%	0%	-1%	10%	5%	64%	-31%	7%		100%		
Total Percent Change from FY 11-12:										-1.19%		-1.08%

- ¹ Modified Residential Household Waste in FY 2011/2012 to NOT include Community Cleanup. Community Cleanup was included in FY2010/2011.
- ² Modified Commercial Waste in FY 2011/2012 NOT to include daily Recycling Trash and small C & D material brought in on Saturdays. Recycling Trash was included in FY2010/2011.
- ³ Grass Clippings are received @ no charge according to adopted fee schedule.
- ⁴ Tires Revenue based on charges listed under the Tire Code (300). Special Fees (EA depending on type) will be included under the main material type code and "Not Specified (999)" will be included in other specific codes.
- ⁵ Miscellaneous = Garbage Arbuckle Creek, Seb Street Sweepings, Sewer Grit, Waste Water - R&B, Community Cleanup, Recycling Trash, Monitors (E-Waste), Animal Carcasses, Special Waste (Other), Contaminated Soil (Board Waived Fees), Contaminated Soil, Asbestos Containing Material, Waste Water Treatment Sludge, Septic Sludge, ASR.
- ⁶ Begun Including this category in FY 2011/2012 in order to account for 100% of tonnage & revenue as listed in the Transaction Daily Reports for each month.



Attachment E4 - Reference 3

PROJECT NUMBER: 08345-012-01
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 Waste Density Calculations
 BY: M. Pollman Date: 11/5/14

	Annual Waste Tonnage (tons)	Annual Waste Tonnage Reference	Annual Waste Volume Consumed (Cubic Yards)	Annual Waste Volume Reference	Calculated Waste Density (TCY)	Calculated Waste Density (PCF)
Class I Landfill (FY12-13)	65,463	Table 1	93,447	Table 5	0.70	52
Class I Landfill (FY11-12)	67,181	FY11-12	95,840	FY11-12	0.70	52
		Value used in Calculations¹:			0.70	52
C&DD Landfill (FY12-13)	9,642	Table 1	6,633	Table 7	1.45	108
C&DD Landfill (FY11-12)	4,862	FY11-12	8,358	FY11-12	0.58	43
		Value used in Calculations²:			0.58	43
Ag Plastic (FY12-13)	634	Table 1	2,883	Table 8	0.22	16
Ag Plastic (FY11-12)	634	FY11-12	2,922	FY11-12	0.22	16
		Value used in Calculations³:			0.22	16

Notes:

- 1 - Used average of FY12-13 and FY11-12 waste density calculations.
- 2 - Used FY11-12 waste density calculations because FY12-13 calculations are not realistic for a C&DD waste density.
- 3 - Used average of FY12-13 and FY11-12 waste density calculations.

Table 1

**Summary of Solid Waste Received
FY 2012 / 2013**

Class I Wastes Received

Residential and Household Wastes	37,449
Commercial Wastes	28,014
Other Class I Waste	0
Sub-total	65,463 tons

C&D Wastes Received

Inert Debris	9,642
Site Clearing Vegetation	0
Clean Concrete, Roof Shingles, RSM for Landfill Road Base & Cover Material	5,053
Sub-total	14,695 tons

Other Wastes Received

Horticultural Waste	6,116
White Goods	8
Metals from Class I and C&D Landfills	36
Tires	392
Agricultural Plastic	634
Automobile Shredded Residue (ASR)	0
Sub-total	7,186 tons

Total Wastes Received 87,344 tons

Recycled Materials

Horticultural Waste	6,116
White Goods	8
Metals from Class I and C&D Landfills	36
Tires	392
Agricultural Plastic	634
Clean Concrete, Roof Shingles, RSM for Landfill Road Base & Cover Material	5,053
Automobile Shredded Residue (ASR)	0
Total	12,239 tons
Percent of Total	14.01%

Landfilled Wastes

MSW	65,463
C&D	9,642
Ag - Plastic	634
Total	75,739 tons
Percent of Total	86.71%

Table 8

**ANNUAL VOLUME CONSUMED
AGRICULTURAL PLASTIC
TOTAL DISPOSAL VOLUME: 230,128 CY**

Fiscal Year	Annual Volume Consumed		Cumulative Volume Consumed Since Start of Operations (7/15/99)	
	Cubic Yards ⁽²⁾	Percent of Total Disposal Volume ⁽²⁾	Cubic Yards	Percent of Total Disposal Volume ⁽²⁾
FY 06/07	4,806	2.09%	15,703 ⁽¹⁾	6.82%
FY 07/08	1,049	0.46%	16,752 ⁽¹⁾	7.28%
FY 08/09	3,194	1.39%	19,946 ⁽¹⁾	8.67%
FY 09/10	2,479	1.08%	22,425 ⁽¹⁾	9.74%
FY 10/11	1,215	0.53%	23,640 ⁽¹⁾	10.27%
FY 11/12 ⁽³⁾	(1,003)	-0.44%	22,637 ⁽¹⁾	9.84%
FY 12/13 ⁽³⁾	2,883	1.25%	25,519 ⁽¹⁾	11.09%

(1) Based on topographic survey and computer analysis (actual).

(2) Tables modified by Ramon D. Gavarrete, P.E., on October 28, 2010 to allow excel to perform mathematical operations.

(3) Air space recovered due to compaction, decomposition, and settlement of ag-plastics waste.



PROJECT NUMBER: 08345-012-01 SHEET: 1 OF 1
 PROJECT NAME: HIGHLANDS COUNTY
 SUBJECT: Capacity and Design Life Analysis
 BY: M. Pollman Date: 8/12/14

Reference 4

Year	BEBR Population Projections					
	Low	Percent Increase	Medium	Percent Increase	High	Percent Increase
2011	98,955		98,955		98,955	
2012	98,955	0.0%	98,955	0.0%	98,955	0.0%
2013	97,790	-1.2%	99,829	0.9%	101,788	2.9%
2014	96,638	-1.2%	100,711	0.9%	104,702	2.9%
2015	95,500	-1.2%	101,600	0.9%	107,700	2.9%
2016	95,916	0.4%	102,696	1.1%	109,480	1.7%
2017	96,335	0.4%	103,804	1.1%	111,290	1.7%
2018	96,755	0.4%	104,924	1.1%	113,129	1.7%
2019	97,176	0.4%	106,056	1.1%	114,999	1.7%
2020	97,600	0.4%	107,200	1.1%	116,900	1.7%
2021	97,839	0.2%	108,201	0.9%	118,628	1.5%
2022	98,078	0.2%	109,212	0.9%	120,382	1.5%
2023	98,318	0.2%	110,232	0.9%	122,161	1.5%
2024	98,559	0.2%	111,261	0.9%	123,967	1.5%
2025	98,800	0.2%	112,300	0.9%	125,800	1.5%
2026	98,880	0.1%	113,167	0.8%	127,437	1.3%
2027	98,960	0.1%	114,040	0.8%	129,095	1.3%
2028	99,040	0.1%	114,920	0.8%	130,775	1.3%
2029	99,120	0.1%	115,806	0.8%	132,476	1.3%
2030	99,200	0.1%	116,700	0.8%	134,200	1.3%
2031	99,100	-0.1%	117,431	0.6%	135,744	1.2%
2032	99,000	-0.1%	118,166	0.6%	137,306	1.2%
2033	98,900	-0.1%	118,906	0.6%	138,886	1.2%
2034	98,800	-0.1%	119,651	0.6%	140,484	1.2%
2035	98,700	-0.1%	120,400	0.6%	142,100	1.2%
2036	98,479	-0.2%	121,033	0.5%	143,569	1.0%
2037	98,259	-0.2%	121,670	0.5%	145,054	1.0%
2038	98,039	-0.2%	122,310	0.5%	146,554	1.0%
2039	97,819	-0.2%	122,953	0.5%	148,069	1.0%
2040	97,600	-0.2%	123,600	0.5%	149,600	1.0%

Note: 2012, 2015, 2020, 2025, 2030, 2035 and 2040 population data based on data from University of Florida Bureau of Economic and Business Research (BEBR), Florida Population Studies, Bulletin 162 (Revised) March 2012, "Projections for Florida Populations by County, 2011 - 2040". All other years are interpolated.

PART F

GENERAL CRITERIA FOR LANDFILLS

1 100-YEAR FLOODPLAIN

Previously submitted 2014 Class I Application, Part F, Figure F.1 provides a 100-year floodplain map showing that the HCSWMC Ag Plastic Landfill is not within any 100-year floodplain. Therefore, the Ag Plastic Landfill area satisfies the requirements of Rule 62-701.340(4)(b), FAC.

2 HORIZONTAL SEPARATION

The previously submitted drawings provided in 2004 Ag Plastic Application and 2009 Ag Plastic Application, Section 4 and 2014 Class I Application, Appendix B show that greater than 100 feet of horizontal separation exists between the nearest property boundary and the Ag Plastic Landfill. Therefore, the distance between the property boundary and the toe of the proposed final cover slope exceeds 100 feet, meeting the minimum separation requirement in Rule 62-701.340(3)(c), FAC.

PART G

LANDFILL CONSTRUCTION REQUIREMENTS

No construction is proposed with this permit renewal application; therefore, Part G is not applicable.

PART H

HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS

No new hydrogeological investigations were performed for this permit renewal application; therefore, Part H is not applicable.

PART I

GEOTECHNICAL INVESTIGATION REQUIREMENTS

No new geotechnical investigation was conducted for this permit renewal application; therefore, Part I is not applicable.

PART J

VERTICAL EXPANSION OF LANDFILLS

No vertical expansion of landfills is proposed with this permit renewal application; therefore, Part J is not applicable.

PART K

LANDFILL OPERATION REQUIREMENTS

An Operation Plan (Appendix A) includes the policies, procedures, and guidelines for operations of the Ag Plastic Landfill.

1 TRAINED OPERATOR

Refer to Section 1 of the Operation Plan included in Appendix A.

2 LANDFILL OPERATION PLAN

a. Operating and Maintenance Personnel

Refer to Section 2.1 of the Operation Plan included in Appendix A.

b. Emergency Preparedness

Refer to Section 2.2 of the Operation Plan included in Appendix A.

c. Waste Control

Refer to Sections 2.3 of the Operation Plan included in Appendix A.

d. Weighing of Waste

Refer to Section 2.4 of the Operation Plan included in Appendix A.

e. Traffic Control and Unloading

Refer to Section 2.5 of the Operation Plan included in Appendix A.

f. Filling Waste

Refer to Section 2.6 of the Operation Plan included in Appendix A.

g. Waste Compaction and Application of Cover

Refer to Section 2.7 of the Operation Plan included in Appendix A.

h. Gas, Leachate, and Stormwater Controls

Refer to Section 2.8 of the Operation Plan included in Appendix A.

i. Water Quality Monitoring

Refer to Section 2.9 of the Operation Plan included in Appendix A. Water quality monitoring is not required for the Ag Plastic Landfill.

j. Maintenance of Leachate Collection System

Refer to Section 2.10 of the Operation Plan included in Appendix A. The Ag Plastic Landfill has no leachate collection system.

3 DESCRIPTION OF THE LANDFILL OPERATION RECORD

Refer to Section 3 of the Operation Plan included in Appendix A.

4 WASTE RECORDS

Refer to Section 4 of the Operation Plan included in Appendix A.

5 METHODS OF ACCESS CONTROL

Refer to Section 5 of the Operation Plan included in Appendix A.

6 LOAD CHECKING PROGRAM

Refer to Section 6 of the Operation Plan included in Appendix A.

7 PROCEDURES FOR SPREADING AND COMPACTING WASTE

Procedures for spreading and compacting waste are described in the Operation Plan included in Appendix A.

a. Waste Layer Thickness and Compaction Frequencies

Refer to Section 7.1 of the Operation Plan included in Appendix A.

b. Special Considerations—First Layer

Although not applicable to current operations, refer to Section 7.2 of the Operation Plan included in Appendix A.

c. Slopes and Planned Lift Depths of the Working Face

Refer to Sections 7.3 of the Operation Plan included in Appendix A.

d. Width of the Working Face

Refer to Section 7.4 of the Operation Plan included in Appendix A.

e. Initial Cover

Refer to Sections 7.5 and 7.6 of the Operation Plan included in Appendix A.

f. Application Procedures of Initial Cover

Refer to Sections 7.5 and 7.6 of the Operation Plan included in Appendix A.

g. Application Procedures of Intermediate Cover

Refer to Section 7.7 of the Operation Plan included in Appendix A.

h. Time Frames for Applying Final Cover

Refer to Section 7.8 of the Operation Plan included in Appendix A.

i. Scavenging and Salvaging Control

Refer to Section 7.9 of the Operation Plan included in Appendix A.

j. Litter Policing Methods

Refer to Section 7.10 of the Operation Plan included in Appendix A.

k. Erosion Control Procedures

Refer to Section 7.11 of the Operation Plan included in Appendix A.

8 OPERATIONAL PROCEDURES FOR LEACHATE MANAGEMENT

Refer to Section 8 of the Operation Plan included in Appendix A. Leachate collection and management is not applicable to the Ag Plastic Landfill.

9 IMPLEMENTATION OF GAS MANAGEMENT SYSTEM

Refer to Section 9.0 of the Operation Plan included in Appendix A. Gas monitoring is not specifically required for the Ag Plastic Landfill.

10 OPERATING AND MAINTAINING STORMWATER MANAGEMENT SYSTEM

Refer to Section 10 of the Operation Plan included in Appendix A.

11 EQUIPMENT AND OPERATION FEATURE REQUIREMENTS

Refer to Section 11 of the Operation Plan included in Appendix A.

a. Sufficient Equipment

Refer to Sections 11.1 and 11.2 of the Operation Plan included in Appendix A.

b. Reserve Equipment

Refer to Sections 11.1 and 11.2 of the Operation Plan included in Appendix A.

c. Communications Equipment

Refer to Section 11.3 of the Operation Plan included in Appendix A.

d. Dust Control

Refer to Section 11.4 of the Operation Plan included in Appendix A.

e. Fire Protection and Emergencies

Refer to Section 11.5 of the Operation Plan included in Appendix A.

f. Litter Control Devices

Refer to Section 11.6 of the Operation Plan included in Appendix A.

g. Signs

Refer to Section 11.7 of the Operation Plan included in Appendix A.

12 ALL-WEATHER ACCESS ROAD, INSIDE PERIMETER ROAD, AND OTHER ROADS

Refer to Section 12 of the Operation Plan included in Appendix A.

13 ADDITIONAL RECORD KEEPING AND REPORTING

Refer to Section 13 of the Operation Plan included in Appendix A.

a. Permit Applications Records

Refer to Section 13.1 of the Operation Plan included in Appendix A.

b. Monitoring, Calibration, and Maintenance Records

Refer to Section 13.2 of the Operation Plan included in Appendix A.

c. Annual Estimates and Life Spans

Refer to Section 13.3 of the Operation Plan included in Appendix A.

d. Archiving and Retrieving Records

Refer to Section 13.4 of the Operation Plan included in Appendix A.

PART L

WATER QUALITY MONITORING REQUIREMENTS

No water quality monitoring is required for the Ag Plastic Landfill, and no new water quality monitoring is proposed with this permit renewal application; therefore, Part L is not applicable.

Water quality monitoring is performed as part of the HCSWMC Class I Landfill operations. Refer to the 2014 Class I Landfill Permit Number 0038570-030-SO/01 for the water quality monitoring plan.

PART M

SPECIAL WASTE HANDLING REQUIREMENTS

No special waste is accepted at the Ag Plastic Landfill, and no change in waste acceptance is proposed with this permit renewal application; therefore, Part M is not applicable.

Special waste is managed at the HCSWMC as part of the Class I Landfill operations.

The HCSWMC will handle special waste in accordance with Rule 62-701.520, FAC. Refer to the 2014 Class I Landfill Application Operation Plan – Appendix A, including the policies, procedures, and guidelines for special waste handling requirements.

PART N

GAS MANAGEMENT SYSTEM REQUIREMENTS

No special gas management system is required at the Ag Plastic Landfill, and no change to the gas management system is proposed with this permit renewal application; therefore, Part N is not applicable.

The typical plastic waste deposited in the Ag Plastic Landfill does not produce landfill gas.

The HCSWMC will manage and monitor landfill gas to minimize off-site odors, lateral migration of gases, and damage to vegetation. Refer to the 2014 Class I Landfill Application for the operation protocol for gas control.

PART O

LANDFILL FINAL CLOSURE REQUIREMENTS

1 CLOSURE PERMIT REQUIREMENTS

This permit application is for the operation of the active Ag Plastic Landfill. In accordance with Rule 62-701.600(2), FAC, the Highlands County Department of Solid Waste Management (HCDSWM) will obtain authorization from FDEP before initiating closure of the Ag Plastic Landfill or part of it. HCDSWM will request a modification of the permit to address substantive changes in the Closure Plan. Final closure is not expected to occur for the Ag Plastic Landfill for several years (refer to Part E); therefore, this section is not applicable and does not propose any changes to the closure design submitted previously as part of the 2004 Ag Plastic Application. However, the following closure requirements shall be met upon closure:

a. Application

HCDSWM will submit a closure application to FDEP before initiating closure of the Ag Plastic Landfill at least 90 days before final receipt of wastes. If the landfill is operating under an FDEP permit, the owner or operator will request a modification of the permit in lieu of submitting a closure permit application.

b. Closure Plan Requirements

At the time of closure, the Closure Plan will be updated and will include the following:

- (1) A closure report.
- (2) A closure design with a project specific QA/QC.
- (3) A closure operation plan.
- (4) Closure procedures.
- (5) A plan for long-term care.
- (6) A demonstration that proof of financial responsibility for long-term care.

This Closure Plan will be in accordance with Section 62-701.600, FAC.

2 CLOSURE DESIGN PLAN

The Ag Plastic Landfill final cover will include 2-feet thick soil cover with sod. An updated Closure Design Plan will be provided at the time of closure and will include the following in accordance with Rule 62-701.600(3), FAC:

- a. Closure phases.
- b. Existing topography and final grading.
- c. Closure provisions.

- d. Final elevations before settlement.
- e. Side slope design.
- f. Final cover installation.
- g. Final cover design requirements including:
 - (1) Protective soil layer design.
 - (2) Erosion control vegetation.
 - (3) Geomembrane barrier layer design.
 - (4) Cover system stability analysis.
- h. Stormwater control.
- i. Access control.
- j. Gas management system.

3 CLOSURE OPERATION PLAN

The Closure Operation Plan will be provided at the time of closure and will include the following in accordance with Rule 62-701.600(4), FAC:

a. Closure Actions

Closure actions will consist of installing the landfill cap and stormwater management system. The landfill staff or contractor can complete the closure.

b. Time Schedule

The closure schedule will be provided at time of closure. In accordance with Rule 62-701, FAC, long-term care will be a minimum of 30 years.

c. Financial Responsibility

Refer to Part R for financial responsibility.

d. Water Quality Monitoring Plan (62-701.510, FAC)

A Water Quality Monitoring Plan will continue to be followed at closure.

e. Gas Management System (62-701.530, FAC)

A gas management system will be in place at closure.

4 CLOSURE CERTIFICATION

Certification of closure construction will include the following in accordance with Rule 62-701.600(6), FAC.

a. Survey Monuments

The final elevation of this landfill is more than 20 feet above the natural land surface, so no survey monuments are required.

b. Final Survey Report

A final survey will be submitted in accordance with Rule 62-701.610(3), FAC.

5 DECLARATION TO THE PUBLIC

After FDEP approves the closure, the landfill owner shall file a declaration to the public in the deed records office of the County Clerk in accordance with Rule 62-701.600(7), FAC.

6 OFFICIAL DATE OF CLOSING

The official date of closing shall be determined per Rule 62-701.600(8), FAC. Upon receipt of the documents required in Rule 62-701.600(6) and (7), FAC, FDEP shall within 30 days acknowledge by letter to the facility operator that notice of termination of operations and closing of the facility has been received. The date of this letter will be the official date of closing.

7 TEMPORARY CLOSURE PROCEDURES

If the landfill must be closed temporarily, Highlands County will follow the procedures in Rule 62-701.600(7), FAC. A 12-inch layer of soil and bahia sod will be placed over the waste in case of a temporary closure.

PART P

OTHER CLOSURE PROCEDURES

Information presented in this application is intended to provide the general intent of the closure procedures of the Ag Plastic Landfill. Detailed closure procedures will be provided with the closure application.

1 USE OF CLOSED LANDFILL AREAS

Once the Ag Plastic Landfill is closed, no other use will be allowed without prior consultation with FDEP in accordance with Rule 62-701.610(1), FAC. The facility owner at this time has no plans to use the closed landfill area.

2 RELOCATION OF WASTES

Once the Ag Plastic Landfill is closed, no relocation of waste within the footprint of the landfill will be allowed without a modification to the closure permit in accordance with Rule 62-701.610(2), FAC.

PART Q

LONG-TERM CARE

Information presented in this application is intended to provide the general intent of the proposed closure and long-term care of the Ag Plastic Landfill. More information concerning the closure and long-term care will be provided at the time of closure.

1 GAS COLLECTION AND MONITORING SYSTEM

The Ag Plastic Landfill does not accept putrescible waste and is not required to have a gas collection and monitoring system. This section is not applicable to the Ag Plastic Landfill.

2 STABILIZATION REPORTS

During the long-term care period, the County will submit a report to FDEP every 5 years addressing stabilization of the landfill. The stabilization report will address subsidence and stormwater management. Gas collection, gas management, and leachate management are not required for the Ag Plastic Landfill. Since the Ag Plastic Landfill is not closed, this section is not applicable.

3 PROPERTY ACCESS

The landfill owner or operator shall possess or acquire a sufficient interest in, or a right to use, the property for which a permit is issued, including the access route onto the property to carry out the requirements of this rule. The permittee shall retain the right of entry to the landfill property for the long-term care period, after termination of solid waste operations, for inspection, monitoring, and maintenance of the site.

4 REPLACEMENT OF MONITORING DEVICES

Monitoring is not specifically required for the Ag Plastic Landfill. Monitoring is performed as part of the other permitted landfills at the HCSWMC. If a monitoring well or other device required by the monitoring plan is destroyed or fails to operate for any reason, the landfill owner or operator shall notify FDEP in writing immediately upon discovery. Inoperative monitoring devices shall be replaced with functioning devices within 60 days of the discovery of the malfunctioning unit unless FDEP notifies the landfill owner or operator otherwise in writing.

5 COMPLETION OF LONG-TERM CARE

This section is not applicable to the active Ag Plastic Landfill. After the long-term care period for each solid waste management unit is completed, the owner or operator shall notify FDEP that a certification, signed and sealed by a Professional Engineer, verifying that long-term care has been completed in accordance with the Closure Plan, has been placed in the operating record.

PART R

FINANCIAL ASSURANCE

Information presented in this section will be used to describe the financial mechanism to be used to demonstrate proof of financial assurance to FDEP for the renewal of the Ag Plastic Landfill operations permit.

1 COST ESTIMATES

The closure and long-term care cost estimates prepared on FDEP Form 62-701.900(28) for the Ag Plastic Landfill are included as Attachment R.1-1. These cost estimates were prepared by a Professional Engineer for a third party performing the work on a per unit basis, with the source of the estimates indicated in accordance with Rule 62-701.630(3), FAC. Explanation of costs is included in Attachment R.2-2.


2 PROCEDURES FOR PROVIDING ANNUAL COST ADJUSTMENTS

HCSWMC will provide an annual closure and long-term care cost adjustment for inflation to FDEP in accordance with Rule 62-701.630(4), FAC. The closure and long-term care costs will be listed separately. HCSWMC uses and plans to continue the use of an escrow account to demonstrate financial responsibility.

3 FUNDING MECHANISMS

HCSWMC uses and plans to continue the use of an escrow account to demonstrate financial responsibility.

Attachment R.1-1
Financial Assurance Cost Estimate
Form 62-701.900(28)



Florida Department of Environmental Protection

Bob Martinez Center
2600 Blair Stone Road
Tallahassee, Florida 32399-2400

DEP Form # 62-701.900(28), F.A.C.
Form Title: Closure Cost Estimating Form For Solid Waste Facilities
Effective Date: January 6, 2010
Incorporated in Rule 62-701.630(3), F.A.C.

CLOSURE COST ESTIMATING FORM FOR SOLID WASTE FACILITIES

Date of DEP Approval: _____

I. GENERAL INFORMATION:

Facility Name: HCSWMC - Ag Plastic Landfill WACS ID: 00074956
 Permit Application or Consent Order No.: 0038570-23-SO/08 Expiration Date: 2/17/2015
 Facility Address: 12700 Arbuckle Creek Road, Sebring, Florida 33870
 Permittee or Owner/Operator: Highlands County Board of County Commissioners
 Mailing Address: 12700 Arbuckle Creek Road, Sebring, Florida 33870

Latitude: 27° 30' 14" Longitude: 81° 19' 4"
 Coordinate Method: Google Earth Datum: WGS 84
 Collected by: M. Pollman Company/Affiliation: Jones Edmunds

Solid Waste Disposal Units Included in Estimate:

Phase / Cell	Acres	Date Unit Began Accepting Waste	Active Life of Unit From Date of Initial Receipt of Waste	If active: Remaining life of unit	If closed: Date last waste received	If closed: Official date of closing
Ag Plastic	6	2005	87*	78*		

*Active Life calculated based on estimated closure date of 2092 from Attachment E.4 of the Permit Renewal Application dated December 2014.

Total disposal unit acreage included in this estimate: Closure: 6 Long-Term Care: 6

Facility type: Class I Class III C&D Debris Disposal
 (Check all that apply) Other: Agricultural Plastic Disposal Unit

II. TYPE OF FINANCIAL ASSURANCE DOCUMENT (Check type)

- Letter of Credit* Insurance Certificate Escrow Account
- Performance Bond* Financial Test Form 29 (FA Deferral)
- Guarantee Bond* Trust Fund Agreement

* - Indicates mechanisms that require the use of a Standby Trust Fund Agreement

III. ESTIMATE ADJUSTMENT

40 CFR Part 264 Subpart H as adopted by reference in Rule 62-701.630, Florida Administrative Code, (F.A.C.) sets forth the method of annual cost estimate adjustment. Cost estimates may be adjusted by using an inflation factor or by recalculating the maximum costs of closure in current dollars. Select one of the methods of cost estimate adjustment below.

(a) Inflation Factor Adjustment

(b) Recalculated or New Cost Estimates

Inflation adjustment using an inflation factor may only be made when a Department approved closure cost estimate exists and no changes have occurred in the facility operation which would necessitate modification to the closure plan. The inflation factor is derived from the most recent Implicit Price Deflator for Gross National Product published by the U.S. Department of Commerce in its survey of Current Business. The inflation factor is the result of dividing the latest published annual Deflatory by the Deflator for the previous year. The inflation factor may also be obtained from the Solid Waste website www.dep.state.fl.us/waste/categories/swfr or call the Financial Coordinator at (850) 245-8706.

This adjustment is based on the Department approved closing cost estimate dated: _____

Latest Department Approved Closing Cost Estimate:		Current Year Inflation Factor, <i>e.g. 1.02</i>			Inflation Adjusted Closing Cost Estimate:
_____	x	_____	=		_____

This adjustment is based on the Department approved long-term care cost estimate dated: _____

Latest Department Approved Annual Long-Term Care Cost Estimate:		Current Year Inflation Factor, <i>e.g. 1.02</i>			Inflation Adjusted Annual Long-Term Care Cost Estimate:
_____	x	_____	=		_____

Number of Years of Long Term Care Remaining:			x		_____
--	--	--	---	--	-------

Inflation Adjusted Long-Term Care Cost Estimate:			=		_____
--	--	--	---	--	-------

Signature by: Owner/Operator Engineer

(check what applies)

Harold S. Boudreau III
Signature

730 NE Waldo Road
Address

Harold S. Boudreau, III, PE, Project Engineer
Name & Title

Gainesville, FL 32641
City, State, Zip Code

12/19/2014
Date

hsboudreau@jonesedmunds.com
E-Mail Address

352-377-5821
Telephone Number

IV. ESTIMATED CLOSING COST (check what applies)

Recalculated Cost Estimate **New Facility Cost Estimate**

- Notes: 1. Cost estimates for the time period when the extent and manner of landfill operation makes closing most expensive.
 2. Cost estimate must be certified by a professional engineer.
 3. Cost estimates based on third party suppliers of material, equipment and labor at fair market value.
 4. In some cases, a price quote in support of individual item estimates may be required.

Description	Unit	Number of Units	Cost / Unit	Total Cost
1. Proposed Monitoring Wells (Do not include wells already in existence)				
	EA			
Subtotal Proposed Monitoring Wells:				\$ -
2. Slope and Fill (bedding layer between waste and barrier layer - Existing at time of closure):				
Excavation	CY			-
Placement and Spreading	CY			\$ -
Compaction	CY			\$ -
Off-Site Material	CY			\$ -
Delivery	CY			-
Subtotal Slope and Fill:				\$ -
3. Cover Material (Barrier Layer - Not Required):				
Off-Site Clay (see Item 4)	CY		\$ -	-
Synthetics -Geomembrane	SY			\$ -
Synthetics - GCL	SY			-
Synthetics - Geonet	SY			-
Synthetics - Other (explain)				-
Subtotal Cover Material:				\$ -
4. Top Soil Cover				
Off-Site Material (2 ft)	CY	24,490	\$ 8.51	\$ 208,413
Delivery	CY	Included in Material		-
Spread (includes compaction)	CY	24,490	\$ 2.44	\$ 59,757
Subtotal Top Soil Cover:				\$ 268,170
5. Vegetative Layer				
Sodding	SY	35,138	\$ 1.28	\$ 45,065
Hydroseeding	AC	-	\$ -	-
Fertilizer	AC	-	\$ -	-
Mulch	AC	-	\$ -	-
Other (explain)			\$ -	-
Subtotal Vegetative Layer:				\$ 45,065
6. Stormwater Control System				
Earthwork	CY	56	\$ 4.36	\$ 244
Grading	SY	Included in Earthwork		-
Piping	LF	500	\$ 40.89	\$ 20,445
Ditches	LF	Included in Earthwork		-
Berms	CY	711	\$ 10.95	\$ 7,785
Control Structures	EA	2 , 2	\$2064, \$1500	\$ 7,128
Other (explain)				
Subtotal Stormwater Control System:				\$ 35,602

Description	Unit	Number of Units	Cost / Unit	Total Cost
7. Passive Gas Control:				
Wells	EA	-		-
Pipe and Fittings	LF	-		-
Monitoring Probes	EA	-		-
NSPS/Title V requirements	LS	-		-
Subtotal Passive Gas Control:				\$ -

8. Active Gas Extraction Control:				
Traps	EA	-		-
Sumps	EA	-		-
Flare Assembly	EA	-		-
Flame Arrestor	EA	-		-
Mist Eliminator	EA	-		-
Flow Meter	EA	-		-
Blowers	EA	-		-
Collection System	LF	-		-
Other (explain)	EA	-		-
Subtotal Active Gas Extraction Control:				\$ -

9. Security System				
Fencing	LF	-		-
Gate(s)	EA	-		-
Sign(s)	EA	-		-
Subtotal Security System:				\$ -

10. Engineering				
Closure Plan Report	LS	1	\$ 35,000	\$ 35,000
Certified Engineering Drawings	LS	1	\$ 3,500	\$ 3,500
NSPS/Title V Air Permit	LS			\$ -
Final Survey	LS	1	\$ 1,500	\$ 1,500
Certification of Closure	LS	1	\$ 3,500	\$ 3,500
Other (explain)	LS		-	
Subtotal Engineering:				\$ 43,500

Description	Hours	Cost / Hour	Hours	Cost / Hour	TOTAL
11. Professional Services					
	Contract Management		Quality Assurance		
P.E. Supervisor	20	\$ 165	20	\$ 165	\$ 6,600
On-Site Engineer	0	\$ 100	50	\$ 90	\$ 4,500
Office Engineer	20	\$ 100	0	\$ 100	\$ 2,000
On-Site Technician	0	\$ 85	200	\$ 80	\$ 16,000
Other (explain)	20	\$ 60		\$ 60	\$ 1,200
Contract Administrator					

Description	Unit	Number of Units	Cost / Unit	Total Cost
Quality Assurance Testing	LS	1	\$ 5,000.00	\$ 5,000
Subtotal Professional Services:				\$ 35,300

Subtotal of 1-11 Above: \$ 427,637

12. Contingency 5 % of Subtotal of 1-11 Above \$ 21,382

Subtotal Contingency: \$ 21,382

Estimated Closing Cost Subtotal: \$ 449,019

Description	Total Cost
--------------------	-------------------

13. Site Specific Costs

Mobilization, Bonds, 5% % of Subtotal of Items 1-9 Above \$ 17,441.84
and Insurance

Other (explain) _____

Subtotal Site Specific Costs: \$ 17,442

TOTAL ESTIMATED CLOSING COSTS (\$): \$ 466,461

V. ANNUAL COST FOR LONG-TERM CARE

See 62-701.600(1)a.1., 62-701.620(1), 62-701.630(3)a. and 62-701.730(11)b. F.A.C. for required term length. For landfills certified closed and Department accepted, enter the remaining long-term care length as "Other" and provide years remaining.

(Check Term Length) 5 Years 20 Years 30 Years Other, Years

Notes: 1. Cost estimates must be certified by a professional engineer.

2. Cost estimates based on third party suppliers of material, equipment and labor at fair market value.

3. In some cases, a price quote in support of individual item estimates may be required.

All items must be addressed. Attach a detailed explanation for all items marked not applicable (N/A)

Description	Sampling Frequency (Events / Year)	Number of Wells	(Cost / Well) / Event	Annual Cost
1. Groundwater Monitoring [62-701.510(6), and (8)(a)]				
Monthly	12	_____	_____	_____
Quarterly	4	_____	_____	_____
Semi-Annual	2	_____	_____	_____
Annual	1	_____	_____	_____
Subtotal Groundwater Monitoring:				\$ _____ -
2. Surface Water Monitoring [62-701.510(4), and (8)(b)]				
Monthly	12	_____	_____	-
Quarterly	4	_____	_____	-
Semi-Annual	2	_____	_____	\$ _____ -
Annual	1	_____	_____	-
Subtotal Surface Water Monitoring:				\$ _____ -
3. Gas Monitoring [62-701.400(10)]				
Monthly	12	_____	_____	-
Quarterly	4	_____	_____	-
Semi-Annual	2	_____	_____	-
Annual	1	_____	_____	-
Subtotal Gas Monitoring:				\$ _____ -
4. Leachate Monitoring [62-701.510(5), (6)(b) and 62-701.510(8)c]				
Monthly	12	_____	_____	-
Quarterly	4	_____	_____	-
Semi-Annual	2	_____	_____	-
Annual	1	_____	_____	-
Other (explain) _____	_____	_____	_____	-
Subtotal Leachate Monitoring:				\$ _____ -

Description	Unit	Number of Units / Year	Cost / Unit	Annual Cost
5. Leachate Collection/Treatment Systems Maintenance				
<u>Maintenance</u>				
Collection Pipes	LF	_____	_____	-
Sumps, Traps	EA	_____	_____	-
Lift Stations	DY	_____	_____	\$ _____ -
Cleaning	LF	_____	_____	\$ _____ -
Tanks	EA	_____	_____	-

Description	Unit	Number of Units / Year	Cost / Unit	Annual Cost	
5. (continued)					
<u>Impoundments</u>					
Liner Repair	SY			\$ -	
Sludge Removal	DY			\$ -	
<u>Aeration Systems</u>					
Floating Aerators	EA			-	
Spray Aerators	EA			-	
<u>Disposal</u>					
Off-site (Includes transportation and disposal)	1000 gallon			-	
Subtotal Leachate Collection / Treatment Systems Maintenance:				\$ -	
6. Groundwater Monitoring Wells Maintenance					
Monitoring Wells	LF		\$ -		
Replacement	EA				
Abandonment	EA				
Subtotal Groundwater Monitoring Well Maintenance:				\$ -	
7. Gas System Maintenance					
Piping, Vents	EA			\$ -	
Blowers	EA			\$ -	
Flaring Units	EA			-	
Meters, Valves	EA			-	
Compressors	EA			-	
Flame Arrestors	EA			-	
Operation	LS			-	
Subtotal Gas System Maintenance:				\$ -	
8. Landscape Maintenance					
Mowing	8 /year	AC	6.6	\$ 21.82	\$ 1,152
Fertilizer		AC			
Subtotal Landscape Maintenance:				\$ 1,152	
9. Erosion Control and Cover Maintenance					
Sodding	0.22 AC	SY	1,065	\$ 1.28	\$ 1,366
Regrading		AC	0.2	\$ 3,146.00	\$ 692
Liner Repair		SY		\$ -	
Clay		CY			
Subtotal Erosion Control and Cover Maintenance:				\$ 2,058	
10. Storm Water Management System Maintenance					
Conveyance Maintenance		LS-CY	1,200	\$ 1.68	\$ 2,016
Subtotal Storm Water Management System Maintenance:				\$ 2,016	
11. Security System Maintenance					
Fences		LS			-
Gate(s)		EA			-
Sign(s)		EA			-
Subtotal Security System Maintenance:				\$ -	

Description	Unit	Number of Units / Year	Cost / Unit	Annual Cost
12. Utilities	LS			\$ -
			Subtotal Utilities:	\$ -
13. Leachate Collection/Treatment Systems Operation				
<u>Operation</u>				
P.E. Supervisor	HR			\$ -
On-Site Engineer	HR			\$ -
Office Engineer	HR			\$ -
On-Site Technician	HR			\$ -
Materials	LS			-
			Subtotal Leachate Collection/Treatment System Operation:	\$ -
14. Administrative				
P.E. Supervisor	HR	4	\$ 165.00	\$ 660
On-Site Engineer	HR	8	\$ 90.00	\$ 720
Office Engineer	HR	24	\$ 100.00	\$ 2,400
Onsite Technician	HR	8	\$ 80.00	\$ 640
Other	HR			-
			Subtotal Administrative:	\$ 4,420
Subtotal of 1-14 Above:				\$ 9,646
15. Contingency	5	% of Subtotal of 1-14 Above		\$ 482
			Subtotal Contingency:	\$ 482

Description	Unit	Number of Units / Year	Cost / Unit	Annual Cost
16. Site Specific Costs				
			\$ -	-
			Subtotal Site Specific Costs:	\$ -
ANNUAL LONG-TERM CARE COST (\$ / Year):				\$ 10,128
Number of Years of Long-Term Care:				30
TOTAL LONG-TERM CARE COST (\$):				\$ 303,840

VI. CERTIFICATION BY ENGINEER

This is to certify that the Cost Estimates pertaining to the engineering features of this solid waste management facility have been examined by me and found to conform to engineering principles applicable to such facilities. In my professional judgment, the Cost Estimates are a true, correct and complete representation of the financial liabilities for closing and/or long-term care of the facility and comply with the requirements of Rule 62-701.630 F.A.C. and all other Department of Environmental Protection rules, and statutes of the State of Florida. It is understood that the Cost Estimates shall be submitted to the Department annually, revised or adjusted as required by Rule 62-701.630(4), F.A.C.

Harold S. Boudreau III
Signature

730 NE Waldo Road
Mailing Address

Harold S. Boudreau, III, PE, Project
Name and Title (please type)

Gainesville, FL, 32641
City, State, Zip Code

12/19/2014
Date

hsboudreau@jonesedmunds.com
E-Mail address (if available)

PE No. 77030
Florida Registration Number
(please affix seal) ★

(352) 377-5821
Telephone Number



VII. SIGNATURE BY OWNER/OPERATOR

Ramon Gavarrete
Signature of Applicant

12700 Arbuckle Creek Rd.
Mailing Address

Ramon Gavarrete, PE, County Engineer
Name and Title (please type)

Sebring, FL 33870
City, State, Zip Code

rgavarre@hcbcc.org
E-Mail address (if available)

(863) 402-7786
Telephone Number

Attachment R.1-2

Closure and Long-Term Care Cost Estimating Form for Solid Waste Facilities

Justification and Sources of Estimates

CLOSURE AND LONG-TERM CARE COST ESTIMATING FORM FOR SOLID WASTE FACILITIES

JUSTIFICATION AND SOURCES OF ESTIMATES

HIGHLANDS COUNTY SOLID WASTE MANAGEMENT CENTER FACILITY

AG PLASTIC LANDFILL

INTRODUCTION, GENERAL INFORMATION, AND ASSUMPTIONS

The following information provides justification for quantities and unit prices for the closure and long-term care cost estimates in accordance with Rule 62-701.630(3)(a). This information is provided in support of the cost estimate provided in the *Closure Cost Estimating Form for Solid Waste Facilities*, FDEP Form 62-701.900(28). The cost estimates are based on a third party performing the work on a per-unit basis with the source of the estimates indicated. "Number of Units" (quantities) and "Costs/Unit" (unit costs) are explained for each line item where applicable based on the final cover design presented in the May 28, 2004 Permit Application Document.

The final cover consists of, from top to bottom:

- Vegetative Cover (sod)
- Final Cover Soil: 24 inches (top 6 inches capable of supporting vegetation)
- Barrier Subgrade: 6 inches (existing at time of closure).

Table 1 presents the general information and assumptions used to calculate the closure and long-term care cost estimates:

Table 1 General Information and Assumptions

Facility Name:	Highlands County Solid Waste Management Center Facility
Facility Type:	Ag Plastic Landfill
Landfill Footprint:	6 acres (261,360 SF)
Closure Surface Area (3D):	6.6 acres (287,496 SF)
Soil Loss Factor	15%
Synthetics /Sod Loss Factor	10%
Long-Term Care Period	30 years

Table 2 presents calculations for soil volumes used in the closure cost estimates:

Table 2 Soil Volume Calculations

Thickness (ft)	Surface Area (SF)	Loss Factor (%)	Soil Volume (CF)	Soil Volume (CY)
0.5	287,496	15%	165,310	6,123
1.0	287,496	15%	330,620	12,245
1.5	287,496	15%	495,931	18,368
2.0	287,496	15%	661,241	24,490

Table 3 presents calculations for surface area units such as sodding and maintenance:

Table 3 Geosynthetic and Sod Area Calculations

3D Surface Area	Unit	Loss Factor	Surface Area
287,496	SF	10%	316,246
31,944	SY	10%	35,138
6.6	AC	10%	7.2

Third-party unit costs quotes were obtained where possible. When third-party quotes were not available, unit costs were obtained from the following references:

- RS Means Online (www.rsmeansonline.com)
- FDOT Historical Cost Statewide Averages, Annual Statewide Averages – 2013–2014 (<http://www.dot.state.fl.us/specificationoffice/Estimates/HistoricalCostInformation/HistoricalCost.shtm>)
- Jones Edmunds estimate based on recent, similar projects

Quotes and references for costs are attached. In some cases the Engineer's judgment was used to estimate unit costs based on experience. Table 4 defines the abbreviations used in the cost estimate.

Table 4 List of Abbreviations

AC	Acre	LF	Linear foot
CF	Cubic foot (ft ³)	LS	Lump sum
CY	Cubic yard (yd ³)	MSF	1,000 square feet
DY	Day	SF	Square foot (ft ²)
EA	Each	SY	Square yard (yd ²)
HR	Hour	YR	Year

IV. ESTIMATED CLOSING COST – RECALCULATED COST ESTIMATE

1. PROPOSED MONITORING WELLS (DO NOT INCLUDE WELLS ALREADY IN EXISTENCE.)

No additional monitoring wells will be installed at time of closure.

2. SLOPE AND FILL (BEDDING LAYER BETWEEN WASTE AND BARRIER LAYER)

The final cover will be placed over the existing intermediate cover. A minimum of 6 inches of intermediate bedding layer will remain before the 2-foot-thick final cover soil is placed. This cost is not included because the bedding layer will be placed before the time of closure.

3. COVER MATERIAL (BARRIER LAYER)

The final cover will include a 2-foot-thick soil layer included in Item 4. A barrier layer is not required for the unlined Ag Plastic Landfill.

4. TOP SOIL COVER

The final cover will consist of 2-foot-thick compacted soil layer. The top 6 inches of the 2-foot-thick final cover soil will support vegetation. The cost of delivery of the off-site soil is included in the unit cost.

OFF-SITE MATERIAL

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Off-Site Material	CY	24,490	\$8.51/CY	<i>FDOT: 0120 2 2 Borrow Excavation, truck measure</i>

DELIVERY

Delivery is included in Off-Site Material.

PLACEMENT SPREADING AND COMPACTION

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Placement and Spreading	CY	24,490	\$1.90/CY	<i>RS Means Online</i>
Compaction	CY	24,490	\$0.54/CY	<i>RS Means Online</i>
Total	CY	24,490	\$2.44/CY	

5. VEGETATIVE LAYER

This item includes installing sod on the final cover soil. The quantity is calculated based on the closure area plus Sod loss factor as shown in Table 3.

SODDING

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Sodding	SY	35,138	\$1.28	<i>Bid Average</i>

HYDROSEEDING

Hydroseeding is not proposed at the time of closure.

FERTILIZER

Fertilizer is not proposed at the time of closure.

MULCH

Mulch is not proposed for the vegetative layer.

OTHER (EXPLAIN)

No other materials are proposed for the vegetative layer.

6. STORMWATER CONTROL SYSTEM

This item includes materials and installation costs for the stormwater control downcomer piping as shown on previously submitted drawings.

EARTHWORK

This item is the cost to construct the downcomers, including trenching and filling to lay pipe. The cross-sectional area for pipe trench is assumed to be 3 SF for the downcomers (500 LF) and 24 SF for the terrace berm (800 LF).

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Downcomers	CY	56	\$4.36/CY	<i>FDOT: 0120 1 Regular Excavation</i>

GRADING

Stormwater control system grading is included in Earthwork.

PIPING

This item includes the cost of stormwater control piping that consists of terrace underdrains and let-down piping.

Description	Unit	Number of Units	Cost/Unit	Cost Reference
FDOT Type II	LF	500	\$40.89/LF	<i>FDOT: 0440 1 20 Underdrain, Type II</i>

DITCHES

Perimeter stormwater control system ditches are existing and are not included in the closure costs.

BERMS

This item is the cost to construct the berm on the terrace. The cross-sectional area for the terrace berm is 24 SF (800 LF).

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Berms	CY	711	\$10.95/CY	<i>RS Means Online</i>

CONTROL STRUCTURES

This item includes let-down drop inlets and energy dissipaters. We assumed that drop inlets are similar in cost to FDOT Type C Ditch Bottom Inlets.

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Drop Inlets	EA	2	\$2,064/EA	<i>FDOT: 0425 1521 Inlets, DT BOT, TYPE C, <10'</i>
Energy Dissipaters	EA	2	\$1,500/EA	<i>FDOT: 0430610129 U-Endwall, STD 261, 1:2 SLP, 15"</i>

OTHER (EXPLAIN)

No other stormwater control structures are proposed.

7. PASSIVE GAS CONTROL

Because the Ag Plastic Landfill does not accept putrescible waste, gas controls are not required and this item is not included in the closure design.

8. ACTIVE GAS EXTRACTION CONTROL

Because the Ag Plastic Landfill does not accept putrescible waste, gas controls are not required and this item is not included in the closure design.

9. SECURITY SYSTEM

No additional security system including fencing, gates, and signs are proposed at the time of closure because the security system is existing.

10. ENGINEERING

This item includes costs for engineering associated with the design, permitting, and certification of the final closure including Closure Plan Report, Certified Engineering Drawings, Final Survey, and Certification of Closure. These costs are estimated by Jones Edmunds based on experience with similar projects and are typical for an engineering consultant performing these tasks.

CLOSURE PLAN REPORT

This item is estimated to be a 10% of the closure costs for Items 1 through 9, based on Jones Edmunds' estimate to prepare a closure design and permit application.

CERTIFIED ENGINEERING DRAWINGS

This item is estimated to be a 1% of the closure costs for Items 1 through 9, based on Jones Edmunds' estimate to prepare bid documents for closure construction.

NSPS/TITLE V AIR PERMIT

This item is not required.

FINAL SURVEY

This item is estimate to be cost \$200/AC based on previous experience, plus a ground survey cost of 10%.

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Final Survey	AC	6.6	\$200/AC	<i>Pickett & Associates, Inc. estimate for current topo</i>

CERTIFICATION OF CLOSURE

This item is estimated to be a 1% of the construction costs for Items 1 through 9, based on Jones Edmunds' estimate.

OTHER (EXPLAIN)

No other engineering services are projected at this time.

11. PROFESSIONAL SERVICES

This item includes costs for professional services for closure construction including contract management and quality assurance. These costs are estimated by Jones Edmunds based on experience with similar projects and are typical for a consulting engineer performing these tasks.

CONTRACT MANAGEMENT

Contract management efforts are estimated based on the Jones Edmunds hourly rates and experience with other landfill closures.

QUALITY ASSURANCE

Quality Assurance efforts are estimated based on the Jones Edmunds hourly rates and experience with other landfill closures.

QUALITY ASSURANCE TESTING

Construction quality assurance and quality control (CQA/CQC) responsibilities belong to the general contractor and geomembrane installation subcontractor. Costs shown in Quality Assurance Testing are the third-party CQA activities, which are assumed to be administered by the consulting engineer. These costs were estimated from experience with previous landfill closure projects in Florida.

12. CONTINGENCY

This item includes a 5% contingency of the estimated construction and engineering costs. This percentage is typical based on experience with similar landfill construction projects.

13. SITE-SPECIFIC COSTS

Site-specific costs include cost for mobilization, bonds, and insurance.

MOBILIZATION

This item is 5% of the estimated construction costs (Items 1 through 9). This is a standard percentage in the construction industry.

Description	Unit	Number of Units	Cost/Unit	Cost Reference
Contractor mobilization, bonds, and insurance	LS	1	5%	<i>Jones Edmunds estimate</i>

OTHER ITEMS

No Other Item closure costs are required for Site-Specific Costs.

V. ANNUAL COST FOR LONG-TERM CARE – RECALCULATED COST ESTIMATE

1. GROUNDWATER MONITORING [62-701.510(6), AND (8)(A)]

Groundwater monitoring is not required for the Ag Plastic Landfill.

2. SURFACE WATER MONITORING [62-701.510(4), AND (8)(B)]

Surface water monitoring is not required for the Ag Plastic Landfill.

3. GAS MONITORING [62-701.400(10)]

Gas Monitoring is not required for the Ag Plastic Landfill.

4. LEACHATE MONITORING [62-701.510(5), (6)(B) AND 62-701.510(8)C]

Leachate monitoring is not required by Rule 62-701, FAC, as of the August 12, 2012 rule revision, and is not applicable to the Ag Plastic Landfill.

5. LEACHATE COLLECTION/TREATMENT SYSTEMS MAINTENANCE

Leachate collection and treatment is not required for the Ag Plastic Landfill. The Ag Plastic Landfill does not have a bottom liner and leachate collection system.

6. GROUNDWATER MONITORING WELL MAINTENANCE

Groundwater Monitoring is not required for the Ag Plastic Landfill.

7. GAS SYSTEM MAINTENANCE

Gas collection and control systems are not required for the Ag Plastic Landfill. No putrescible waste is accepted at the Ag Plastic Landfill.

8. LANDSCAPE MAINTENANCE

This item includes cost of mowing the vegetative cover.

MOWING

This item includes the cost of mowing the closed landfill. Mowing is assumed to occur 8 times per year.

Description	Unit	Total Units	Frequency (Events / Year)	Number of Units/ Year	Cost /Unit	Cost Reference
Mowing	AC	6.6	8/YR	52.8	\$21.82	<i>FDOT: 0107 2 Mowing</i>

FERTILIZER

Fertilizing is not proposed.

9. EROSION CONTROL AND COVER MAINTENANCE

This item includes the costs for erosion control and maintenance of the vegetative cover to control erosion by replacing sod as needed and regarding areas of settlement.

SODDING

This item includes the cost of replacing sod over a portion of the final cover area. Sod replacement is assumed to be necessary for 1 acre per year.

Description	Unit	Total Units	Frequency (Events/ Year)	Number of Units/ Year	Cost/Unit	Cost Reference
Sodding	SY	1065	1/YR	1065	\$1.28	<i>Bid Average</i>

REGRADING

This item includes the cost of regrading for erosion control and cover maintenance. This cost assumes a 0.1-acre area.

Description	Unit	Total Units	Frequency (Years/ Event)	Number of Units/ Year	Cost/Unit	Cost Reference
Regrading	AC	0.22	1/YR	0.22	\$0.65/SY (\$3,146/AC)	<i>FDOT - 0162 1 11 Prepared Soil Layer, Finish Soil, 6"</i>

LINER REPAIR

Liner repair is not required.

10. STORMWATER MANAGEMENT SYSTEM MAINTENANCE

This item includes stormwater management system maintenance, specifically cleaning and clearing stormwater ditches.

CONVEYANCE MAINTENANCE

This item includes the cost of maintaining stormwater conveyance. The cost is based on regrading and excavating 500 LF of ditch with a 63 square feet cross-sectional area each year.

Description	Unit	Total Units	Frequency (Years/ Event)	Number of Units/ Year	Cost /Unit	Cost Reference
Stormwater Conveyance Maintenance	CY	1200	1/YR	1200	\$1.68	<i>RS Means</i> 312316420300

11. SECURITY SYSTEM MAINTENANCE

Maintenance of the security system is included in the Class I Landfill long-term care cost estimate and is not included in the Ag Plastic Landfill long-term care cost estimate.

12. UTILITIES

Utility costs are not required for the Ag Plastic Landfill.

13. LEACHATE COLLECTION/TREATMENT SYSTEM OPERATION

This item is not included for the Ag Plastic Landfill because leachate is not collected.

14. ADMINISTRATIVE

This item includes the personnel costs for annual inspections and stabilization reporting, permitting, and financial assurance submittals. The hours are based on Jones Edmunds experience with other landfills and Jones Edmunds hourly rates.

15. CONTINGENCY

A 5% contingency is included.

16. SITE-SPECIFIC COSTS

No site-specific costs are included with this cost estimate for long-term care.

Supporting Information

Closure Item 4- Top Soil Cover - Off-Site Material
Closure Item 6 - Stormwater Control System - Berms

CESPO05 06/25/2013-09.13.01

Page: 2

Florida Department of Transportation
Item Average Unit Cost
From 2012/12/01 to 2013/05/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0104 11	28	\$3.82	\$230,045.61	60,239.000	LF	N	FLOATING TURBIDITY BARRIER
0104 12	13	\$4.89	\$46,980.41	9,604.000	LF	N	STAKED TURBIDITY BARRIER- NYL REINF PVC
0104 15	21	\$1,375.60	\$104,545.34	76.000	EA	N	SOIL TRACKING PREVENTION DEVICE
0104 18	56	\$73.33	\$236,862.48	3,230.000	EA	N	INLET PROTECTION SYSTEM
0104 19	9	\$.34	\$18,762.77	55,215.000	SY	N	CHEMICAL TREATMENT FOR EROSION CONTROL
0107 1	71	\$19.56	\$593,429.35	30,334.830	AC	N	LITTER REMOVAL
0107 2	70	\$31.68	\$906,839.94	28,624.880	AC	N	MOWING
0109 71 2	3	\$63.50	\$37,149.10	585.000	DA	N	FIELD OFFICE, 600 SQ FT
0109 71 3	9	\$65.21	\$189,110.55	2,900.000	DA	N	FIELD OFFICE, 900 SQ FT
0110 1 1	74	\$11,003.78	\$11,957,913.06	1,086.710	AC	N	CLEARING & GRUBBING
0110 3	18	\$31.37	\$3,789,821.03	120,809.000	SF	N	REMOVAL OF EXISTING STRUCTURE
0110 4	42	\$11.34	\$998,336.59	88,005.900	SY	N	REMOVAL OF EXISTING CONCRETE PAVEMENT
0110 6	2	\$2,276.25	\$9,105.00	4.000	EA	N	PLUGGING WATER WELLS, NON-ARTESIAN
0110 7 1	16	\$126.72	\$38,142.02	301.000	EA	N	MAILBOX, F&I SINGLE
0110 8	1	\$12,500.00	\$25,000.00	2.000	DA	N	UNDERWATER DEBRIS REMOVAL
0110 12 1	1	\$200.00	\$1,022,800.00	5,114.000	SY	N	HYDRODEMOLITION, REM OF DECK SURFACE
0110 15 1	2	\$655.37	\$24,904.00	38.000	EA	N	ARBORIST WORK, TREE TRIMMING- LIMBS/ROOT
0110 15 4	3	\$935.63	\$14,970.00	16.000	EA	N	ARBORIST WORK, RELOCATE TREE
0110 20 1	1	\$13.21	\$30,224.48	2,288.000	SF	N	REMOVAL OF EXISTING WALL, MSE WALL
0110 20 3	1	\$49.85	\$43,369.50	870.000	SF	N	REMOVAL OF EXISTING WALL, NOISE WALL
0110 25 1	1	\$118,333.33	\$355,000.00	3.000	LS	N	ASBESTOS ABATEMENT. PROJECT 42919815201
0110 71 1	2	\$252.38	\$419,968.00	1,664.000	LF	N	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL
0110 73	2	\$50.51	\$26,570.00	526.000	LF	N	REMOVE EXISTING BULKHEAD
0110 86	10	\$2,323.51	\$27,882.13	12.000	LS	N	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT
0120 1	53	\$5.55	\$8,527,127.16	1,537,411.360	CY	N	REGULAR EXCAVATION
0120 2 2	19	\$8.51	\$586,821.88	68,954.500	CY	N	BORROW EXCAVATION, TRUCK MEASURE
0120 3	1	\$2.64	\$12,846.24	4,866.000	CY	N	LATERAL DITCH EXCAVATION
0120 4	13	\$6.55	\$301,676.49	46,062.300	CY	N	SUBSOIL EXCAVATION
0120 5	1	\$26.00	\$59,124.00	2,274.000	CY	N	CHANNEL EXCAVATION
0120 6	47	\$7.20	\$8,636,937.54	1,200,175.700	CY	N	EMBANKMENT
0120 71	13	\$15,402.04	\$231,030.64	15.000	LS	N	REGULAR EXCAVATION (3-R PROJECTS ONLY)
0120 72	1	\$64.65	\$31,419.90	486.000	CY	N	GRAVEL FILL
0120 74	1	\$10.00	\$3,000.00	300.000	CY	N	SURCHARGE EMBANKMENT
0121 70	14	\$148.31	\$711,160.44	4,795.020	CY	N	FLOWABLE FILL
0125 1	4	\$46.06	\$726,024.44	15,763.000	CY	N	EXCAVATION FOR STRUCTURES
0125 3	1	\$24.00	\$12,192.00	508.000	CY	N	SELECT BEDDING MATERIAL
0145 2	2	\$2.22	\$199,414.82	89,883.000	SY	N	GEOSYNTHETIC REINF FND OVER SOFT SOIL
0145 71	4	\$4.51	\$114,157.00	25,289.000	SY	N	REINFORCEMENT GRID FOR SOIL STABILIZAT
0145 72	1	\$36.00	\$68,256.00	1,896.000	SY	N	CELLULAR CONFINEMENT FOR SOIL STABILIZAT
0160 4	48	\$2.76	\$4,454,075.98	1,614,041.800	SY	N	TYPE B STABILIZATION


Closure Item 4

Material and Delivery

Closure Item 4 - Top Soil Cover - Placement and Spreading
Closure Item 6 - Stormwater Control System - Berms

Marion County Baseline Landfill
Year 2013 Quarter 2
Unit Detail Report





Prepared By:
Hal Boudreau
Jones Edmunds & Associates, Inc.

LineNumber		Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 31 Earthwork						
312323170020		Fill, dumped material, spread, by dozer, excludes compaction	1.00	L.C.Y.	\$1.90	\$1.90
Division 31 Earthwork Subtotal						\$1.90

Closure Item 4 - Top Soil Cover - Compaction
Closure Item 6 - Stormwater Control System - Berms

Marion County Baseline Landfill
Year 2013 Quarter 2
Unit Detail Report

Prepared By:
Hal Boudreau
Jones Edmunds & Associates, Inc.

LineNumber				Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 31 Earthwork								
312323235040				Compaction, riding, vibrating roller, 4 passes, 6" lifts	1.00	E.C.Y.	\$0.54	\$0.54
Division 31 Earthwork Subtotal								\$0.54

Closure Costs - Item 5 - Vegetative Layer - Sodding
 LTC - Item 9 - Erosion Control and Cover Maintenance - Sodding

HIGHLANDS COUNTY BOARD OF COUNTY COMMISSIONERS

"AWARD TABULATION OF SEALED BIDS"

ITB 13-010 - SOD

BID OPENING 8-2-2012

VENDOR	DESCRIPTION OF SOD FIELD	BAHIA GRASS			FLORATAM GRASS		
		SOD	SOD HAULED & LAID	SOD HAULED LAID & ROLLED	SOD	SOD HAULED & LAID	SOD HAULED LAID & ROLLED
BEAR HOLLOW SOD (LV) P.O. Box 954 Lake Placid, FL 33862 PH: 863-699-5300 E-Verify ID#442886	5000 W. Josephine Rd., Lake Placid, FL 33852	0.0450	0.1330	0.1350	0.2100	0.2800	0.2800
HOWERTON FARMS (LV) P.O. Box 642 Sebring, FL 33871 PH: 863-655-1593 E-Verify ID#592044144	Section 3 TWP 355 RGE 31 E 2100 Bluff Hammock Rd., Lorida, FL 33871	0.0600	0.1470	0.1500	0.2000	0.2500	0.2500

NOTE: LOCAL VENDORS ARE INDICATED BY A DESIGNATION OF (LV).

Average = \$0.1425/sf = \$1.28/cy

RECOMMEND ACCEPTING ALL BIDS PER ADDITIONAL TERMS & CONDITIONS OF THE SPECIFICATIONS. THE LOWEST BIDDER WILL BE CONTACTED FIRST AT ALL TIMES. SHOULD THE LOW BIDDER BE INCAPABLE OF SUPPLYING THE SOD SERVICES REQUIRED, THE NEXT LOWEST BIDDER, AND SO ON, WILL BE CONTACTED UNTIL SOD REQUIREMENTS ARE MET. THE BID WILL BE FOR THE 12 MONTH PERIOD 10/01/2012 THRU 09/30/2013.

BID AWARD RECOMMENDATION APPROVED BY:

Quinn Kisher 8/29/12
 INTERIM COUNTY ADMINISTRATOR DATE

Paul Swartz 8/20/2012
 ADMINISTRATIVE SERVICES DIRECTOR DATE

W. Kyle Green 8/15/2012
 ROAD & BRIDGE SUPERINTENDENT DATE

Closure Cost - Item 6 - Stormwater Control System - Earthwork

CESPO05 04/28/2014-07.00.02

Page: 2

Florida Department of Transportation
Item Average Unit Cost
From 2013/04/01 to 2014/03/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0104 6	1	\$50.00	\$6,600.00	132.000	LF	N	TEMPORARY SLOPE DRAIN / RUNOFF CONT STR
0104 7	2	\$1,550.00	\$9,300.00	6.000	EA	N	SEDIMENT BASIN / CONTAINMENT SYSTEM
0104 9	2	\$1,125.78	\$6,754.68	6.000	EA	N	SEDIMENT BASIN / CONTAINMENT SY CLEANOUT
0104 10 3	92	\$1.13	\$1,533,082.04	1,361,430.800	LF	N	SEDIMENT BARRIER
0104 11	44	\$9.95	\$496,561.85	49,908.000	LF	N	FLOATING TURBIDITY BARRIER
0104 12	25	\$4.58	\$91,534.66	19,968.800	LF	N	STAKED TURBIDITY BARRIER- NYL REINF PVC
0104 15	23	\$1,503.50	\$126,294.11	84.000	EA	N	SOIL TRACKING PREVENTION DEVICE
0104 18	91	\$78.51	\$414,858.06	5,284.000	EA	N	INLET PROTECTION SYSTEM
0104 19	7	\$.52	\$8,961.63	17,095.000	SY	N	CHEMICAL TREATMENT FOR EROSION CONTROL
0107 1	105	\$19.72	\$954,440.67	48,396.207	AC	N	LITTER REMOVAL
0107 2	105	\$35.80	\$1,597,689.37	44,627.611	AC	N	MOWING
0109 71 1	1	\$23.00	\$8,280.00	360.000	DA	N	FIELD OFFICE, 300 SQ FT
0109 71 2	3	\$86.79	\$70,732.00	815.000	DA	N	FIELD OFFICE, 600 SQ FT
0109 71 3	15	\$75.28	\$372,631.40	4,950.000	DA	N	FIELD OFFICE, 900 SQ FT
0109 71 4	3	\$62.91	\$101,600.00	1,615.000	DA	N	FIELD OFFICE,1200 SQ FT
0109 71 5	2	\$94.36	\$143,420.00	1,520.000	DA	N	FIELD OFFICE,1500 SQ FT
0110 1 1	108	\$13,103.13	\$21,021,082.83	1,604.280	AC	N	CLEARING & GRUBBING
0110 3	30	\$32.18	\$6,327,431.35	196,622.100	SF	N	REMOVAL OF EXISTING STRUCTURE
0110 4	60	\$21.31	\$4,732,655.86	222,048.100	SY	N	REMOVAL OF EXISTING CONCRETE PAVEMENT
0110 6	2	\$1,601.25	\$6,405.00	4.000	EA	N	PLUGGING WATER WELLS, NON-ARTESIAN
0110 7 1	32	\$110.67	\$81,783.24	739.000	EA	N	MAILBOX, F&I SINGLE
0110 12 1	1	\$354.63	\$231,573.39	653.000	SY	N	HYDRODEMOLITION, REM OF DECK SURFACE
0110 15	4	\$28,336.18	\$113,344.70	4.000	LS	N	ARBORIST WORK, COMPLETE
0110 15 1	3	\$612.24	\$64,285.00	105.000	EA	N	ARBORIST WORK, TREE TRIMMING- LIMBS/ROOT
0110 15 2	2	\$1,947.18	\$5,841.54	3.000	EA	N	ARBORIST WORK, TREE PRESERV RELOCATION
0110 20 1	1	\$13.21	\$30,224.48	2,288.000	SF	N	REMOVAL OF EXISTING WALL, MSE WALL
0110 20 3	1	\$49.85	\$43,369.50	870.000	SF	N	REMOVAL OF EXISTING WALL, NOISE WALL
0110 71 1	1	\$307.00	\$314,368.00	1,024.000	LF	N	BRIDGE FENDER SYSTEM, REMOVAL & DISPOSAL
0110 73	2	\$18.75	\$86,983.40	4,638.000	LF	N	REMOVE EXISTING BULKHEAD
0110 86	21	\$2,431.95	\$58,366.73	24.000	LS	N	DELIVERY OF SALVAGEABLE MATERIAL TO FDOT
0120 1	71	\$4.36	\$10,909,364.52	2,504,217.800	CY	N	REGULAR EXCAVATION
0120 2 2	30	\$12.00	\$1,193,977.21	99,492.000	CY	N	BORROW EXCAVATION, TRUCK MEASURE
0120 3	1	\$2.64	\$12,846.24	4,866.000	CY	N	LATERAL DITCH EXCAVATION
0120 4	15	\$9.09	\$1,125,618.31	123,846.000	CY	N	SUBSOIL EXCAVATION
0120 5	2	\$30.51	\$121,259.00	3,974.000	CY	N	CHANNEL EXCAVATION
0120 6	64	\$5.76	\$9,070,543.83	1,575,545.400	CY	N	EMBANKMENT
0120 71	22	\$22,462.63	\$606,491.10	27.000	LS	N	REGULAR EXCAVATION (3-R PROJECTS ONLY)
0120 72	4	\$52.41	\$138,303.80	2,639.000	CY	N	GRAVEL FILL
0120 74	1	\$35.00	\$1,295.00	37.000	CY	N	SURCHARGE EMBANKMENT
0121 70	16	\$88.94	\$432,612.66	4,863.920	CY	N	FLOWABLE FILL

**Closure Cost Item 6 -
Earthwork**

Closure Costs - Item 6 - Stormwater Control System - Piping

Florida Department of Transportation
Item Average Unit Cost
From 2013/04/01 to 2014/03/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0430982141	7	\$2,249.52	\$29,243.71	13.000	EA	N	MITERED END SECT, OPTIONAL RD, 48" CD
0430982142	3	\$4,390.25	\$17,561.01	4.000	EA	N	MITERED END SECT, OPTIONAL RD, 54" CD
0430982143	1	\$4,930.00	\$4,930.00	1.000	EA	N	MITERED END SECT, OPTIONAL RD, 60" CD
0430982625	6	\$986.20	\$21,696.40	22.000	EA	N	MITERED END SECT, OPT - OTHER, 18" CD
0430982629	6	\$1,356.81	\$23,065.84	17.000	EA	N	MITERED END SECT, OPT - OTHER, 24" CD
0430982633	1	\$1,454.00	\$1,454.00	1.000	EA	N	MITERED END SECT, OPT - OTHER, 30" CD
0430982638	3	\$2,519.78	\$10,079.12	4.000	EA	N	MITERED END SECT, OPT - OTHER, 36" CD
0430982640	1	\$3,368.26	\$6,736.52	2.000	EA	N	MITERED END SECT, OPT - OTHER, 42" CD
0430984120	1	\$765.00	\$8,415.00	11.000	EA	N	MITERED END SECT, OPTIONAL RD, 8" SD
0430984121	1	\$518.43	\$2,073.72	4.000	EA	N	MITERED END SECT, OPTIONAL RD, 12" SD
0430984123	7	\$526.44	\$18,425.30	35.000	EA	N	MITERED END SECT, OPTIONAL RD, 15" SD
0430984125	29	\$727.07	\$353,357.10	486.000	EA	N	MITERED END SECT, OPTIONAL RD, 18" SD
0430984129	23	\$892.94	\$178,587.23	200.000	EA	N	MITERED END SECT, OPTIONAL RD, 24" SD
0430984133	10	\$2,148.18	\$40,815.51	19.000	EA	N	MITERED END SECT, OPTIONAL RD, 30" SD
0430984138	6	\$3,316.88	\$69,654.56	21.000	EA	N	MITERED END SECT, OPTIONAL RD, 36" SD
0430984140	2	\$4,608.01	\$59,904.08	13.000	EA	N	MITERED END SECT, OPTIONAL RD, 42" SD
0430984141	2	\$5,098.66	\$25,493.28	5.000	EA	N	MITERED END SECT, OPTIONAL RD, 48" SD
0430984623	2	\$596.75	\$4,774.00	8.000	EA	N	MITERED END SECT, OPTIONAL, OTHER, 15" SD
0430984625	16	\$881.79	\$258,364.83	293.000	EA	N	MITERED END SECT, OPT / OTHER, 18" SD
0430984629	10	\$1,503.20	\$163,848.29	109.000	EA	N	MITERED END SECT, OPT / OTHER, 24" SD
0430984633	5	\$2,134.11	\$49,084.51	23.000	EA	N	MITER END SECT, OPT/ELLIP/ARCH, 30" SD
0430984638	3	\$3,722.61	\$81,897.40	22.000	EA	N	MITER END SECT, OPT/ELLIP/ARCH, 36" SD
0430990	1	\$2,747.01	\$8,241.03	3.000	EA	N	MITERED END SECT, REPLACE GRATE
0431 1 1	3	\$139.06	\$169,649.35	1,220.000	LF	N	PIPE LINER, OPTIONAL MATERIAL, 0-24"
0431 1 2	1	\$215.03	\$18,492.58	86.000	LF	N	PIPE LINER, OPTIONAL MATERIAL, 25-36"
0431 1 5	1	\$996.49	\$131,536.68	132.000	LF	N	PIPE LINER, OPTIONAL MATERIAL, 61" AND >
0432 3 7	1	\$3,000.00	\$3,000.00	1.000	EA	N	CHEM GROUT REPAIR, PIPE, NON-TEST, 42"
0436 1 1	7	\$137.26	\$195,874.40	1,427.000	LF	N	TRENCH DRAIN, STANDARD
0440 1 10	3	\$29.64	\$96,197.72	3,246.000	LF	N	UNDERDRAIN, TYPE I
0440 1 20	3	\$23.75	\$220,898.23	9,302.000	LF	N	UNDERDRAIN, TYPE II
0440 1 50	1	\$40.00	\$10,400.00	260.000	LF	N	UNDERDRAIN, TYPE V
0440 70	2	\$1,126.14	\$27,027.36	24.000	EA	N	UNDERDRAIN INSPECTION BOX
0440 73 1	1	\$100.00	\$1,500.00	15.000	LF	N	UNDERDRAIN OUTLET PIPE, 4"
0440 73 2	2	\$18.36	\$15,296.61	833.000	LF	N	UNDERDRAIN OUTLET PIPE, 6"
0440 73 3	2	\$28.30	\$8,065.33	285.000	LF	N	UNDERDRAIN OUTLET PIPE, 8"
0443 70 3	2	\$120.24	\$29,939.50	249.000	LF	N	FRENCH DRAIN, 18"
0443 70 4	4	\$124.64	\$1,142,928.00	9,170.000	LF	N	FRENCH DRAIN, 24"
0443 70 6	1	\$287.00	\$16,072.00	56.000	LF	N	FRENCH DRAIN, 36"
0444 70 11	1	\$151.17	\$3,023.40	20.000	LF	N	DEEP WELL- OPEN HOLE, 24"
0444 71 11	1	\$251.95	\$22,675.50	90.000	LF	N	DEEP WELL CASING, 24"

Closure Costs - Item 6 - Piping

Closure Cost - Item 6 - Stormwater Control System - Inlet structure

CESPO05 06/25/2013-09.13.01

Page: 6

Florida Department of Transportation
Item Average Unit Cost
From 2012/12/01 to 2013/05/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0425 1352	4	\$4,226.94	\$105,673.46	25.000	EA	N	INLETS, CURB, TYPE P-5, >10'
0425 1355	4	\$3,051.79	\$39,673.28	13.000	EA	N	INLETS, CURB, TYPE P-5, PARTIAL
0425 1361	17	\$3,881.78	\$520,157.92	134.000	EA	N	INLETS, CURB, TYPE P-6, <10'
0425 1362	2	\$3,622.28	\$54,334.14	15.000	EA	N	INLETS, CURB, TYPE P-6, >10'
0425 1365	4	\$3,307.02	\$62,833.33	19.000	EA	N	INLETS, CURB, TYPE P-6, PARTIAL
0425 1451	11	\$6,187.31	\$340,301.99	55.000	EA	N	INLETS, CURB, TYPE J-5, <10'
0425 1452	2	\$7,996.31	\$63,970.45	8.000	EA	N	INLETS, CURB, TYPE J-5, >10'
0425 1455	2	\$3,985.00	\$7,970.00	2.000	EA	N	INLETS, CURB, TYPE J-5, PARTIAL
0425 1461	8	\$6,826.84	\$177,497.82	26.000	EA	N	INLETS, CURB, TYPE J-6, <10'
0425 1462	2	\$5,076.48	\$25,382.40	5.000	EA	N	INLETS, CURB, TYPE J-6, >10'
0425 1471	2	\$4,325.17	\$47,576.87	11.000	EA	N	INLETS, CURB, TYPE 7, <10'
0425 1473	2	\$6,184.45	\$68,028.90	11.000	EA	N	INLETS, CURB, TYPE 7, J BOT, <10'
0425 1474	1	\$10,124.57	\$10,124.57	1.000	EA	N	INLETS, CURB, TYPE 7, J BOT, >10'
0425 1501	4	\$2,851.40	\$48,473.81	17.000	EA	N	INLETS, DT BOT, TYPE A, <10'
0425 1503	3	\$4,320.22	\$34,561.76	8.000	EA	N	INLETS, DT BOT, TYPE A, J BOT, <10'
0425 1505	1	\$2,100.00	\$2,100.00	1.000	EA	N	INLETS, DT BOT, TYPE A, PARTIAL
0425 1511	6	\$3,775.24	\$71,729.55	19.000	EA	N	INLETS, DT BOT, TYPE B, <10'
0425 1513	2	\$3,993.00	\$19,965.00	5.000	EA	N	INLETS, DT BOT, TYPE B, J BOT, <10'
0425 1519	1	\$4,500.00	\$4,500.00	1.000	EA	N	INLETS, DT BOT, TYPE B, MODIFY
0425 1521	11	\$2,064.70	\$119,752.76	58.000	EA	N	INLETS, DT BOT, TYPE C, <10'
0425 1523	4	\$2,968.05	\$17,808.32	6.000	EA	N	INLETS, DT BOT, TYPE C, J BOT, <10'
0425 1525	4	\$1,252.77	\$10,022.12	8.000	EA	N	INLETS, DT BOT, TYPE C, PARTIAL
0425 1529	2	\$1,690.64	\$3,381.27	2.000	EA	N	INLETS, DT BOT, TYPE C, MODIFY
0425 1531	4	\$2,771.30	\$116,394.55	42.000	EA	N	INLETS, DT BOT, TYPE C MOD- BACK, <10'
0425 1532	1	\$2,550.00	\$2,550.00	1.000	EA	N	INLETS, DT BOT, TYPE C, MOD, >10'
0425 1533	1	\$6,394.47	\$31,972.35	5.000	EA	N	INLETS, DT BOT, TYPE C, MOD, J BOT, <10'
0425 1541	14	\$2,468.72	\$187,622.99	76.000	EA	N	INLETS, DT BOT, TYPE D, <10'
0425 1543	4	\$5,712.62	\$57,126.20	10.000	EA	N	INLETS, DT BOT, TYPE D, J BOT, <10'
0425 1545	2	\$2,654.42	\$7,963.27	3.000	EA	N	INLETS, DT BOT, TYPE D, PARTIAL
0425 1549	4	\$4,213.80	\$46,351.76	11.000	EA	N	INLETS, DT BOT, TYPE D, MODIFY
0425 1551	10	\$3,193.66	\$293,816.44	92.000	EA	N	INLETS, DT BOT, TYPE E, <10'
0425 1553	2	\$2,400.72	\$9,602.88	4.000	EA	N	INLETS, DT BOT, TYPE E, J BOT, <10'
0425 1555	1	\$2,000.00	\$2,000.00	1.000	EA	N	INLETS, DT BOT, TYPE E, PARTIAL
0425 1559	3	\$5,960.49	\$23,841.96	4.000	EA	N	INLETS, DT BOT, TYPE E, MODIFY
0425 1561	5	\$3,137.43	\$50,198.82	16.000	EA	N	INLETS, DT BOT, TYPE F, <10'
0425 1563	1	\$7,240.00	\$7,240.00	1.000	EA	N	INLETS, DT BOT, TYPE F, J BOT, <10'
0425 1571	3	\$4,108.81	\$86,285.00	21.000	EA	N	INLETS, DT BOT, TYPE G, <10'
0425 1581	4	\$6,702.31	\$80,427.73	12.000	EA	N	INLETS, DT BOT, TYPE H, <10'
0425 1589	2	\$5,512.63	\$16,537.88	3.000	EA	N	INLETS, DT BOT, TYPE H, MODIFY
0425 1601	2	\$4,228.04	\$12,684.13	3.000	EA	N	INLETS, DT BOT, TYPE J, <10'

Closure Cost - Item 6 -
Stormwater Control
System - Inlet structure

Closure Costs - Item 6 - Stormwater Control System - Outlet Energy Dissipator

CESPO05 06/25/2013-09.13.01

Page: 9

Florida Department of Transportation
Item Average Unit Cost
From 2012/12/01 to 2013/05/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0430175154	3	\$164.18	\$203,753.28	1,241.000	LF	N	PIPE CULV, OPT MATL, ROUND, 54"S/CD
0430175215	2	\$52.25	\$9,300.00	178.000	LF	N	PIPE CULV, OPT MATL, OTHER, 15"S/CD
0430175218	11	\$57.59	\$114,148.28	1,982.000	LF	N	PIPE CULV, OPT MATL, OTHER, 18"S/CD
0430175224	8	\$57.40	\$182,011.60	3,171.000	LF	N	PIPE CULV, OPT MATL, OTHER, 24"S/CD
0430175230	5	\$73.74	\$97,489.16	1,322.000	LF	N	PIPE CULV, OPT MATL, OTHER, 30"S/CD
0430175236	5	\$78.94	\$59,128.44	749.000	LF	N	PIPE CULV, OPT MATL, OTHER, 36"S/CD
0430175242	1	\$101.41	\$168,036.37	1,657.000	LF	N	PIPE CULV, OPT MATL, OTHER, 42"S/CD
0430175248	1	\$136.82	\$61,295.36	448.000	LF	N	PIPE CULV, OPT MATL, OTHER, 48"S/CD
0430200 25	1	\$1,553.83	\$3,107.66	2.000	EA	N	FLARED END SECTION, CONCRETE, 18"
0430602125	1	\$1,428.90	\$1,428.90	1.000	EA	N	U-ENDWALL,W \GRATE,STD 260,1:4 SLP,18"
0430602129	1	\$2,180.00	\$4,360.00	2.000	EA	N	U-ENDWALL,W \GRATE,STD 260,1:4 SLP,24"
0430610025	1	\$2,500.00	\$15,000.00	6.000	EA	N	U-ENDWALL,STD 261,1:6 SLP, 18"
0430610029	1	\$2,800.00	\$2,800.00	1.000	EA	N	U-ENDWALL,STD 261,1:6 SLP, 24"
0430610123	1	\$1,516.49	\$3,032.98	2.000	EA	N	U-ENDWALL,STD 261,1:4 SLP, 15"
0430610125	1	\$2,000.00	\$6,000.00	3.000	EA	N	U-ENDWALL,STD 261,1:4 SLP, 18"
0430610323	1	\$1,516.50	\$1,516.50	1.000	EA	N	U-ENDWALL,STD 261,1:2 SLP, 15"
0430610325	1	\$1,551.23	\$3,102.46	2.000	EA	N	U-ENDWALL,STD 261,1:2 SLP, 18"
0430610329	1	\$1,700.00	\$1,700.00	1.000	EA	N	U-ENDWALL,STD 261,1:2 SLP, 24"
0430611025	1	\$1,800.00	\$1,800.00	1.000	EA	N	U-ENDWALL,STD 261,BAFFLES,1:6 SLP,18"
0430611029	1	\$2,100.00	\$2,100.00	1.000	EA	N	U-ENDWALL,STD 261,BAFFLES,1:6 SLP, 24"
0430611123	1	\$1,400.00	\$5,600.00	4.000	EA	N	U-ENDWALL, BAFFLES,STD 261,1:4 SLP, 15"
0430611125	5	\$1,666.29	\$109,975.37	66.000	EA	N	U-ENDWALL, BAFFLES,STD 261,1:4 SLP, 18"
0430611129	3	\$2,445.75	\$46,469.30	19.000	EA	N	U-ENDWALL, BAFFLES,STD 261,1:4 SLP, 24"
0430611225	3	\$1,775.47	\$5,326.40	3.000	EA	N	U-ENDWALL, BAFFLES, STD 261,1:3 SLP,18"
0430611325	1	\$1,800.00	\$19,800.00	11.000	EA	N	U-ENDWALL, BAFFLES, STD 261,1:2 SLP,18"
0430611329	1	\$2,200.00	\$2,200.00	1.000	EA	N	U-ENDWALL, BAFFLES,STD 261,1:2 SLP,24"
0430612029	1	\$1,999.62	\$3,999.24	2.000	EA	N	U-ENDWALL, GRATE, STD 261,1:6 SLP,24"
0430830	7	\$453.77	\$52,110.76	114.840	CY	N	PIPE FILLING AND PLUGGING
0430950	5	\$65.68	\$48,212.12	734.000	CY	N	DESILTING CONCRETE BOX CULVERT,
0430963 1	2	\$12.07	\$1,954.82	162.000	LF	N	PVC PIPE FOR BACK OF SIDEWALK, 4"
0430963 2	4	\$27.44	\$4,636.58	169.000	LF	N	PVC PIPE FOR BACK OF SIDEWALK, NON STAND
0430982123	1	\$1,575.01	\$4,725.03	3.000	EA	N	MITERED END SECT, OPTIONAL RD, 15" CD
0430982125	14	\$1,090.19	\$52,329.10	48.000	EA	N	MITERED END SECT, OPTIONAL RD, 18" CD
0430982129	7	\$1,006.37	\$35,222.91	35.000	EA	N	MITERED END SECT, OPTIONAL RD, 24" CD
0430982133	6	\$1,303.26	\$15,639.12	12.000	EA	N	MITERED END SECT, OPTIONAL RD, 30" CD
0430982138	6	\$1,719.62	\$20,635.38	12.000	EA	N	MITERED END SECT, OPTIONAL RD, 36" CD
0430982140	2	\$2,879.45	\$14,397.24	5.000	EA	N	MITERED END SECT, OPTIONAL RD, 42" CD
0430982141	3	\$2,150.76	\$19,356.83	9.000	EA	N	MITERED END SECT, OPTIONAL RD, 48" CD
0430982625	1	\$563.39	\$2,816.95	5.000	EA	N	MITERED END SECT, OPT - OTHER, 18" CD
0430982629	4	\$1,491.09	\$17,893.08	12.000	EA	N	MITERED END SECT, OPT - OTHER, 24" CD

Closure Costs - Item 6 -
Stormwater Control System -
Outlet Energy Dissipator

LTC - Item 8 - Landscape Maintenance - Mowing

CEAPO05 05/27/2013-07.13.01

Page: 1

Florida Department of Transportation
Item Average Unit Cost
From 2012/05/01 to 2013/04/30

Contract Type: CC AREAS: 09
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0102 1	3	\$225.66	\$383,615.00	1,700.000	DA	N	MAINTENANCE OF TRAFFIC
0102 3	3	\$14.42	\$42,040.80	2,916.000	CY	N	COMMERCIAL MATL FOR DRIVEWAY MAINT
0102 60	3	\$.24	\$21,584.90	90,171.000	ED	N	WORK ZONE SIGN
0102 71 11	1	\$18.50	\$154,086.50	8,329.000	LF	N	BARRIER WALL, TEMP, F&I, CONCRETE
0102 71 14	2	\$25.28	\$71,305.00	2,821.000	LF	N	BARRIER WALL, TEMP, F&I, TYPE K
0102 71 21	1	\$4.00	\$5,356.00	1,339.000	LF	N	BARRIER WALL, TEMP, REL, CONCRETE
0102 71 24	1	\$5.00	\$9,630.00	1,926.000	LF	N	BARRIER WALL, TEMP, REL, TYPE K
0102 74 1	3	\$.14	\$89,984.27	644,900.000	ED	N	TEMP BARR-TYPS I, II, DI, VP, DRUM, LC
0102 74 2	3	\$.21	\$6,942.20	32,639.000	ED	N	BARRICADE, TEMP, TYPE III, 6'
0102 76	3	\$4.20	\$7,217.60	1,720.000	ED	N	ARROW BOARD /ADVANCE WARNING ARROW PANEL
0102 77	3	\$.21	\$4,052.18	19,658.000	ED	N	HIGH INTENSITY FLASH LI, TEMP, TYP B
0102 78	3	\$2.33	\$32,667.60	14,038.000	EA	N	TEMPORARY RETROREFLECTIVE PAVT MARKER
0102 79	2	\$.12	\$3,092.16	25,768.000	ED	N	LIGHTS, BARR WALL MNT, TEMP, TYP C, STDY BRN
0102 89 7	2	\$900.00	\$68,400.00	76.000	LO	N	TEMPORARY CRASH CUSHION, REDIR OPT, NO C
0102 99	1	\$12.00	\$16,704.00	1,392.000	ED	N	PORTABLE CHANGEABLE MESSAGE SIGN, TEMP
0104 10 3	3	\$.75	\$135,723.80	181,695.000	LF	N	SEDIMENT BARRIER
0104 11	2	\$8.00	\$14,656.00	1,832.000	LF	N	FLOATING TURBIDITY BARRIER
0104 12	2	\$5.25	\$3,881.80	740.000	LF	N	STAKED TURBIDITY BARRIER- NYL REINF PVC
0104 15	3	\$1,084.07	\$20,597.36	19.000	EA	N	SOIL TRACKING PREVENTION DEVICE
0104 18	2	\$113.64	\$1,250.00	11.000	EA	N	INLET PROTECTION SYSTEM
0107 1	3	\$18.43	\$178,365.91	9,676.400	AC	N	LITTER REMOVAL
0107 2	3	\$21.82	\$211,092.91	9,676.400	AC	N	MOWING
0110 1 1	3	\$888.15	\$336,322.46	378.679	AC	N	CLEARING & GRUBBING
0110 3	2	\$13.66	\$150,950.75	11,053.000	SF	N	REMOVAL OF EXISTING STRUCTURE
0110 7 1	2	\$167.07	\$501.22	3.000	EA	N	MAILBOX, F&I SINGLE
0120 1	3	\$3.73	\$1,595,033.05	427,629.000	CY	N	REGULAR EXCAVATION
0120 4	1	\$7.50	\$59,302.50	7,907.000	CY	N	SUBSOIL EXCAVATION
0120 5	1	\$8.40	\$24,561.60	2,924.000	CY	N	CHANNEL EXCAVATION
0120 6	3	\$5.54	\$4,433,636.65	800,376.000	CY	N	EMBANKMENT
0160 4	3	\$2.84	\$1,395,602.20	491,124.000	SY	N	TYPE B STABILIZATION
0285701	1	\$5.45	\$202,690.95	37,191.000	SY	N	OPTIONAL BASE, BASE GROUP 01
0285702	1	\$6.45	\$108,147.15	16,767.000	SY	N	OPTIONAL BASE, BASE GROUP 02
0285705	1	\$8.00	\$129,664.00	16,208.000	SY	N	OPTIONAL BASE, BASE GROUP 05
0285709	1	\$10.15	\$1,058,939.35	104,329.000	SY	N	OPTIONAL BASE, BASE GROUP 09
0285711	1	\$11.42	\$1,251,357.92	109,576.000	SY	N	OPTIONAL BASE, BASE GROUP 11
0285712	1	\$12.50	\$584,462.50	46,757.000	SY	N	OPTIONAL BASE, BASE GROUP 12
0286 1	3	\$13.65	\$78,609.47	5,761.000	SY	N	TURNOUT CONSTRUCTION
0327 70 1	1	\$1.00	\$1,689.00	1,689.000	SY	N	MILLING EXIST ASPH PAVT, 1" AVG DEPTH
0327 70 6	1	\$.70	\$68,156.20	97,366.000	SY	N	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH
0327 70 11	2	\$1.13	\$120,296.00	106,904.000	SY	N	MILLING EXIST ASPH PAVT, 2 1/4" AVG DEPTH

Long Term Costs - Item 8 - Landscape Maintenance - Mowing

LT C - Item 9 - Erosion Control and Cover Maintenance - Regrading

CESP005 06/25/2013-09.13.01

Page: 3

Florida Department of Transportation
Item Average Unit Cost
From 2012/12/01 to 2013/05/31

Contract Type: CC STATEWIDE
Displaying: VALID ITEMS WITH HITS
From: 0102 1 To: 9999999

Item	No. of Conts	Weighted Average	Total Amount	Total Quantity	Unit Meas	Obs?	Description
0162 1 11	29	\$.65	\$641,807.35	992,402.000	SY	N	PREPARED SOIL LAYER, FINISH SOIL, 6"
0162 1 12	2	\$12.48	\$40,179.16	3,219.000	SY	N	PREPARED SOIL LAYER, FINISH SOIL, 12"
0210 1 1	2	\$2.44	\$15,375.96	6,302.000	SY	N	REWORKING LIMEROCK BASE, 6"
0210 1 9	2	\$5.11	\$27,265.79	5,330.600	SY	N	REWORKING LIMEROCK BASE, 3"
0210 2	3	\$28.00	\$25,730.61	919.000	CY	N	LIMEROCK-NEW MATERIAL FOR REWORKING BASE
0285701	36	\$9.68	\$1,172,692.55	121,130.600	SY	N	OPTIONAL BASE,BASE GROUP 01
0285702	7	\$8.71	\$893,909.65	102,643.000	SY	N	OPTIONAL BASE,BASE GROUP 02
0285704	11	\$8.96	\$1,850,232.39	206,536.000	SY	N	OPTIONAL BASE,BASE GROUP 04
0285705	2	\$9.08	\$141,114.56	15,537.000	SY	N	OPTIONAL BASE,BASE GROUP 05
0285706	8	\$12.77	\$352,203.33	27,584.000	SY	N	OPTIONAL BASE,BASE GROUP 06
0285707	2	\$15.08	\$150,283.20	9,969.000	SY	N	OPTIONAL BASE,BASE GROUP 07
0285708	2	\$15.59	\$96,926.00	6,218.000	SY	N	OPTIONAL BASE,BASE GROUP 08
0285709	27	\$13.57	\$5,561,855.86	409,713.500	SY	N	OPTIONAL BASE,BASE GROUP 09
0285710	8	\$16.80	\$1,219,613.18	72,588.000	SY	N	OPTIONAL BASE,BASE GROUP 10
0285711	10	\$13.36	\$2,699,278.70	202,079.000	SY	N	OPTIONAL BASE,BASE GROUP 11
0285712	7	\$14.37	\$3,365,610.96	234,161.000	SY	N	OPTIONAL BASE,BASE GROUP 12
0285713	4	\$42.20	\$832,862.77	19,735.000	SY	N	OPTIONAL BASE,BASE GROUP 13
0285714	1	\$92.00	\$69,828.00	759.000	SY	N	OPTIONAL BASE,BASE GROUP 14
0285715	12	\$58.78	\$5,381,055.68	91,538.600	SY	N	OPTIONAL BASE,BASE GROUP 15
0286 1	9	\$10.23	\$270,386.59	26,424.500	SY	N	TURNOUT CONSTRUCTION
0286 2	2	\$117.25	\$30,602.80	261.000	TN	N	TURNOUT CONSTRUCTION-ASPHALT
0327 70 1	31	\$1.49	\$1,224,395.38	824,330.100	SY	N	MILLING EXIST ASPH PAVT, 1" AVG DEPTH
0327 70 2	7	\$2.14	\$611,448.18	285,837.000	SY	N	MILLING EXIST ASPH PAVT,3 1/2" AVG DEPTH
0327 70 3	1	\$6.25	\$2,406.25	385.000	SY	N	MILLING EXIST ASPH PAVT,4 1/2" AVG DEPTH
0327 70 4	20	\$2.32	\$1,643,427.97	708,052.000	SY	N	MILLING EXIST ASPH PAVT, 3" AVG DEPTH
0327 70 5	21	\$1.86	\$2,256,367.46	1,216,096.000	SY	N	MILLING EXIST ASPH PAVT, 2" AVG DEPTH
0327 70 6	38	\$1.84	\$2,480,181.19	1,345,564.000	SY	N	MILLING EXIST ASPH PAVT,1 1/2" AVG DEPTH
0327 70 7	4	\$3.34	\$190,874.09	57,145.100	SY	N	MILLING EXIST ASPH PAVT, 4" AVG DEPTH
0327 70 8	14	\$2.86	\$903,843.89	315,718.000	SY	N	MILLING EXIST ASPH PAVT,2 1/2" AVG DEPTH
0327 70 11	10	\$1.72	\$1,373,550.17	798,182.000	SY	N	MILLING EXIST ASPH PAVT,2 1/4" AVG DEPTH
0327 70 12	6	\$1.11	\$73,554.66	66,231.000	SY	N	MILLING EXIST ASPH PAVT,1 1/4" AVG DEPTH
0327 70 13	12	\$3.00	\$923,132.81	307,290.000	SY	N	MILLING EXIST ASPH PAVT,1 3/4" AVG DEPTH
0327 70 15	10	\$1.35	\$1,175,427.13	870,970.000	SY	N	MILLING EXIST ASPH PAVT,2 3/4" AVG DEPTH
0327 70 16	2	\$2.17	\$94,906.92	43,712.000	SY	N	MILLING EXIST ASPH PAVT, 1/2" AVG DEPTH
0327 70 17	1	\$1.25	\$14,337.50	11,470.000	SY	N	MILLING EXIST ASPH PAVT,3 1/4" AVG DEPTH
0327 70 19	13	\$1.57	\$709,647.78	451,823.000	SY	N	MILLING EXIST ASPH PAVT, 3/4" AVG DEPTH
0327 70 20	1	\$2.66	\$16,313.78	6,133.000	SY	N	MILLING EXIST ASPH PAVT,3 3/4" AVG DEPTH
0327 70 21	1	\$8.00	\$8,632.00	1,079.000	SY	N	MILLING EXIST ASPH PAVT, 7" AVG DEPTH
0327 70 22	1	\$10.15	\$6,709.15	661.000	SY	N	MILLING EXIST ASPH PAVT,4 1/4" AVG DEPT
0327 70 23	1	\$7.45	\$72,607.70	9,746.000	SY	N	MILLING EXIST ASPH PAVT, 6" AVG DEPTH





LT - Item 9 - Erosion
Control and Cover
Maintenance -
Regrading

5061 SE 66th Avenue
Ocala, Florida, 34480

Date: 19-Jul-13

Marion County Baseline Landfill
Year 2013 Quarter 2
Unit Detail Report

Prepared By:
Hal Boudreau
Jones Edmunds & Associates, Inc.

LineNumber				Description	Quantity	Unit	Total Incl. O&P	Ext. Total Incl. O&P
Division 31 Earthwork								
312316420300				Excavating, bulk bank measure, 3 C.Y. capacity = 260 C.Y./hour, backhoe, hydraulic, crawler mounted, excluding truck loading	1.00	B.C.Y.	\$1.68	\$1.68
Division 31 Earthwork Subtotal								\$1.68

Appendix A
Operation Plan



**Landfill Operation Requirements (62-701.500, FAC)
Operation Plan for the Agricultural Plastic Disposal Unit
Permit Number: 0038570-023-SO/08**

Highlands County Solid Waste Management Center, Sebring, FL | December 2014

**LANDFILL OPERATION REQUIREMENTS (62-701.500, FAC)
OPERATION PLAN FOR THE
AGRICULTURAL PLASTIC DISPOSAL UNIT**

Prepared for:

HIGHLANDS COUNTY BOARD OF COUNTY COMMISSIONERS
600 S. Commerce Avenue
Sebring, Florida 33870

Prepared by:

JONES EDMUNDS & ASSOCIATES, INC.
730 NE Waldo Road
Gainesville, Florida 32641

December 2014

TABLE OF CONTENTS

1	TRAINING AND CERTIFICATION OF OPERATORS (62-701.500 (1), FAC)	1-1
2	STANDARD LANDFILL OPERATIONS AND MAINTENANCE (62-701.500(2), FAC)	2-1
2.1	Responsible Persons	2-1
2.2	Contingency Operations.....	2-1
2.2.1	Equipment Failure	2-2
2.2.2	Alternative Landfill to Accept Waste	2-3
2.2.3	Poor Weather Conditions	2-3
2.2.4	Accidents.....	2-4
2.2.4.1	Vehicular Accidents.....	2-4
2.2.4.2	Personal Injury	2-4
2.3	Control/Inspection of Incoming Waste	2-4
2.4	Weighing or Measuring Incoming Waste	2-5
2.5	Vehicle Traffic Control and Unloading	2-5
2.6	Method and Sequence of Filling Wastes	2-5
2.7	Waste Compaction and Application of Cover	2-5
2.8	Operation of Gas, Leachate, and Storm Water Controls	2-5
2.9	Water Quality Monitoring.....	2-6
2.10	Leachate Collection System.....	2-6
3	OPERATING RECORDS (62.701.500(3), FAC)	3-1
4	WASTE RECORDS (62.701.500(4), FAC)	4-1
5	CONTROL OF ACCESS (62.701.500(5), FAC)	5-1
6	MONITORING OF WASTE (62.701.500(6), FAC)	6-1
6.1	Load Checking Program	6-1
6.2	Handling Hazardous Wastes.....	6-1
6.3	Recording Inspection Results	6-1
6.4	Employee Training for Detection of Unauthorized Material	6-1
7	WASTE HANDLING REQUIREMENTS (62.701.500(7), FAC)	7-1
7.1	Layer Thickness and Compaction Frequencies	7-1
7.2	First Layer Above Liner	7-1
7.3	Working Face and Side Grade Slopes and Lift Depths	7-1
7.4	Working Face Maximum Width	7-1
7.5	Initial Cover	7-1
7.6	Initial Cover Application Procedure	7-1

7.7	Intermediate Cover Application Procedure	7-1
7.8	Final Cover Applications Procedures	7-1
7.9	Scavenging.....	7-1
7.10	Litter Policing Methods.....	7-1
7.11	Erosion Control Procedures.....	7-2
8	LEACHATE MANAGEMENT (62.701.500(8), FAC).....	8-1
9	GAS MONITORING (62.701.500(9), FAC).....	9-1
10	STORMWATER SYSTEM MANAGEMENT (62.701.500(10), FAC)	10-1
11	EQUIPMENT AND OPERATION FEATURES (62.701.500(11), FAC).....	11-1
11.1	On-Site Equipment.....	11-1
11.2	Reserve Equipment.....	11-1
11.3	Communication Equipment.....	11-1
11.4	Dust Control Devices	11-1
11.5	Fire Protection and Fire Fighting Facilities.....	11-1
11.6	Litter Control Devices	11-2
11.7	Signs	11-2
12	ACCESS ROADS (62.701.500(12), FAC).....	12-1
12.1	All-Weather Road	12-1
12.2	Perimeter and Other Onsite Roads.....	12-1
13	RECORDKEEPING (62.701.500(13), FAC).....	13-1
13.1	Permit Application Documentation	13-1
13.2	Monitoring Information	13-1
13.3	Remaining Life and Capacity Estimate	13-1
13.4	Archiving and Retrieving Records.....	13-1

INTRODUCTION

The Highlands County Solid Waste Management Center (HCSWMC) receives approximately 500 and 1,000 tons per year of agricultural plastic film, plastic irrigation tubing, and piping from the caladium and strawberry fields in the County. The waste is delivered twice a year in the spring and fall. The amount received depends on whether a moratorium on field-burning is in place during the spring. All loads containing nothing but agricultural plastic film and soil are diverted from the scalehouse to the Florida Department of Environmental Protection (FDEP)-approved Agricultural Plastic Disposal Unit (Ag Plastic Landfill). A full-time spotter makes sure that the plastic film does not contain cardboard rolls, wood pallets, agricultural products, or garbage. Unacceptable agricultural waste is diverted to the Class I landfill for disposal.

1 TRAINING AND CERTIFICATION OF OPERATORS (62-701.500 (1), FAC)

Highlands County Department of Solid Waste Management (HCDSWM) maintains a policy that all personnel in the following positions will be trained and certified as landfill operators in the Florida in accordance with Rule 62-701.320(15), FAC, within 6 months after completing their initial probationary period as a new employee at the landfill as a condition of continued employment. Certification will be obtained through an FDEP-approved 24-hour initial training course. At all times when the landfill is in operation, a trained and certified landfill operator will be on site.

- Landfill Operations Manager
- Landfill Equipment Operators

Certified operators are required to maintain their certification by completing 16 hours of FDEP-approved continuing training education within the following 3 years.

Landfill spotters will be trained and certified in accordance with FAC Rule 62-701.320(15) through an FDEP-approved 8-hour training course and will maintain their certification by completing 4 hours of FDEP approved continuing training education within the following 3 years.

The Landfill Operations Manager is responsible for day-to-day operation of the landfill. At least one "certified landfill operator" will be present on site during all hours of operation that the HCSWMC receives solid waste. At least one trained spotter will be present at each landfill working face at all times that solid waste is dumped from collection vehicles to detect unauthorized wastes.

Documentation and proof of training, including continual training education, tests, or courses, will be maintained at the Facility and will be available for inspection by FDEP.

2 STANDARD LANDFILL OPERATIONS AND MAINTENANCE (62-701.500(2), FAC)

2.1 RESPONSIBLE PERSONS

The order of responsibility for operation of the Ag Plastic Landfill is as follows:

1. Board of County Commissioners for Highlands County, Florida
600 S. Commerce Avenue
Sebring, Florida 33870
(863) 402-6500

2. June Fisher
County Administrator
County Government Center
600 South Commerce Avenue
Sebring, Florida 33870
(863) 402-6500

3. Ramon Gavarrete, PE
Highlands County Engineer
505 South Commerce Avenue
Sebring, Florida 33870
(863) 402-6877 office
(863) 402-6548 fax
(863) 381-6875 cell

4. Richard "Dick" Gorman
Landfill Operations Manager
Highlands County Solid Waste Management Center
12700 Arbuckle Creek Road
Sebring, Florida 33870
Mailing Address
(863) 402-7786 office
(863) 402-7785 fax
(863) 381-7071 cell

The staffing levels at the landfill are shown on the organizational chart for the HCDSWM on file with the Class I Landfill Operation Permit Application.

2.2 CONTINGENCY OPERATIONS

If an emergency occurs or regulated hazardous wastes are identified by random load checking or are otherwise discovered to be improperly deposited at the landfill, the landfill operator will promptly notify FDEP by calling (850) 413-9911 or (800) 320-0519. During normal business hours, the permittee will call (239) 332-6975.

The contingency plan addresses the following four potential emergencies:

- Equipment Failure
- Alternative Landfills to Accept Waste
- Poor Weather Conditions
- Accidents

2.2.1 EQUIPMENT FAILURE

The HCSWMC is a self-sufficient operation that is funded through a solid waste enterprise fund that derives its revenue from landfill tipping fees, an annual non-ad-valorem assessment charged to households in the unincorporated areas of the County, and the sales of recyclable materials. The HCDSWM purchases, owns, and repairs all of its equipment. It replaces old equipment on a scheduled basis to modernize its fleet and keep equipment in reliable working order. The County has equipment to provide backup capability in case a key piece of equipment is down for service. Following is a list of the HCSWMC Equipment:

HCSWMC Equipment:	Number
42 ton steel wheel landfill compactor	2
Track type bulldozer	4
750 John Deere bulldozer	1
Hydraulic tarping machine	1
Hydraulic excavating pan	1
Track type loader	1
Wheel type loader	1
0.8 cubic yard track excavator with hydraulic grapple and auger	1
2.0 cubic yard track excavator with stiff thumb	1
Motor grader	1
4,000 gallon water truck with cannon	1
Truck tractor	1
Dump truck	1
5,000 gallon leachate transport tanker	1
Low-boy equipment transport trailer	1

The HCDSWM also has a mutual aid agreement with the County Road and Bridge Department to provide backup equipment from time to time as needed. This equipment includes: bulldozers, wheel loaders, excavators, dump trucks, and water trucks.

This available equipment provides ample backup equipment for any needs the landfill operators might have.

In addition to the equipment owned by Highlands County, the County has an annual bid in place at all times that permits renting equipment at a predetermined rate without special Board of County Commissioners' approval.

Operators are trained on all machines so that personnel changes do not adversely affect the solid waste operations. As a standard of operations, an overtime account is budgeted and the Landfill Operations Manager or the Recycling Program Manager has the authority to authorize overtime when it is needed. Additional Road and Bridge Department personnel are available by radio.

2.2.2 ALTERNATIVE LANDFILL TO ACCEPT WASTE

If Ag Plastic Landfill cannot receive waste, the waste will be left in the fields until the disposal facility reopens or diverted to the Class I Landfill or an alternative landfill. Under the Class I Landfill Operation Permit, Highlands County has an agreement with an alternate landfill for acceptance of waste in an emergency.

2.2.3 POOR WEATHER CONDITIONS

The County may have to temporarily close the working face of the landfill due to locally severe weather conditions that would pose a safety hazard to operators and customers or to winds in excess of 35 mph that would prohibit safe waste-dumping conditions. The conditions that would warrant temporary closure of the landfill include the presence of nearby lightning strikes, high winds, intense on-site rainfall, or an approaching tornado. The landfill is tied into the DTN Satellite Weather Monitoring Network and Thorguard Lightning Prediction System to alert personnel in the landfill office of approaching electrical storms. This equipment is used to monitor the direction and speed of storms and to determine when the danger has passed and the working face can be re-opened.

The procedures for a temporary closure of the landfill are as follows:

1. The County Engineer, HCDSWM Landfill Operations Manager, or Landfill Operations Manager will declare a temporary shutdown and will direct the scalehouse operator to halt all incoming refuse collections trucks at the scalehouse until the severe weather condition passes. All County personnel and any refuse haulers present in the active disposal cell will cease work and take shelter off the cell. No one will remain on the landfill disposal cells during the storm.
2. The Landfill Operations Manager will telephone the County-franchised refuse collection contractors; the municipalities of Avon Park, Lake Placid, and Sebring; and farms using the Ag Plastic Landfill, when an emergency shutdown occurs. They will be notified again by phone once the landfill operations are resumed. Typical emergency shutdowns are expected to last 10 minutes to over 1 hour in duration.
3. The Landfill Operations Manager will direct the restart of landfill operations as soon as weather and site conditions permit. If landfill operations are halted by severe weather conditions that occur after 4:30 PM (normal closing time is 5:15 PM), the landfill will remain closed for the rest of the day and any refuse collection trucks arriving after 4:30 PM will be asked to return the next morning.
4. The landfill will document emergency shutdowns recording the date, time of day, and duration of the shutdown. A count will be made of the number of collection vehicles held up or turned away during the temporary shutdown. Typically, temporary landfill shutdowns do not occur more than 15 to 20 times per year.

The County may also close the entire HCSWMC for 1 or more days during a declared tropical storm or hurricane. Closure would occur when the sustained wind speed from an approaching tropical storm or hurricane reaches 45 mph. The landfill closure would be coordinated with the County Department of Emergency Management Services, and public announcements of the closure would be made over local radio and television stations. Closure of the landfill would also be coordinated with both County-franchised

refuse collection contractors and the municipalities of Avon Park, Lake Placid, and Sebring to occur concurrently with the cessation of refuse collection activities throughout the County as the storm passes over the area. Once the tropical storm or hurricane is over, the landfill will be reopened as soon as it is determined to be safe by the HCDSWM Landfill Operations Manager Arbutle Creek Road is passable and not closed due to localized flooding.

2.2.4 ACCIDENTS

The following emergency or equipment procedures will be followed for the various types of accidents that may occur at the facility.

2.2.4.1 Vehicular Accidents

- Determine if personal injury has occurred. If so, contact the Landfill Operations Manager.
- Determine if the vehicle(s) can be safely moved under its own power. If so, move the vehicle(s) out of the way of normal traffic flow.
- If the vehicle(s) cannot move under its own power and is interrupting traffic flow, push the vehicle(s) out of the way with site equipment or reroute traffic if serious injuries are involved.
- Notify the Landfill Operations Manager and the County Risk Manager (863-402-6792) of the details of the accident.
- Arrange to have disabled vehicles towed from the site to maintain operations.

2.2.4.2 Personal Injury

- Determine the nature and extent of the injuries.
- If qualified, administer emergency first-aid techniques.
- Call 911 for outside emergency assistance.
- Report the incident to the Landfill Operations Manager and the County Risk Manager (863-402-6792).
- If injuries require non-emergency medical attention, arrange to transport victim(s) to a place of professional medical care (e.g., hospital emergency room, doctor's office, and clinic) by conventional means.

2.3 CONTROL/INSPECTION OF INCOMING WASTE

Large signs are posted at the entrance to the HCSWMC and at the scalehouse that alert the public of the types of waste not accepted at the Class I landfill, C&D waste landfill, and Ag Plastic Landfill. The County provides a household hazardous waste collection program for all households based at the County Recycling Facility. Hazardous materials removed from waste or brought into the landfill site separately by waste haulers or residents are transferred to the hazardous waste storage area at the Recycling Facility where they are inventoried and removed by a licensed hazardous waste collection company under contract to the County.

The scale operator questions the haulers regarding what their loads contain and then directs the hauler to the proper disposal area. Loads containing prohibited material can be rejected at this point.

If a significant amount of regulated hazardous wastes is discovered as the load is being dumped or spread or otherwise discovered to be improperly deposited at the landfill, the area will be immediately secured with barriers and the landfill operator will promptly notify the Florida Department of Environmental Protection (FDEP) by calling (239) 332-6975 and the branch office in Sebring at (863) 314-5975 during normal business hours. Outside normal business hours, FDEP will be notified by calling (850) 413-9911 or (800) 320-0519. Arrangements will be made with the generator to properly dispose of the material using the hazardous waste contractor.

2.4 WEIGHING OR MEASURING INCOMING WASTE

Incoming waste will be weighed at the scalehouse with inbound and outbound 60-ton electronic vehicle scales. The scalehouse is equipped with a computerized vehicle recording system and a security camera with color monitor. The scales are certified by the State and calibrated quarterly.

2.5 VEHICLE TRAFFIC CONTROL AND UNLOADING

All traffic entering the HCSWMC must pass the scalehouse. A full-time spotter will be employed to control the vehicles coming into the site, along with full-time heavy equipment operators. The spotter and the operators have the authority to direct traffic. The spotter is trained to identify unacceptable waste and is stationed at the working face to monitor the incoming waste.

2.6 METHOD AND SEQUENCE OF FILLING WASTES

Plastic waste will be placed in 10-foot lifts. A second lift will not begin until the first lift is completed within the perimeter dikes.

2.7 WASTE COMPACTION AND APPLICATION OF COVER

After completing a 10-foot lift, the waste will be covered with a 12-inch-thick layer of 50/50 mixture of soil and shredded yard waste as intermediate cover. The cover soil is blended on-site four to six times per year and stockpiled for use. Soil is obtained from on-site borrow pits.

The final cover system will be designed in accordance with Rule 62-701.600(5), FAC. The final cover will be placed as portions of the facility reach final grade. The final cover consists of a minimum of 24 inches of soil over the waste and a layer of sod.

2.8 OPERATION OF GAS, LEACHATE, AND STORM WATER CONTROLS

Only agricultural waste plastic film, waste plastic tubing, and waste plastic pipe can be disposed of in this facility. This disposal facility cannot accept degradable wastes. Since the waste is inert and not degradable, the facility does not have a landfill gas management or monitoring system or a leachate management system.

The stormwater system does not require routine operation. All stormwater flows by gravity from the perimeter ditches into the stormwater management system for the HCSWMC. The stormwater retention system is designed with a positive outflow control structure, which flows into a spreader swale. The retention system is designed to be a 35-acre productive wetlands marsh that needs no mowing or cleaning.

The maintenance of the stormwater system requires semi-annual mowing of the upland ditches and swales. Machine-cleaning of the ditches and swales is scheduled as needed.

2.9 WATER QUALITY MONITORING

No separate water quality monitoring is required for this disposal unit.

2.10 LEACHATE COLLECTION SYSTEM

This disposal unit has no leachate collection system.

3 OPERATING RECORDS (62.701.500(3), FAC)

Permits, drawings, and records required by 62-701.500(3), FAC, will be kept and maintained in the on-site HCSWMC office. The records are considered an integral part of the Operation Plan and are available during operating hours upon request by FDEP personnel. The HCDSWM Director, will be responsible for filing and storing all operational records. The minimum records to be kept as part of the official operating record are:

- Current permits and applications including supporting data and engineering drawings.
- Monthly waste disposal records.
- Inspection records.
- On-site rain gauge data.
- Monthly operating reports (FDEP monthly facility report).
- Annual estimates of remaining capacity (permitted disposal) in cubic yards.
- Regulatory agency inspection reports.
- Groundwater, surface water, and leachate sampling plan, including well construction information, sampling locations, and water quality sampling results.
- All official notifications to or from FDEP regarding the facility.
- Training verifications/certifications.

4 WASTE RECORDS (62.701.500(4), FAC)

The County keeps monthly records of waste tonnages for the following categories:

- Residential waste.
- Commercial waste.
- Tires.
- Yard waste.
- White goods.
- Agricultural plastic film.
- Non-friable asbestos.
- Contaminated soil.
- Leachate aeration basin sludge.
- Construction and demolition debris.

The HCSWMC waste records are compiled monthly sent to FDEP annually.

5 CONTROL OF ACCESS (62.701.500(5), FAC)

The landfill design includes methods to control access and provides a buffer designated into the overall landfill including the following:

- A fenced boundary to keep the general public from coming onto the site.
- A gated access point controlled at all times during landfill operations.
- A raised and vegetated berm around the boundary of the site to prevent any adverse visual impacts.
- Internal locked gates on site roads to limit access inside the facility.

The HCSWMC operates and accepts waste Monday through Saturday from 7:30 AM to 5:15 PM for franchised hauler compactor vehicles. All other vehicles must be off the landfill site by 5:00 PM.

6 MONITORING OF WASTE (62.701.500(6), FAC)

6.1 LOAD CHECKING PROGRAM

A full-time spotter and full-time heavy-equipment operators control the vehicles coming onto the site. The spotter and the operators have the authority to direct traffic. The spotter is trained to identify unacceptable waste and is stationed at the working face to monitor the incoming waste. The spotters visually inspect all dumped loads as the loads are discharged from the collection vehicles and as the load is spread into 2-foot layers by the compactor or bulldozer. Prohibited materials are removed when found. If unauthorized wastes are found, the owner or shipper of the wastes will be contacted to determine the identity of the waste sources.

6.2 HANDLING HAZARDOUS WASTES

No hazardous wastes will be accepted at the facility for disposal. If an emergency occurs or regulated hazardous wastes are identified by random load checking or are otherwise discovered to be improperly deposited at the landfill, the landfill operator will promptly notify FDEP as described in Section 2.3.

The area where the wastes are deposited shall immediately be cordoned off from public access. If the generator or hauler cannot be identified, the landfill operator will ensure the cleanup, transportation, and disposal of the waste at a permitted hazardous waste management facility. Subsequent shipments from sources found or suspected to be previously responsible for shipping regulated hazardous waste will be subject to precautionary measures before the facility accepts the wastes.

6.3 RECORDING INSPECTION RESULTS

Results from inspections will be recorded in writing and retained at the landfill for at least 3 years. This information will include date and time of inspection, name of hauling firm, name of driver of the vehicle, vehicle license plate number, source of waste as stated by the driver, and observations made by HCSWMC personnel during the inspection. The inspector will sign the written record.

6.4 EMPLOYEE TRAINING FOR DETECTION OF UNAUTHORIZED MATERIAL

Inspectors, solid waste technicians, and attendants are trained to identify unauthorized wastes or hazardous materials. Each scalehouse attendant and spotter is trained to identify unacceptable waste. Large signs are posted at the entrance of the landfills that alert the public of the types of waste not accepted in the landfill. A household hazardous waste collection program is available to all households in Highlands County.

If unauthorized material is transported to the facility, the HCDSWM Director will be notified immediately and appropriate actions taken to remove any unauthorized materials or wastes from the facility (see Section 2.3).

If an emergency occurs, the hazardous material response team with the Highlands County Department of Emergency Management will be notified at (863) 385-1112.

7 WASTE HANDLING REQUIREMENTS (62.701.500(7), FAC

7.1 LAYER THICKNESS AND COMPACTION FREQUENCIES

The waste plastic will be spread in 2-foot layers and compacted to achieve 10-foot lifts.

7.2 FIRST LAYER ABOVE LINER

The disposal area will not have a liner, so the first layer has no special considerations.

7.3 WORKING FACE AND SIDE GRADE SLOPES AND LIFT DEPTHS

The working face will be maintained at a slope no greater than 3:1. The side slopes of the working area will be maintained at a slope no greater than 3:1. The maximum lift is 10 feet.

7.4 WORKING FACE MAXIMUM WIDTH

The working face will have a typical width of 100 feet but will be subject to change to accommodate the volume of incoming traffic and to maintain safe operating conditions.

7.5 INITIAL COVER

No initial cover will be applied to this plastic waste.

7.6 INITIAL COVER APPLICATION PROCEDURE

This plastic waste does not require initial cover.

7.7 INTERMEDIATE COVER APPLICATION PROCEDURE

Intermediate cover includes the soil / yard waste blend (Section 2.7) applied over 10-foot lifts and exterior slopes.

7.8 FINAL COVER APPLICATIONS PROCEDURES

Two feet of final cover soil and sod will be applied to the outer slopes at final grade. Freshly-laid sod will be irrigated until the sod is established.

7.9 SCAVENGING

Scavenging is not permitted at any time. The HCSWMC is fenced, and the gates are locked when the HCSWMC is closed. When the HCSWMC is open, staff monitor the disposal areas and are authorized to stop any scavenging.

7.10 LITTER POLICING METHODS

Due to the nature of the agricultural waste plastic film, tubing, and piping, litter is not a problem. All litter blown and found on the ground surface outside the landfill is picked up by hand within 24 hours of when the litter is generated. County staff also patrols all on-site roads for litter daily. During winter, when passing cold fronts cause strong northeast winds, County staff, with the help of the Sheriff's Department, also conduct litter patrols along Arbuckle Creek Road from Lorida to Highlands Avenue.

7.11 EROSION CONTROL PROCEDURES

Exterior berms and intermediate and final cover slopes will be graded and sodded to control erosion.

8 LEACHATE MANAGEMENT (62.701.500(8), FAC)

This disposal facility does not have a leachate management system. Only agricultural waste plastic film, waste plastic tubing, and waste plastic pipe can be disposed of in this facility.

9 GAS MONITORING (62.701.500(9), FAC)

This disposal facility cannot accept degradable wastes and is not required to have a landfill gas management or monitoring system.

10 STORMWATER SYSTEM MANAGEMENT (62.701.500(10), FAC)

The landfill will use the following stormwater best management practices (BMPs):

- Side swales
- Grass
- Sod
- Perimeter ditches

The stormwater management system operation and maintenance will include the following:

- All stormwater conveyance systems will be inspected periodically or after major storm events.
- Accumulated sediment will be removed as necessary.

The stormwater management system will be operated and maintained as necessary to meet applicable standards of Chapters 62-302 and 62-25, FAC.

11 EQUIPMENT AND OPERATION FEATURES (62.701.500(11), FAC)

11.1 ON-SITE EQUIPMENT

The landfill will be operated with the landfill equipment noted in Section 2.2.1. Most of this equipment is under warranty with service provided by the vendor. The remaining equipment is maintained by trained heavy-equipment mechanics that work for the County. The County mechanics are also equipped with service trucks. A standing agreement between the County Road and Bridge Department and HCDSWM also provides for work to be done on landfill equipment.

Equipment replacement is a budgeted part of the HCDSWM. The tipping fee schedule has an adequate amount budgeted for equipment replacement when a machine has reached its useful life span. The older machines are often kept as a backup to the newer machines, as long as they are serviceable, economical to run, and safe.

Standard safety equipment are maintained in the same operating condition as when it was delivered. This equipment meets all OSHA requirements. A safety inspection is made of all equipment, once a quarter, by the County Safety Department and County Shop Supervisor. The County Shop Supervisor notes any deficiencies and necessary repairs are scheduled.

11.2 RESERVE EQUIPMENT

Reserve equipment is available from the County Road and Bridge Department by agreement and by rental with pre-approved rental rates. Reserve equipment can be on site within 24 hours.

11.3 COMMUNICATION EQUIPMENT

The landfill has phones in the office, scalehouse, and maintenance building. In addition to the phone system, the scalehouse and landfill office are equipped with a base radio station can contact the Landfill Operations Manager's vehicle and handheld radios assigned to the operators and spotters. The Landfill Operations Manager is also equipped with a cell phone.

11.4 DUST CONTROL DEVICES

HCSWMC includes dust-free paved roads or roads vegetated with grass or other cover to prevent any dust problem. The 1,000-foot buffer area will also keep any dust from migrating off site. If necessary, the landfill's large-capacity water system can be used to eliminate any dust problems. The County uses a pressurized 4,000-gallon water truck capable of delivering a 60-foot-wide spray of water for dust control on unpaved roads.

11.5 FIRE PROTECTION AND FIRE FIGHTING FACILITIES

The HCSWMC is equipped with multiple methods of fire protection and suppression, including a 6-inch water supply pipeline capable of delivering a sustained flow of 200 gallons per minute at 40-psi pressure from a hydrant in the equipment staging area about 100 feet from the entrance to Cell I B. The County may also use the 4,000-gallon water trucks equipped with water cannons for fire suppression. An 8-inch-diameter dry hydrant (drafting hydrant) will provide fire suppression next to the north bank of the west borrow pit, less than 300 feet from the future waste tire stockpile area. The hydrant meets the County Fire Marshal's requirement of providing a minimum sustained flow of 1,000 gallons per minute for 3 hours to fight a tire pile fire. A second drafting hydrant has been installed in the west bank of the west firing range pond about 200 feet north of the gas blower and flare facility. The facility is also equipped with two landfill

compactors and three bulldozers with enclosed cabs and large trash blades that can be used to dig out and smother a landfill fire.

If a landfill fire occurs during the day, the Landfill Operations Manager or his designee will call 911 to report the fire and solicit the support of the Lorida Volunteer Fire Department and backup firefighting resources from the Sebring Volunteer Fire Department as required. When the landfill is closed, area residents or motorists on Arbuckle Creek Road may report the fire to 911. The County Department of Emergency Management Services monitors all calls and will notify the HCDSWM Director and Landfill Operations Manager at home of the report of a fire. The HCDSWM Director and Landfill Operations Manager will immediately report to the landfill to direct fire-fighting operations and will summon landfill operations staff as required to help contain and extinguish any refuse fire in the landfill disposal cells.

Any fire in the landfill waste will be initially hosed down to suppress the flames and reduce the rate of the lateral spread of the burn area. Then the landfill heavy equipment will rapidly excavate the burning or smoldering waste and shove it away from the burn area onto an adjacent area of the landfill that is sealed with a layer of intermediate cover soil. As the burning or smoldering waste is spread out in a thin layer on the surface of the intermediate cover, it will be hosed down and track-rolled to extinguish the fire. The waste will then be turned over with the heavy equipment so it can be hosed down and track-rolled a second time. Waste in the burn area showing evidence of having been charred by the fire will be excavated from the burn area and hosed down.

Charred or burning waste excavated from the landfill will be isolated from the landfill by a physical firebreak. This waste will be allowed to cool down for a minimum of 12 hours to make sure that the fire is entirely extinguished before the waste is pushed back into the landfill, compacted, and covered.

The Lorida Volunteer Fire Department would respond to any structural fires that occur at the landfill site. This Fire Department has a standing "Automatic Aid" agreement with 13 other fire departments, if needed.

11.6 LITTER CONTROL DEVICES

As a part of the daily operation of the landfill, the landfill operator inspects the lands around the landfill and any litter is picked up before it can be blown over into the buffer area. The property fence line is inspected regularly to make sure that no debris from the landfill accumulates at the fence.

11.7 SIGNS

At the entrance to the landfill, signs are posted indicating the operating authority as the Board of County Commissioners; traffic directions and speed limit; disposal areas; hours of operation (7:30 AM to 5:00 PM, Monday through Saturday); and tip fees and disposal restrictions for hazardous waste, biohazardous waste, containers with liquids, and construction and demolition debris. Signs also indicate the route to the Ag Plastic Landfill.

12 ACCESS ROADS (62.701.500(12), FAC)

12.1 ALL-WEATHER ROAD

The access road to the landfill is asphalt pavement. This road's drainage is part of the original design. The paved road will be maintained with standard road maintenance equipment and resurfaced as required to maintain a good all-weather access road.

12.2 PERIMETER AND OTHER ONSITE ROADS

Internal roads will be inspected periodically and repaired in a timely manner.

13 RECORDKEEPING (62.701.500(13), FAC)

13.1 PERMIT APPLICATION DOCUMENTATION

Records of all information used to develop or support the permit applications and any supplemental information submitted to comply with Chapter 62-701, FAC pertaining to construction of the facility will be kept throughout the life of the facility. Records pertaining to the operation of the landfill will be kept for the life of the facility.

13.2 MONITORING INFORMATION

Records of all monitoring, including maintenance records and copies of all reports required by permit, will be retained for at least 10 years. Background water quality records will be kept for the life of the facility.

13.3 REMAINING LIFE AND CAPACITY ESTIMATE

An annual estimate will be made to determine the remaining capacity and design life at the existing constructed HCSWMC landfills. Annual estimates will be based on a design capacity and surveyed elevations. The estimate will be made and reported annually to FDEP as part of the annual update to the closure and long-term care cost estimates.

13.4 ARCHIVING AND RETRIEVING RECORDS

All records pertaining to the operation of the facility will be retained throughout the design life of the landfill. All monitoring records and calibration and maintenance records and reports required by the landfill operation permit will be retained for at least 10 years.