

Morris, John R.

From: Adams, David <AdamsDS@HillsboroughCounty.ORG>
Sent: Monday, August 25, 2014 3:45 PM
To: Morris, John R.
Cc: Lyons, John; Byer, Kimberly; Ruiz, Larry; Greenwell, Jeffry; Tedder, Richard; Moore, Clark B.; Morgan, Steve; Schipfer, Andy; 'Ely, Ernest'; 'Siemering, Richard'; 'Joseph H. O'Neill P.E. (joneill@civildesignservicesinc.com)'; 'brian_miller@doh.state.fl.us'; SWD_Waste (Shared Mailbox); ADaPT EDD (Shared Mailbox); Restrepo, Carlos; Curtis, Robert
Subject: Southeast County Landfill - Sinkhole IAMP Report No. 47 - July 2014
Attachments: SCLF - Sinkhole IAMP Report No 47.pdf

Dear Mr. Morris,

Attached please find an electronic copy of the Southeast County Landfill (SCLF) Sinkhole - Initial Assessment Monitoring Plan (IAMP) Report No. 47. This report provides the analytical data from the monthly sampling event conducted at the SCLF on July 2-3, 2014. As required, the ADaPT files from this sampling event are provided, and I have copied Clark Moore, SWD_Waste@dep.state.fl.us, and the Adapt mailbox in Tallahassee on this e-mail. A hard copy of this report has been sent to your attention via the USPS. Should you have any questions, or require any additional information, please feel free to call me directly at 813-663-3221.

Respectfully,

David S. Adams, P.G.
Environmental Manager
Public Utilities Department - BSOC
Hillsborough County BOCC
phone: 813-663-3221
VOIP 43944
e-mail: adamsds@hillsboroughcounty.org
web: <http://www.hillsboroughcounty.org>

Please note: all correspondence to or from this office is subject to Florida's Public Records laws.





Public Utilities

August 25, 2014

Board of County Commissioners

Kevin Beckner
Victor D. Crist
Ken Hagan
Al Higginbotham
Lesley "Les" Miller Jr.
Sandra L. Murman
Mark Sharpe

County Administrator

Michael S. Merrill

County Administrator Executive Team

Lucia Garsys
Carl S. Harness
Gregory S. Horwedel
Liana Lopez
Bonnie Wise

County Internal Auditor

Michelle Leonhardt

County Attorney

Chip Fletcher

Public Utilities

PO Box 1110
Tampa, FL 33601-1110
Phone: (813) 272-5977
Fax: (813) 272-5589

Mr. John Morris, P.G.
Florida Department of Environmental Protection
Waste Permitting Section
13051 Telecom Parkway
Temple Terrace, FL 33637

RE: **Southeast County Landfill
Laboratory Analytical Results
Initial Assessment Monitoring Plan
Report No. 47– July 2014**

Dear Mr. Morris:

The Hillsborough County Public Utilities Department (County) is pleased to provide the analytical results from the July 2014 sampling event conducted as part of the continuation of the Initial Assessment Monitoring Plan (IAMP). The IAMP was developed to address the potential impacts to groundwater from the sinkhole on the edge of Phase VI at the Southeast County Landfill (SCLF), which was discovered on December 14, 2010.

As part of the agreement between the County and Florida Department of Environmental Protection Southwest District Office (Department), four (4) upper Floridan/Limestone aquifer monitoring wells, designated as TH-72, TH-76, TH-77, and TH-78 are sampled on a monthly schedule. Representative samples were collected from each of these four (4) monitoring wells on July 2-3, 2014 and analyzed for total dissolved solids (TDS), chloride, total ammonia, arsenic, iron, sodium, and five (5) field parameters. Each sample collected was analyzed by our contracted laboratory, Test America, Inc. The following paragraphs summarize the parameter specific results pertinent to the evaluation of potential water quality impacts from the sinkhole at the SCLF.

Mr. John Morris, P.G.

August 25, 2014

Page 2

pH

pH was observed at 9.08 pH units in the new upper Floridan aquifer (UFA) monitoring well, TH-78, which is above the Secondary Drinking Water Standard (SDWS) acceptable range of 6.5 - 8.5 pH units. The elevated pH value observed does not appear to be representative of the unaffected UFA. The pH values in down gradient monitoring wells TH-72, TH-76, and TH-77 were recorded at 6.86, 7.46, and 7.44 pH units.

Turbidity

Turbidity values in monitoring wells TH-72, TH-76, TH-77, and TH-78 were recorded at 1.34, 19.5, 1.56, and 19.3 Nephelometric Turbidity Units (NTUs), respectively. The turbidity values observed are consistent with the historical data for these wells, and the new UFA well, TH-78, does not appear to have any issues with turbidity.

Conductivity

The conductivity values observed in monitoring wells TH-72, TH-76, TH-77, and TH-78 were 2,388, 421, 409, and 363 micromhos per centimeter (umhos/cm), respectively. Monitoring well TH-72 is the closest location to the sinkhole, and continues to exhibit water quality impacts. The elevated conductivity observed is likely attributable to the waste in the deep areas of the sinkhole and the subsurface grouting processes conducted as part of the sinkhole stabilization and remediation. Conductivity values in down gradient monitoring well TH-76, TH-77, and TH-78 are relatively low and appear to be consistent with the unaffected deep wells across the site.

Total Dissolved Solids (TDS)

The TDS in monitoring well TH-72 was observed at 1,300 mg/l, which continues to be above the SDWS of 500 mg/l. Down gradient monitoring wells, TH-76, TH-77, and TH-78 exhibited TDS values of 230, 230, and 210 mg/l, respectively, which is consistent with the water quality of the unaffected deep wells across the site.

Chloride

Chloride was observed at 570 mg/l in monitoring well TH-72, which is above the SDWS of 250 mg/l. The elevated chloride value observed is likely attributable to waste in the sinkhole and the grouting activities. Chloride values in the down gradient monitoring wells TH-76, TH-77, and TH-78 were observed at 12, 9.6, and 43 mg/l, which is consistent with the unaffected deep wells across the site.

Iron

Total iron concentrations in two (2) of the four (4) monitoring wells were observed above the SDWS of 0.3 mg/l. Monitoring wells TH-72 and TH-78 exhibited iron at 0.72 and 1 mg/l, respectively, and TH-76 and TH-77 exhibited iron at 0.2 and 0.14 mg/l. The iron concentrations observed in these wells have been consistent, and the iron appears to be naturally occurring in some areas of the limestone formation, and may be the result of impacts from the past strip mining activities in area.

Sodium

Sodium was observed at a concentration of 220 mg/l in monitoring well TH-72, which is above the PDWS of 160 mg/l. The elevated sodium value is likely attributable to the waste in the sinkhole and/or the grouting activities. Sodium values in down gradient monitoring wells TH-76, TH-77, and TH-78 were observed at 20, 17, and 38 mg/l, which is consistent with the unaffected deep wells across the site.

Groundwater Elevations and Direction of Flow

On July 2, 2014, the County collected groundwater and surface water elevation data at sixty-five (65) locations across the site, including twenty eight (28) surficial aquifer wells, seven (7) upper Floridan (limestone) aquifer wells, twenty three (23) piezometers, and six (6) surface water sites. No significant changes to the patterns of flow in the surficial aquifer were noted in the data set, and the flow diagram provided is consistent with the observations over the extensive period of record. The elevations observed within the wells closest to the sinkhole indicate that flow patterns continue to be affected in that area, which has not been unexpected. However, the overall direction of flow within the surficial aquifer remains toward the west/northwest across the site.

A contour diagram of the upper Floridan / Limestone aquifer has been prepared for the general area around the sinkhole and is included with this submittal. This diagram was generated manually in AutoCad™ utilizing only the three data points closest to the sinkhole. During this sampling event, the change in elevation between TH-72 and TH-76 is - 0.09 ft. and TH-72 and TH-77 is + 0.16 ft. The County is currently evaluating the measuring point elevation for TH-78, and we will provide this information in the August IAMP report.

Conclusions

The water quality observed in the July 2014 IAMP sampling event indicates that monitoring well TH-72, which is closest to the sinkhole, continues to exhibit impacts to water quality in the upper Floridan aquifer. The impacts observed include elevated conductivity, TDS, chloride, iron and sodium. These impacts are not unexpected in the immediate vicinity of the sinkhole feature, and TH-72 is less than fifty feet away from the surface expression, and likely even closer the subsurface karst feature where waste and grout are likely present. Down gradient monitoring wells, TH-76, TH-77, and TH-78 exhibit good water quality with no evidence of impact from the sinkhole. Conductivity values, TDS, sodium and chloride are all very low and consistent with the historical data sets for the unaffected upper Floridan aquifer groundwater monitoring wells at the SCLF. The water quality observations continue to support the position that the impacts from the sinkhole are limited in extent and do not appear to be migrating beyond the area in very close proximity to the former sinkhole.

Recommendations

The County continues to move forward with implementation of the IAMP, which includes the monthly sampling of the four upper Floridan / Limestone aquifer groundwater monitoring wells, TH-72, TH-76, TH-77, and TH-78, and the quarterly sampling of the three surficial aquifer wells, TH-73, TH-74, and TH-75.

Mr. John Morris, P.G.
August 25, 2014
Page 4

The County shall continue to evaluate any water quality changes in both the surficial and upper Floridan aquifer wells, and present the findings in the monthly IAMP reports. Monthly sampling shall continue for the short term.


However, it should be noted the IAMP has been conducted for over three and half years, and the consistency of the data set supports complete closure of this monitoring plan. A select group of the IAMP wells, designed to provide long term protectiveness, should be included in the semi-annual sampling required by the Landfill Operations Permit No. 35435-022-SO/01. It is anticipated that an application for modification of the permit will include this proposed approach.

Enclosed for your review please find a site location map depicting the location of the monitoring wells sampled, the water quality data summary table for this sampling event, a groundwater elevation data table, groundwater contour and flow diagrams for the surficial and upper Floridan / Limestone aquifers, the historical data summary tables for the wells sampled this month, and the complete analytical data report from our contracted laboratory, Test America, Inc. Should you have any questions or require any additional information please feel free to call me at (813) 663-3221.


Respectfully submitted,

 8/25/2014

David S. Adams, P.G.
Environmental Manager
Public Utilities Department




xc: John Lyons, Director, Public Works Department
Kim Byer, Public Works Department, Solid Waste Division
Larry Ruiz, Public Works Department, Solid Waste Division
Jeff Greenwell, Public Utilities Department, Environmental Services
Richard Tedder, FDEP Tallahassee
Clark Moore, FDEP Tallahassee
Steve Morgan, FDEP, Southwest District
Andy Schipfer, EPC
Ernest Ely, WMI
Brian Miller, DOH
Rich Siemering, HDR
Bob Curtis, HDR
Joe O'Neill, CDS



LEGEND

- 001 ▲ LEACHATE SAMPLING LOCATION
- P-1S ○ SHALLOW PIEZOMETER
- P-1D ○ DEEP PIEZOMETER
- SUP-1 ● SUPPLY WELL
- TH-32 ○ INACTIVE MONITORING WELL LOCATION AND DESIGNATION
- P-8D ● PIEZOMETER TO MONITOR HYDRAULIC DIVIDE
- 1D □ SURFACE WATER MONITORING SITE LOCATION
- TH-22A ○ MONITORING SITE LOCATION MONITOR WELL
- * FLORIDIAN AQUIFER
- 1A** ○ STAFF GAUGE
- TH-73 ○ MONITORING WELL SAMPLED AS PART OF IAMP

NOTES:
1. TOPOGRAPHICAL INFORMATION COMPILED FROM EXISTING CONDITIONS SURVEY PERFORM BY PICKETT & ASSOCIATES DATED JAN 2013.



**Southeast County Landfill
Laboratory Analytical Data
Upper Floridan Groundwater Monitoring Wells
July 2-3, 2014**

GENERAL PARAMETERS	TH-72	TH-76	TH-77	TH-78	MCL STANDARD
conductivity (umhos/cm) (field)	2,388	421	409	363	NS
dissolved oxygen (mg/l) (field)	0.29	0.3	0.34	0.41	NS
pH (field)	6.86	7.46	7.44	9.08	(6.5 - 8.5)**
temperature (°C) (field)	23.54	22.83	23.65	23.89	NS
turbidity (NTU) (field)	1.34	19.5	1.56	19.3	NS
total dissolved solids (mg/l)	1,300	230	230	210	500**
chloride (mg/l)	570	12	9.6	43	250**
ammonia nitrogen (mg/l as N)	24	0.49	0.48	0.44	NS
METALS (mg/l)					MCL STANDARD
arsenic	0.004 u	0.004 u	0.004 u	0.0019 i	0.01*
iron	0.72	0.2	0.14 i	1	0.3**
sodium	220	20	17	38	160*
Note: Ref. Groundwater Guidance Concentrations, FDEP 2012					
MCL = Maximum Contaminant Level					
BDL = Below Detection Limit					
NTU = Nephelometric Turbidity Units					
NS = No Standard					
i = reported value is between the laboratory method detection limit and practical quantitation limit.					
u = parameter was analyzed but not detected.					
* = Primary Drinking Water Standard					
** = Secondary Drinking Water Standard					
1,300	Exceeds Standards				
ug/l = micrograms per liter					
mg/l = milligrams per liter					


Southeast County Landfill

Groundwater and Surface Water Elevations

July 2, 2014

Measuring Point	T.O.C. Elevations	W.L.	W.L.	Time
I.D.	(NGVD)	B.T.O.C.	(NGVD)	
P-4D	140.78	22.32	118.46	11:22 AM
P-4S	140.95	10.29	130.66	11:25 AM
P-5D	151.94	Dry	Dry	9:22 AM
P-6D-A	148.01	25.65	122.36	9:31 AM
P-7D	138.92	17.14	121.78	10:27 AM
P-8D	138.34	17.82	120.52	11:39 AM
P-11D	138.02	17.14	120.88	11:36 AM
P-12S	134.97	13.84	121.13	11:42 AM
P-13S	140.21	18.25	121.96	10:49 AM
P-14S	138.56	16.46	122.10	10:44 AM
P-15S	139.19	17.37	121.82	10:35 AM
P-16S	143.38	15.73	127.65	10:17 AM
P-16I	144.15	23.48	120.67	10:16 AM
P-16D	143.84	23.19	120.65	10:15 AM
P-17S	137.35	12.72	124.63	9:47 AM
P-17I	137.32	15.52	121.80	9:48 AM
P-17D	137.22	15.70	121.52	9:50 AM
P-18S	129.86	18.08	111.78	8:57 AM
P-19	133.36	10.93	122.43	9:26 AM
P-20	132.38	11.65	120.73	9:37 AM
P-21	122.79	2.88	119.91	11:03 AM
P-22	128.35	8.35	120.00	11:05 AM
P-23	143.13	23.00	120.13	11:09 AM
TH-19*	130.27	98.81	31.46	10:05 AM
TH-20A	131.86	9.32	122.54	12:04 PM
TH-20B	132.57	10.20	122.37	12:06 PM
TH-22	128.82	5.11	123.71	12:17 PM
TH-22A	129.27	5.75	123.52	12:15 PM
TH-24A	128.23	5.15	123.08	12:09 PM
TH-28A	131.10	28.22	102.88	8:27 AM
TH-30	128.88	23.98	104.90	8:40 AM
TH-32	129.90	14.66	115.24	9:02 AM
TH-35	145.98	28.19	117.79	9:58 AM
TH-36A	152.70	32.84	119.86	10:09 AM
TH-38A	130.68	10.09	120.59	11:56 AM
TH-38B	131.81	13.98	117.83	11:58 AM
TH-40*	124.99	93.65	31.34	8:16 AM
TH-41*	125.00	98.54	26.46	8:19 AM
TH-42*	116.74	75.27	41.47	9:06 AM
TH-57	128.36	18.92	109.44	8:23 AM
TH-58	127.88	27.95	99.93	8:36 AM
TH-61	138.73	16.95	121.78	10:52 AM
TH-61A	139.45	17.50	121.95	10:54 AM
TH-64	139.64	16.80	122.84	10:47 AM
TH-65	135.40	14.24	121.16	11:48 AM
TH-66	130.58	8.53	122.05	11:51 AM
TH-66A	130.66	8.97	121.69	11:53 AM
TH-67	129.51	5.92	123.59	11:59 AM
TH-68	140.01	17.65	122.36	10:29 AM
TH-69A	144.97	25.34	119.63	11:33 AM
TH-70A	146.63	25.94	120.69	11:29 AM
TH-71A	146.95	26.54	120.41	11:15 AM
TH-72*	130.96	97.64	33.32	8:33 AM
TH-73	131.07	30.85	100.22	8:30 AM
TH-74	109.08	9.63	99.45	12:28 PM
TH-75	106.92	7.93	98.99	12:30 PM
TH-76*	111.21	77.98	33.23	10:08 AM
TH-77*	119.88	86.40	33.48	10:04 AM
TH-78*	120.75	ND	ND	10:18 AM
SW-3A	3.0'=125.53'	0.70	123.23	8:10 AM
SW-3B2B	3.0'=97.97'	Dry	Dry	8:46 AM
SW-3C2	6.0'=92.33'	1.16	87.49	8:51 AM
Mine Cut #1	4.0'=122.14'	2.36	120.50	10:32 AM
Mine Cut #2	6.0'=123.47'	2.63	120.10	10:02 AM
Mine Cut #3	4.0'=112.27'	2.34	110.61	9:10 AM
Mine Cut #4	5.0'=97.54'	1.34	93.88	9:16 AM
NGVD = National Geodetic Vertical Datum				
T.O.C. = Top of Casing				
B.T.O.C. = Below Top of Casing				
* = Floridan Well				
ND = No Data - Potential Error in Survey				
W.L. = Water Level				





JULY 2014
 UPPER FLORIDAN / LIMESTONE AQUIFER CONTOUR DIAGRAM
 IN THE VICINITY OF THE FORMER SINKHOLE
 SOUTHEAST COUNTY LANDFILL
 HILLSBOROUGH COUNTY, FLORIDA

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-72

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm)	dissolved oxygen (mg/l)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
01/27/2011	115.69	15.27	551	0.39	7.43	22.88	3.2	320	32	0.22	0.004 u	0.52	32
02/03/2011	112.18	18.78	565	1.09	7.38	22.95	9.9	300	32	0.21	0.004 u	0.62	27
02/10/2011	109.80	21.16	514	1.58	7.34	22.65	3.2	340	31	0.28	0.004 u	0.54	31
02/14/2011	108.18	22.78	483	1.15	7.36	22.7	3.5	320	32	0.24	0.0013 u	0.58	32
02/24/2011	111.71	19.25	513	0.19	7.34	22.85	1	350	32	0.22	0.004 u	0.53	31
03/03/2011	111.88	19.08	579	0.77	7.35	22.8	0.8	330	31	0.23	0.004 u	0.43	32
03/10/2011	113.65	17.31	551	1.26	7.41	22.73	0.9	320	30	0.18	0.004 u	0.35	31
03/17/2011	112.85	18.11	388	1.05	7.34	22.9	0.9	330	30	0.31	0.004 u	0.25	31
03/24/2011	114.33	16.63	1192	1.5	7.58	23.1	1.5	1,100	350	9	0.004 u	0.64	130
04/01/2011	115.70	15.26	928	0.16	7.41	22.8	3.6	520	110	2	0.004 u	0.24	59
04/08/2011	112.10	18.86	810	0.92	7.35	23.13	6.1	420	87	1.9	0.004 u	0.22	51
05/05/2011	116.21	14.75	609	0.71	7.67	23.01	6.6	320	33	0.3	0.004 u	0.27	37
06/03/2011	119.19	11.77	607	0.71	7.65	23.35	4.51	340	32	0.57	0.004 u	0.2	34
07/07/2011	113.30	17.66	606	0.72	7.4	23.25	3.94	150	64	2.1	0.004 u	7.9	27
08/04/2011	103.31	27.65	564	0.33	7.29	23.18	0.4	380	33	0.21	0.004 u	0.18	34
09/09/2011	97.99	32.97	536	1.11	7.29	23.2	0.6	340	34	0.41	0.004 u	0.18	36
10/04/2011	99.45	31.51	471	1.89	7.31	23.13	1.1	290	31	0.3	0.004 u	0.14	34
11/03/2011	103.37	27.59	550	1.8	7.28	23.04	1.51	290	32	0.29	0.004 u	0.15	34
12/08/2011	106.80	24.16	528	1.92	7.31	22.9	0.73	320	29	0.32	0.004 u	0.13	33
01/05/2012	113.08	17.88	535	0.2	7.23	22.74	0.44	330	32	0.29	0.004 u	0.097	31
02/10/2012	113.86	17.10	511	0.94	7.3	22.89	1.39	310	28	0.28	0.004 u	0.13	30
03/07/2012	121.00	9.96	575	0.27	7.15	23.23	0.5	310	25	0.22	0.004 u	0.11	31
04/05/2012	124.96	6.00	522	1.09	7.08	23.18	0.65	280	28	0.41	0.004 u	0.11	29
05/03/2012	126.55	4.41	746	1.6	6.9	23.46	0.81	380	72	2.3	0.004 u	0.54	49
06/07/2012	120.46	10.50	641	0.72	7.07	23.4	0.26	370	46	1	0.004 u	0.23	37
07/05/2012	104.95	26.01	900	0.23	6.54	23.52	0.4	650	190	2.9	0.004 u	0.39	70
08/03/2012	98.26	32.70	843	0.89	6.77	23.6	2.23	730	210	3	0.004 u	0.48	78
09/06/2012	91.18	39.66	2,357	0.2	6.51	23.62	1.05	1,300	570	12	0.004 u	1.1	170
10/04/2012	90.19	40.77	1,654	0.6	6.43	23.22	0.46	1,500	650	25	0.004 u	1.9	210
11/07/2012	99.29	31.67	2,488	0.76	6.58	23.03	0.74	1,400	540	15	0.004 u	1.4	180
12/05/2012	101.82	29.14	2,416	0.23	6.49	23.18	0.45	1,300	540	13	0.004 u	1.3	180
01/03/2013	100.65	30.31	2,430	1.1	6.44	23.09	0.42	1,400	500	15	0.004 u	1.3	170
02/07/2013	105.58	25.38	2,206	0.6	6.5	23.1	0.22	1,100	470	13	0.004 u	1.1	160
03/07/2013	110.00	20.96	1,234	0.3	6.61	22.85	0.41	770	290	11	0.004 u	1.1	110
04/04/2013	111.35	19.61	1,252	0.33	6.74	23.15	0.9	870	260	10	0.004 u	1	100
05/02/2013	109.56	21.40	1,615	0.18	6.83	23.16	0.45	810	300	8.6	0.004 u	0.87	110
06/04/2013	109.62	21.34	1,440	0.31	7.13	23.3	0.27	850	290	8.4	0.004 u	0.82	120
07/03/2013	98.72	32.24	1,450	0.18	7.03	23.5	0.41	820	280	8.8	0.004 u	0.79	120
08/02/2013	ND	ND	1,256	0.46	6.88	23.43	0.2	800	290	6.8	0.004 u	0.72	120
09/05/2013	87.92	43.04	1,001	0.61	6.98	23.45	1.17	760	290	7.6	0.004 u	0.71	110
10/02/2013	87.39	43.57	1,568	0.32	6.86	23.53	12.6	1,000	350	7.4	0.004 u	0.79	120
11/06/2013	97.90	33.06	2,145	0.16	6.69	23.36	0.8	1,200	450	12	0.004 u	0.64	170
12/05/2013	98.50	32.46	2,615	0.39	6.74	23.45	0.58	1,200	580	16	0.004 u	0.65	200
01/03/2014	99.02	31.94	2,220	0.84	6.83	22.88	1.64	1,200	580	25	0.004 u	0.67	230
02/06/2014	99.50	31.46	2,452	0.13	6.69	23.13	2.07	1,300	580	23.3	0.004 u	0.71	210
03/04/2014	97.91	33.05	2,173	0.24	6.67	23.4	1.33	1,500	580	22	0.004 u	0.74	220
04/03/2014	96.22	34.74	1,992	0.22	6.74	23.35	1.33	1,400	590	27	0.0013 u	0.71	220
05/06/2014	100.22	30.74	2,247	0.46	6.81	23.5	1.22	1,400	590	24	0.004 u	0.64	230
06/03/2014	102.58	28.38	2,771	0.34	6.45	23.46	0.96	1,400	570	27	0.004 u	0.73	220

New survey data beginning with 10/4/2012.

u = parameter was analyzed but not detected

i = reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.

j3 = estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.

ND = No Data - water levels collected during quarterly ADR.

1,100 EXCEEDS STANDARD

**Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-76**

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
05/02/2013	89.83	21.38	450	0.22	7.63	22.81	36.9	220	13	0.4	0.004 u	1.1	20
06/04/2013	89.91	21.30	401	0.27	7.86	22.9	16.2	240	13	0.4	0.004 u	0.66	22
07/03/2013	79.04	32.17	398	0.19	8	23	28.6	210	12	0.34	0.004 u	0.99	22
08/02/2013	ND	ND	343	0.22	7.57	23.02	42.2	230	13	0.26	0.004 u	1.6	21
09/05/2013	68.22	42.99	278	0.21	7.74	22.97	46	240	12	0.32	0.004 u	1.5	20
10/02/2013	67.69	43.46	399	0.22	7.61	22.99	61.9	120	13	0.38	0.004 u	1.7	20
11/06/2013	78.19	33.02	446	0.64	7.54	22.84	29	260	13	0.36	0.004 u	1.1	20
12/05/2013	78.80	32.41	478	0.48	7.45	22.9	19.2	240	12	0.35	0.004 u	0.96	20
01/03/2014	79.38	31.83	398	0.58	7.67	22.35	19.4	190	12	0.23	0.004 u	1.1	20
02/06/2014	79.87	31.34	446	0.14	7.54	22.57	18.1	230	12	0.45	0.004 u	0.96	20
03/04/2014	78.20	33.01	434	0.18	7.36	22.7	26.2	230	12	0.33	0.004 u	0.69	20
04/03/2014	76.54	34.67	441	0.18	7.46	22.82	24.7	210	12	0.6	0.0013 u	0.34	19
05/06/2014	80.52	30.69	427	0.24	7.56	22.85	12.7	220	12	0.38	0.004 u	0.65	21
06/03/2014	82.85	28.36	423	0.3	7.47	22.82	16.8	240	12	0.47	0.004 u	0.64	20

u = parameter was analyzed but not detected

ND = No Data - water levels collected during quarterly ADR.

1.1

EXCEEDS STANDARD

Hillsborough County Southeast Landfill
Laboratory Analytical Results from IAMP Groundwater Monitoring
TH-77

Date	Depth to Water (feet)	Water Table Elevation (NGVD)	conductivity (umhos/cm) (field)	dissolved oxygen (mg/l) (field)	pH (field)	temperature (°C) (field)	turbidity (NTU) (field)	total dissolved solids (mg/l)	chloride (mg/l)	ammonia nitrogen (mg/l as N)	arsenic (mg/l)	iron (mg/l)	sodium (mg/l)
05/02/2013	98.31	21.57	440	0.57	7.39	23.39	59.4	190	9.4	0.39	0.004 u	1.2	17
06/04/2013	98.38	21.50	384	0.56	7.86	23.59	35.4	230	8.9	0.42	0.004 u	0.89	18
07/03/2013	87.48	32.40	388	0.41	7.8	23.7	38.4	210	8.9	0.4	0.004 u	1.1	17
08/02/2013	ND	ND	334	0.47	7.44	23.66	42.9	230	9.2	0.36	0.004 u	1.1	18
09/05/2013	76.66	43.22	269	0.83	7.61	23.68	47.1	230	8.9	0.35	0.004 u	0.96	16
10/02/2013	76.14	43.72	383	0.69	7.5	23.59	52.7	240	9.1	0.39	0.004 u	1.3	17
11/06/2013	86.68	33.20	423	0.74	7.43	23.51	25.1	230	9.7	0.36 j3	0.004 u	0.68	17
12/05/2013	87.29	32.59	451	0.9	7.44	23.6	16.4	220	9	0.36	0.004 u	0.58	17
01/03/2014	87.87	32.01	371	0.85	7.65	23.18	16.5	160	9.1	0.39	0.004 u	0.63	17
02/06/2014	88.30	31.58	424	0.09	7.53	23.39	4.62	250	9.2	0.27	0.004 u	0.26	16
03/04/2014	86.70	33.18	418	0.36	7.34	23.38	1.12	230	9.3	0.32	0.004 u	0.21	16
04/03/2014	85.02	34.86	430	0.28	7.45	23.47	1.97	220	9.4	0.61	0.0013 u	0.18	15
05/06/2014	89.02	30.86	414	0.34	7.52	23.47	1.01	220	9.7	0.59	0.004 u	0.19	17
06/03/2014	91.34	28.54	464	0.27	7.47	23.49	0.88	230	9.7	0.75	0.004 u	0.19	17

u = parameter was analyzed but not detected

j3 = estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.

ND = No Data - water levels collected during quarterly ADR.

1.2 EXCEEDS STANDARD

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.

TestAmerica Tampa
6712 Benjamin Road
Suite 100
Tampa, FL 33634
Tel: (813)885-7427

TestAmerica Job ID: 660-61477-1

Client Project/Site: SELF-IAMP Monitoring Wells

For:

Hillsborough Co Public Utilities Dept
Environmental Services Group
Brandon Support Operations Complex
332 North Falkenburg Rd, 2nd Floor
Tampa, Florida 33619

Attn: David Adams



Authorized for release by:
7/17/2014 12:16:54 PM

Nancy Robertson, Project Manager II
(813)885-7427
nancy.robertson@testamericainc.com

LINKS

Review your project
results through
TotalAccess

Have a Question?



Visit us at:
www.testamericainc.com

The test results in this report meet all 2003 NELAC and 2009 TNI requirements for accredited parameters, exceptions are noted in this report. This report may not be reproduced except in full, and with written approval from the laboratory. For questions please contact the Project Manager at the e-mail address or telephone number listed on this page.

This report has been electronically signed and authorized by the signatory. Electronic signature is intended to be the legally binding equivalent of a traditionally handwritten signature.

Results relate only to the items tested and the sample(s) as received by the laboratory.



Table of Contents

Cover Page	1
Table of Contents	2
Sample Summary	3
Case Narrative	4
Definitions/Glossary	5
Detection Summary	6
Client Sample Results	8
QC Sample Results	14
QC Association Summary	19
Lab Chronicle	22
Method Summary	24
Certification Summary	25
Chain of Custody	27
Receipt Checklists	37

Sample Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
660-61477-1	BLANK FIELD	Ground Water	07/02/14 11:40	07/02/14 15:40
660-61477-2	TH-78	Water	07/02/14 11:59	07/02/14 15:40
660-61500-1	DUPLICATE NOT BLANK	Ground Water	07/03/14 00:00	07/03/14 15:20
660-61500-2	TH-72	Water	07/03/14 12:50	07/03/14 15:20
660-61500-3	TH-76	Water	07/03/14 11:30	07/03/14 15:20
660-61500-4	TH-77	Water	07/03/14 10:22	07/03/14 15:20

Case Narrative

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Job ID: 660-61477-1

Laboratory: TestAmerica Tampa

Narrative

Job Narrative 660-61477-1

Comments

No additional comments.

Receipt

The samples were received on 7/2/2014 3:40 PM and 7/3/2014 3:20 PM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperatures of the 2 coolers at receipt time were 2.9° C and 3.0° C.

Metals

Method 6020A: The method blank for batch 337901 contained iron above the method detection limit (MDL). Associated samples were not re-analyzed because results were less than the reporting limit (RL) OR practical quantitation limit (PQL).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

General Chemistry

Method 350.1: The field blank for batch 338037 contained NH₃ above the method detection limit (MDL). Re-analysis confirmed the result.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

Definitions/Glossary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Qualifiers

HPLC/IC

Qualifier	Qualifier Description
U	Indicates that the compound was analyzed for but not detected.

Metals

Qualifier	Qualifier Description
J3	Estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
U	Indicates that the compound was analyzed for but not detected.
I	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.

General Chemistry

Qualifier	Qualifier Description
J3	Estimated value; value may not be accurate. Spike recovery or RPD outside of criteria.
U	Indicates that the compound was analyzed for but not detected.
I	The reported value is between the laboratory method detection limit and the laboratory practical quantitation limit.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
α	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Detection Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: BLANK FIELD

Lab Sample ID: 660-61477-1

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Ammonia as N	0.029	I	0.050	0.026	mg/L	1		350.1	Total/NA

Client Sample ID: TH-78

Lab Sample ID: 660-61477-2

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	43		1.0	0.50	mg/L	2		300.0	Total/NA
Arsenic	1.9	I	2.5	1.3	ug/L	1		6020A	Total Recoverable
Iron	1000		100	33	ug/L	1		6020A	Total Recoverable
Sodium	38		0.50	0.25	mg/L	1		6020A	Total Recoverable
Ammonia as N	0.44		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	210		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	9.08				SU	1		Field Sampling	Total/NA
Field Temperature	23.89				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.41				mg/L	1		Field Sampling	Total/NA
Specific Conductance	363				uS/cm	1		Field Sampling	Total/NA
Turbidity	19.3				NTU	1		Field Sampling	Total/NA

Client Sample ID: DUPLICATE NOT BLANK

Lab Sample ID: 660-61500-1

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	580		10	5.0	mg/L	20		300.0	Total/NA
Iron	700		200	50	ug/L	1		6010B	Total Recoverable
Sodium	220		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	26		1.0	0.52	mg/L	20		350.1	Total/NA
Total Dissolved Solids	1300		50	50	mg/L	1		SM 2540C	Total/NA

Client Sample ID: TH-72

Lab Sample ID: 660-61500-2

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	570		10	5.0	mg/L	20		300.0	Total/NA
Iron	720		200	50	ug/L	1		6010B	Total Recoverable
Sodium	220		0.50	0.31	mg/L	1		6010B	Total Recoverable
Ammonia as N	24		1.0	0.52	mg/L	20		350.1	Total/NA
Total Dissolved Solids	1300		50	50	mg/L	1		SM 2540C	Total/NA
Field pH	6.86				SU	1		Field Sampling	Total/NA
Field Temperature	23.54				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.29				mg/L	1		Field Sampling	Total/NA
Specific Conductance	2388				uS/cm	1		Field Sampling	Total/NA
Turbidity	1.34				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-76

Lab Sample ID: 660-61500-3

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	12		0.50	0.25	mg/L	1		300.0	Total/NA

This Detection Summary does not include radiochemical test results.

TestAmerica Tampa

Detection Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-76 (Continued)

Lab Sample ID: 660-61500-3

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Iron	200		200	50	ug/L	1		6010B	Total
									Recoverable
Sodium	20		0.50	0.31	mg/L	1		6010B	Total
									Recoverable
Ammonia as N	0.49		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	230		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	7.46				SU	1		Field Sampling	Total/NA
Field Temperature	22.83				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.30				mg/L	1		Field Sampling	Total/NA
Specific Conductance	421				uS/cm	1		Field Sampling	Total/NA
Turbidity	19.5				NTU	1		Field Sampling	Total/NA

Client Sample ID: TH-77

Lab Sample ID: 660-61500-4

Analyte	Result	Qualifier	PQL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	9.6		0.50	0.25	mg/L	1		300.0	Total/NA
Iron	140	I	200	50	ug/L	1		6010B	Total
									Recoverable
Sodium	17		0.50	0.31	mg/L	1		6010B	Total
									Recoverable
Ammonia as N	0.48		0.050	0.026	mg/L	1		350.1	Total/NA
Total Dissolved Solids	230		10	10	mg/L	1		SM 2540C	Total/NA
Field pH	7.44				SU	1		Field Sampling	Total/NA
Field Temperature	23.65				Degrees C	1		Field Sampling	Total/NA
Oxygen, Dissolved	0.34				mg/L	1		Field Sampling	Total/NA
Specific Conductance	409				uS/cm	1		Field Sampling	Total/NA
Turbidity	1.56				NTU	1		Field Sampling	Total/NA

This Detection Summary does not include radiochemical test results.

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: BLANK FIELD

Lab Sample ID: 660-61477-1

Date Collected: 07/02/14 11:40

Matrix: Ground Water

Date Received: 07/02/14 15:40

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			07/07/14 15:24	1

Method: 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	1.3	U	2.5	1.3	ug/L		07/07/14 12:49	07/08/14 12:13	1
Iron	33	U	100	33	ug/L		07/07/14 12:49	07/08/14 12:13	1
Sodium	0.25	U	0.50	0.25	mg/L		07/07/14 12:49	07/08/14 12:13	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.029	I	0.050	0.026	mg/L			07/07/14 15:43	1
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L			07/08/14 11:55	1

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-78

Date Collected: 07/02/14 11:59

Date Received: 07/02/14 15:40

Lab Sample ID: 660-61477-2

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	43		1.0	0.50	mg/L			07/07/14 15:39	2

Method: 6020A - Metals (ICP/MS) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	1.9	I	2.5	1.3	ug/L		07/07/14 12:49	07/08/14 12:21	1
Iron	1000		100	33	ug/L		07/07/14 12:49	07/08/14 12:21	1
Sodium	38		0.50	0.25	mg/L		07/07/14 12:49	07/08/14 12:21	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.44		0.050	0.026	mg/L			07/07/14 14:24	1
Total Dissolved Solids	210		10	10	mg/L			07/08/14 11:55	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	9.08				SU			07/02/14 11:59	1
Field Temperature	23.89				Degrees C			07/02/14 11:59	1
Oxygen, Dissolved	0.41				mg/L			07/02/14 11:59	1
Specific Conductance	363				uS/cm			07/02/14 11:59	1
Turbidity	19.3				NTU			07/02/14 11:59	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: DUPLICATE NOT BLANK

Lab Sample ID: 660-61500-1

Date Collected: 07/03/14 00:00

Matrix: Ground Water

Date Received: 07/03/14 15:20

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	580		10	5.0	mg/L			07/09/14 18:31	20

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		07/08/14 06:30	07/08/14 09:42	1
Iron	700		200	50	ug/L		07/08/14 06:30	07/08/14 09:42	1
Sodium	220		0.50	0.31	mg/L		07/08/14 06:30	07/08/14 09:42	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	26		1.0	0.52	mg/L			07/09/14 16:30	20
Total Dissolved Solids	1300		50	50	mg/L			07/10/14 15:39	1

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-72

Date Collected: 07/03/14 12:50

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-2

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	570		10	5.0	mg/L			07/09/14 18:46	20

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		07/08/14 06:30	07/08/14 09:55	1
Iron	720		200	50	ug/L		07/08/14 06:30	07/08/14 09:55	1
Sodium	220		0.50	0.31	mg/L		07/08/14 06:30	07/08/14 09:55	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	24		1.0	0.52	mg/L			07/09/14 16:30	20
Total Dissolved Solids	1300		50	50	mg/L			07/10/14 15:39	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	6.86				SU			07/03/14 12:50	1
Field Temperature	23.54				Degrees C			07/03/14 12:50	1
Oxygen, Dissolved	0.29				mg/L			07/03/14 12:50	1
Specific Conductance	2388				uS/cm			07/03/14 12:50	1
Turbidity	1.34				NTU			07/03/14 12:50	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-76

Date Collected: 07/03/14 11:30

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-3

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	12		0.50	0.25	mg/L			07/09/14 19:02	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		07/08/14 06:30	07/08/14 09:59	1
Iron	200		200	50	ug/L		07/08/14 06:30	07/08/14 09:59	1
Sodium	20		0.50	0.31	mg/L		07/08/14 06:30	07/08/14 09:59	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.49		0.050	0.026	mg/L			07/09/14 12:04	1
Total Dissolved Solids	230		10	10	mg/L			07/10/14 15:39	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.46				SU			07/03/14 11:30	1
Field Temperature	22.83				Degrees C			07/03/14 11:30	1
Oxygen, Dissolved	0.30				mg/L			07/03/14 11:30	1
Specific Conductance	421				uS/cm			07/03/14 11:30	1
Turbidity	19.5				NTU			07/03/14 11:30	1

TestAmerica Tampa

Client Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-77

Date Collected: 07/03/14 10:22

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-4

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	9.6		0.50	0.25	mg/L			07/09/14 19:48	1

Method: 6010B - Metals (ICP) - Total Recoverable

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		07/08/14 06:30	07/08/14 10:02	1
Iron	140	I	200	50	ug/L		07/08/14 06:30	07/08/14 10:02	1
Sodium	17		0.50	0.31	mg/L		07/08/14 06:30	07/08/14 10:02	1

General Chemistry

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as N	0.48		0.050	0.026	mg/L			07/09/14 12:04	1
Total Dissolved Solids	230		10	10	mg/L			07/10/14 15:39	1

Method: Field Sampling - Field Sampling

Analyte	Result	Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Field pH	7.44				SU			07/03/14 10:22	1
Field Temperature	23.65				Degrees C			07/03/14 10:22	1
Oxygen, Dissolved	0.34				mg/L			07/03/14 10:22	1
Specific Conductance	409				uS/cm			07/03/14 10:22	1
Turbidity	1.56				NTU			07/03/14 10:22	1

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 680-337926/13

Matrix: Water

Analysis Batch: 337926

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			07/07/14 13:43	1

Lab Sample ID: LCS 680-337926/14

Matrix: Water

Analysis Batch: 337926

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	10.0	9.83		mg/L		98	90 - 110

Lab Sample ID: LCSD 680-337926/15

Matrix: Water

Analysis Batch: 337926

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	10.0	9.84		mg/L		98	90 - 110	0	30

Lab Sample ID: 660-61457-I-1 MS

Matrix: Water

Analysis Batch: 337926

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	6.2		10.0	16.5		mg/L		104	80 - 120

Lab Sample ID: 660-61457-I-1 MSD

Matrix: Water

Analysis Batch: 337926

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	6.2		10.0	16.1		mg/L		99	80 - 120	3	30

Lab Sample ID: MB 680-338282/5

Matrix: Water

Analysis Batch: 338282

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.25	U	0.50	0.25	mg/L			07/09/14 13:53	1

Lab Sample ID: LCS 680-338282/6

Matrix: Water

Analysis Batch: 338282

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	10.0	10.0		mg/L		100	90 - 110

Lab Sample ID: LCSD 680-338282/7

Matrix: Water

Analysis Batch: 338282

Client Sample ID: Lab Control Sample Dup

Prep Type: Total/NA

Analyte	Spike Added	LCSD Result	LCSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	10.0	10.0		mg/L		100	90 - 110	0	30

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Lab Sample ID: 660-61500-3 MS

Matrix: Water

Analysis Batch: 338282

Client Sample ID: TH-76

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	12		10.0	22.0		mg/L		100	80 - 120

Lab Sample ID: 660-61500-3 MSD

Matrix: Water

Analysis Batch: 338282

Client Sample ID: TH-76

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Chloride	12		10.0	21.8		mg/L		97	80 - 120	1	30

Method: 6010B - Metals (ICP)

Lab Sample ID: MB 660-149588/1-A

Matrix: Water

Analysis Batch: 149606

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 149588

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	4.0	U	10	4.0	ug/L		07/08/14 06:30	07/08/14 09:32	1
Iron	50	U	200	50	ug/L		07/08/14 06:30	07/08/14 09:32	1
Sodium	0.31	U	0.50	0.31	mg/L		07/08/14 06:30	07/08/14 09:32	1

Lab Sample ID: LCS 660-149588/2-A

Matrix: Water

Analysis Batch: 149606

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 149588

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	1000	1040		ug/L		104	80 - 120
Iron	1000	1020		ug/L		102	80 - 120
Sodium	10.0	10.4		mg/L		104	80 - 120

Lab Sample ID: 660-61500-1 MS

Matrix: Ground Water

Analysis Batch: 149606

Client Sample ID: DUPLICATE NOT BLANK

Prep Type: Total Recoverable

Prep Batch: 149588

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	4.0	U	1000	1080		ug/L		108	80 - 120
Iron	700		1000	1690		ug/L		99	80 - 120
Sodium	220		10.0	234	J3	mg/L		130	80 - 120

Lab Sample ID: 660-61500-1 MSD

Matrix: Ground Water

Analysis Batch: 149606

Client Sample ID: DUPLICATE NOT BLANK

Prep Type: Total Recoverable

Prep Batch: 149588

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Arsenic	4.0	U	1000	1090		ug/L		109	80 - 120	0	20
Iron	700		1000	1710		ug/L		101	80 - 120	1	20
Sodium	220		10.0	233	J3	mg/L		123	80 - 120	0	20

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Method: 6020A - Metals (ICP/MS)

Lab Sample ID: MB 680-337901/1-A

Matrix: Water

Analysis Batch: 338259

Client Sample ID: Method Blank

Prep Type: Total Recoverable

Prep Batch: 337901

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Arsenic	1.3	U	2.5	1.3	ug/L		07/07/14 12:49	07/08/14 10:53	1
Iron	70.4	I	100	33	ug/L		07/07/14 12:49	07/08/14 10:53	1
Sodium	0.25	U	0.50	0.25	mg/L		07/07/14 12:49	07/08/14 10:53	1

Lab Sample ID: LCS 680-337901/2-A

Matrix: Water

Analysis Batch: 338259

Client Sample ID: Lab Control Sample

Prep Type: Total Recoverable

Prep Batch: 337901

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	100	104		ug/L		104	75 - 125
Iron	5000	5220		ug/L		104	75 - 125
Sodium	5.00	5.13		mg/L		103	75 - 125

Lab Sample ID: 660-61467-A-1-B MS

Matrix: Water

Analysis Batch: 338259

Client Sample ID: Matrix Spike

Prep Type: Total Recoverable

Prep Batch: 337901

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Arsenic	1.3	U	100	98.7		ug/L		99	75 - 125
Iron	33	U	5000	5160		ug/L		103	75 - 125
Sodium	63		5.00	87.0	J3	mg/L		472	75 - 125

Lab Sample ID: 660-61467-A-1-C MSD

Matrix: Water

Analysis Batch: 338259

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total Recoverable

Prep Batch: 337901

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Arsenic	1.3	U	100	93.8		ug/L		94	75 - 125	5	20
Iron	33	U	5000	4550		ug/L		91	75 - 125	13	20
Sodium	63		5.00	78.5	J3	mg/L		303	75 - 125	10	20

Method: 350.1 - Nitrogen, Ammonia

Lab Sample ID: MB 680-338037/5

Matrix: Water

Analysis Batch: 338037

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as v	0.026	U	0.050	0.026	mg/L			07/07/14 11:37	1

Lab Sample ID: LCS 680-338037/42

Matrix: Water

Analysis Batch: 338037

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as v	1.00	1.00		mg/L		100	90 - 110

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Method: 350.1 - Nitrogen, Ammonia (Continued)

Lab Sample ID: 640-48413-K-2 MS

Matrix: Water

Analysis Batch: 338037

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as v	0.091		1.00	1.19		mg/L		110	90 - 110

Lab Sample ID: 640-48413-K-2 MSD

Matrix: Water

Analysis Batch: 338037

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as v	0.091		1.00	1.20	J3	mg/L		111	90 - 110	1	30

Lab Sample ID: 640-48413-K-1 DU

Matrix: Water

Analysis Batch: 338037

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Ammonia as v	0.11		0.115		mg/L		5	30

Lab Sample ID: MB 680-338405/12

Matrix: Water

Analysis Batch: 338405

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Ammonia as v	0.026	U	0.050	0.026	mg/L			07/09/14 13:23	1

Lab Sample ID: LCS 680-338405/14

Matrix: Water

Analysis Batch: 338405

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as v	1.00	1.01		mg/L		101	90 - 110

Lab Sample ID: 660-61495-A-3 MS

Matrix: Water

Analysis Batch: 338405

Client Sample ID: Matrix Spike

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Ammonia as v	0.11		1.00	1.23	J3	mg/L		113	90 - 110

Lab Sample ID: 660-61495-A-3 MSD

Matrix: Water

Analysis Batch: 338405

Client Sample ID: Matrix Spike Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MSD Result	MSD Qualifier	Unit	D	%Rec	%Rec. Limits	RPD	RPD Limit
Ammonia as v	0.11		1.00	1.22	J3	mg/L		112	90 - 110	1	30

Lab Sample ID: 660-61500-2 DU

Matrix: Water

Analysis Batch: 338405

Client Sample ID: TH-72

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Ammonia as v	24		24.0		mg/L		1	30

TestAmerica Tampa

QC Sample Results

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Method: SM 2540C - Solids, Total Dissolved (TDS)

Lab Sample ID: MB 660-149607/1

Matrix: Water

Analysis Batch: 149607

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L	-		07/08/14 11:55	1

Lab Sample ID: LCS 660-149607/2

Matrix: Water

Analysis Batch: 149607

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Dissolved Solids	10000	9860		mg/L	-	99	80 - 120

Lab Sample ID: 640-48434-A-2 DU

Matrix: Water

Analysis Batch: 149607

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Total Dissolved Solids	1200		1120		mg/L	-	4	20

Lab Sample ID: MB 660-149706/1

Matrix: Water

Analysis Batch: 149706

Client Sample ID: Method Blank

Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	PQL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Total Dissolved Solids	5.0	U	5.0	5.0	mg/L	-		07/10/14 15:39	1

Lab Sample ID: LCS 660-149706/2

Matrix: Water

Analysis Batch: 149706

Client Sample ID: Lab Control Sample

Prep Type: Total/NA

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Total Dissolved Solids	10000	9910		mg/L	-	99	80 - 120

Lab Sample ID: 640-48498-J-2 DU

Matrix: Water

Analysis Batch: 149706

Client Sample ID: Duplicate

Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Total Dissolved Solids	290		328		mg/L	-	13	20

TestAmerica Tampa

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

HPLC/IC

Analysis Batch: 337926

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61457-I-1 MS	Matrix Spike	Total/NA	Water	300.0	
660-61457-I-1 MSD	Matrix Spike Duplicate	Total/NA	Water	300.0	
660-61477-1	BLANK FIELD	Total/NA	Ground Water	300.0	
660-61477-2	TH-78	Total/NA	Water	300.0	
LCS 680-337926/14	Lab Control Sample	Total/NA	Water	300.0	
LCSD 680-337926/15	Lab Control Sample Dup	Total/NA	Water	300.0	
MB 680-337926/13	Method Blank	Total/NA	Water	300.0	

Analysis Batch: 338282

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61500-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	300.0	
660-61500-2	TH-72	Total/NA	Water	300.0	
660-61500-3	TH-76	Total/NA	Water	300.0	
660-61500-3 MS	TH-76	Total/NA	Water	300.0	
660-61500-3 MSD	TH-76	Total/NA	Water	300.0	
660-61500-4	TH-77	Total/NA	Water	300.0	
LCS 680-338282/6	Lab Control Sample	Total/NA	Water	300.0	
LCSD 680-338282/7	Lab Control Sample Dup	Total/NA	Water	300.0	
MB 680-338282/5	Method Blank	Total/NA	Water	300.0	

Metals

Prep Batch: 149588

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61500-1	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	3005A	
660-61500-1 MS	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	3005A	
660-61500-1 MSD	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	3005A	
660-61500-2	TH-72	Total Recoverable	Water	3005A	
660-61500-3	TH-76	Total Recoverable	Water	3005A	
660-61500-4	TH-77	Total Recoverable	Water	3005A	
LCS 660-149588/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
MB 660-149588/1-A	Method Blank	Total Recoverable	Water	3005A	

Analysis Batch: 149606

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61500-1	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	6010B	149588
660-61500-1 MS	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	6010B	149588
660-61500-1 MSD	DUPLICATE NOT BLANK	Total Recoverable	Ground Water	6010B	149588
660-61500-2	TH-72	Total Recoverable	Water	6010B	149588
660-61500-3	TH-76	Total Recoverable	Water	6010B	149588
660-61500-4	TH-77	Total Recoverable	Water	6010B	149588
LCS 660-149588/2-A	Lab Control Sample	Total Recoverable	Water	6010B	149588
MB 660-149588/1-A	Method Blank	Total Recoverable	Water	6010B	149588

Prep Batch: 337901

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61467-A-1-B MS	Matrix Spike	Total Recoverable	Water	3005A	
660-61467-A-1-C MSD	Matrix Spike Duplicate	Total Recoverable	Water	3005A	
660-61477-1	BLANK FIELD	Total Recoverable	Ground Water	3005A	
660-61477-2	TH-78	Total Recoverable	Water	3005A	

TestAmerica Tampa

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Metals (Continued)

Prep Batch: 337901 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
LCS 680-337901/2-A	Lab Control Sample	Total Recoverable	Water	3005A	
MB 680-337901/1-A	Method Blank	Total Recoverable	Water	3005A	

Analysis Batch: 338259

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61467-A-1-B MS	Matrix Spike	Total Recoverable	Water	6020A	337901
660-61467-A-1-C MSD	Matrix Spike Duplicate	Total Recoverable	Water	6020A	337901
660-61477-1	BLANK FIELD	Total Recoverable	Ground Water	6020A	337901
660-61477-2	TH-78	Total Recoverable	Water	6020A	337901
LCS 680-337901/2-A	Lab Control Sample	Total Recoverable	Water	6020A	337901
MB 680-337901/1-A	Method Blank	Total Recoverable	Water	6020A	337901

General Chemistry

Analysis Batch: 149607

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-48434-A-2 DU	Duplicate	Total/NA	Water	SM 2540C	
660-61477-1	BLANK FIELD	Total/NA	Ground Water	SM 2540C	
660-61477-2	TH-78	Total/NA	Water	SM 2540C	
LCS 660-149607/2	Lab Control Sample	Total/NA	Water	SM 2540C	
MB 660-149607/1	Method Blank	Total/NA	Water	SM 2540C	

Analysis Batch: 149706

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-48498-J-2 DU	Duplicate	Total/NA	Water	SM 2540C	
660-61500-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	SM 2540C	
660-61500-2	TH-72	Total/NA	Water	SM 2540C	
660-61500-3	TH-76	Total/NA	Water	SM 2540C	
660-61500-4	TH-77	Total/NA	Water	SM 2540C	
LCS 660-149706/2	Lab Control Sample	Total/NA	Water	SM 2540C	
MB 660-149706/1	Method Blank	Total/NA	Water	SM 2540C	

Analysis Batch: 338037

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
640-48413-K-1 DU	Duplicate	Total/NA	Water	350.1	
640-48413-K-2 MS	Matrix Spike	Total/NA	Water	350.1	
640-48413-K-2 MSD	Matrix Spike Duplicate	Total/NA	Water	350.1	
660-61477-1	BLANK FIELD	Total/NA	Ground Water	350.1	
660-61477-2	TH-78	Total/NA	Water	350.1	
LCS 680-338037/42	Lab Control Sample	Total/NA	Water	350.1	
MB 680-338037/5	Method Blank	Total/NA	Water	350.1	

Analysis Batch: 338405

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61495-A-3 MS	Matrix Spike	Total/NA	Water	350.1	
660-61495-A-3 MSD	Matrix Spike Duplicate	Total/NA	Water	350.1	
660-61500-1	DUPLICATE NOT BLANK	Total/NA	Ground Water	350.1	
660-61500-2	TH-72	Total/NA	Water	350.1	
660-61500-2 DU	TH-72	Total/NA	Water	350.1	
660-61500-3	TH-76	Total/NA	Water	350.1	

TestAmerica Tampa

QC Association Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

General Chemistry (Continued)

Analysis Batch: 338405 (Continued)

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61500-4	TH-77	Total/NA	Water	350.1	
LCS 680-338405/14	Lab Control Sample	Total/NA	Water	350.1	
MB 680-338405/12	Method Blank	Total/NA	Water	350.1	

Field Service / Mobile Lab

Analysis Batch: 149574

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61477-2	TH-78	Total/NA	Water	Field Sampling	

Analysis Batch: 149743

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
660-61500-2	TH-72	Total/NA	Water	Field Sampling	
660-61500-3	TH-76	Total/NA	Water	Field Sampling	
660-61500-4	TH-77	Total/NA	Water	Field Sampling	

Lab Chronicle

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: BLANK FIELD

Date Collected: 07/02/14 11:40

Date Received: 07/02/14 15:40

Lab Sample ID: 660-61477-1

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	337926	07/07/14 15:24	PAT	TAL SAV
Total Recoverable	Prep	3005A			337901	07/07/14 12:49	SP	TAL SAV
Total Recoverable	Analysis	6020A		1	338259	07/08/14 12:13	BWR	TAL SAV
Total/NA	Analysis	350.1		1	338037	07/07/14 15:43	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149607	07/08/14 11:55	TKO	TAL TAM

Client Sample ID: TH-78

Date Collected: 07/02/14 11:59

Date Received: 07/02/14 15:40

Lab Sample ID: 660-61477-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	337926	07/07/14 15:39	PAT	TAL SAV
Total Recoverable	Prep	3005A			337901	07/07/14 12:49	SP	TAL SAV
Total Recoverable	Analysis	6020A		1	338259	07/08/14 12:21	BWR	TAL SAV
Total/NA	Analysis	350.1		1	338037	07/07/14 14:24	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149607	07/08/14 11:55	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	149574	07/02/14 11:59	FS	TAL TAM

Client Sample ID: DUPLICATE NOT BLANK

Date Collected: 07/03/14 00:00

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-1

Matrix: Ground Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		20	338282	07/09/14 18:31	PAT	TAL SAV
Total Recoverable	Prep	3005A			149588	07/08/14 06:30	GH1	TAL TAM
Total Recoverable	Analysis	6010B		1	149606	07/08/14 09:42	GAF	TAL TAM
Total/NA	Analysis	350.1		20	338405	07/09/14 16:30	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149706	07/10/14 15:39	TKO	TAL TAM

Client Sample ID: TH-72

Date Collected: 07/03/14 12:50

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-2

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		20	338282	07/09/14 18:46	PAT	TAL SAV
Total Recoverable	Prep	3005A			149588	07/08/14 06:30	GH1	TAL TAM
Total Recoverable	Analysis	6010B		1	149606	07/08/14 09:55	GAF	TAL TAM
Total/NA	Analysis	350.1		20	338405	07/09/14 16:30	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149706	07/10/14 15:39	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	149743	07/03/14 12:50	FS	TAL TAM

TestAmerica Tampa

Lab Chronicle

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Client Sample ID: TH-76

Date Collected: 07/03/14 11:30

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-3

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	338282	07/09/14 19:02	PAT	TAL SAV
Total Recoverable	Prep	3005A			149588	07/08/14 06:30	GH1	TAL TAM
Total Recoverable	Analysis	6010B		1	149606	07/08/14 09:59	GAF	TAL TAM
Total/NA	Analysis	350.1		1	338405	07/09/14 12:04	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149706	07/10/14 15:39	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	149743	07/03/14 11:30	FS	TAL TAM

Client Sample ID: TH-77

Date Collected: 07/03/14 10:22

Date Received: 07/03/14 15:20

Lab Sample ID: 660-61500-4

Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dilution Factor	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	338282	07/09/14 19:48	PAT	TAL SAV
Total Recoverable	Prep	3005A			149588	07/08/14 06:30	GH1	TAL TAM
Total Recoverable	Analysis	6010B		1	149606	07/08/14 10:02	GAF	TAL TAM
Total/NA	Analysis	350.1		1	338405	07/09/14 12:04	JME	TAL SAV
Total/NA	Analysis	SM 2540C		1	149706	07/10/14 15:39	TKO	TAL TAM
Total/NA	Analysis	Field Sampling		1	149743	07/03/14 10:22	FS	TAL TAM

Laboratory References:

TAL SAV = TestAmerica Savannah, 5102 LaRoche Avenue, Savannah, GA 31404, TEL (912)354-7858

TAL TAM = TestAmerica Tampa, 6712 Benjamin Road, Suite 100, Tampa, FL 33634, TEL (813)885-7427

Method Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Method	Method Description	Protocol	Laboratory
300.0	Anions, Ion Chromatography	MCAWW	TAL SAV
6010B	Metals (ICP)	SW846	TAL TAM
6020A	Metals (ICP/MS)	SW846	TAL SAV
350.1	Nitrogen, Ammonia	MCAWW	TAL SAV
SM 2540C	Solids, Total Dissolved (TDS)	SM	TAL TAM
Field Sampling	Field Sampling	EPA	TAL TAM

Protocol References:

EPA = US Environmental Protection Agency

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

SM = "Standard Methods For The Examination Of Water And Wastewater",

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

Laboratory References:

TAL SAV = TestAmerica Savannah, 5102 LaRoche Avenue, Savannah, GA 31404, TEL (912)354-7858

TAL TAM = TestAmerica Tampa, 6712 Benjamin Road, Suite 100, Tampa, FL 33634, TEL (813)885-7427

Certification Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Laboratory: TestAmerica Tampa

The certifications listed below are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
Florida	NELAP	4	E84282	06-30-15

Laboratory: TestAmerica Savannah

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
	AFCEE		SAVLAB	
A2LA	DoD ELAP		399.01	02-28-15
A2LA	ISO/IEC 17025		399.01	02-28-15
Alabama	State Program	4	41450	06-30-15
Arkansas DEQ	State Program	6	88-0692	01-31-15
California	NELAP	9	3217CA	07-31-14 *
Colorado	State Program	8	N/A	12-31-14
Connecticut	State Program	1	PH-0161	03-31-15
Florida	NELAP	4	E87052	06-30-15
GA Dept. of Agriculture	State Program	4	N/A	06-30-14 *
Georgia	State Program	4	N/A	06-30-15
Georgia	State Program	4	803	06-30-15
Guam	State Program	9	09-005r	04-16-15
Hawaii	State Program	9	N/A	06-30-15
Illinois	NELAP	5	200022	11-30-14
Indiana	State Program	5	N/A	06-30-14 *
Iowa	State Program	7	353	07-01-15
Kentucky (DW)	State Program	4	90084	12-31-14
Kentucky (UST)	State Program	4	18	06-30-15
Louisiana	NELAP	6	30690	06-30-14 *
Louisiana (DW)	NELAP	6	LA140023	12-31-14
Maine	State Program	1	GA00006	08-16-14 *
Maryland	State Program	3	250	12-31-14
Massachusetts	State Program	1	M-GA006	06-30-15
Michigan	State Program	5	9925	06-30-14 *
Mississippi	State Program	4	N/A	06-30-14 *
Montana	State Program	8	CERT0081	01-01-15
Nebraska	State Program	7	TestAmerica-Savannah	06-30-14 *
New Jersey	NELAP	2	GA769	06-30-15
New Mexico	State Program	6	N/A	06-30-14 *
New York	NELAP	2	10842	03-31-15
North Carolina (DW)	State Program	4	13701	07-31-14 *
North Carolina (WW/SW)	State Program	4	269	12-31-14
Oklahoma	State Program	6	9984	08-31-14
Pennsylvania	NELAP	3	68-00474	06-30-15
Puerto Rico	State Program	2	GA00006	12-31-14
South Carolina	State Program	4	98001	06-30-14 *
Tennessee	State Program	4	TN02961	06-30-15
Texas	NELAP	6	T104704185-08-TX	11-30-14
USDA	Federal		SAV 3-04	06-11-17
Virginia	NELAP	3	460161	06-14-15
Washington	State Program	10	C805	06-10-15
West Virginia (DW)	State Program	3	9950C	12-31-14
West Virginia DEP	State Program	3	94	06-30-14 *

* Certification renewal pending - certification considered valid.

TestAmerica Tampa

Certification Summary

Client: Hillsborough Co Public Utilities Dept
Project/Site: SELF-IAMP Monitoring Wells

TestAmerica Job ID: 660-61477-1

Laboratory: TestAmerica Savannah (Continued)

All certifications held by this laboratory are listed. Not all certifications are applicable to this report.

Authority	Program	EPA Region	Certification ID	Expiration Date
Wisconsin	State Program	5	999819810	08-31-14
Wyoming	State Program	8	8TMS-L	06-30-14 *

* Certification renewal pending - certification considered valid.

TestAmerica Tampa

Testamento

THE LEADER IN THE FASHION WORLD

www.testamericainc.com
Phone: (813) 885 7427

Alternate Laboratory Name/Location:

Phone: _____
Fax: _____

Division of Custody

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: SELF IAMP		SITE LOCATION:	
WELL NO: TH-78	SAMPLE ID: TH-78	DATE: 7-2-14	

PURGING DATA

WELL DIAMETER (inches): 2	TUBING DIAMETER (inches): 3/8	WELL SCREEN INTERVAL DEPTH: 178.14 feet to 163.14 feet	STATIC DEPTH TO WATER (feet): 82.26	PURGE PUMP TYPE OR BAILER: BP
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable) = (178.14 feet - 82.26 feet) X .16 gallons/foot = 15.35 gallons				
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable) = gallons + (gallons/foot X feet) + gallons = gallons				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): 177.14	FINAL PUMP OR TUBING DEPTH IN WELL (feet): 177.14	PURGING INITIATED AT: 10.25	PURGING ENDED AT: 11.59	TOTAL VOLUME PURGED (gallons): 23.5

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (circle units) μmhos/cm or μS/cm	DISSOLVED OXYGEN (circle units) mg/L or % saturation	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
11.27	15.5	15.5	.25	82.29	9.70	23.94	360	.56	17.4	NONE	NONE
11.43	4	19.5	.25	82.29	9.67	23.95	361	.49	16.0	↓	↓
11.59	4	23.5	.25	82.29	9.08	23.89	363	.41	19.3	↓	↓

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0008; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.006; 1/2" = 0.010; 5/8" = 0.016

PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: ANDREW BALLOON / ZACK PATTERSON		SAMPLER(S) SIGNATURE(S): 		SAMPLING INITIATED AT: 11.59	SAMPLING ENDED AT: 12.09
PUMP OR TUBING DEPTH IN WELL (feet): 177.14		TUBING MATERIAL CODE: T	FIELD-FILTERED: Y (N)	FILTER SIZE: _____ μm	
FIELD DECONTAMINATION: PUMP Y (N) Dedicated		TUBING Y (N) Dedicated	DUPLICATE: Y (N)		

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (mL per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH			

SEE COC FOR ANALYSIS

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)

SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.
2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)
pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: SELF IAMP	SITE LOCATION:	
WELL NO: FIELD BLANK	SAMPLE ID: FIELD BLANK	DATE: 7-2-14

PURGING DATA

WELL DIAMETER (inches): N/A	TUBING DIAMETER (inches): N/A	WELL SCREEN INTERVAL DEPTH: / feet to / feet	STATIC DEPTH TO WATER (feet): N/A	PURGE PUMP TYPE OR BAILER: N/A
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH -- STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable)				
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable)				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): N/A	FINAL PUMP OR TUBING DEPTH IN WELL (feet): N/A	PURGING INITIATED AT: N/A	PURGING ENDED AT: N/A	TOTAL VOLUME PURGED (gallons): N/A

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (circle units) μmhos/cm or μS/cm	DISSOLVED OXYGEN (circle units) mg/L or % saturation	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
FIELD BLANK											

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0006; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.008; 1/2" = 0.010; 5/8" = 0.016

PURGING EQUIPMENT CODES: B = Bailor; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: ANDREW BALLOON / ZACK PATTERSON				SAMPLER(S) SIGNATURE(S): <i>Zack Patterson</i>		SAMPLING INITIATED AT: 11.40		SAMPLING ENDED AT: 11.55	
PUMP OR TUBING DEPTH IN WELL (feet): N/A				TUBING MATERIAL CODE: T		FIELD-FILTERED: Y (N)		FILTER SIZE: _____ μm	
FIELD DECONTAMINATION: PUMP Y N Dedicated				TUBING Y N Dedicated		DUPLICATE: Y (N)			

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (mL per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH			

SEE COC FOR ANALYSIS ↙

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)

SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailor; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.
 2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)
 pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

THE LITERARY COUNCIL OF THE UNITED STATES

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

1
2
3
4
5
6
7
8
9
10
11
12
13
14

Form FD 9000-24
GROUNDWATER SAMPLING LOG

SITE NAME: SELF IAMP		SITE LOCATION: Lithia, FL	
WELL NO: TH-77	SAMPLE ID: TH-77	DATE: 7-3-14	

PURGING DATA

WELL DIAMETER (Inches): 2	TUBING DIAMETER (Inches): 3/8	WELL SCREEN INTERVAL DEPTH: 154.2 feet to 169.2 feet	STATIC DEPTH TO WATER (feet): 86.55	PURGE PUMP TYPE OR BAILER: BP
WELL VOLUME PURGE: 1 WELL VOLUME = (TOTAL WELL DEPTH - STATIC DEPTH TO WATER) X WELL CAPACITY (only fill out if applicable) = (169.2 feet - 86.55 feet) X .16 gallons/foot = 13.23 gallons				
EQUIPMENT VOLUME PURGE: 1 EQUIPMENT VOL. = PUMP VOLUME + (TUBING CAPACITY X TUBING LENGTH) + FLOW CELL VOLUME (only fill out if applicable) = _____ gallons + (_____ gallons/foot X _____ feet) + _____ gallons = _____ gallons				
INITIAL PUMP OR TUBING DEPTH IN WELL (feet): 168.2	FINAL PUMP OR TUBING DEPTH IN WELL (feet): 168.2	PURGING INITIATED AT: 9.28	PURGING ENDED AT: 10.22	TOTAL VOLUME PURGED (gallons): 19.98

TIME	VOLUME PURGED (gallons)	CUMUL. VOLUME PURGED (gallons)	PURGE RATE (gpm)	DEPTH TO WATER (feet)	pH (standard units)	TEMP. (°C)	COND. (circle units) μmhos/cm or μS/cm	DISSOLVED OXYGEN (circle units) mg/L or % saturation	TURBIDITY (NTUs)	COLOR (describe)	ODOR (describe)
10.04	13.32	13.32	.37	86.74	7.42	23.61	409	.43	7.71	NONE	NONE
10.13	3.33	16.65	.37	86.74	7.44	23.58	409	.34	3.39	↓	↓
10.22	3.33	19.98	.37	86.74	7.44	23.65	409	.34	1.56	↓	↓

WELL CAPACITY (Gallons Per Foot): 0.75" = 0.02; 1" = 0.04; 1.25" = 0.06; 2" = 0.16; 3" = 0.37; 4" = 0.65; 5" = 1.02; 6" = 1.47; 12" = 5.88
TUBING INSIDE DIA. CAPACITY (Gal./Ft.): 1/8" = 0.0006; 3/16" = 0.0014; 1/4" = 0.0026; 5/16" = 0.004; 3/8" = 0.006; 1/2" = 0.010; 5/8" = 0.016
PURGING EQUIPMENT CODES: B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; PP = Peristaltic Pump; O = Other (Specify)

SAMPLING DATA

SAMPLED BY (PRINT) / AFFILIATION: ANDREW BALLOON / ZACK PATTERSON				SAMPLER(S) SIGNATURE(S): <i>[Signature]</i>		SAMPLING INITIATED AT: 10.22		SAMPLING ENDED AT: 10.30	
PUMP OR TUBING DEPTH IN WELL (feet): 168.2				TUBING MATERIAL CODE: T		FIELD-FILTERED: Y ☒ N ☐		FILTER SIZE: _____ μm	
FIELD DECONTAMINATION: PUMP Y ☐ N ☒ Dedicated				TUBING Y ☐ N ☒ Dedicated		DUPLICATE: Y ☐ N ☒			

SAMPLE CONTAINER SPECIFICATION				SAMPLE PRESERVATION			INTENDED ANALYSIS AND/OR METHOD	SAMPLING EQUIPMENT CODE	SAMPLE PUMP FLOW RATE (mL per minute)
SAMPLE ID CODE	# CONTAINERS	MATERIAL CODE	VOLUME	PRESERVATIVE USED	TOTAL VOL ADDED IN FIELD (mL)	FINAL pH			

SEE COC FOR ANALYSIS

MATERIAL CODES: AG = Amber Glass; CG = Clear Glass; PE = Polyethylene; PP = Polypropylene; S = Silicone; T = Teflon; O = Other (Specify)
SAMPLING EQUIPMENT CODES: APP = After Peristaltic Pump; B = Bailer; BP = Bladder Pump; ESP = Electric Submersible Pump; RFPP = Reverse Flow Peristaltic Pump; SM = Straw Method (Tubing Gravity Drain); O = Other (Specify)

NOTES: 1. The above do not constitute all of the information required by Chapter 62-160, F.A.C.
2. STABILIZATION CRITERIA FOR RANGE OF VARIATION OF LAST THREE CONSECUTIVE READINGS (SEE FS 2212, SECTION 3)
pH: ± 0.2 units Temperature: ± 0.2 °C Specific Conductance: ± 5% Dissolved Oxygen: all readings ≤ 20% saturation (see Table FS 2200-2); optionally, ± 0.2 mg/L or ± 10% (whichever is greater) Turbidity: all readings ≤ 20 NTU; optionally ± 5 NTU or ± 10% (whichever is greater)

Revision Date: February 2009

THE LEADER IN ENVIRONMENTAL TESTING

* ICOC got stuck to
FBIEX pouch - mostly destroyed

Chain of Custody Record

Client Information (Sub Contract Lab) Client Contact: Shipping/Receiving Company: TestAmerica Laboratories, Inc. Address: 5102 LaRoche Avenue, City: Savannah State, Zip: GA, 31404 Phone: 912-354-7858(Tel) 912-352-0165(Fax) Email: Project Name: SELF-IAMP Monitoring Wells Site: Southeast Landfill		Lab PM: Robertson, Nancy E-Mail: nancy.robertson@testamericainc.com Carrier Tracking No(s): Lab #: Job #: Preservation Codes: A - HCL B - NaOH C - Zn Acetate D - Nitric Acid E - NaHSO4 F - MeOH G - Amchlor H - Ascorbic Acid I - Ice J - DI Water K - EDTA L - EDA Other: M - Hexane N - None O - AsNaO2 P - Na2O4S Q - Na2SO3 R - Na2S2O3 S - H2SO4 T - TSP Dodacahydrate U - Acetone V - MCAA W - ph 4-5 Z - other (specify)	
Sample Information Due Date Requested: 7/14/2014 TAT Requested (days): PO #: WO #: Project #: 66003915 SSOW#:		Analysis Requested Total Number of Containers:	
Sample Identification - Client ID (Lab ID)		Special Instructions/Note:	
Duplicate (660-61500-1)	Sample Date: 7/3/14	Sample Time: Eastern	Sample Type (C=comp, G=grab):
TH-72 (660-61500-2)	Sample Date: 7/3/14	Sample Time: 12:50 Eastern	Sample Type: Water
TH-76 (660-61500-3)	Sample Date: 7/3/14	Sample Time: 11:30 Eastern	Sample Type: Water
TH-77 (660-61500-4)	Sample Date: 7/3/14	Sample Time: 10:22 Eastern	Sample Type: Water
Possible Hazard Identification Unconfirmed Deliverable Requested: I, II, III, IV, Other (specify)		Sample Disposal (A fee may be assessed if samples are retained longer than 1 month) ☐ Return To Client ☐ Disposal By Lab ☐ Archive For Months Special Instructions/QC Requirements:	
Empty Kit Relinquished by: Relinquished by: RPRICE Relinquished by: Relinquished by:		Date: 7-7-14 1413 Date/Time: 7-7-14 1413 Date/Time: 7-7-14 1413 Date/Time: 7-7-14 1413	
Custody Seals Intact: ☐ Yes ☐ No Custody Seal No.:		Cooler Temperature(s) °C and Other Remarks: 6.0 6.2 5.8 5.6	

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-61477-1

Login Number: 61477

List Source: TestAmerica Tampa

List Number: 1

Creator: Williams, Jennifer

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	False	Check done at department level as required.

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-61477-1

Login Number: 61477

List Number: 2

Creator: Conner, Keaton

List Source: TestAmerica Savannah

List Creation: 07/03/14 06:05 PM

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-61477-1

Login Number: 61500

List Source: TestAmerica Tampa

List Number: 1

Creator: Williams, Jennifer

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	True	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	False	Check done at department level as required.

Login Sample Receipt Checklist

Client: Hillsborough Co Public Utilities Dept

Job Number: 660-61477-1

Login Number: 61500

List Number: 2

Creator: West, Lauren H

List Source: TestAmerica Savannah

List Creation: 07/08/14 07:32 AM

Question	Answer	Comment
Radioactivity wasn't checked or is $\leq$ background as measured by a survey meter.	N/A	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	N/A	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	N/A	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is $<6\text{mm}$ (1/4").	N/A	
Multiphasic samples are not present.	True	
Samples do not require splitting or compositing.	True	
Residual Chlorine Checked.	N/A	