
APPLICATION FOR SOLID WASTE MANAGEMENT FACILITY PERMIT FOR CONSTRUCTION-OTHER



Lena Road Landfill Manatee County, Florida

January 2000

Prepared by:

McKim & Creed Engineers, P.A. 601 Cleveland Street, Suite 205 Clearwater, Florida 34615





Florida Department of Environmental Protection Twin Towers Office Bldg. • 2600 Blair Stone Road • Tallahassee, FL 32399-2400

DEP Form # 62-701.90(1)
Form Title Solid Waste Management Facility Permit
Effective Date May 19, 1994

DEP Application No. _

(Filled by DEP)

ELLI TOTAL TOTAL


JAN 1 2 2000

SOUTH THE DISTRICT TALLER

STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL PROTECTION

SOLID WASTE MANAGEMENT FACILITY PERMIT

APPLICATION INSTRUCTIONS AND FORMS



U.E.P. JAN 9 2 2000 I. General

Solid Waste Management Facilities shall be permitted pursuant to Section 403.70 is Florida Statutes, (FS) and in accordance with Florida Administrative Code (FAC) Chapter 62-70 in the Department District minimum of six copies of the application shall be submitted to the Department District Office having jurisdiction over the facility. The appropriate fee in accordance with Chapter 62-4, FAC, and Rule 62-701.320(5)(c), FAC, shall be submitted with the application by check made payable to the Department of Environmental Regulation (DEP).

Complete appropriate sections for the type of facility for which application is made. Entries shall be typed or printed in ink. All blanks shall be filled in or marked "not applicable" or "no substantial change". Information provided in support of the application shall be marked "submitted" and the location of this information in the application package indicated. The application shall include all information, drawings, and reports necessary to evaluate the facility. Information required to complete the application is listed on the attached pages of this form.

II. Application Parts Required for Construction and Operation Permits

- Α. Landfills and Ash Monofills - Submit parts A,B, D through R, and T
- Asbestos Monofills Submit parts A,B,D,E,F,I,K, M through Q, and T В.
- C. Industrial Solid Waste Facilities - Submit parts A,B, D through Q, and T
- Volume Reduction Facilities Submit parts A,C,D,S, and T D.
- Materials Recovery Facilities Submit parts A,C,D,S, and T

NOTE: Portions of some parts may not be applicable.

NOTE: For facilities that have been satisfactorily constructed in accordance with their construction permit, the information required for A,B,C,D, and E type facilities does not have to be resubmitted for an operation permit if the information has not substantially changed during the construction period. appropriate portion of the form should be marked "no substantial change".

III. Application Parts Required for Closure Permits

- Landfills and Ash Monofills Submit parts A,B, N through R, and T Α.
- В. Asbestos Monofills - Submit parts A,B, M through Q, and T
- Industrial Solid Waste Facilities Submit parts A,B, N through Q, and T C.
- Volume Reduction Facilities Submit parts A,C,S, and T D.
- Ė. Materials Recovery Facilities - Submit parts A,C,S, and T

NOTE: Portions of some parts may not be applicable.

IV. Permit Renewals

The above information shall be submitted at time of permit renewal in support of the new permit. However, facility information that was submitted to the Department to support the expiring permit, and which is still valid, does not need to be re-submitted for permit Portions of the application not re-submitted shall be marked "no substantial change" on the application form.

V. Application Codes

S - Submitted

LOCATION - Physical location of information in application

N/A - Not Applicable

N/C - No Substantial Change

VI. LISTING OF APPLICATION PARTS

חסגם	70	CENTEDAT	TATEODMACUTOAL
PART	A -	GENERAL	INFORMATION

PART B- DISPOSAL FACILITY GENERAL INFORMATION

PART C- MATERIALS RECOVERY / VOLUME REDUCTION FACILITY GENERAL INFORMATION

PART D- SOLID WASTE MANAGEMENT FACILITY PERMIT GENERAL REQUIREMENTS

PART E- LANDFILL PERMIT GENERAL REQUIREMENTS

PART F- GENERAL CRITERIA FOR LANDFILLS

PART G- LANDFILL CONSTRUCTION REQUIREMENTS

PART H- HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS

PART I- GEOTECHNICAL INVESTIGATION REQUIREMENTS

PART J- VERTICAL EXPANSION OF LANDFILLS

PART K- LANDFILL OPERATION REQUIREMENTS

PART L- WATER QUALITY AND LEACHATE MONITORING REQUIREMENTS

PART M- SPECIAL WASTE HANDLING REQUIREMENTS

PART N- LANDFILL CLOSURE REQUIREMENTS

PART O- CLOSURE PROCEDURES

PART P- LONG TERM CARE REQUIREMENTS

PART Q- FINANCIAL RESPONSIBILITY REQUIREMENTS

PART R- CLOSURE OF EXISTING LANDFILL REQUIREMENTS

PART S- MATERIALS RECOVERY FACILITY REQUIREMENTS

PART T- CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

STATE OF FLORIDA

DEPARTMENT OF ENVIRONMENTAL PROTECTION APPLICATION FOR PERMIT TO CONSTRUCT, OPERATE, MODIFY OR CLOSE A SOLID WASTE MANAGEMENT FACILITY

Please Type or Print

GENERAL INFORMATION			
Type of facility:			
Disposal [X]			
Class I Landfill Class II Landfill Class III Landfill Other	[X] [] []	Ash Monofill Asbestos Monofill Industrial Solid Waste	[]
Volume Reduction []			
Incinerator Composting Materials Recovery Other	[_] [] []	Pulverizer / Shredder Compactor / Baling Plant Energy Recovery	[]
Type of application:			
Construction Operation	[X] [)	Construction/Operation Closure	[]
Classification of applicat	ion:		
New Renewal	[]	Substantial Modification Minor Modification	[] [X]
Facility name: Lena Road	Landfill		
DEP ID number: GMS 4041C	02025	County: Manatee	
Facility location (main en	trance): <u>333</u>	33 Lena Road, Bradenton, FL	34202
Location coordinates:			
Section: 1 Township:	34S Range	: 18E/Sect. 6, 35S, 19E/Sect	1, 35S, 183 35S
UTMs: Zone	km E	km N	302
Latitude: 27 ° 28 '	00 " Tona:	itude: 82 ° 27 ' 00 "	

8.	Applicant name (operating authority): Manatee County
. •	Mailing address: 4410 66th Street West, Bradenton, FL 34210 Street or P.O. Box City State Zip
	Contact person: Len Bramble Telephone: (941) 792-8811
	Title: Director of Public Works
9.	Authorized agent/Consultant: McKim & Creed, PA
	Mailing address: 601 Cleveland Street, Ste. 205, Clearwater, FL 33755 Street or P.O. Box City State Zip
	Contact person: A. Street Lee Telephone: (727) 442-7196
	Title: Senior Project Manager
10.	Landowner(if different than applicant): Manatee County Board of County Commissioners
	Mailing address: 112 Manatee Avenue West, Bradenton, FL 34205 Street or P.O. Box City State Zip
	Contact person: Len Bramble Telephone: (941) 792-8811
11.	Cities, towns and areas to be served: Manatee County, Long Boat Key South, small
	amount received from surrounding counties
12.	Population to be served:
	Current: 245,889 Five-Year Projection: 267,603
13.	Volume of solid waste to be received: $1,300$ yds^3-/day tons/day $garlons/day$
14.	Date site will be ready to be inspected for completion: N/A
15.	Estimated life of facility: 30 years
16.	Estimated costs:
	Total Construction: \$ N/A Closing Costs: \$ N/A
17.	Anticipated construction starting and completion dates:
	From: $01/01/00$ To: $01/01/02$

B.	DISPOSAL FACILITY GENERAL INFO	ORMATION						
1.	Provide brief description of application:	disposal fac	cility design and	operati	ions planned by this	.		
	Landfilling of Municipal Sol	id Waste.	Collection and s	torage	of household haza	rdous		
	waste, tires and white good	ls which ar	re removed by the	ne cont	tractor. Collection	and		
	processing of yard waste.				W			
	TITE AND INC.							
2.	Facility site supervisor: \underline{Gu}	s DiFonzo						
	Title: Solid Waste Manager	Te	elephone: (<u>941</u>)_7	95-3473	3			
3.	Disposal area: Total 312 ac:	res; Used 1	98 acres; Avail	lable $oldsymbol{1}_{_{_{_{_{_{_{_{_{_{_{_{_{_{_{_{_{_{_$	14 acres			
4.	Weighing scales used: Yes [X]	No []						
5.	Security to prevent unauthorized use: Yes [X] No []							
6.	Charge for waste received:	\$/yds	$\frac{23}{2}$ \$/ton	n				
7.	Surrounding land use, zoning:							
	Residential Agricultural Commercial	[X] [X) []	Industrial None Other	[] [] [X]	Transportation &	Utilitie		
8.	Types of waste received:							
	Residential Commercial Incinerator / WTE ash Treated biohazardous Water treatment sludge Air treatment sludge Agricultural Asbestos Other	(X)	C & D debris Shredded/cut ti Yard trash Septic tank Industrial Industrial slud Domestic sludge	[X] [X] [X] ge [X]				
9.	Salvaging permitted: Yes []	No.[X]		*				
10.	Attendant: Yes [X] No []	Trained op	erator: Yes [X]	No []				
11.	Spotters: Yes [X] No [] N	umber of spo	otters used: 2					
12	Site located in: Floodplain	[] [[] []	ande [] Oth	er (X)	IIn Lands			

13.	Property recorded as a Dispos	sal Site	in County Land Records: Yes [X	No []
14.	Days of operation: Monday	- Saturd	lay	·
15.	Hours of operation:8:00 a.m	. to 5:0	0 p.m.	
16.	Days Working Face covered:	6		
17.	Elevation of water table:	29 Ft. N	GVD	
18.	Number of monitoring wells:	27		
19.	Number of surface monitoring	points:	5 with one to be eliminated	
20.	Gas controls used: Yes $[X]$	No []	Type controls: Active []	Passive [X
	Gas flaring: Yes [X] No []	Gas recovery: Yes [] No [Xì
21.	Landfill Unit - liner type:			
	Natural soils Single clay liner Single geomembrane Single composite Slurry wall Other	[X] [] [] [X] []	Double geomembrane Geomembrane & composite Double composite None	[] [] []
22.	Leachate collection method:			
	Collection pipes Geonets Well points Perimeter ditch Other	[X] [] [] []	Sand layer Gravel layer Interceptor trench None	[] [] []
23.	Leachate storage method:			
	Tanks Other	[]	Surface impoundments	[X]
24.	Leachate treatment method:			
	Oxidation Secondary Advanced Other	[] [] []	Chemical treatment Settling None	[]

Leacha	te disposal method:				~~
	Recirculated Transported to WWTP Injection well Other	[] [] []	Pumped to WWTP Discharged to surface water Evaporation (ie: Perc Pond)	[X] [] []	gn.
For le	achate discharged to sur	face waters:			
	Name and Class of receiv	ring water: _	N / A		
Storm	Water: Collected: Yes	[X] No []	Type of treatment: Sand Filt	ers	
			Cypress Strand, Gates Cree	k via onsite	wetlands Class III
Manage	ement and Storage of Surf	ace Waters (MSSW) Permit number or status	s:Ma <u>nagement</u>	•
of s S041	urface waters on Stage -21117. Stages II and	s I, II, and III are for	d III is permitted by Opera the permitted by MSSW Pe	tion Permit rmit No. 403	143.01.

PEDRM 62-701.900(1) ifective 05-19-94

Energy recovery, in units shown:
High pressure steam, lb/hr Low pressure steam, lb/hr Electricity, kw/hr Gas, ft³/hr Other: Process water management: Chilled water, gal/hr Oil, gal/hr Oil, BTU/hr Gas, BTU/hr
Recycled: Yes [] No []
Treatment method used:
Discharged to: Surface waters [] Underground [] Other []
Name and Class of receiving water:
Storm Water:
Collected: Yes [] No [] Type of treatment:
Name and Class of receiving water:
ERP Permit number or status:
Final residue produced:
% of normal processing rate
% of maximum processing rate
Disposed of at (Site name):
Supplemental fuel used:
Type: Quantity used/hour:
Costs:
Estimated operating costs (material-energy revenue): \$
Total cost/ton: \$ Net cost/ton: \$
State pollution control bond financing amount: \$
Estimated amount of tax exemptions that will be requested: \$

D.	SOLID WASTE	MANAG	EMENT	FACILITY	Y PERMIT GENERAL REQUIREMENTS (62-701.320, FAC)
<u>s</u>	LOCATION	N/A	N/C		
<u>X</u>	- Programme L. L. L.			1.	Six copies, at minimum, of the completed application form, all supporting data and reports; (62-701.320(5)(a),FAC)
<u>X</u>	(Previously	<u>Su</u> t	omitte	ed)2.	Engineering and/or professional certification (signature, date and seal) provided on the applications and all engineering plans, reports and supporting information for the application; (62-701.320(6),FAC)
<u>X</u>				3.	A letter of transmittal to the Department; (62-701.320(7)(a),FAC)
<u>X</u>				4.	A completed application form dated and signed by the applicant; (62-701.320(7)(b),FAC)
<u>X</u>	(Previously	Subm	it <u>ted</u>)) 5.	Permit fee specified in Rule 62-4.050, FAC and Rule 62-701.320(5)(c), FAC in check or money order, payable to the Department; (62-701.320(7)(c),FAC)
		X		6.	An engineering report addressing the requirements of this rule and with the following format: a cover sheet, text printed on 8 1/2 inch by 11 inch consecutively numbered pages, a table of contents or index, the body of the report and all appendices including an operation plan, contingency plan, illustrative charts and graphs, records or logs of tests and investigations, engineering calculations; (62-701.320(7)(d),FAC))
******		<u>X</u>		7.	Operation Plan; (62-701.320(7)(e)1,FAC)
		_X.		8.	Contingency Plan; (62-701.320(7)(e)2,FAC)
				9.	Plans or drawings for the solid waste management facilities in appropriate format (including sheet size restrictions, cover sheet, legends, north arrow, horizontal and vertical scales, elevations referenced to NGVD) showing; (62-702.320(7)(f),FAC)
		<u>X</u>			 A regional map or plan with the project location;
		_X.			b. A vicinity map or aerial photograph no more than 1 year old;
		<u>X</u>			c. A site plan showing all property boundaries certified by a registered Florida land surveyor;

<u>s</u>	LOCATION	N/A	N/C		
					d. Other necessary details to support the engineering report.
			<u>X</u>	10.	Proof of property ownership or a copy of appropriate agreements between the facility operator and property owner authorizing use of property; $(62-701.320(7)(g),FAC)$
		. <u></u> -	<u>X</u>	11.	For facilities owned or operated by a county, provide a description of how, if any, the facilities covered in this application will contribute to the county's achievement of recycling goals contained in Section 403.706,FS; (62-701.320(7)(h),FAC)
	To be prov	ided i	<u>X</u> if	12.	Provide a history and description of any enforcement actions taken by the Department against the applicant for violations of applicable statutes, rules, orders or permit conditions relating to the operation of any solid waste management facility in this state; (62-701.320(7)(i),FAC)
<u>X</u>	Required			13.	Proof of publication in a newspaper of general circulation of notice of application for a permit to construct or substantially modify a solid waste management facility; (62-702.320(8),FAC)
		<u>X</u>	 <u></u>	14.	Provide a description of how the requirements for airport safety will be achieved including proof of required notices if applicable; (62-701.320(12),FAC)

* Items noted as N/A have been covered in previous Operation Permit Application on file with FDEP.

E.	LANDFILL PE	RMIT G	ENERAL	REQUIR	EMENTS	(62-701.330, FAC)
<u>s</u>	LOCATION	N/A	N/C			
		X	_	1.	old a zonin suffi water	city map or aerial photograph no more than 1 year and of appropriate scale showing land use and local ag within one mile of the landfill and of cient scale to show all homes or other structures, bodies, and roads other significant features of vicinity. All significant features shall be ded; (62-701.330(4)(a),FAC)
		<u>X</u>		2.	old s	tity map or aerial photograph no more than 1 year showing all airports that are located within five of the proposed landfill; (62-701.330(4)(b),FAC)
		<u>X</u>		3.		plan with a scale not greater than 200 feet to the showing; $(62-701.330(4)(c),FAC)$
	·	<u>X</u>			a.	Dimensions;
		<u>X</u>			b.	Locations of proposed and existing water quality monitoring wells;
		<u>X</u>			c.	Locations of soil borings;
		<u>X</u>			d.	Proposed plan of trenching or disposal areas;
		<u>X</u>			e.	Cross sections showing original elevations and proposed final contours which shall be included either on the plot plan or on separate sheets;
		<u>X</u>			f.	Any previously filled waste disposal areas;
	•	<u>X</u>			g.	Fencing or other measures to restrict access.
				4.	to th	graphic maps with a scale not greater than 200 feet ne inch with 5-foot contour intervals showing; 01.330(4)(d),FAC):
		<u>X</u>			a.	Proposed fill areas;
		<u>X</u>			b.	Borrow areas;
<u>X</u>					c.	Access roads;
<u>X</u>					d.	Grades required for proper drainage;
	···	<u>X</u>			e.	Cross sections of lifts;

^{*}Items noted as N/A have been covered in previous Operation Permit Application on file with FDEP.

<u>s</u>	LOCATION	N/A	N/C			
<u>X</u>		<u>X</u>			f.	Special drainage devices if necessary;
		<u>X</u>			g.	Fencing;
		<u>X</u>			h.	Equipment facilities.
				5.		ort on the landfill describing the following; 01.330(4)(e),FAC)
_		<u>X</u>			a.	The current and projected population and area to be served by the proposed site;
		<u>X</u>			b.	The anticipated type, annual quantity, and source of solid waste, expressed in tons;
		<u>X</u>			c.	The anticipated facility life;
		<u>X</u>			d.	The source and type of cover material used for the landfill.
		<u>X</u>		6.	conduc	le evidence that an approved laboratory shall t water quality monitoring for the facility in lance with Rule 62-160,FAC; (62-701.330(4)(h),FAC)
		<u>X</u>		7.	demons and	le a statement of how the applicant will strate financial responsibility for the closing long-term care of the landfill; (62-80(4)(i),FAC)
F.	GENERAL CRI	TERIA	FOR LAI	NDFILLS	(62-70	1.340,FAC)
		<u>X</u>	_	1.	landfi locate restri tempor unless	be (and show on a Federal Insurance stration flood map, if available) how the ll or solid waste disposal unit shall not be ed in the 100-year floodplain where it will ct the flow of the 100-year flood, reduce the tary water storage capacity of the floodplain compensating storage is provided, or result is a set of solid waste; (62-701.340(4)(b),FAC)
		<u>X</u>		2.	waste proper toe	the how the minimum horizontal separation between deposits in the landfill and the landfill try boundary shall be 100 feet, measured from the of the proposed final cover slope; (62-40(4)(c),FAC)
		<u>X</u>	-	3.	landfi	the what methods shall be taken to screen the ill from public view where such screening can ically be provided; (62-701.340(4)(d),FAC)

*Items noted as N/A have been covered in previous Operation Permit Application of file with FDEP.

LOCATION	N/A	N/C			
	<u>X</u>		1.	solid wa	how the landfill shall be designed so that ste disposal units will be constructed and t planned intervals throughout the design the landfill; (62-701.400(2),FAC)
			2.	Landfill	liner requirements; (62-701.400(3),FAC)
					neral construction requirements; 2-701.400(3)(a),FAC):
	_ <u>X</u>			(1	Provide test information and documentation to ensure the liner will be constructed of materials that have appropriate physical, chemical, and mechanical properties to prevent failure;
	<u>X</u>			(2	Document foundation is adequate to prevent liner failure;
Approx Art Julius to State Landon Commission	<u>X</u>	destruction 200		(3	Constructed so bottom liner will not be adversely impacted by fluctuations of the ground water;
	<u>X</u> _			(4	Designed to resist hydrostatic uplift if bottom liner located below seasonal high ground water table;
	X			(5) Installed to cover all surrounding earth which could come into contact with the waste or leachate.
				b. Co	mposite liners; (62-701.400(3)(b),FAC)
	_ <u>X</u>			(1) Upper 'geomembrane thickness and properties;
	<u>X</u>			(2) Design leachate head for primary LCRS including leachate recirculation if appropriate;
	_ <u>X</u>			(3	Design thickness in accordance with Table A and number of lifts planned for lower soil component.

<u>8</u>	LOCATION	N/A	N/C	c.	Doubl	e liners; (62-701.400(3)(c),FAC)
		<u>X</u>			(1)	Upper and lower geomembrane thicknesses and properties;
		<u>X</u>	_		(2)	Design leachate head for primary LCRS to limit the head to one foot above the liner;
		<u>X</u>			(3)	Lower geomembrane sub-base design;
		<u>X</u>			(4)	Leak detection and secondary leachate collection system minimum design criteria ($k \ge 1$ cm/sec, head on lower liner <_1 inch, head not to exceed thickness of drainage layer);
				d.		ards for geomembranes; 01.400(3)(d),FAC)
		<u>X</u>			(1)	Field seam test methods to ensure all field seams are at least 90 percent of the yield strength for the lining material;
		<u>X</u>	****		(2)	Design of 24-inch-thick protective layer above upper geomembrane liner;
		<u>X</u>	_		(3)	Describe operational plans to protect the liner and leachate collection system when placing the first layer of waste above 24-inch-thick protective layer.
				e.		nthetic specification requirements; 01.400(3)(e),FAC)
		<u>X</u>	_		(1)	Definition and qualifications of the designer, manufacturer, installer, QA consultant and laboratory, and QA program;
		<u>X</u>	and the same of th		(2)	Material specifications for geomembranes, geotextiles, geogrids, and geonets;

<u>s</u>	LOCATION	N/A	N/C		
		<u>X</u>		(3)	Manufacturing and fabrication specifications including geomembrane raw material and roll QA, fabrication personnel qualifications, seaming equipment and procedures, overlaps, trial seams, destructive and nondestructive seam testing, seam testing location, frequency, procedure, sample size and geomembrane repairs;
		<u>X</u>	_	(4)	Geomembrane installation specifications including earthwork, conformance testing, geomembrane placement, installation personnel qualifications, field seaming and testing, overlapping and repairs, materials in contact with geomembrane and procedures for lining system acceptance;
		<u>X</u>	_	(5)	Geotextile and geogrid specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil materials;
		<u>X</u>		(6)	Geonet specifications including handling and placement, conformance testing, stacking and joining, repair, and placement of soil materials;
			f.		ards for soil components 10.400(3)(f),FAC):
		_X	_	(1)	Description of construction procedures including overexcavation and backfilling to preclude structural inconsistencies and procedures for placing and compacting soil component in layers;
		<u>X</u>	_	(2)	Demonstration of compatibility of the soil component with actual or simulated leachate in accordance with EPA Test Method 9100 or an equivalent test method;
_		<u>X</u>	_	(3)	Procedures for testing in-situ soils to demonstrate they meet the specifications for soil liners;

<u>s</u>	LOCATION	N/A	N/C		(4)		fications for soil component of liner ling at a minimum:
		X				(a)	Allowable particle size distribution, Atterberg limits, shrinkage limit;
		<u>X</u>				(b)	Placement moisture and dry density criteria;
—		<u>X</u>				(c)	Maximum laboratory-determined saturated hydraulic conductivity using simulated leachate;
		<u>X</u>				(d)	Minimum thickness of soil liner;
		<u>X</u>				(e)	Lift thickness;
		<u>X</u>				(f)	Surface preparation (scarification);
		<u>X</u>				(g)	Type and percentage of clay mineral within the soil component;
		<u>X</u>			(5)	field satur	dures for constructing and using a test section to document the desired ated hydraulic conductivity and ness can be achieved in the field.
						llectic (4),FAC	on and removal system (LCRS);
				a.	_	_	and secondary LCRS requirements; (4)(a),FAC)
<u>X</u>	Appendix A	/ <u>Tec</u> l	nn <u>ica</u> l	Specifications	5(1)		ructed of materials chemically tant to the waste and leachate;
<u>X</u>	Appendix A	/T <u>ec</u> l	n <u>ica</u> l	Specifications	(2)		sufficient mechanical properties to nt collapse under pressure;
<u>X</u>	Appemdox A	/Tec	h <u>nic</u> al	Specification	s (3)	Have geote	granular material or synthetic xtile to prevent clogging;
<u>X</u>	Appendix A	/ <u>T ec</u> l	n <u>ica</u> l	Specifications	5(4)	clogg	method for testing and cleaning ed pipes or contingent designs for ting leachate around failed areas;

S	LOCATION	N/A	N/C			
_					b.	Primary LCRS requirements; (62-701.400(4)(b),FAC)
		<u>X</u>				(1) Bottom 12 inches having hydraulic conductivity \geq 1 x 10 ⁻³ cm/sec;
		<u>X</u>				(2) Total thickness of 24 inches of material chemically resistant to the waste and leachate;
		<u>X</u>				(3) Bottom slope design to accomodate for predicted settlement;
		<u>X</u>	_			(4) Demonstration that synthetic drainage material, if used, is equivalent or better than granular material in chemical compatibility, flow under load and protection of geomembrane liner.
				4.	Leach	ate recirculation; (62-701.400(5),FAC)
		<u>X</u>			a.	Describe general procedures for recirculating leachate;
		<u>X</u>			b.	Describe procedures for controlling leachate runoff and minimizing mixing of leachate runoff with storm water;
		<u>X</u>			c.	Describe procedures for preventing perched water conditions and gas buildup;
		<u>X</u>			đ.	Describe alternate methods for leachate management when it cannot be recirculated due to weather or runoff conditions, surface seeps, wind-blown spray, or elevated levels of leachate head on the liner;
*******		_X			e.	Describe methods of gas management to control odors and migration of methane;
		<u>X</u>	—		f.	If leachate irrigation is proposed, describe treatment methods and standards for leachate treatment prior to irrigation over final cover and provide documentation that irrigation does not contribute significantly to leachate generation.

<u>s</u>	LOCATION	N/A N/C
		<u>X</u>
		<u>X</u>
		<u>X</u>
		<u>X</u>
	•	<u>X</u>
		<u>X</u>

5.

- Leachate storage tanks and leachate surface impoundments; (62-701.400(6),FAC)
 - a. Surface impoundment requirements; (62-701.400(6)(b),FAC)
 - (1) Documentation that the design of the bottom liner will not be adversely impacted by fluctuations of the ground water;
 - (2) Designed in segments to allow for inspection and repair as needed without interruption of service;
 - (3) General design requirements;
 - (a) Double liner system consisting of an upper and lower 60-mil minimum thickness geomembrane;
 - (b) Leak detection and collection system with hydraulic conductivity > 1 cm/sec;
 - (c) Lower geomembrane placed on subbase $\stackrel{>}{\sim}$ 6 inches thick with $k < 1 \times 10^{-5}$ cm/sec;
 - (d) Design calculation to predict potential leakage through the upper liner;
 - (e) Daily inspection requirements and notification and corrective action requirements if leakage rates exceed that predicted by design calculations;
 - (4) Description of procedures to prevent uplift, if applicable;
 - (5) Design calculations to demonstrate minimum two feet of freeboard will be maintained;
 - (6) Procedures for controlling vectors and
 off site odors.

<u>s</u>	LOCATION	N/A	N/C			
				b.		e-ground leachate storage tanks; 701.400(6)(c),FAC)
—		<u>X</u>	· 		(1)	Describe tank materials of construction and ensure foundation is sufficient to support tank;
		<u>X</u>			(2)	Describe procedures for cathodic protection if needed for the tank;
		<u>X</u>			(3)	Describe exterior painting and interior lining of the tank to protect it from the weather and the leachate stored;
		<u>X</u>			(4)	Describe secondary containment design to ensure adequate capacity will be provided and compatibility of materials of construction;
		<u>X</u>			(5)	Describe design to remove and dispose of stormwater from the secondary containment system;
		<u>X</u>			(6)	Describe an overfill prevention system such as level sensors, gauges, alarms and shutoff controls to prevent overfilling;
					(7)	Inspections, corrective action and reporting requirements;
		X				(a) Overfill prevention system weekly;
		<u>X</u>				(b) Exposed tank exteriors weekly;
		X	_			(c) Tank interiors when tank is drained or at least every three years;
		<u>X</u>				(d) Procedures for immediate corrective action if failures detected;
		<u>X</u>				(e) Inspection reports available for department review.
				c.		rground leachate storage tanks; 701.400(6)(d),FAC)
		<u>X</u>			(1)	Describe materials of construction;
		<u>X</u>			(2)	A double-walled tank design system to be used with the following requirements;

<u>s</u>	LOCATION	N/A	N/C				
							(a) Interstitial space monitoring at least weekly;
		<u>X</u>					(b) Corrosion protection provided for primary tank interior and external surface of outer shell;
		<u>X</u>					(c) Interior tank coatings compatible with stored leachate;
		<u>X</u>					(d) Cathodic protection inspected weekly and repaired as needed;
		<u>X</u>				(3)	Describe an overfill prevention system such as level sensors, gauges, alarms and shutoff controls to prevent overfilling and provide for weekly inspections;
_		<u>X</u>				(4)	Inspection reports available for department review.
		<u>X</u>			đ.		ale provided for routine maintenance of (62-701.400(6)(e),FAC)
				6.		_	ns construction quality assurance (CQA):
		<u>X</u>			a.	Provi	de CQA Plan including:
		<u>X</u>				(1)	Specifications and construction requirements for liner system;
		<u>X</u>				(2)	Detailed description of quality control testing procedures and frequencies;
-		<u>X</u>				(3)	Identification of supervising professional engineer;
	#-450	<u>X</u>				(4)	Identify responsibility and authority of all appropriate organizations and key personnel involved in the construction project;
	90-000 Sec. 1	<u>X</u>				(5)	State qualifications of CQA professional engineer and support personnel;
		<u>X</u>				(6)	Description of CQA reporting forms and

<u>s</u>	LOCATION	N/A	N/C			
_		<u>X</u>			b.	An independent laboratory experienced in the testing of geosynthetics to perform required testing;
				7. So	il Lin	er CQA (62-701.400(8)FAC)
		<u>X</u>			a.	Documentation that an adequate borrow source has been located with test results or description of the field exploration and laboratory testing program to define a suitable borrow source;
		<u>X</u>	*********		b.	Description of field test section construction and test methods to be implemented prior to liner installation;
 .		<u>X</u>			c.	Description of field test methods including rejection criteria and corrective measures to insure proper liner installation.
				8.	Surfa	ce water management systems; (62-701.400(9),FAC)
		<u>X</u>			a.	Design of surface water management system to isolate surface water from waste filled areas and to control stormwater run-off;
		<u>X</u>			b.	Details of stormwater control design including retention ponds, detention ponds, and drainage ways;
				9.	Gas c	ontrol systems; (62-701.400(10),FAC)
	·	<u>X</u>			a.	Design details for gas control system including collection pipes and vents, and passive venting or vacuum extraction details;
		<u>X</u>			b.	Documentation that the gas control system will not impact the liner or leachate control system;
		<u>X</u>			c.	Proposed methods of odor control including flaring designs in accordance with Chapter 62-296, FAC;
					d.	Description of a routine gas monitoring program to ensure gas control system is operating properly including:
	70-100P-2-1	<u>X</u>				(1) Location of monitoring points;

<u>s</u>	LOCATION	N/A	N/C				
		<u> </u>				(2)	Requirements for quarterly sampling of all monitoring points;
		<u>X</u>				(3)	Description of corrective measures to be completed within 60 days of detection of elevated levels of explosive gases;
		<u>X</u>			e.		iption of condensate collection and sal methods.
				10.	Landi	ill ga	s recovery facilities; (62-701.400(11),FAC)
****		X			a.		mation required in Rules 62-701.320(7) and 1.330(4), FAC supplied;
		<u>X</u>			b.		mation required in Rule 62-701.600(4), FAC
	•	_ <u>X</u>			c.	rates	ate of current and expected gas generation and description of condensate disposal ds provided;
		_ <u>X</u>			d.		iption of procedures for condensate ing, analyzing and data reporting provided;
		_ <u>X</u>			e.		re plan provided describing methods to ol gas after recovery facility ceases tion;
		<u> </u>			f.	if r	rmance bond provided to cover closure costs not already included in other landfill re costs.
		<u>X</u>		11.	docum of p botto	mentation rotection m line	lls designed in ground water, provide on that the landfill will provide a degree on equivalent to landfills designed with rs not in contact with ground water; (12),FAC)

LOCATION	N/A	N/C			
			1.		t a hydrogeological investigation and site report ding at least the following information:
V-71,4054-805-1-1	<u>X</u>			a.	Regional and site specific geology and hydrogeology;
	<u>X</u>			b.	Direction and rate of ground water and surface water flow including seasonal variations;
	<u>X</u>			c.	Background quality of ground water and surface water;
	<u>X</u>			d.	Any on-site hydraulic connections between aquifers;
	<u>X</u>			е.	Site stratigraphy and aquifer characteristics for confining layers, semi-confining layers, and all aquifers below the landfill site that may be affected by the landfill;
	<u>X</u>			f.	Site topography and soil characteristics;
	<u>X</u>			g.	Inventory of all public and private water wells within a one-mile radius of the landfill including well top of casing and bottom elevations, name of owner, age and usage of each well, stratigraphic unit screened, well construction technique and static water level;
	<u>X</u>	-		h.	Description of topography, soil types and surface water drainage systems;
	<u>X</u>			i.	An inventory of all public and private water wells within one mile of the landfill.
	<u>X</u>			j.	Existing contaminated areas on landfill site.
	X		2.	Repor	rt signed, sealed and dated by PE or PG.

I.	GEOTECHNICAL INVESTIGATION REQ	UIREMEN	TTS (62-701.410(2),FAC)
<u>s</u>	LOCATION N/A N/C		
	1.	defin	t a geotechnical site investigation report ing the engineering properties of the site ding at least the following:
<u>X</u>	PSI Report Enclosed	a.	Description of subsurface conditions including soil stratigraphy and ground water table conditions;
X	PSI Report Enclosed	b.	Investigate for the presence of muck, previously filled areas, soft ground, lineaments and sink holes;
<u>X</u>	PSI Report Enclosed	C.	Estimates of average and maximum high water table across the site;
		đ.	Foundation analysis including:
	X		(1) Foundation bearing capacity analysis;
	<u>X</u>		(2) Total and differential subgrade settlement analysis;
	<u>X</u>		(3) Slope stability analysis;
<u>X</u>	PSI Report Enclosed	e.	Description of methods used in the investigation and includes soil boring logs, laboratory results, analytical calculations, cross sections, interpretations and conclusions;
	X	f.	An evaluation of fault areas, seismic impact zones, and unstable areas as described in 40 CFR 258.13, 40 CFR 258.14 and 40 CFR 258.15.
X	PSI Report Enclosed 2.	Repor	t signed, sealed and dated by PE or PG.

J.	VERTICAL E	KPANSIO	N OF	LANDFILI	S (62-701.430, FAC)
<u>s</u>	LOCATION	N/A	N/C	-	
		X_		1.	Describe how the vertical expansion shall not cause or contribute to leachate leakage from the existing landfill or adversely affect the closure design of the existing landfill;
		<u>X</u>	4	2.	Describe how the vertical expansion over unlined landfills will meet the requirements of Rule 62-701.400, FAC with the exceptions of Rule 62-701.430(1)(c),FAC;
		<u>X</u>	*********	3.	Provide foundation and settlement analysis for the vertical expansion;
		_ <u>X</u>		4.	Provide total settlement calculations demonstrating that the final elevations of the lining system, that gravity drainage, and that no other component of the design will be adversely affected;
		_ <u>X</u>		5.	Minimum stability safety factor of 1.5 for the lining system component interface stability and deep stability;
		<u>X</u>		6.	Provide documentation to show the surface water management system will not be adversely affected by the vertical expansion;
—		<u>X</u>		7.	Provide gas control designs to prevent accumulation of gas under the new liner for the vertical expansion.
ĸ.	LANDFILL O	PERATIC	N RE	QUIREMENT	S (62-701.500, FAC)
	 		X	1.	Provide documentation that landfill will have at least one trained operator during operation and at least one trained spotter at each working face; (62-701.500(1),FAC)
				2.	Provide a landfill operation plan including procedures for: (62-701.500(2), FAC)
			_X		 Designating responsible operating and maintenance personnel;
			_X	<u>.</u>	b. Contingency operations for emergencies;
			X	-	c. Controlling types of waste received at the landfill;

<u>s</u>	LOCATION	N/A	N/C			
	**		<u>X</u>		d.	Weighing incoming waste;
		<u> </u>	<u>X</u>		e.	Vehicle traffic control and unloading;
			X		f.	Method and sequence of filling waste;
# Tolomorphism		_	<u>X</u>		g.	Waste compaction and application of cover;
			<u>X</u>		h.	Operations of gas, leachate, and stormwater controls;
			<u>X</u>		i.	Water quality monitoring.
		- —	<u>X</u>	3.	to be where FDEP	de a description of the landfill operation record used at the landfill; details as to location of various operational records will be kept (i.e. permit, engineering drawings, water quality is, etc.) (62-701.500(3),FAC)
			<u>X</u>	4.		be the waste records that will be compiled y and provided to the Department quarterly; (62-701.500(4),FAC)
	77.714.741		<u>X</u>	5.	Descri	be methods of access control; (62-701.500(5),FAC)
	***************************************		_X	6.	landfi	be load checking program to be implemented at the all to discourage disposal of unauthorized wastes a landfill; (62-701.500(6),FAC)
				7.	Descri at the	be procedures for spreading and compacting waste a landfill that include: (62-701.500(7),FAC)
			<u>X</u>		a.	Waste layer thickness and compaction frequencies;
·			<u>X</u>		b.	Special considerations for first layer of waste placed above liner and leachate collection system;
	-		<u>X</u>		c.	Slopes of cell working face and side grades above land surface, planned lift depths during operation;
			<u>X</u>		đ.	Maximum width of working face;

<u>s</u>	LOCATION	N/A	N/C		
	•			e.	Description of type of initial cover to be used at the facility that controls:
			<u>X</u>		(1) Disease vector breeding/animal attraction
			<u>X</u>		(2) Fires
·			<u>X</u>		(3) Odors
			<u>X</u>		(4) Blowing litter
			<u>X</u>		(5) Moisture infiltration
			<u>X</u>	f.	Procedures for applying initial cover including minimum cover frequencies;
		<u> </u>	<u>X</u>	g.	Procedures for applying intermediate cover;
		<u> </u>	<u>X</u>	h.	Time frames for applying final cover;
			<u>X</u>	i.	Description of litter policing methods;
			<u>X</u>	j.	Erosion control procedures.
			8.		ibe operational procedures for leachate management ding; (62-701.500(8),FAC)
	Appendix B*	·	<u>X</u>	a.	Leachate level monitoring, sampling, analysis and data results submitted to the Department;
			<u>X</u>	b.	Operation and maintenance of leachate collection and removal system, and treatment as required;
			<u>X</u>	c.	Procedures for managing leachate if it becomes regulated as a hazardous waste;
			<u>X</u>	d.	Agreements for off-site discharge and treatment of leachate;
			<u>X</u>	e.	Contingency plan for managing leachate during emergencies or equipment problems;
			<u>X</u>	f.	Procedures for recording quantities of leachate generated in gal/day;
		<u> </u>	<u>X</u>	g.	Procedures for comparing precipitation experienced at the landfill with leachate generation rates.

*Taken from Part K of Operating Permit Application

<u>s</u>	LOCATION	N/A	N/C			
·			<u>X</u>	9.	Descr: landf	ibe routine gas monitoring program for the ill as required by Rule 62-701.400(10),FAC; (62-701.500(9),FAC)
			<u>X</u>	10.	landf.	ibe procedures for operating and maintaining the ill stormwater management system to comply with tandards of Chapters 62-3, 62-302 and 62-25, FAC; 62-701.500(10),FAC)
				11.		ment and operation feature requirements; 01.500(11),FAC)
			<u>X</u>		a.	Sufficient equipment for excavating, spreading, compacting and covering waste;
			X		b.	Reserve equipment or arrangements to obtain additional equipment within 24 hours of breakdown;
			X		C.	Communications equipment;
			<u>X</u>		d.	Personnel shelter and sanitary facilities, first aid equipment;
			<u>X</u>		e.	Dust control methods;
			X		f.	Fire protection capabilities and procedures for notifying local fire department authorities in emergencies;
			<u>X</u>		g.	Litter control devices;
			<u>X</u>		h.	Signs indicating operating authority, traffic flow, hours of operation, disposal restrictions.
			<u>X</u>	12.	insid acces	de a description of all-weather access road, e perimeter road and other roads necessary for s which shall be provided at the landfill; (62-701.500(12),FAC)

<u>s</u>	LOCATION	N/A	N/C			•					
				13.	Additional record keeping and reporting requirements; (62-701.500(13),FAC)						
			<u>X</u>		and st	s used for developing permit applications applemental information maintained for the period of the landfill;					
		<u>·</u>	<u>X</u>		mainte	ring information, calibration and nance records, copies of reports required mit maintained for at least 10 years;					
		· · · · ·	<u>X</u>		c. Backgr mainta landfi	ined for the design period of the					
			<u>X</u>		of cor areas	in annual estimates of the remaining life astructed landfills and of other permitted not yet constructed and submit this te annually to the Department.					

<u>s</u>	LOCATION	N/A	N/C			•
			<u>X</u> 1.	submi: water	tted de and le	ty and leachate monitoring plan shall be escribing the proposed ground water, surface eachate monitoring systems and shall meet at ollowing requirements;
			<u>X</u>	a.	and s	on the information obtained in the geological investigation and signed, dated ealed by the PG or PE who prepared it; 01.510(2)(a),FAC)
			<u>X</u>	b.	Compr	sampling and analysis preformed by izations having Department approved ehensive Quality Assurance Plans; (62-10(2)(b),FAC)
				c.		d water monitoring requirements; 701.510(3),FAC)
			<u>X</u>		(1)	Detection wells located downgradient from and within 50 feet of disposal units;
	Direct law or		<u>X</u>		(2)	Downgradient compliance wells as required;
			<u>X</u>		(3)	Background wells screened in all aquifers below the landfill that may be affected by the landfill;
<u>X</u>	Plan C-13				(4)	Location information for each monitoring well;
_		X			(5)	Well spacing no greater than 500 feet apart for downgradient wells and no greater than 1500 feet apart for upgradient wells unless site specific conditions justify alternate well spacings;
X	Plan C-12				(6)	Well screen locations properly selected;
<u>X</u> _	DEP/SWFWMD	Pro	cedures		(7)	Procedures for properly abandoning monitoring wells;
		-X			(8)	Detailed description of detection sensors if proposed.

NOTE: Relocation of monitoring well shown on plans previously submitted. Well constructio detail is included on plans.

<u>s</u>	LOCATION	N/A	N/C	đ.	Surface water monitoring requirements;
				u.	(62-701.510(4), FAC)
			<u>X</u>		 Location of and justification for all proposed surface water monitoring points;
		<u> </u>	<u>X</u>		(2) Each monitoring location to be marked and its position determined by a registered Florida land surveyor;
			<u>X</u>	e.	Leachate sampling locations proposed; (62-701.510(5), FAC)
				f.	Routine sampling frequency and requirements; (62-701.510(6),FAC)
			<u>X</u>		(1) Background ground water and surface water sampling and analysis requirements;
			<u>X</u>		(2) Leachate semi-annual and annual sampling and analysis requirements;
<u>. </u>			X		(3) Detection well semi-annual sampling and analysis requirements;
	·		<u>X</u>		(4) Compliance well sampling and analysis requirements;
			<u>X</u>		(5) Surface water sampling and analysis requirements.
			X	g.	Describe procedures for implementing assessment monitoring and corrective action as required; (62-701.510(7),FAC)
			<u>X</u>	h.	Water quality monitoring report requirements; (62-701.510(9),FAC)
			<u>X</u>		(1) Semi-annual report requirements;
			X		(2) Bi-annual report requirements signed, dated and sealed by PG or PE.

M.	SPECIAL WAS	TE HAN	DLING	REQUIRE	MENTS	(62-701.520, FAC)					
<u>s</u>	LOCATION	N/A	N/C								
		·	<u>X</u>	1.		ibe procedures for managing motor vehicles; 01.520(1),FAC)					
			. X	2.		ibe procedures for landfilling shredded waste; 01.520(3),FAC)					
			<u>X</u>	3.	Describe procedures for asbestos waste disposal; (62-701.520(4),FAC)						
	***		<u>X</u>	4.	Descr (62-7	<pre>ibe procedures for contaminated soil disposal; 01.520(5), FAC)</pre>					
N.	LANDFILL FI	NAL CL	OSURE	REQUIRE	MENTS	(62-701.600,FAC)					
				1.	Closu	re schedule requirements; (62-701.600(2),FAC)					
		<u>X</u>			a.	Documentation that a written notice including a schedule for closure will be provided to the Department at least one year prior to final receipt of wastes;					
		<u>X</u>			b.	Notice to user requirements within 120 days of final receipt of wastes;					
	***************************************	. <u>X</u>			c.	Notice to public requirements within 10 days of final receipt of wastes.					
				2.	Closu 701.6	re permit general requirements; (62-00(3),FAC)					
		X			a.	Application submitted to Department at least 90 days prior to final receipt of wastes;					
					b.	Closure plan shall include the following:					
		<u>X</u>				(1) Closure report;					
		<u>X</u>	**********			(2) Closure design plan;					
		<u>X</u>				(3) Closure operation plan;					
		X				(4) Closure procedures;					

(5) Plan for long term care;

<u>s</u>	LOCATION	N/A	N/C				•
		_ <u>X</u>				(6)	A demonstration that proof of financial responsibility for long term care will be provided.
				3.	Clos	ure rep	ort requirements; (62-701.600(4),FAC)
					a.	Gener	al information requirements;
		<u>X</u>				(1)	Identification of landfill;
		X_				(2)	Location, description and vicinity map;
		<u>X</u>				(3)	Total acres of disposal areas and landfill property;
		X				(4)	Legal property description;
		X				(5)	History of landfill;
		<u>X</u>				(6)	Identification of types of waste disposed of at the landfill.
		<u>X</u>			b.	quali	echnical investigation report and water ty monitoring plan required by Rule 01.330(4),FAC;
		<u>X</u>			c.	prese	use information report indicating: ification of adjacent landowners; zoning; ent land uses; and roads, highways -of-way, or easements.
	-	<u>X</u>			d.	landf inclu	et on actual or potential gas migration at ills containing biodegradable wastes adding detailed description of test and stigation methods used;
		<u>X</u>			е.	landf of g and conce	t assessing the effectiveness of the fill design and operation including results geotechnical investigations, surface water storm water management, gas migration and entrations, condition of existing cover, and see of waste disposed of at the landfill;
				4.	Closu	ıre de ıre des	sign requirements to be included in the ign plan: (62-701.600(5),FAC)
		X			a.	Plan	sheet showing phases of site closing;

<u>s</u>	LOCATION	N/A	N/C								
		<u>X</u>		b.	Drawing propose	gs showing ed final grade		topo	graphy	and	
		<u>X</u>		c.		ions to clo ed design dime		when	they	reach	
		<u>X</u>		d.	Final e	elevations bef	ore settle	ment;			
	•	<u>X</u>		e.	down s	lope design	ways, ener	gy dis	sipator	s and	
				f.		iscussion of expected precipitation effects; inal cover installation plans including:					
—	<u> </u>	<u>X</u>				CQA plan for cover;	installing	and t	esting	final	
	***************************************	<u>X</u>				Schedule for final receipt		final	cover	after	
		<u>X</u>				Description o				pecies	
		<u>X</u>				Top gradient minimize eros		maximiz	e runo:	ff and	
		<u>X</u>				Provisions fo			to be	used	
				g.	Final o	cover design 1	equirement	s:			
		<u>X</u>			(1)	Protective so	il layer de	sign;			
		X			(2)	Barrier soil	layer desig	n;			
		<u>X</u>			(3)	Erosion contro	ol vegetati	on;			
		X			(4)	Geomembrane ba	arrier laye	r desig	m.		
		<u>X</u>		h.	Propose	ed method of s	stormwater	control	;		
		<u>X</u>		i.	Propose	ed method of a	access cont	rol;			
		<u>X</u>		j.		otion of prop ll, if any;	osed final	use of	the o	closed	

<u>s</u>	LOCATION	N/A N/C			
			5.		re operation plan shall include: 01.600(6),FAC)
		<u>X</u>		a.	Detailed description of actions which will be taken to close the landfill;
		<u>X</u>		b.	Time schedule for completion of closing and long term care;
		<u>X</u>		C.	Describe proposed method for demonstrating financial responsibility;
		<u>X</u>		đ.	Indicate any additional equipment and personnel needed to complete closure.
		<u>X</u>		e.	Development and implementation of the water quality monitoring plan required in Rule 62-701.510, FAC.
		<u>X</u>		f.	Development and implementation of routine gas monitoring program required in Rule 62-701.400(10)(c), FAC.
		<u>X</u>	6.	proce	fication for and detailed description of edures to be followed for temporary closure of the fill, if desired; (62-701.600(7),FAC)

ο.	CLOSURE PROCED	URES	(62-	-701.61	.0,FAC)
<u>s</u>	LOCATION N	/ <u>A</u>	N/C		
	-	X		1.	Survey monuments; (62-701.610(2),FAC)
		X_		2.	Final survey report; (62-701.610(3),FAC)
		<u>X</u> _		3.	Certification of closure construction completion; (62-701.610(4),FAC)
		X		4.	Declaration to the public; (62-701.610(5),FAC)
		<u>X</u> _		5.	Official date of closing; (62-701.610(6),FAC)
		<u>X</u> _		6.	Use of closed landfill areas; (62-701.610(7),FAC)
P.	LONG TERM CARE	REQ	UIREME	NTS (6.	2-701.620, FAC)
<u>X</u>	See Appendix	C C		1.	Right of property access requirements; (62-701.620(4),FAC)
<u>X</u>	See Appemdix	<u>C</u>		2.	Successors of interest requirements; (62-701.620(5),FAC)
<u>X</u>	See Appendix	C C		3.	Requirements for replacement of monitoring devices; (62-701.620(7),FAC)
<u>X</u>	See Appendix	<u>C</u>	_	4.	Completion of long term care signed and sealed by professional engineer (62-701.620(8), FAC).
Q.	FINANCIAL RESP	onsi	BILITY	REQUI	REMENTS (62-701.630,FAC)
			<u>X</u>	1.	Provide cost estimates for closing, long term care, and corrective action costs estimated by a PE for a third party performing the work, on a per unit basis, with the source of estimates indicated; $(62-701.630(3)\&(7), FAC)$.
			<u>X</u>	2.	Describe procedures for providing annual cost adjustments to the Department based on inflation and changes in the closing, long-term care, and corrective action plans; (62-701.630(4)&(8), FAC).
		_	<u>X</u>	3.	Describe funding mechanisms for providing proof of financial assurance and include appropriate financial assurance forms; (62-701.630(5),(6),&(9), FAC).

<u>s</u>	LOCATION	N/A N/C	_	
		<u>X</u>	1.	Demonstration that facility does not pose a bird hazard to aircraft as specified in Rule 62-701.320(12)(b), FAC.
		<u>X</u>	2.	Demonstration that facility does not restrict the flow of the 100-year flood, reduce water storage capacity or result in wash-out of solid waste as specified in Rule 62-701.340(4)(b), FAC.
		<u>X</u>	3.	Demonstration that facility is not located in a fault area, seismic zone or unstable area as specified in Rule 62-701.410(2)(c), FAC.
			4.	Request for extension of closure criteria as specified in Rule 62-701.640(2)(a) & (2)(b), FAC.
_		<u>X</u>	-	 a. Demonstration of no alternative disposal capacity.
	-	<u>X</u>	-	b. Demonstration of no threat to human health or the environment.
s.	MATERIALS I	RECOVERY FA	CILITY RE	QUIREMENTS (62-701.700,FAC)
	<u> </u>	v		
		<u> </u>	1.	Demonstration of financial assurance to cover closing costs, if required; (62-701.700(4),FAC)
		<u>X</u>	2.	
			-	costs, if required; (62-701.700(4),FAC) Materials recovery facility requirements;
		<u>X</u>	-	costs, if required; (62-701.700(4),FAC) Materials recovery facility requirements; (62-701.700,FAC) a. Submit information required in Rule 62-701.320,FAC
		<u>X</u> <u>X</u>	-	Materials recovery facility requirements; (62-701.700,FAC) a. Submit information required in Rule 62-701.320,FAC b. Submit an engineering report including the

<u>s</u>	LOCATION	N/A	N/C		
***************************************		<u>X</u>	- .	(3)	Description of operation and functions of all processing equipment with design criteria and expected performance;
		<u>X</u>		(4)	Description of flow of solid waste, expected regular facility operations, procedures for start up and shut down, potential safety hazards and control methods including fire protection;
distribution		<u>X</u>	_	(5)	Description of loading, unloading, and processing areas;
		<u>X</u>		(6)	Identification and capacity of temporary on-site storage areas for materials handled and provisions for solid waste and leachate containment;
		<u>X</u>		(7)	Identification of potential ground water and surface water contamination;
		<u>X</u>		(8)	Plan for disposal of unmarketable recyclables and residue and contingencies for waste handling during breakdowns.
			c.	Subm	t the following operational information:
		<u>X</u>		(1)	Operation and maintenance manual;
		<u>X</u>		(2)	Waste control plan to manage unauthorized wastes;
	****	_ <u>X</u>		(3)	Contingency plan for emergencies;
		<u>X</u>		(4)	Closure plan including the following:
		<u>X</u>			(a) Notification to Department 180 days prior to closure;
		<u>X</u>			(b) Procedures for removal of all waste within 30 days of receipt of final waste;
		<u>X</u>			(c) Completion of closure activities within 180 days of receipt of final waste and notification to the

Department that closure is complete.

Effective 05-19-94

T. CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

A. Applicant

The undersigned applicant or authorized representative of
Manatee County is aware that statements made in this form and
sttached information are an application for a Construction-Other Permi
rom the Florida Department of Environmental Regulation and certifies that th
nformation in this application is true, correct and complete to the best of his
mowledge and belief. Further, the undersigned agrees to comply with the provisions
of Chapter 403, Florida Statutes, and all rules and regulations of the Department.
t is understood that the Permit is not transferable, and the Department will be
otified prior to the sale or legal transfer of the permitted facility.

Signature of Applicant or Agent

Len Bramble, P.E. Director of Public Works
Name and Title

Date: 1-7-2000

Attach letter of authorization if agent is not a governmental official, owner, or corporate officer.

B. Professional Engineer Registered in Florida or Public Officer as required in Section 403.707 and 403.707(5), Florida Statutes.

This is to certify that the engineering features of this solid waste management facility have been designed/examined by me and found to conform to engineering principals applicable to such facilities. In my professional judgement, this facility, when properly maintained and operated, will comply with all applicable statutes of the State of Florida and rules of the Department. It is agreed that the undersigned will provide the applicant with a set of instructions of proper maintenance and operation of the facility.

Signature

A. Street Lee, P.E.

Name and Title (please type)

49212

Florida Registration Number (please/affix seal)

Committee in the Committee of the Commit

• Date:

McKim & Creed, PA

601 Cleveland St., Suite 205

Mailing Address

Clearwater, FL 33755

City, State, Zip Code

(727) 442-7196

Telephone Number

DEP FORM 62-701.900(1) Effective 05-19-94

Page 41 of 41

APPENDIX A

Section G – Item 3 Leachate Collection and Removal System

Narrative Overview

This project involves the replacement of an existing section of the leachate collection system along the western side of the Stage III area. The existing leachate system is currently functional however the County desires to improve the functionality of the system to better control the level of ground water inside the contained landfill area. This work will be in conjunction with the construction of an access roadway along the perimeter of the Stage III area for access to the County's Southeast Regional Wastewater Treatment plant. Relocating this access will allow the County to eliminate the current access road in the long term that currently separates the Stage III area from the other sections of the landfill to provide better traffic flow.

Several improvements are to be completed with this minor system modification. These are:

- 1. Increase depth of the pipe collection system to aid in lowering the water level and thereby increasing the inward gradient along the western edge of the landfill.
- 2. Eliminate the existing surface water infiltration collection system by installing new surface water catch basins. This will improve the surface drainage in the western portion of the Stage III area and will reduce the volume of leachate that has to be collected by the leachate collection pipeline.
- 3. The replacement of the leachate collection pipeline will allow the County to improve the hydraulic conditions of the system by gaining an improved horizontal and vertical alignment
- 4. The existing leachate pump station in the northwest corner of the Stage III area will be lowered to improve the capability of the system to effectively lower the ground water level inside the slurry wall.
- 5. The pumping capacity of the upgraded pump station will be increased from 600 gpm to 800 gpm which will improve the effectiveness of the system in this area.

Materials of construction are selected to be resistant to chemical attack from leachate. The piping for the system is proposed to be HDPE pipe that will be more rigid and stronger than the existing corrugated HDPE material and easier to clean and maintain than the existing system. The manholes are all to be constructed of HDPE. Details and specifications of these materials is included in the plans submitted.

APPENDIX B

PART K.

LANDFILL OPERATION REQUIREMENTS

PART K. LANDFILL OPERATION REQUIREMENTS

1. TRAINED OPERATORS

At least one trained operator and spotter will be site at all times of waste disposal operations. A current copy of training documentation is included in Appendix E.

2. OPERATION PLAN

See Appendix A.

3. OPERATING RECORD

The Operating Record consist of all records, reports, analytical results, demonstrations, and notifications required by Chapter 62-701, F.A.C., all permits and permit modifications, and training records. The Operating Record will be maintained within the filing system at the landfill.

4. WASTE RECORDS

Monthly records are developed for the waste categories received at the landfill. Current categories include:

Residential Mixed, Commercial Mixed (Long Boat Key-South), Clean-up, Illegal, Sludge, Out-of-County, C&D, Yard Waste, Mulch, Mulch (North County), Fuel, Debris, Tires, Tires (Out-of-County), Illegal Tires, White Goods, White Goods (Out-of-County)

Monthly waste records are submitted to the Department on a quarterly basis.

5. ACCESS CONTROLS

Access to the landfill is maintained by a six-foot high chain link fence along the entrance of the landfill and a barbed-wire fence around the remainder of the site. The access gates are locked at the end of each business day.

6. LOAD CHECKS

The County has a random load inspection program in-place and inspects at least three loads per week. Spot checking also occurs at the active face. If the spotters detect a load of unauthorized waste while the hauler is still present, the waste is reloaded into the vehicle and is removed from the site. If the hauler cannot be identified, it is the County's responsibility to remove the waste from the landfill for proper disposal.

7. WASTE COMPACTION

a. Waste Layer Thickness

Waste is typically dumped at the toe of the working face and is spread over the face in a maximum of two-foot lifts prior to compaction. This procedure continues throughout the day for a typical lift thickness of no more than 20 feet.

b. First Waste Layer

This section is not applicable for this permit application.

c. Slopes and Lift Depths

Interior slopes may be as great as 3:1 (H:V) other than the active face. The proposed final slope is also 3:1. To minimize the cover soil requirement, the lift depths are should be limited to 20 feet or less.

d. Working Face

The active face width should be no greater than necessary to accommodate the peak number of disposal vehicles at one time. The wider the active face, the more cover soil is used. The County use an active face of 150 feet. The working area of the active face slope is approximately 5:1. Active face side slopes are limited to 3:1. The objective for the dimensions of the active face is to maximize the volume to surface area ratio.

e. <u>Initial Cover Controls</u>

This permit application considers soil cover as the only initial cover material. Soil will be applied at a minimum thickness of six inches to control vectors, fires, odors, blown litter, and water infiltration.

f. Initial Cover Application Procedures

During the working day, initial cover will be stockpiled near the active face for use at the end of each day. Dozers used for spreading waste will spread the cover soil over the exposed refuse.

g. Intermediate Cover

An additional 12 inches of cover (intermediate cover) will be placed on areas that are not expected to receive additional wastes within 180 days. These areas will be grassed to reduce erosion. Prior to placement of additional wastes in these areas, the intermediate cover may be removed and stockpiled adjacent to the active face for use as initial cover.

h. Final Cover Timing

The next closure project is planned to occur in the year 2000 as shown in the DEP-approved Fill Sequence Plan. The timing of this partial closure sequence was due to the availability of areas at final grade. Based on the waste generation projections used in the Fill Sequence development, the slopes along the south and west sides of Stage I will not be at final grade until 1999 and the top deck available for closure in 2000. Therefore, to reduce construction costs associated with contractor mobilization, economies of scale, and engineering costs of design and construction related services, one closure project was proposed to include all of the available areas in Stage I upon moving to Stage III. This area will receive final cover as scheduled in the DEP-approved Fill Sequence Plan.

I. Litter Policing

Litter fences are installed near the active face to capture wind-blown litter. The site is policed when needed to remove additional litter from the site.

j. Erosion Control

Erosion has been controlled with grassing and terraces. Manatee County has implemented an aggressive sodding plan to protect side slopes from erosion. Temporary piping will be used to remove runoff from the terraces rather than allowing the terrace to merely reduce the sheet flow velocity. This temporary piping will drain collected runoff for discharge into the perimeter stormwater pond. Temporary discharge structures will be used to control erosion at the stormwater pond edge. These drainage features are shown in the approved Fill Sequence Plan.

8. LEACHATE MANAGEMENT

Leachate Level Monitoring

Leachate levels and adjacent groundwater levels outside of the slurry wall are monitored monthly with use of piezometers and wells, respectively. The leachate collection system pumping is engaged to provide an inward gradient.

An inward gradient is maintained throughout most of the site. Stage III (PZ 15) has been the only area containing waste to have consecutive monthly outward gradients from May 1995 to November 1996. Over this time period, this piezometer has had an average outward gradient of 1.1 feet. Manatee County is implementing measures to create an inward gradient in this area. Table K-1 summarizes the gradient across the slurry wall.

Table K-1
Groundwater Gradient Data

										G	RADIE	TV				·				
WELL#	STAGE	5/95	6/95	7/95	8/95	9/95	10/95	11/95	12/95	2/96	3/96	4/96	5/96	6/96	7/96	7/96	8/96	9/96	10/96	11/96
MW 5	ľ	0	0	0	0	0	0	0		Ó	0	2.45	1.82	2.92	3.37	3.37	1.35	1.97	2.34	2.3
MW 2/PZ 2	1	3.7	4.86	3.22	5.05	2.01	5.14	2.51	0.83	3.46	3.43	2.61	1.98	2.76	3.32	3.32	3.03	1.94	2.47	2.07
MW 1/PZ 3	1	5.55	2.34	2.16	2.45	1.98	0.69	1.62	2.08	1.31	2.44	1.96	5.14	3.68	5.02	5.02	4.24	5.13	4.48	3.72
CW 4/PZ 4	1	3.8			-4.77							5.1	4.44	3.2	5.21	5.21	4.92	4.23	3.88	5.14
CW 5A/PZ 5	1		5.35	0.14	8.62	8.81	9.05	9.06	8.52	8	7.9	7.61	6.67	7.12	7.9	7.9	7.07	6.16	6.53	5.6
PZ6	1		-31	-31.3	-28.8	-31.6	-31.7	-31.1	-32	-29.3	-30.3	-32.3	-32.5	-30.5	-31.5	-31.5	-31.5	-30.6	-30.8	-30.5
MW 6/PZ 7		2.8	4.13	3.52	1.45	3.45	4.4	2.28	0.87	4	3.89	3.17	2.67	3.58	3.63	3.63	3.64	3.95	3.37	1.69
LR2-5/PZ 8	- 11	-0.48	-0.18	-0.98	-1.99	-1.96	1.44	-3.3	-0.84	-2.16	-0.22	1.98	2.86	3.07	3.27	3.27	4.64	3.31	2.11	1.03
LR2-3/PZ 9	!	-4.27	-3.92	-4.64	-5.45	-6.16	-2.62	-6.05	-4.78	-5.34	-4.66	-1.22	-0.59	-0.79	-1.39	-1.39	1.6	-0.31	-1.81	-3.27
LR2-2/PZ 10		-0.27	-0.61	-1.77	-2.67	-2.61	0.79	-3.41	-2.14	-2.26	-0.4	3.1	7.15	2.8	2.01	2.01	6.68	3.61	2.21	-0.52
LR2-1/PZ 11		1.5	1.69	0.84	-0.97	-0.28	4.48		2.43	0.08	2.16	5.16	6.13	5.87	4.85	4.85	7.98	5.15	4.01	2.23
GC 2/PZ 12	III	0.57	3.05	1.62	0.6	1.18	1.54	2.51	2.47	3.41	3.98	3.75	1.24	4.47	4.16	4.16	2	5.48	2.67	1.48
GC 3/PZ 13	111	1.49	2.32	2.18	0.48	3.14	3.43	2.52	2.36	2.39	2.99	2.67	1.32	4.29	4.03	4.03	1.72	3.04	1.42	1.4
GC 4/PZ 14	Ш	0.22	2.51	8.2	-3.16	0.19	0.69	0.9	0.57	0.87	1.93	1.05	0.06	2.04	1.74	1.74	0.91	0.39	1.03	0.19
GC 1A/PZ 15	111		-1.36	-0.42	-3.26	-1.51	-1.44	-1.18	-1.01	-1.66	0.07	-0.24	-0.26	0.44	-1.02	-1.02	-3.11	-1.01	-1.15	-0.99
PZ 15A	111	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
GC 5/PZ 16	111	0.51	2.48	0.48	-2.33	0.26	0.25	0.34	0.39	0.27	0.38	0.76	5.84	1.34	1.74	1.74	-0.7	1.04	0.5	-0.59
GC 6/PZ 17	111	2.28	2.45	3.24	0.14	1.83				0.94	2.74	2.86	3.8	3.62	2.45	2.45	-0.73	2.14	1.64	1.98

b. Operation and Maintenance of Leachate Collection System

Visual observations of flow rates from various areas of the landfill are recorded to indicate possible problems with the leachate collection system. In the event a suspected block has occurred, the leachate lines will be inspected with a TV camera, and if appropriate, cleaned by hydrojetting. As required by permit the leachate collection lines were inspected via TV on November 1997. This inspection revealed a broken leachate collection pipe in Stage III near Piezometer 15. This pipe is being repaired.

c. Leachate as Hazardous Waste

Leachate from the landfill has historically been very weak and management as a hazardous waste is not necessary. Therefore, it is not included in this application.

d. Off-Site Discharge Agreements

All leachate is treated at a County-owned wastewater treatment plant adjacent to the landfill.

e. <u>Leachate Management Contingency Plan</u>

The Lena Road Landfill is located adjacent to a County owned waste water treatment plant. Leachate is collected at the landfill and pumped via pipeline to the treatment plant.

In the event of short duration system failure, the landfill can be used to store leachate. The County intends to maintain a one-foot inward gradient across the slurry wall. Based on average flow rates, each inch of storage in the landfill will provide over two weeks of storage volume. Thus, only six inches of the available volume would be used in a three month period. In the event sufficient storage is not available in the landfill, one of the options described in the following paragraph can be used.

In the event of prolonged lift station failure or pipeline failure, portable pumps and/or temporary piping can be used to pump the collected leachate to the treatment plant.

In the event of an extended power outage at the landfill, the County will rent a portable generator to provide power to the lift station.

Any treatment plant operational or power problems will be addressed by the treatment plant as a part of its permitting procedures. A generator is available to provide emergency power at the treatment plant.

Leachate can also be trucked to the County's Southwest Treatment Plant.

f. Leachate Generation Recording

Daily leachate generation records are obtained from a flow totalizer on the three pump stations discharging to the leachate pond and to the wastewater treatment plant. The pump stations include two for the Stage I area and one for Stage III.

g. <u>Precipitation/Leachate Comparison</u>

Monthly precipitation records were compared to leachate generation records. The leachate/rainfall records from May 1995 to November 1996 are shown in Table K-2. The accompanying figure shows the a graphical representation for the data. Also included with this table is the quantity of leachate that is apparently recirculated back into landfill from the leachate pond. This "recirculation" is passive in nature and is driven by the head difference between the leachate pond and the leachate level in the landfill.

9. GAS MONITORING

The landfill has a routine gas migration monitoring plan in-place. Gas migration is monitored using the gas monitoring wells around the site. While sampling is conducted monthly, the minimum sample frequency for this permit shall be quarterly. With the presence of the slurry wall and surrounding pond, gas migration is extremely unlikely. Monitoring results are presented in Table K-3. For ease reading this table, LEL concentration values of zero were not included. No data available is indicated with a "dash".

Two migration monitoring locations are proposed to be eliminated. These locations (GMP 7 and GMW 18) are both within the Stage III fill area. Gas migration within the landfill adjacent to abandoned structures is not applicable.

10. STORMWATER MANAGEMENT

The surface water management system is divided into three separate and distinct drainage basins (Stage I, II and III). Stage I utilizes perimeter ditches to route stormwater runoff to the stormwater pond located at the southwest corner of Stage I. Stage I discharges to Cypress Stand via an underdrain filter system located beneath the west perimeter ditch, and an overflow weir also located in the southwest corner of Stage I. The majority of runoff collected in the stormwater pond is treated in the adjacent wastewater treatment facility prior to discharge.

Stages II and III were permitted by Southwest Florida Water Management District in August 1990, (MSSW Permit No. 403143.01). The stormwater management systems for Stages II and III consist of 25 foot wide perimeter ditches, ten inch underdrain filtration pipes, and grate inlets. Attenuation is accomplished within the perimeter ditches through raised grate inlets. The perimeter ditches for Stages II and III were constructed several feet above the existing grade to allow separation between the underdrain filter system and the seasonal high water table.

According to the SWFWMD Staff Report dated July 18, 1990:

"The post-development peak discharge rate will equal the pre-development rate of 350 cfs for the 25 year - 24 hour rainfall event of 8.0 inches. The Department of Regulation issued a dredge and fill permit which included stormwater management for this project. The system approved by DER is an effluent filtration system designed to treat the first 0.5 inches of runoff with the total treatment volume recovered within the required 36 hours. This design meets the criteria as established

Table K-2
Rainfall / Leachate Comparison

		Leachate (Million Gallons)											
Month	Rain (in)	Stage I	Stage III	Total	Treated	Recirculation							
May-95	1.34	2.68	3.68	6.35	3.63	2.72							
Jun-95	8.43	15.00	1.25	16.25	8.28	7.97							
Jul-95	11.21	13.21	2.02	15.23	7.75	7.47							
Aug-95	14.25	10.89	6.53	17.42	10.63	6.79							
Sep-95	8.55	8.76	5.84	14.60	13.81	0.79							
Oct-95	8.97	12.23	8.38	20.61	13.56	7.05							
Nov-95	1.2	8.73	6.75	15.48	11.51	3.97							
Dec-95	1.3	4.42	1.89	6.30	9.38	-3.08							
Jan-96	0.86	1.93	1.49	3.42	1.19	2.23							
Feb-96	1.2	2.05	1.42	3.47	3.43	0.04							
Mar-96	5.55	3.30	2.36	5.66	7.32	-1.66							
Apr-96	1.46	8.82	2.91	11.73	5.60	6.13							
May-96	7.76	10.13	2.32	12.45	2.52	9.93							
Jun-96	7.43	10.07	4.45	14.52	3.43	11.09							
Jul-96	4.81	12.85	4.89	17.74	9.34	8.41							
Aug-96	5.78	9.28	2.19	11.47	1.75	9.72							
Sep-96	3.56	8.00	3.94	11.95	2.12	9.83							
Oct-96	4.31	8.82	4.25	13.07	2.97	10.10							
Nov-96	0.5	4.41	1.75	6.16	1.55	4.61							
Average	5.183	8.19	3.59	11.78	6.30	5.48							




Table K-3
Landfill Gas Migration Monitoring Data

								LFG	Migr	ation	Well									L	FG N	lonit	orin	g Po	int	
Month	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	1	2	3	4	5	6	7	8
May-95	2			8							1				8				-	-	 	-	-	-	-	-
Jun-95		2	1	5	2	2		2				1						2				-	-	_	-	
Jul-95	2						•						3					70					_			╁
Aug-95											ļ						l —									\vdash
Sep-95																	l	· · · · · ·				 	-		-	
Oct-95														48									-	 		†
Nov-95		,																				\vdash	-		-	_
Dec-95																							-		-	
Jan-96													-							2	4		3		2	\vdash
Feb-96		2																	1		1					
Mar-96												1	1	1	1.		2	1	1	1	1	1		2	3	1
Apr-96																										
May-96																	-				-					
Jun-96													7	29				23					3			
Jul-96														12				9								
Aug-96											-		8	17												
Sep-96											11															
Oct-96											2			$\neg \neg$	-											

in Chapter 40D-4, F.A.C." and,

"Grate inlets at elevations set to detain the necessary storage volumes will discharge into an existing ditch or sheet flow to existing wetlands."

At final buildout, the stormwater systems for Stages II and III will collect the runoff from 118 and 58 acres, respectively. The drainage from the scale, administrative and maintenance facilities flows to the Stage III drainage system. Currently, the only stormwater collected, conveyed, and discharged through these underdrain systems is that rainfall that falls directly into the ditches themselves.

11. EQUIPMENT/OPERATION FEATURES

a. Sufficient Equipment

The County has sufficient equipment to provide flexible landfill operations. Table K-5 provides a list of the current landfill heavy equipment for daily operations.

b. Reserve Equipment

The above table indicates the County possesses sufficient equipment to operate the landfill. In the event the dozer is out of service, the compactors can be used to spread refuse over the active face. The County can rent needed equipment in the event needed equipment is not available from County sources within 24 hours.

c. <u>Communication Equipment</u>

All equipment operators and traffic controllers are equipped with hand held radios. This radio transmission service links the field personnel to the office and management.

d. Shelter/Sanitation/First Aid Features

Shelter and sanitation facilities are provided at the scale house and landfill office. First aid kits are provided in the cab of all heavy equipment vehicles.

e. Dust Control

Dust control is provided with use of a water wagon on the internal access roads. Dust is also controlled with the use of vegetation on the slopes of the filled areas.

f. Fire Protection

Fire protection in the working face is provided with the use of stockpiles of soil adjacent to the active face. Water wagons for dust suppression are also available for fire protection. In the event of a hot load, the hauler is directed to place the load in a containable area for extinguishing the fire. The load will be monitored for several days to insure the fire is completely out. Upon complete satisfaction the fire is extinguished, the load will be moved to the active face for proper disposal. In the event

the County personnel can not extinguish a fire, the Manatee County Fire Department will be notified for assistance. The heavy equipment are also provided with fire extinguishers.

g. <u>Litter Control Devices</u>

Litter control fences are used near the active face to control litter. Also, the chain link fence along entrance offers secondary control of blowing litter.

Table K-4 LANDFILL EQUIPMENT

YEAR	MAKE	MODEL	DESCRIPTION
1990			WATER TANKER
1989	CATERPILLAR	623E	PAN
1996	CATERPILLAR	623F	PAN
1996	CATERPILLAR	623F	PAN
	FORD		TRACTOR
1992	MICHIGAN		LOADER
1995	JOHN DEERE		TRACTOR
	JOHN DEERE		ВАСКНОЕ
1996	CATERPILLAR		COMPACTOR
1992	CATERPILLAR		COMPACTOR
1996	CATERPILLAR		COMPACTOR
1994	CATERPILLAR	D7H	DOZER
1994	CATERPILLAR	D7H	DOZER
1996	CATERPILLAR	D7HLGP	DOZER
1996	CATERPILLAR	D7HLGP	DOZER
		D400D	DUMP TRUCK

h. Signs

Signs are used around the site to direct traffic to the active face, white goods area, tire area, used motor oil collection center, lead-acid battery drop-off, clean debris, yard waste, mulch site, sludge disposal areas, warnings of heavy equipment, speed limits, disposal rates and hours of operation, and prohibitions.

12. ALL-WEATHER ACCESS ROADS

The main haul road in the landfill is paved. Wet-weather areas are provided near the paved haul road to reduce traversing poor road conditions for disposal vehicles. Wet-weather roads are constructed of compacted limerock and shell. The perimeter road along the slurry wall is also passable in all weather events.

13. RECORDS & REPORTING

Required landfill records are reported to the Department on a quarterly basis. All records are maintained at the landfill for a minimum period of 10 years or for the design period as specified below. The design period is projected to end in the year 2058 (unless long term care is decreased).

a. Permit Application Development

All reports used to develop permit applications and operation records will be maintained for the design period. Records such as geotechnical investigations, foundation analyses, demonstration reports, and previous permits and regulations are examples of records to be maintained.

b. Monitoring Records

All water quality, gas, and leachate monitoring records are required to be maintained for at least ten years.

c. <u>Background Water Quality</u>

Background water quality (ground and surface waters) reports are required to be maintained for the design period.

d. Remaining Site-Life Estimates

Estimated site-life projections are required and will be submitted annually to the Department.

APPENDIX C

Section P - Long Term Care

1. Rights of Property Access

Manatee County will maintain ownership and access rights to the access road for purposes of operating and maintaining the Southeast Regional Wastewater Treatment Plant.

2. Successors of Interest

The County will maintain ownership of tis portion of the facility for access to the plant.

3. Replacement of Monitoring Devices

Any monitoring devices that are damaged will be replaced by the County. The Department will be notified within 60 days of the discovery of an inoperable or non-functioning monitoring device.

4. Completion of Long Term Care Certification

See Operating Permit Application - Part P.