1574376 (1)

NOTE

THE FOLLOWING PIEZOMETERS SHALL BE PLUGGED AND ABANDONED IN ACCORDANCE WITH RULE 17-21.10(4) F.A.C. AND CHAPTER 40D-3 SOUTHWEST FLORIDA WATER MANAGEMENT DISTRICT BY A LICENSED WATER WELL CONTRACTOR.

C+400-12	A+400-20
B-13+35	C-32
C-13+35	C+400-36
B+400-20	B-40
D+400-36	E-32

PROPERTY BOUNDARY

EXISTING GATE

2MW4

D+400-4 C+300-4 1006.35' N90° 0' 0"E A+400-4

4MW4

1431.10' S0° 0' 0"E

1119.97' N46° 33' 0"W

F-8 D-8 C-8

EXISTING BUILDING FOUNDATIONS TO BE DEMOLISHED & REMOVED OFF SITE.

SWALE

RETENTION POND 2

D+400-12 C+400-12 C+13-35 B-13+35 A-13+35

CELL BERM

CELL SW-1

HOLDING TANKS

E-16 D-16

EXISTING WELL SHALL BE PLUGGED AND ABANDONED IN ACCORDANCE WITH CHAP. 17-21.10(4)F.A.C. AND S.W.F.W.M.D.

SWALE 1434.67' N90° 0' 0"W TIPPING AREA

B+400-20 A+400-20

1665.83' S20° 44' 10"E

F-20 D+400-20 C+400-20

910.85' S20° 45' 43"E

F-24 E-24 D-24 B-24 A-24

24' ROAD

622.54' N54° 46' 31"E

N 1469480.86 E 322032.74

4MW3

WHITE GOODS HOLDING AREA

6' CHAIN LINK FENCE

1838.27' S89° 40' 4"E

2MW3 4MW3

RETENTION POND

BORROW AREA

2MW3 2MW10 H-32 G-32 F-32

14' ROAD

SWALE 2MW8 4MW8

CELL 1 CELL 2 CELL 3 CELL 4

P-3 P-5

932.12' S0° 48' 2"W

279.39' N0° 12' 5"E

SCALE

P-2 G-40 P-4

CHAIN LINK GATE

F.P.C. TOWER #193 & #194

N 1468398.90 E 318533.08

N 1468398.90 E 319041.36

403.38' N89° 47' 40"E

H-40

OFFICE

2MW7 4MW7 24' ROAD F-40

CHAIN LINK GATE

WELL

DRAIN FEILD SEPTIC TANK

1260.16' N89° 47' 44"E

CONNECTING 24' SERVICE ROAD

314.72' N89° 47' 13"E

474.95' N0° 22' 19"E

494.50' N0° 22' 20"E

305.53' S36° 57' 39"W

566.88' N36° 57' 39"E

EXISTING GATE

1364.73' N90° 0' 0"E

24' ENTRANCE ROAD

1395.34' N90° 0' 0"E

H-48 G-48

EXISTING GOPHER TORTOISE RECEPTOR AREA

I-56 H-56 G-56

RETENTION POND 4

4MW1 2MW1

REFUSE-TO-ENERGY FACILITY SITE LIMIT

N 1466842.02 E 320541.29

EXISTING WELL SITE

(F.P.C. OWNED)

EXISTING GATE

EXISTING GATE

PROPERTY BOUNDARY

HAYS ROAD

295' FLORIDA POWER CORPORATION RIGHT OF WAY

N 1469198.90 E 318679.30

D+400-28 C+400-28

N 1469198.90 E 319187.58

E-32

BORROW AREA

MIN. BOTTOM EL. 45.0

CELL BERM

TIPPING AREA

1482.53' N90° 0' 0"W

749.49' N0° 20' 52"W

SWALE

C-32

CELL A-1

HOLDING TANKS

D+400-36 C+400-36

1268.02' N90° 0' 0"W

SWALE

RETENTION POND 1

B-40

24' ROAD

E-40 D-40 C-40

INSET A (SEE SHEET C-11)

MAINTENANCE BUILDING

666.89' N90° 0' 0"E

D+400-44 C+400-44

539.26' N90° 0' 0"E

697.46' N0° 20' 51"W

1373.44' N0° 22' 48"W

457.05' N36° 28' 9"E

1229.85' N90° 0' 0"E

N 1467595.37 E 320542.48

2MW2 4MW2

P-48

PROPERTY BOUNDARY

PROPERTY BOUNDARY

SCALE: 1" = 300'

N

D.E.R.

MAR 18 1991

SOUTHWEST DISTRICT TAMPA

PRINTED MAR 6 1991

LEGEND

- PROPOSED SHALLOW GROUNDWATER MONITORING WELL LOCATION
- PROPOSED DEEP GROUNDWATER MONITORING WELL LOCATION
- 2 MW — EXISTING 2-INCH DIA. SHALLOW MONITORING WELL
- 4 MW — EXISTING 4-INCH DIA. DEEP MONITORING WELL
- C-40 — EXISTING PEIZOMETER LOCATION
- TOP OF INTERIOR BERM
- TOP OF EXTERIOR BERM
- EXISTING 3 STRAND BARBED WIRE FENCE
- CLASS I LANDFILL LIMIT OF WORK
- CLASS III LANDFILL LIMIT OF WORK

REV. NO.	DATE	DRWN	CHKD.	REMARKS

DESIGNED BY: CJG
DRAWN BY: SBB
CHECKED BY: LKS
APPROVED BY: DM
DATE: AUG. 1989

CAMP DRESSER & McKEE INC.

performance engineers, scientists, planners & management consultants

CDM

WEST PASCO COUNTY CLASS I LANDFILL - PHASE I CONSTRUCTION DRAWINGS

SITE LAYOUT

PASCO COUNTY, FLORIDA

PROJECT NO. 6104-03

SHEET NO. C-6

DATE OF PLOT IS: 6-MAR-1991 16:20
NAME OF FILE IS: ZFK:[NOJ.37JAP]K03C06_DGN;2