

Florida Department of Environmental Protection Inspection Checklist

FACILITY INFORMATION:

Facility Name: POLAR BUSINESS SOLUTIONS, INC.

On-site Inspection Start Date: 03/06/2020 On-site Inspection End Date: 03/06/2020

WACS No.: 102998

Facility Street Address: 911 S. WOODROW WILSON STREET BAY #16

City: PLANT CITY

County Name: HILLSBOROUGH

Zip: 33563

INSPECTION PARTICIPANTS:

(Include ALL Landfill and Department Personnel with Corresponding Titles)

Principal Inspector: Alexis R Black, Inspector

Other Participants: Donald Murray, Owner;

INSPECTION TYPE:

Routine Closure Inspection for WPF - Waste Tire Processing Facility

ATTACHMENTS TO THE INSPECTION CHECKLIST:

This Cover Page to the Inspection Checklist may include any or all of the following attachments as appropriate.

Note: Checklist items with shaded boxes are for informational purposes only.

9.0 - SECTION 9.0 - WASTE TIRE FACILITIES

Inspection Date: 03/06/2020

9.0 - SECTION 9.0 - WASTE TIRE FACILITIES

Requirements:

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

som pod	ential violations and areas of concern are discussed further at the end	oi triis	inspe	Cuon	ероп
Item No.	SOLID WASTE PROHIBITIONS (unless "grandfathered" in, see 62-701.300(18))	Ok	Not Ok	Unk	N/A
9.1.1	Unauthorized storage, processing, or disposal of solid waste except as authorized at a permitted solid waste management facility or other exempt facility? 62-701.300(1)(a)		1		
9.1.2	Unauthorized disposal or storage prohibited, except yard trash, within 500 feet of a potable water well? 62-701.300(2)(b)	1			
9.2	Unauthorized storage or disposal of yard trash prohibited within the minimum setbacks of (Check any that are Not OK) 62-701.300(12) 100 feet from potable water wells (except on-site)? 50 feet from water bodies?	1			
9.3	Unauthorized disposal or storage prohibited in any natural or artificial body of water including ground water and wetlands? (Does not apply to standing water after a storm event) 62-701.300(2)(d)	1			
9.4	Unauthorized disposal or storage prohibited, except yard trash, within 200 feet of any natural or artificial body of water, including wetlands without permanent leachate controls, except impoundments or conveyances which are part of an on-site, permitted stormwater management system or on-site water bodies with no off-site discharge? 62-701.300(2)(e)	1			
9.5	Unauthorized open burning of solid waste prohibited except in accordance with Department requirements? 62-701.300(3)	1			
Item No.	WASTE TIRE FACILITY - GENERAL REQUIREMENTS FOR STORAGE	Ok	Not Ok	Unk	N/A
9.6	If the facility accepts tires from the public, is a sign posted at the facility entrance stating operating hours, cost of disposal and site rules? 62-711.540(1)(a)				1
9.7	Are operations involving the use of open flames conducted no closer than 25 feet of a waste tire pile? 62-711.540(1)(b)				1
9.8	If the facility accepts tires from the public, is an attendant always present on site when the site is open for business? 62-711.540(1)(c)				1
9.9	Are fire protection services assured through notification to local fire protection authorities? 62-711.540(1)(d)	1			
9.10	Is an annual fire safety survey conducted? 62-711.540(1)(d)				1
9.11	Is a copy of the annual fire safety report made part of the next quarterly report? 62-711.540(1)(d)				1
9.12	Does the facility have an Emergency Preparedness Manual (EPM) on-site? 62-711.540(1)(e)	1			
9.13	Does the EPM contain the following information? (Check all that are Not OK) Contact names and numbers 62-711.540(1)(e)1 List of emergency response equipment and locations on-site 62-711.540(1)(e)2 Procedures to be followed in the event of a fire 62-711.540(1)(e)3	1			
9.14	Is the operator at the facility maintaining records of the quantity of waste tires received at the site, stored at the site, and shipped from the site? 62-711.540(1)(g) and 62-711.400(5)	1			
9.15	If the operator of the site is not the owner of the property, has written authorization been obtained from the property owner to operate the facility? 62-711.540(1)(h)	1			
9.16	Is adequate communications equipment available at the site? 62-711.540(1)(i)	1			
9.17	Is the owner or operator providing for control of mosquitoes and rodents so as to protect the public health and welfare? 62-711.540(1)(j)	1			

Inspection Date: 03/06/2020

Item No.	WASTE TIRE FACILITY - STORAGE INDOORS	Ok	N ₀	ot k	Unk	N/A
9.18	Are waste tire piles more than 50 feet in width? 62-711.540(2)(a)	1				
9.19	Are waste tire piles along a wall more than 25 feet in width? 62-711.540(2)(a)	1				
9.20	Are widths of main aisles between piles less than 8 feet? 62-711.540(2)(b)	1				
9.21	Is there less than 3 feet of clearance between the top of storage to sprinkler detectors or roof structures? 62-711.540(2)(c)			1		
9.22	Is there less than 3 feet of clearance between waste tire piles and unit heaters, etc.? 62-711.540(2)(d)	1				
9.23	If waste tires are stored up to 15 feet high, do walls between adjacent warehouse areas and between manufacturing and warehouse areas have at least a four-hour fire rating? 62-711.540(2)(e)	1				
9.24	If waste tires are stored over 15 feet high, do walls between manufacturing and warehouse areas have a fire rating of not less than six hours and do steel columns have one-hour fireproofing? If the top of storage exceeds 20 feet in height, do columns and their connections with other structural members have two-hour fireproofing? 62-711.540(2)(f)	1				
9.25	Is the access controlled through the use of doors, fences, gates, natural barriers or other means? 62-711.540(2)(h)	1				
Item No.	WASTE TIRE FACILITY - STORAGE OUTDOORS		Ok	Not Ok	Unk	N/A
9.26	Is the waste tire site operated within 200 feet from a body of water? 62-711.540(3)(a)					1
9.27	Does the waste tire pile have a width less than 50 feet? 62-711.540(3)(b)					1
9.28	Does the waste tire pile have an area less than 10,000 sq. ft? 62-711.540(3)(b)					1
9.29	Does the waste tire pile have a height less than 15 feet? 62-711.540(3)(b)					1
9.30	Is there a 50 feet wide fire lane around the perimeter of the waste tire pile? 62-711.540(3)(0					1
9.31	Is there unobstructed access to the fire lane? 62-711.540(3)(c)					1
9.32	Is the access controlled through the use of doors, fences, gates, natural barriers or other means? 62-711.540(3)(d)					1
9.33	Is the site kept free of grass, underbrush, and other potentially flammable vegetation? 62 711.540(3)(f)	-				1
9.34	Is the site bermed or given other adequate protection to prevent liquid runoff from enterin water bodies? 62-711.540(3)(e)	g				1
9.35	Are residuals contained on-site and disposed of in a permitted solid waste management facility or properly recycled? 62-711.540(5)					1
9.36	Does the waste tire site qualify for the exceptions to the technical and operational standa as allowed by rule? 62-711.540(6)	rds				1
Item No.	WASTE TIRE FACILITY - COLLECTION CENTER		Ok	Not Ok	Unk	N/A
9.37	Are no more than 1,500 tires at the collection center at any one time? 62-711.550(1)(a)					1
9.38	Are all waste tires, which are not used tires, removed from site yearly for recycling, processing, or disposal? 62-711.550(1)(b)					1

Inspection Date: 03/06/2020

Current Violations:

Rule: 62-701.300(1)(a)

Question Number: 9.1.1

Explanation: On March 24, 2020, Donald Murray emailed the Department explaining that this

facility no longer processes waste tires and that he would like to surrender his permit to the Department. Mr. Murray also explained that 15 waste tires are at the facility and he will dispose of them in accordance with Department rules. At the time of this email, no photo documentation demonstrating the waste tires were removed from the premise was received. Following the Department's receipt of this email, Department personnel contacted Mr. Murray via phone to discuss the

disposal of these remaining waste tires. As of March 27, 2020, photo

documentation showing all waste tires removed from the facility was not provided,

and therefore the facility cannot be closed.

Corrective Action: Within 30 days of the date listed on the attached Compliance Assistance Offer

letter, please email photo documentation of all waste tires removed from the facility to the Department. Upon receipt of this documentation, the Department will

move forward with closing the facility.

Rule: 62-711.540(2)(c)


Question Number: 9.21

Explanation: See Item 9.1.1.

Corrective Action: See Item 9.1.1.

ATTACHMENTS:

3/6/20 - Waste Tires On-site



Inspection Date: 03/06/2020

Signed:						
Alexis R Black	Inspector PRINCIPAL INSPECTOR TITLE					
PRINCIPAL INSPECTOR NAME						
Oex BL	DEP	03/27/2020				
PRINCIPAL INSPECTOR SIGNATURE	ORGANIZATION	DATE				
Donald Murray	Owner					
REPRESENTATIVE NAME	REPRESENTATIVE TITLE					
	Polar Business Solutions, I	nc. d/b/a				
NO SIGNATURE REQUIRED	Bird Planter	_				
REPRESENTATIVE SIGNATURE	ORGANIZATION					
NOTE: By signing this document, the Site Report and is not admitting to the accuracy of or areas of concern.						
Report Approvers:						
Approver: Steve Tafuni	Inspection Approval Date	e: 03/27/2020				