

# KERRY BARNETT FIRE SAFETY CONSULTING

43951 CR 54E, KATHLEEN, FL 33849  
813-778-4981 kbarnett@firesafetycons.com

## Business Information

Name: Central Florida Tire Terminal  
Address: 301 S Feagan Ave  
Avon Park, FL  
Contact: \_\_\_\_\_  
Tel No: 863-452-5788  
Occupancy: Mixed

Permit Number: n/a  
Inspection: Annual  
Re-inspection: Yes ☐ No ☒ Number: 0  
Scheduled Date: 4/10/19 Time: 925 am  
Re-inspection Date: \_\_\_\_\_  
Inspector: Kerry Barnett

## Inspection Results

Pass

☐

Fail

☐

Conditional

☒

This inspection was conducted utilizing the Florida Fire Prevention Code and any other applicable standard or code.

## Comments

An annual inspection was completed with Fire Chief present. Prior to inspection, code changes were discussed with the occupant. Code changed as of Jan 1, 2018 and existing facility had 5 years from that date to comply with the change as to how they store tires outside. This authority (in agreement with the Fire Chief) will start that time frame to comply as of this inspection date. It is noted that this is an existing business that has been in business for many years at this site and would not be able to comply as the code is written without a large financial impact in how the business operates. Therefore at this time, change required will assist in minimizing risk and making the property safer for the occupants, as well as, providing better access for fire department operations should a fire emergency occur.

### Outside Storage (5 years)

- Ensure at every gate signage is posted listed business name, operating hours and telephone number (as other signs on property)
- Every entrance into a building shall have NO SMOKING signs installed.
- Tire height may not exceed 8 feet
- Width of piles may not exceed 50 feet
- Separation distance between tire piles and buildings to tires shall be a minimum of 20 feet
- Tire storage shall be removed from unloading area and out from under roof storage at the unloading area.
- Emergency tools shall be kept in at least two different areas (list of tools noted in code provided)
- Repair/Reinstall security guards on top of perimeter fencing (barbed wire area)
- Tire storage shall be located a minimum of 10 ft from perimeter fencing, except where covered storage is located on the perimeter.
- Tire shavings shall be removed from all surface areas and properly disposed of

### Interior Storage (1 year)

- Tire storage may not be in a row (single row) stacked or on tread in rack, no longer than 25 ft
- Tire storage requires minimum 18 in from ceiling
- 8 ft is required between rows (side to side/end to end/side to end)
- Exits shall be unobstructed

Inspector Signature: Kerry Barnett

Date: 4/10/19 Time: 1045 am

Representative Signature: \_\_\_\_\_

Total Time: 1 h 20 m Page 1 of 1