

Bonifay Fire-Rescue



Form: Preplan Form

Occupancy: **Son's Tire Inc.**

Occupancy ID: **11**

Address: **202 S Waukesha ST**

Bonifay FL 32425

Inspection Type: **Pre-Plan**

Inspection Date: **4/22/2022**

By: **Martin, Ryan (114)**

Time In: **13:55**

Time Out: **15:54**

Authorized Date: **Not Authorized** By:

Inspection Topics:

Exits

Repair or maintain exit doors and hardware to operate properly.

Well maintained exit doors and panic hardware provide safe and easy egress from a building.

Status: PASS

Notes:

Remove obstructions from exits, aisles, corridors, and stairways.

Clear exit access is essential to prevent panic or accidental falling of occupants during evacuation.

Status: PASS

Notes:

Remove storage from beneath exit stairs.

Items stored beneath stairs present a fire risk that can endanger persons using that escape route.

Status:

Notes:

Unlock all exit doors during business hours.

Locked exit doors make it impossible for occupants to escape safely and quickly.

Status: PASS

Notes: All rollup doors are opened during business hours. No doors are locked and exits are clearly visible. Signs are posted to prohibit customers from access to work areas.

Provide exit signs with letters at least 6 inches high on a contrasting background.

Clearly identified exits enable persons to quickly and safely leave the building in an emergency.

Status: NOT OBSERVED

Notes: All exterior doors are roll up doors. No exit sign required.

Remove unapproved locks or latches from exit doors.

Exit doors must be free to open without delay in the event of an emergency.

Status: PASS

Notes:

Exit Lighting

Repair lighted exit signs or emergency lighting.

Exit signs and emergency illumination are essential during evacuations. The exit sign will indicate to occupants the correct door to reach safely.

Status:

Notes:

Provide lighting for exits, aisles, corridors, and stairways.
Well lighted exit ways prevent panic, and provide safer egress for occupants.

Status:
Notes:

Fire Extinguishers

Mount extinguishers where readily available, not more than 5 feet above floor.
Extinguishers must be easily within reach of all occupants, but not where they will be subject to damage.

Status: PASS
Notes: Owner was in process of updating fire extinguishers. New extinguishers were posted that were adequate for the structure.

Post signs indicating location where extinguishers are not readily visible.
Where extinguishers are not clearly visible, signs help occupants find the equipment in a hurry.

Status: PASS
Notes: All extinguishers are readily visible.

Portable fire extinguishers are due for annual maintenance on:
Annual maintenance will provide for properly charge and serviced extinguishing devices, and assure proper operation if needed to fight a small fire.

Status: PASS
Notes: 04/2023

Provide X extinguisher(s) of a X minimum rating.
Extinguishers provided need to be appropriate to the type of hazard.

Status: PASS
Notes:

Fire Protection Access and Equipment

Install approved protective covers on fire department hose connection.
Protective covers must be installed on the supply connection to prevent accumulations of debris that might inhibit the system's effectiveness.

Status:
Notes:

Provide and maintain smoke detectors in proper operating condition.
The proper installation and maintenance of smoke detectors is of the utmost importance. In the event of a fire, they will notify occupants, and, in some cases, may automatically notify the Fire Department.

Status: PASS
Notes: Residence and customer service areas have smoke detectors.

The X system(s) is/are due for confidence testing and certification. Please see the attached report.
Life safety and fire protection equipment must be properly inspected and tested from time to time to assure its effective operation.

Status:
Notes:

Maintain access to and operation of standpipes, fire hose, sprinkler valves, fire hydrants, fire extinguishers, and other fire protection equipment

Fire protection equipment must have clear access and be operational at all times to be effective in an emergency.

Status:
Notes:

Provided minimum 4 inches high address numbers so they are visible from the street.

Address numbers are critical to help emergency personnel find people who may need some sort of aid. The numbers must contrast with their background for greatest visibility.

Status: PASS

Notes:

Remove obstructions and provide access in fire lanes.

Large fire apparatus need room to effectively maneuver in the event of an emergency.

Status: PASS

Notes:

Fire Separations

Keep attic and scuttle covers closed, and ceiling tiles in place.

Ceilings are an integral part of the building's fire protection. If kept in place, the ceiling will protect roof structures from premature collapse.

Status: PASS

Notes:

Remove obstructions from fire doors and maintain to operate properly.

Fire and smoke doors should not be blocked open or obstructed or fire and smoke will easily travel through the opening and cause excessive risk to life and property.

Status: PASS

Notes:

Seal unapproved openings with approved material.

Flame, smoke, and hot gases can easily travel through holes and pipe chases, thus creating more damage and a hazard to occupants.

Status: PASS

Notes:

Housekeeping

Arrange storage in orderly manner to provide for exiting and fire department access.

Good housekeeping makes an area safer for occupants and contributes less fuel to a fire. When storage is orderly, fire fighters can get fast access to minimize fire damage.

Status:

Notes:

Remove or store rubbish, waste material, oily rags in closed metal containers.

Safety containers for oily and greasy rags are designed to prevent spontaneous ignition of their contents. Other highly flammable wastes must be separated from sources of ignition.

Status: PASS

Notes:

Clean grease filters and hood/duct system over cooking equipment.

Regular cleaning of the hood, duct, and filters will eliminate flammable grease build-up and provide proper ventilation of heat through the exhaust outlet.

Status:

Notes:

Provide approved waste containers for combustible waste.

Heavy duty or metal containers are necessary to confine a fire in the receptacle to prevent it spreading to the building.

Status: PASS

Notes:

Remove storage to at least 18 inches below level of sprinklers (36 inches for storage piled over 12 feet high)

Storage too close to a sprinkler will not allow the water spray to properly penetrate the fire and extinguish it.

Status:

Notes:

Chain all compressed gas cylinders in an upright position and provide protective caps.

Compressed gas cylinders, empty or full, can take off like a rocket in any direction if they fail and rupture.

Status: PASS

Notes:

Boiler, mechanical, and electrical panel rooms shall not be used for storage.

Combustible materials in these equipment rooms often get put too close to sources of heat and a fire will likely result.

Status:

Notes:

Post and enforce 'No Smoking' signs.

'No Smoking' areas are designated because the use of smoking materials in those areas could cause a fire.

Status: PASS

Notes:

Reduce storage height to at least 2 feet below ceiling.

In the even of a fire, fire fighters may need to open a hole in the roof to let heat and smoke out. Storage and other obstructions will prevent rapid ventilation efforts.

Status: PASS

Notes: All items within 2 ft of ceiling are non-combustible and decorative.

Move the dumpster at least 5 feet from the building or overhangs.

Dumpsters are a common fire target of vandals. Moving the dumpster away will reduce the risk of a fire spreading to the building.

Status: PASS

Notes:

Flammable Liquids

Discontinue use of Class 1 liquids (gasoline, etc.) for cleaning.

These liquids are highly volatile and can be easily ignited by sparks, pilot lights, or other sources of heat.

Status:

Notes:

Storage in excess of 10 gallons shall be in an approved cabinet.

In the event of a fire, flammable liquids can readily accelerate its spread. Confining the stored liquids to secure cabinets will limit this fire exposure.

Status:

Notes:

Discontinue pouring from containers exceeding 5 gallons or provide pump taking suction from top.

Larger flammable liquid containers are difficult to handle, and their contents are easily spilled. Pumps taking suction from the top restrict the amount likely to be discharged accidentally.

Status:

Notes:

Store liquids away from exits, aisles, corridors, or stairways.

The accelerating effect of flammable liquids in a fire can quickly make safe exit impossible.

Status: PASS

Notes:

Use only approved safety can for portable dispensing of flammable liquids.

Safety containers for flammable or combustible liquids are designed to prevent flammable fumes from escaping or accidental spills.

Status: PASS

Notes:

Electrical

Discontinue use of extension cords in lieu of permanent wiring.

Temporary wire does not afford the durability, safety, and protection from shock or fire that is found in the construction of an enclosed electrical system.

Status: PASS

Notes: Owner was in process of converting temporary wiring to permanent wiring.

Maintain at least 30 inches clearance in front of electrical panel.

Access to electrical panels must be cleared to allow for general inspection and emergency shutdown.

Status: PASS

Notes:

Each outlet box shall have a cover faceplate or fixture canopy.

Covers protect people from being shocked by exposed wires, prevent spread of electrical current, and heat and flame during short circuits.

Status: PASS

Notes:

Discontinue use of non-approved multi-plug adapters.

Multi-plug adapters invite the overuse of the circuit that can result in overheating and a fire.

Status:

Notes:

Maintain wiring in good condition and protect from damage.

Worn or broken wires and plugs present a fire hazard and risk of electrical short circuit that can result in a fire.

Status: PASS

Notes: Wiring was consistent with commercial wiring code of its era and has been maintained to a satisfactory commercial standard.

Additional Time Spent on Inspection:

Category	Start Date / Time	End Date / Time
Notes: No Additional time recorded		

Total Additional Time: 0 minutes

Inspection Time: 119 minutes

Total Time: 119 minutes


Summary:

Overall Result: Passed

Inspector Notes: Owner is in process of fixing wiring and installing fire extinguishers.

Inspector:

Name: Martin, Ryan
Rank: Lieutenant


Signature

04/22/2022
Date


Representative Signature:

Signature

Date



Overview



Legend

-  Parcels
-  Roads
-  City Labels

Parcel ID 0531-3-3-26-1.000
Sec/Twp/Rng n/a
Property Address
District n/a
Brief Tax Description n/a

Alternate ID n/a
Class n/a
Acreage n/a

Owner Address n/a

(Note: Not to be used on legal documents)

Date created: 4/21/2022
Last Data Uploaded: 4/20/2022 10:56:27 AM

Developed by  **Schneider**
GEOSPATIAL



8

0.55 ac.

11

0.264 ac.

5

4

9

0.159 ac. 0.562 ac.

4.1

5

14

0.071 ac.

1

#1

0.838 ac.

0.838 ac.

0.52 ac.

26

2

0.114 ac.

116

0.275 ac.

5

0.67 ac.

1

0.744 ac.

7

8

0.103 ac.

11