Board of County Commissioners — Sumter County, Florida ————

910 N. Main Street, Room 201 • Bushnell, FL 33513-6146 • Phone (352) 793-0200 • FAX: (352) 793-0207 Website http://sumtercountyfl.gov

Dept. of Environmental

Protection

FEB 10

February 17, 2009

Southwest Distric.

Ms. Deborah Getzoff, Director Southwest District Florida Department of Environmental Protection (DEP) 13051 N. Telecom Parkway Temple Terrace, FL 33637

RE: 08-2376; DEP v. Sumter County

Dear Ms. Getzoff:

Thank you for the phone call last week, your understanding of our solution in progress, and your willingness to accept the investment of which we are moving out to bid to substitute as in-kind payment of the fine proposed by DEP.

As we discussed, I have attached the civil engineer's construction cost estimate (\$179,880.01) of the sewage system to serve both the Animal Control Department operations along with the leachate and septic systems of the Solid Waste Department.

Also, attached is the set of civil engineering drawings in which you will note on sheet C601 – Manhole #8 will serve as the transfer station leachate collection point. On the same sheet you will note the proposed connection of the system to the City of Bushnell Wastewater Treatment Facility.

The proposed bid opening date is April 30, 2009 following receipt of our Southwest Florida Water Management District stormwater permit.

Richard "Dick" Hoffman, Dist 1 (352) 753-1592 or 793-0200 910 N. Main Street Bushnell, FL 33513

> Randy Mask, Dist 5 2nd Vice Chairman Office: (352) 793-0200 Home: (352) 793-3930 910 N. Main Street Bushnell, FL 33513

Doug Gilpin, Dist 2 Vice Chairman (352) 793-0200 910 N. Main Street Bushnell, FL 33513

Bradley S. Arnold, County Administrator (352) 793-0200 910 N. Main Street Bushnell, FL 33513-6146 Michael E. Francis, Dist 3 (352) 753-1592 or 793-0200 910 N. Main Street Bushnell, FL 33513

Gloria R. Hayward, Clerk & Auditor (352) 793-0215 209 North Florida Street Bushnell, FL 33513 Garry Breeden, Dist 4 Chairman (352) 793-0200 910 N. Main Street Bushnell, FL 33513

County Attorney The Hogan Law Firm Post Office Box 485 Brooksville, Florida 34605 Thank you again for the partnership opportunity to place the funds proposed as a fine towards the construction of this project. $Protect_{CO}$

xc:

Bradley Arnold **County Administrator**

Representative Marlene O'Toole

Sumter County Board of County Commissioners

Mr. Gary Kuhl, Public Works Director

Attachments: Klima Weeks Construction Costs

Vitetta / Klima Weeks Civil Engineering Drawings



GRAND TOTAL

CONSTRUCTION COSTS

Dept. of EnvironProtection.

FEB 19 2009

Project Name: Date of Estimate:

Sumter Animal Control Addn Southwest Distriction

\$179,880.01

Item Description **Unit Price** Quantity Unit Total Construction Costs DEMOLITION ITEMS Tree Removal \$2,120.00 2,120.00 ls Existing Paving Removal 410 \$10.00 \$ 4,100.00 SV Fence Removal \$500.00 \$ 500.00 1 Is 5,000.00 Septic Tank Demolition 5 \$1,000.00 \$ ea Silt Fencina 610 lf \$1.00 \$ 610.00 Subtotal Demolition \$12,330.00 NEW CONSTRUCTION 3,190.00 Earthwork 580 СУ \$5.50 6" PVC Storm 40 lf \$10.55 \$ 422.00 MES 4 \$250.00 S 1,000.00 ea 650 S 3,250.00 Swale Grading If \$5.00 \$ 6" PVC Sanitary 454 lf \$10.55 4,789.70 \$ 420.00 Cleanouts \$70.00 6 ea 8" PVC Sanitary 863 \$13.30 11,477.90 lf \$16,500.00 Sanitary Manholes 6 ea \$2,750.00 Connect to Exist. 4 \$250.00 \$1,000.00 ea Open Cut Pavement 1545 \$15.00 \$ 23,175.00 sy \$ 18,000.00 \$18,000.00 Lift Station 1 Is 2778 \$21,251.70 2.5" San. Force Main If \$7.65 Directional Drilling 2778 lf \$8.25 \$22,918.50 Air Release Valves 3 \$500.00 \$1,500.00 ea 220 \$1,540.00 2" San. Force Main If \$7.00 Saw cut exist. Slab 100 If \$3.75 \$375.00 Remove Exist Slab 17 \$21.40 \$363.80 sy 17 \$1,213.80 Replace Slab \$71.40 sy Trenching, Backfill, Com 17 \$100.00 \$1,700.00 СУ \$5,000.00 Add Simplex for Bath 1 ls \$5,000.00 \$2,500.00 Connect to Plant 1 Is \$2,500.00 \$2,500.00 Misc Fittings/Testing \$2,500.00 1 Is Subtotal of New Const. \$ 144,087.40 TOTAL \$156,417.40 Mob/Demob/Cont (15%) \$ 23,462.61