



Florida Department of
Environmental Protection
Inspection Checklist

FACILITY INFORMATION:

Facility Name: LIBERTY TIRE RECYCLING, LLC (FRMERLY) FL. TIRE RECYCLING,INC

On-Site Inspection Start Date: 09/16/2010

On-Site Inspection End Date: 09/16/2010

WACS No.: 70963

Facility Street Address: 10151 RANGE LINE ROAD

City: PORT ST.LUCIE

County Name: ST. LUCIE

Zip: 34987

INSPECTION PARTICIPANTS:

(Include ALL Landfill and Department Personnel with Corresponding Titles)

Principal Inspector: Robyn S. James, Inspector

Other Participants: Leigh-Ann Dawes, Inspector; Phil Tuohy, Region Manager; Joe Lurix, Waste Program Administrator

INSPECTION TYPE:

Routine Operation Inspection for Waste Processing - Tire Processing Facility

Complaint Investigation Inspection for Waste Processing - Tire Processing Facility

ATTACHMENTS TO THE INSPECTION CHECK LIST:

This Cover Page to the Inspection Checklist may include any or all of the following attachments as appropriate.

SECTION 1.0 - FILE REVIEW

SECTION 9.0 - WASTE TIRE FACILITIES

SECTION 13.0 - COMPLAINT INVESTIGATIONS

Inspection Date: 09/16/2010

SECTION 1.0 - FILE REVIEW**Requirements:**

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

Item No.	FILE REVIEW (Pre- or Post-Inspection, as appropriate.) Completed	Ok	Not Ok	Unk	N/A
1.1	For landfills and C&D disposal facilities, does the facility have a current plan for the method and sequence of filling wastes? 62-701.500(2)(f) for landfills; 62-701.730(7)(a) for C&D debris sites				✓
1.2	For landfills, are the following records being reported to the Department?(Check any that are Not OK) <input type="checkbox"/> Waste reports (annually) 62-701.500(4) <input type="checkbox"/> Annual estimate of remaining life 62-701.500(13)(c)				✓
1.3	Is leachate sampled, tested and disposed as required? 62-701.500(8)(a), 62-701.510(6)(c)				✓
1.4	Is gas monitoring being performed as required by the permit? 62-701.500(9), 62-701.530(2)				✓
1.5	Are the results of the gas sampling reported to the Department quarterly? 62-701.530(2)(c)				✓
1.6	Is water quality sampling and testing performed according to standard procedures and at the required frequencies? 62-701.510(2) for landfills; 62-701.730(4)(b) and (10) for C&D debris sites; 62-713.400(3) for stationary soil treatment facilities.				✓
1.7	Do the results of the water quality testing suggest there may be adverse impacts to water quality from the operation of the solid waste facility? 62-701.510(3) and (4); 62-701.730(4)(c) and (10) for C&D debris sites; 62-713.400(3) for stationary soil treatment facilities.				✓
1.8	For closed landfills and C&D disposal facilities with final elevations higher than 20 feet above grade, has a final survey report verifying the final elevations and contours of the facility been submitted to the Department? 62-701.600(6)(b), 62-701.730(9)(d)				✓
1.9	Is financial assurance adequate? 62-701.630 for landfills; 62-701.710(7)(a) and (10)(a) for waste processing facilities; 62-701.730(11)(a) for C&D debris facilities; 62-713.600(6)(a) for stationary soil treatment facilities; 62-711.500(3) for waste tire facilities. NOTE: The Solid Waste Financial Coordinator in Tallahassee can assist with this information.		✓		
1.10	Are cost estimates current and adjusted every year? 62-701.630(4) for landfills; 62-701.710(7)(b) and (10)(a) for waste processing facilities; 62-701.730(11)(b) and (c) for C&D debris facilities; 62-713.600(6)(b) and (c) for stationary soil treatment facilities; 62-711.500(3) for waste tire facilities.		✓		
1.11	For C&D debris disposal and disposal with recycling facilities, is an Annual Report submitted to the Department for the disposal operation by April 1st of each year? 62-701.730(12)				✓
1.12	For C&D recycling facilities with no disposal, is an Annual Report for the recycling facility submitted to the Department by April 1st of each year? 62-701.710(9)(b)				✓
1.13	For compost facilities, has the compost product been sampled and analyzed every 20,000 tons or every 3 months (whichever is sooner)? 62-709.530(1)				✓
1.14	For compost facilities, has the annual report been submitted by June 1st? 62-709.530(3)				✓

Inspection Date: 09/16/2010

SECTION 9.0 - WASTE TIRE FACILITIES**Requirements:**

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

Item No.	SOLID WASTE PROHIBITIONS (unless "grandfathered" in, see 62-701.300(18)) Completed	Ok	Not Ok	Unk	N/A
9.1.1	Unauthorized storage, processing, or disposal of solid waste except as authorized at a permitted solid waste management facility or other exempt facility? 62-701.300(1)(a)	✓			
9.1.2	Unauthorized disposal or storage prohibited, except yard trash, within 500 feet of a potable water well? 62-701.300(2)(b)	✓			
9.2	Unauthorized storage or disposal of yard trash prohibited within the minimum setbacks of (Check any that are Not OK) 62-701.300(12) <input type="checkbox"/> 100 feet from potable water wells (except on-site)? <input type="checkbox"/> 50 feet from water bodies?				✓
9.3	Unauthorized disposal or storage prohibited in any natural or artificial body of water including ground water and wetlands? (Does not apply to standing water after a storm event.) 62-701.300(2)(d)	✓			
9.4	Unauthorized disposal or storage prohibited, except yard trash, within 200 feet of any natural or artificial body of water, including wetlands without permanent leachate controls, except impoundments or conveyances which are part of an on-site, permitted stormwater management system or on-site water bodies with no off-site discharge? 62-701.300(2)(e)				✓
9.5	Unauthorized open burning of solid waste prohibited except in accordance with Department requirements? 62-701.300(3)				✓

Item No.	WASTE TIRE FACILITY - GENERAL REQUIREMENTS FOR STORAGE Completed	Ok	Not Ok	Unk	N/A
9.6	If the facility accepts tires from the public, is a sign posted at the facility entrance stating operating hours, cost of disposal and site rules? 62-711.540(1)(a)	✓			
9.7	Are operations involving the use of open flames conducted no closer than 25 feet of a waste tire pile? 62-711.540(1)(b)	✓			
9.8	If the facility accepts tires from the public, is an attendant always present on site when the site is open for business? 62-711.540(1)(c)	✓			
9.9	Are fire protection services assured through notification to local fire protection authorities? 62-711.540(1)(d)	✓			
9.10	Is an annual fire safety survey conducted? 62-711.540(1)(d)		✓		
9.11	Is a copy of the annual fire safety report made part of the next quarterly report? 62-711.540(1)(d)		✓		
9.12	Does the facility have an Emergency Preparedness Manual (EPM) on-site? 62-711.540(1)(e)	✓			
9.13	Does the EPM contain the following information? (Check all that are Not OK) <input type="checkbox"/> Contact names and numbers 62-711.540(1)(e)1 <input type="checkbox"/> List of emergency response equipment and locations on-site 62-711.540(1)(e)2 <input type="checkbox"/> Procedures to be followed in the event of a fire 62-711.540(1)(e)3	✓			
9.14	Is the operator at the facility maintaining records of the quantity of waste tires received at the site, stored at the site, and shipped from the site? 62-711.540(1)(g) and 62-711.400(5)	✓			
9.15	If the operator of the site is not the owner of the property, has written authorization been obtained from the property owner to operate the facility? 62-711.540(1)(h)	✓			
9.16	Is adequate communications equipment available at the site? 62-711.540(1)(i)	✓			
9.17	Is the owner or operator providing for control of mosquitoes and rodents so as to protect the public health and welfare? 62-711.540(1)(j)	✓			

Item No.	WASTE TIRE FACILITY - STORAGE INDOORS Completed	Ok	Not Ok	Unk	N/A
----------	---	----	--------	-----	-----

Inspection Date: 09/16/2010

Item No.	WASTE TIRE FACILITY - STORAGE INDOORS Completed	Ok	Not Ok	Unk	N/A
9.18	Are waste tire piles more than 50 feet in width? 62-711.540(2)(a)				✓
9.19	Are waste tire piles along a wall more than 25 feet in width? 62-711.540(2)(a)				✓
9.20	Are widths of main aisles between piles less than 8 feet? 62-711.540(2)(b)				✓
9.21	Is there less than 3 feet of clearance between the top of storage to sprinkler detectors or roof structures? 62-711.540(2)(c)				✓
9.22	Is there less than 3 feet of clearance between waste tire piles and unit heaters, etc.? 62-711.540(2)(d)	✓			
9.23	If waste tires are stored up to 15 feet in height, do walls have at least a 4- hour fire rating? 62-711.540(2)(e)				✓
9.24	If waste tires are stored more than 15 feet in height, do walls have a fire rating of not less than 6 hours and columns one hour FR? If more than 20 feet, do columns and its connections with other structural members have two hour FR? 62-711.540(2)(f)				✓
9.25	Is the access controlled through the use of doors, fences, gates, natural barriers or other means? 62-711.540(2)(h)				✓

Item No.	WASTE TIRE FACILITY - STORAGE OUTDOORS Completed	Ok	Not Ok	Unk	N/A
9.26	Is the waste tire site operated within 200 feet from a body of water? 62-711.540(3)(a)				✓
9.27	Does the waste tire pile have a width less than 50 feet? 62-711.540(3)(b)	✓			
9.28	Does the waste tire pile have an area less than 10,000 sq. ft? 62-711.540(3)(b)		✓		
9.29	Does the waste tire pile have a height less than 15 feet? 62-711.540(3)(b)	✓			
9.30	Is there a 50 feet wide fire lane around the perimeter of the waste tire pile? 62-711.540(3)(c)		✓		
9.31	Is there unobstructed access to the fire lane? 62-711.540(3)(c)		✓		
9.32	Is the access controlled through the use of doors, fences, gates, natural barriers or other means? 62-711.540(3)(d)	✓			
9.33	Is the site kept free of grass, underbrush, and other potentially flammable vegetation? 62-711.540(3)(f)	✓			
9.34	Is the site bermed or given other adequate protection to prevent liquid runoff from entering water bodies? 62-711.540(3)(e)	✓			
9.35	Are residuals contained on-site and disposed of in a permitted solid waste management facility or properly recycled? 62-711.540(5)	✓			
9.36	Does the waste tire site qualify for the exceptions to the technical and operational standards as allowed by rule? 62-711.540(6)	✓			

Item No.	WASTE TIRE FACILITY - COLLECTION CENTER Completed	Ok	Not Ok	Unk	N/A
9.37	Are no more than 1,500 tires at the collection center at any one time? 62-711.550(1)(a)	✓			
9.38	Are all waste tires, which are not used tires, removed from site yearly for recycling, processing, or disposal? 62-711.550(1)(b)	✓			

Inspection Date: 09/16/2010

SECTION 13.0 - COMPLAINT INVESTIGATIONS**Requirements:**

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

Item No.	SOLID WASTE PROHIBITIONS (unless "grandfathered" in, see 62-701.300(18)) Completed	Ok	Not Ok	Unk	N/A
13.1	Unauthorized storing, processing, or disposing of solid waste except as authorized at a permitted solid waste management facility or a facility exempt from permitting under this chapter? 62-701.300(1)(a)				✓
13.2	Unauthorized storing, processing, or disposing of solid waste in a manner or location that causes air quality standards to be violated or water quality standards or criteria of receiving waters to be violated? 62-701.300(1)(b)				✓
13.3	Unauthorized disposal or storage prohibited, except yard trash, within 500 feet of a potable water well? 62-701.300(2)(b)				✓
13.4	Unauthorized disposal or storage in a dewatered pit without liner or leachate controls? 62-701.300(2)(c)				✓
13.5	Unauthorized disposal or storage prohibited in any natural or artificial body of water including ground water and wetlands? (Does not apply to standing water after a storm event.) 62-701.300(2)(d)				✓
13.6	Unauthorized disposal or storage prohibited, except yard trash, within 200 feet of any natural or artificial body of water, including wetlands without permanent leachate controls, except impoundments or conveyances which are part of an on-site, permitted stormwater management system or on-site water bodies with no off-site discharge? 62-701.300(2)(e)				✓
13.7	Unauthorized storage or disposal on the right of way of any public highway, road or alley? 62-701.300(2)(f)				✓
13.8	Unauthorized open burning of solid waste prohibited except in accordance with Department requirements? 62-701.300(3)				✓
13.9	Are the following unauthorized wastes or special wastes properly managed? (Check any that are Not OK)				
13.9.1	CCA treated wood being ground into mulch, compost, or any wood product that is applied to the ground or burned 62-701.300(14)				✓
13.10	Unauthorized storage or disposal of yard trash within 100 feet of potable water wells (except on-site), and/or 50 feet of water bodies? 62-701.300(12)				✓
13.11	Waste tire prohibitions:				
13.11.1	Maintaining a waste tire site consisting of more than 1500 tires that is not an integral part of a permitted waste tire processing facility. 62-711.400(1)				✓
13.11.2	Disposing of waste tires except as permitted at a permitted solid waste management facility. 62-711.400(2)				✓
13.11.3	Storing waste tires only as a part of a waste tire collection center, permitted waste tire processing facility, permitted solid waste management facility, or other exempt facility. 62-711.400(4)	✓			
13.11.4	Contracting with only registered or exempt waste tire collectors for the transportation, disposal, or processing of more than 25 waste tires. 62-711.400(5)				✓

Current Areas Of Concern:

Rule: 62-711.540(3)(b)

Question Number: 9.28

Explanation: This area is 260ft width x 465ft between x 10ft in height, this area is where the fire took place and is being removed.

Corrective Action: Remove burnt waste tires and create the neccessary fire lanes.

Inspection Date: 09/16/2010

Rule: 62-701.630, 62-713.600(6)(a), 62-701.710(10)(a), 62-701.710(7)(a), 62-711.500(3), 62-701.730(11)(a)
Question Number: 1.9
Explanation: Financial Assurance on file for Feb. 2010.
Corrective Action: Updated Financial Assurance is needed in order to be in compliance with conditions of the permit.

Rule: 62-713.600(6)(b), 62-713.600(6)(c), 62-701.730(11)(c), 62-701.630(4), 62-701.710(10)(a), 62-711.500(3), 62-701.730(11)(b), 62-701.710(7)(b)
Question Number: 1.10
Explanation: Financial on File Feb. 2010
Corrective Action: Needs to be updated

Rule: 62-711.540(1)(d)
Question Number: 9.10
Explanation: No fire survey on file
Corrective Action: Fire Survey must be submitted to the Dept. in 30 days.

Rule: 62-711.540(3)(c)
Question Number: 9.30
Explanation: There are no fire lanes on-site.
Corrective Action: 30 days to have fire lanes in place in accordance with permit as the facility cleans up area.

Rule: 62-711.540(3)(c)
Question Number: 9.31
Explanation: Due to recent fire at the facility, there are no fire lanes.
Corrective Action: Facility has 30 days to reconstruct the fire lanes.

Rule: 62-711.540(1)(d)
Question Number: 9.11
Explanation: No fire survey on file
Corrective Action: Fire Survey must be submitted to the Dept. in 30 days.

COMMENTS:

09/16/2010

Liberty had a fire August 31, 2010.

Large off road tires - will be removed from the facility.

Inspection Date: 09/16/2010

Recovered Metal is sold to a Steel Mill.

There was no fire lines or fire safety survey available on site. the facility has 30 days to correct the areas of concerns.

When the facility changed owners the financial assurance was submitted in February 2010. The facility has to update the financial assurance. The financial assurance for the facility is due Sept. 1 of each year.

ATTACHMENTS:

Beginning of fire Area



Length of The Tire (burned)



View of Retention Pond



Trench being dugged



Inspection Date: 09/16/2010

Signed:

Robyn S. James

PRINCIPAL INSPECTOR NAME

Inspector

PRINCIPAL INSPECTOR TITLE**PRINCIPAL INSPECTOR SIGNATURE**

9/16/2010

DATE

Leigh-Ann Dawes

INSPECTOR NAME

Inspector

INSPECTOR TITLE

NO SIGNATURE

INSPECTOR SIGNATURE


FDEP

ORGANIZATION

Phil Tuohy

REPRESENTATIVE NAME

Region Manager

REPRESENTATIVE TITLE**REPRESENTATIVE SIGNATURE**

Liberty Tire

ORGANIZATION

9/16/2010

DATE**Report Approvers:**

Joe Lurix

SUPERVISOR NAME

Waste Program Administrator

SUPERVISOR TITLE

NO SIGNATURE

SUPERVISOR SIGNATURE

FDEP

ORGANIZATION

NOTE: By signing this document, the Site Representative only acknowledges receipt of this Inspection Report and is not admitting to the accuracy of any of the items identified by the Department as "Not Ok" or areas of concern.