



Florida Department of Environmental Protection

Bob Martinez Center
2600 Blairstone Road
Tallahassee, Florida 32399-2400

Charlie Crist
Governor

Jeff Kottkamp
Lt. Governor

Michael W. Sole
Secretary

March 19, 2009

Guy Manzi
Spectrum Industrial Services Inc
85 Spectrum Cove
Alabaster, AL 35007

Re: Florida Hazardous Waste Transporter Approval

Dear Guy Manzi:

Your Florida Hazardous Waste Transporter Approval Certificate is enclosed. The terms and conditions of approval are specified in Sections 62-730.170 and 62-730.171, Florida Administrative Code(FAC), a copy of which is enclosed for your reference. Please note the following.

1. You must demonstrate proof of liability coverage on an annual basis, even if your insurance policy is issued on a multi-year basis. If no changes in status or insurance coverage have occurred, you can meet this requirement by submitting a certificate of liability coverage form along with the two copies of the Hazardous Waste Transporter Status Form, copies of which are available upon request from the Department of Environmental Protection.
2. A copy of your insurance policy, together with any endorsements, must be maintained at your principal place of business.
3. Your insurer can not terminate your coverage until 30 days after filing written notice with DEP, by Certified mail, that your policy has expired or has been canceled.
4. Any changes to the information specified on your approval certificate will render it null and void. It is your responsibility to advise DEP of any changes in liability coverage or status.
5. A copy of Hazardous Waste Transporter Status Form, complete with the Department approval shall be carried in each vehicle transporting hazardous waste for the transportation company.

Guy Manzi
March 19, 2009
Page Two

If you intend to operate a hazardous waste transfer facility, you must submit a Transfer Facility Form [Form 62-730.900(6)]. Notification also must include a contingency and emergency plan and a facility closure plan in accordance with Rule 62-730.171(3)(a), F.A.C. The owner or operator must also demonstrate to the satisfaction of the Department that the location complies with the relevant siting requirements listed in section 403.7211(2) Florida Statutes (F.S) before the location is used as a transfer facility.

If you are currently operating an authorized transfer facility, you must maintain records of incoming and outgoing hazardous waste shipments. These records must include generator names and manifest numbers, and, unless otherwise approved by the Department, must be maintained at the transfer facility in accordance with Rule 62-730.171(6), F.A.C.

If you have any questions, please contact me at 850/245-8755.

Sincerely,

A handwritten signature in black ink, appearing to read "Richard Neves". The signature is written in a cursive, flowing style.

Richard Neves
Hazardous Waste Management Section

RN

Enclosures: Hazardous Waste Transporter Approval Certificate
Hazardous Waste Transporter Status Form (with insurance verification)
Sections [62-730.170](#) and [62-730.171](#) , FAC



Florida Department of Environmental Protection

Bob Martinez Center
2600 Blairstone Road
Tallahassee, Florida 32399-2400

Charlie Crist
Governor

Jeff Kottkamp
Lt. Governor

Michael W. Sole
Secretary

HAZARDOUS WASTE TRANSPORTER CERTIFICATE OF APPROVAL

This is to certify that the carrier specified below has been approved as a hazardous waste transporter in Florida. The terms and conditions of this certificate require that the holder comply with all applicable portions of Chapter 62-730, Florida Administrative Code. This certificate shall be rendered null and void if any information contained within becomes obsolete. The certificate shall remain valid through the expiration date specified below.

TRANSPORTER: Spectrum Industrial Services Inc

FACILITY ID NO: ALR000044743

FACILITY ADDRESS: 125 Spectrum Cove
Alabaster, AL 35007

INSURANCE CARRIER: GREAT DIVIDE INSURANCE COMPANY

INSURANCE POLICY#: BAP150720710

EFFECTIVE DATE: January 01, 2009

EXPIRATION DATE: January 01, 2010

APPROVED TRANSFER FACILITY: NO

APPROVAL ISSUED BY:  DATE: March 19, 2009

Richard Neves
Hazardous Waste Management Section
850/245-8755

Are your services commercially available? Yes

STATE OF FLORIDA

HAZARDOUS WASTE TRANSPORTER STATUS FORM

1. Transporter Identification:

Transporter Name: Spectrum Industrial Services, Inc.
Transporter EPA ID: ALR000044743
Location Address: 125 Spectrum Cove
Alabaster, Alabama 35007

Contact: Sharee Earl Telephone: 205-664-2000
Mailing Address: 85 Spectrum Cove
Alabaster, Alabama 35007

II. Insurance Information:

Insurance Company Great Divide Insurance Co (Auto) Natuillus Ins. Co (Excess)
Address 7233 East Butherus Drive
Scottsdale, AZ 85260-2410

Contact: Barry Faulkner Telephone: 205-263-5108
Policy Number: BAP150720710 Auto FFX15020510 Excess
Expiration date: 1/1/2010

III. Waste Information:


EPA Waste Codes for Waste Routinely or Usually Transported:

D001 D002 D006 D007 F003 F005 F006

Comments: _____

IV. Certification:

I certify under penalty of law that the above information is true, correct, and complete to the best of my knowledge.

Guy T. Manzi President
Print/Type Name Title
 2/12/09
Signature Date Signed

V. The transporter identified above is in compliance with the financial responsibility requirements for hazardous waste transporters pursuant to Chapter 62-730.170, Florida Administrative Code. The forms submitted by the transporter show compliance with the financial responsibility through 01/01/10 Date

APPROVED by Sebrena L. Bolton, changes approved by the Certifier by phone 3/19/2009

Signature of Florida Department of Environmental Protection Representative Date Signed

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

POLLUTION LIABILITY – BROADENED COVERAGE FOR COVERED AUTOS – BUSINESS AUTO, MOTOR CARRIER AND TRUCKERS COVERAGE FORMS

This endorsement modifies insurance provided under the following:

BUSINESS AUTO COVERAGE FORM
MOTOR CARRIER COVERAGE FORM
TRUCKERS COVERAGE FORM

With respect to coverage provided by this endorsement, the provisions of the Coverage Form apply unless modified by the endorsement.

A. Liability Coverage is changed as follows:

1. Paragraph **a.** of the **Pollution** Exclusion applies only to liability assumed under a contract or agreement.
2. With respect to the coverage afforded by Paragraph **A.1.** above, Exclusion **B.6. Care, Custody Or Control** does not apply.

B. Changes In Definitions

For the purposes of this endorsement, Paragraph **D.** of the **Definitions** Section is replaced by the following:

- D.** "Covered pollution cost or expense" means any cost or expense arising out of:
1. Any request, demand, order or statutory or regulatory requirement that any "insured" or others test for, monitor, clean up, remove, contain, treat, detoxify or neutralize, or in any way respond to, or assess the effects of "pollutants"; or
 2. Any claim or "suit" by or on behalf of a governmental authority for damages because of testing for, monitoring, cleaning up, removing, containing, treating, detoxifying or neutralizing, or in any way responding to or assessing the effects of "pollutants".

"Covered pollution cost or expense" does not include any cost or expense arising out of the actual, alleged or threatened discharge, dispersal, seepage, migration, release or escape of "pollutants":

- a. Before the "pollutants" or any property in which the "pollutants" are contained are moved from the place where they are accepted by the "insured" for movement into or onto the covered "auto"; or
- b. After the "pollutants" or any property in which the "pollutants" are contained are moved from the covered "auto" to the place where they are finally delivered, disposed of or abandoned by the "insured".

Paragraphs **a.** and **b.** above do not apply to "accidents" that occur away from premises owned by or rented to an "insured" with respect to "pollutants" not in or upon a covered "auto" if:

- (1) The "pollutants" or any property in which the "pollutants" are contained are upset, overturned or damaged as a result of the maintenance or use of a covered "auto"; and
- (2) The discharge, dispersal, seepage, migration, release or escape of the "pollutants" is caused directly by such upset, overturn or damage.

62-730.170 Standards Applicable to Transporters of Hazardous Waste.

- (1) The Department adopts by reference 40 CFR Part 263 revised as of July 1, 2007.
- (2) In addition to the requirements of subsection (1) of this rule, no person shall transport a hazardous waste within the state for which either a manifest is required under 40 CFR Part 262 [as adopted in subsection 62-730.160(1), F.A.C.] or a reclamation agreement is entered between a generator and recycler pursuant to 40 CFR 263.20 [as adopted in subsection 62-730.170(1), F.A.C.] unless compliance with the following special requirements have been demonstrated.
 - (a) The transporter shall have and maintain financial responsibility for sudden accidental occurrences in a minimum amount of \$1,000,000 per occurrence for combined coverage of injury to persons and for damage to property and the environment from the spillage of hazardous waste while such wastes are being transported including the costs of cleaning up the spill. Such financial responsibility shall be issued by an agent or company authorized or licensed to transact business in the State of Florida. Such financial responsibility shall be maintained at all times, be exclusive of legal defense costs, and be established by any one or a combination of the following:
 1. Evidence of casualty/liability insurance on an occurrence basis with or without a deductible. With the deductible the Insurer is liable for the payment of amounts within any deductible applicable to the policy, with a right of reimbursement by the insured for any such payment made by the Insurer. Each insurance policy must be evidenced by a certificate of liability insurance or amended by attachment of an endorsement.
 2. Surety bonds.
 - (b) Evidence of coverage shall include submittal of an originally signed copy of one or more of the following forms, which are hereby adopted and incorporated by reference:
 1. Hazardous Waste Transporter Certificate of Liability Insurance, Form 62-730.900(5)(a), effective date January 29, 2006.
 2. Hazardous Waste Transporter Liability Endorsement, Form 62-730.900(5)(b), effective date January 29, 2006
 3. Hazardous Waste Transporter Liability Surety Bond, Form 62-730.900(5)(c), effective date January 29, 2006. Rule 62-730.900, F.A.C., contains information on obtaining a copy of these forms.
 - (c) The insurance policy, including all endorsements, or the liability surety bond must be maintained at the carrier's principal place of business.
 - (d) Whenever requested by the Secretary (or designee) of the Florida Department of Environmental Protection, the Insurer agrees to furnish to the Department a signed duplicate original of the policy and all endorsements.
 - (e) The transporter shall annually submit to the Department two originally signed Transporter Status Forms, Form 62-730.900(5)(d), effective date January 5, 1995, which is hereby adopted and incorporated by reference. Rule 62-730.900, F.A.C., contains information on obtaining a copy of this form. The Department shall complete the approval part of the form and return one of the originally signed forms to the transporter after verifying that the transporter is complying with the financial responsibility requirements of this section. A copy of this form complete with the Department approval shall be carried in each vehicle transporting hazardous waste for the transporter. This approval is non-transferable and non-assignable.
 - (f) This subsection does not apply to any person who transports hazardous waste only on the site of a hazardous waste generator or a permitted hazardous waste treatment, storage, or disposal facility.
 - (g) States and the federal government are exempt from the requirements of this subsection.
- (3) Evidence of financial responsibility, updated for the current year, shall be verified annually by the submission of the appropriate form described in paragraph (2)(b) of this section or by the submission of a certificate of insurance. A certificate of insurance shall include a certification by the insurer that the original insurance policy and all endorsements are still in full force and effect as evidenced on the original forms submitted to the Department.

Specific Authority 403.704, 403.721, 403.724, 403.8055 FS. Law Implemented 403.704, 403.721, 403.724 FS. History—New 11-8-81, Amended 5-31-84, 9-13-84, Formerly 17-30.17, Amended 9-19-86, 3-31-87, 5-26-87, 6-28-88, Formerly 17-30.170, Amended 1-25-89, 8-13-90, 9-10-91, 10-14-92, 10-7-93, Formerly 17-730.170, Amended 1-5-95, 4-30-97, 8-19-98, 2-4-00, 12-20-00, 8-1-02, 10-1-04, 1-29-06, 4-6-06, 5-1-07, 4-25 08.

62-730.171 Transfer Facilities.

- (1) 40 CFR 263.12 [as adopted by reference in subsection 62-730.170(1), F.A.C.] provides that transporters who store manifested hazardous waste in proper containers at a transfer facility for 10 days or less are exempt from regulation as a hazardous waste facility. If the waste is stored for more than 10 days, the facility is subject to the permitting requirements for a hazardous waste storage facility.
- (2) (a) The transporter who is owner or operator of a transfer facility which stores manifested shipments of hazardous waste for more than 24 hours but 10 days or less (hereinafter referred to as “the transfer facility”) shall obtain an EPA/DEP identification number for each transfer facility location and notify the Department using Form 62-730.900(1)(b), “8700-12FL – Florida Notification of Regulated Waste Activity,” effective date January 4, 2009 [adopted by reference in paragraph 62-730.150(2)(a), F.A.C.].
 - (b) Notification pursuant to this subsection shall be submitted at least 30 days before the storage of hazardous waste is to begin at a transfer facility.
 - (c) The notification shall include the information and documentation required by subsection 62-730.171(3), F.A.C.
 - (d) The transfer facility shall annually submit updated information on Form 62-730.900(1)(b), “8700-12FL – Florida Notification of Regulated Waste Activity,” effective date January 4, 2009, which is adopted and incorporated by reference at paragraph 62-730.150(2)(a), F.A.C.
- (3) (a) The following items constitute initial transfer facility notification:
 1. Certification by a responsible corporate officer of the transporter that the proposed location satisfies the criteria of Section 403.7211(2), F.S. The Certification shall state a factual basis for the conclusion that the location criteria are met, and how those facts were determined.
 2. Completed Form 62-730.900(1)(b), “8700-12FL – Florida Notification of Regulated Waste Activity,” effective date January 4, 2009, which is adopted and incorporated by reference at paragraph 62-730.150(2)(a), F.A.C.
 3. Evidence of the transporter’s financial responsibility as required under subsection 62-730.170(3), F.A.C.
 4. A brief general description of the transfer facility operations, including customer base, anticipated waste codes, operating procedures, structures and equipment (with the maximum design capacity for storage), including engineering drawings or sketches if any.
 5. A copy of a closure plan demonstrating that the transfer facility will be closed in a manner which satisfies the closure performance, notification, and decontamination standards of 40 CFR 265.111, 265.112, 265.114 and 265.115 [as adopted by reference in subsection 62-730.180(2), F.A.C.].
 6. A copy of the contingency and emergency plan required by paragraph 62-730.171(4)(a), F.A.C.
 7. A map or maps of the transfer facility, depicting property boundaries, access control, buildings or other structures and pertinent features (such as recreation areas, runoff and stormwater control systems, access or internal roads, sanitary and process sewer systems, loading and unloading areas, and fire control equipment.)
- (b) A transporter who is operating a transfer facility must notify the Department prior to making changes in any of the items listed in paragraph 62-730.171(3)(a), F.A.C.
- (c) No person shall operate a transfer facility before receiving confirmation from the Department that the initial notification package is complete and technically adequate and receiving an EPA identification number for the transfer facility.
- (4) A transfer facility shall comply with the following requirements:
 - (a) 40 CFR Part 265 Subparts B (general facility standards), C (preparedness and prevention), D (contingency and emergency plan), and I (management of containers), with the exception of 265.13, as adopted by reference in subsection 62-730.180(2), F.A.C.
 - (b) The aisle space requirements described in 40 CFR 265.35 and the special requirements for incompatible wastes described in 40 CFR 265.177(c) shall not apply at transfer facilities to containers stored in trucks loaded in accordance with DOT regulations described in 40 CFR 263.10 [as adopted by reference in subsection 62-730.170(1), F.A.C.].
- (5) Hazardous waste stored at transfer facilities in containers or vehicles shall be stored on a manmade surface which is capable of preventing spills or releases to the ground.
- (6) The transfer facility shall maintain a written record of the items listed below. This recordkeeping requirement applies to all hazardous waste that enters and leaves the transfer facility, including hazardous waste generated by CESQGs. Records required in this subsection shall be maintained in permanent form for at least three years and shall be available for inspection by the Department. The records shall be kept at the facility unless the Department gives written approval to do otherwise.
 - (a) Manifest number for each shipment that enters and leaves the facility, or, for a shipment from a CESQG without a manifest, an identifying number from the shipping document.
 - (b) The date when all hazardous waste enters and leaves the facility.
 - (c) The generator’s name and the EPA/DEP identification number. For CESQGs without an EPA/DEP identification number, the record shall include the name and address of the generator.
 - (d) Amounts of hazardous waste and hazardous waste codes associated with each shipment into and out of the facility.
- (7) Within 60 days of closure of the transfer facility, the transporter who is owner or operator of the transfer facility shall submit to the Department a certification that the facility has been closed in accordance with the specifications in the closure plan. The certification shall be signed by the owner or operator of the transfer facility, by the owner of the real property where the transfer facility is located, and by a Florida-registered, professional engineer.
- (8) Construction, initial operation or substantial modification of a transfer facility which stores shipments of hazardous waste that are required to be manifested, and which does not comply with the location standards in Section 403.7211, F.S., is prohibited. A transporter operating a transfer facility is subject to the demonstration requirements of subsections 62-730.182(3)-(8), F.A.C., regarding substantial modification.

Specific Authority 403.0877, 403.704, 403.721 FS. Law Implemented 403.0877, 403.704, 403.721 FS. History—New 3-2-86, Amended 6-28-88, Formerly 17-30.171, Amended 8-13-90, 9-10-91, 10-14-92, Formerly 17-730.171, Amended 1-5-95, 1-29-06, 10-28-08, 1-4-09.