

*Comment on Task* *Black Book*  
 STATE OF FLORIDA  
 DEPARTMENT OF ENVIRONMENTAL REGULATION  
*Certification included Permit Application*

TWIN TOWERS OFFICE BUILDING  
 2800 BLAIR STONE ROAD  
 TALLAHASSEE, FLORIDA 32399-2400



BOB MARTINEZ  
 GOVERNOR  
 DALE TWACHTMANN  
 SECRETARY

RCRA PERMITTING -- ROUTING SLIP


Facility/Item: Safety Klean - Tallahassee

Pats No: H037 - 171747

Date Document Received: \_\_\_\_\_

Date Action Required: \_\_\_\_\_

Action Is:        Urgent  
                           Routine


TO	Name	SIGNATURE	DATE
<input type="checkbox"/>	JOHN GRIFFIN	_____	_____
<input type="checkbox"/>	DIANE HUNT	_____	_____
<input type="checkbox"/>	SATISH KASTURY	_____	_____
<input type="checkbox"/>	SHELTON GRAVES	_____	_____
<input checked="" type="checkbox"/>	RABIN PRUSTY		_____
<input type="checkbox"/>	DEBRA OUTLEY	_____	_____
<input type="checkbox"/>	MERLIN RUSSELL	_____	_____
<input type="checkbox"/>	AMOS OYELOWO	_____	_____
<input type="checkbox"/>	FRED WICK	_____	_____
<input type="checkbox"/>	JANET ASHWOOD	_____	_____
<input type="checkbox"/>	ROBERT FROST	_____	_____
<input checked="" type="checkbox"/>	BILL NEIMES	_____	_____
<input type="checkbox"/>	JIM LEBAR	_____	_____

REQUIRED ACTION & COMMENT:

\_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

RETURN TO: SEA FOR FILING !

LOGGED IN



State of Florida  
DEPARTMENT OF ENVIRONMENTAL REGULATION

For Routing To Other Than The Addressee	
To: <u>FACILITY FILES</u>	Location: _____
To: _____	Location: _____
To: _____	Location: _____
From: _____	Date: _____

# Interoffice Memorandum

TO: Bill Kellenberger, District Engineer Pensacola

THROUGH: Tom Moody, P.E. Administrator, Pensacola  
Satish Kastury, Administrator *in charge*  
Hazardous Waste Regulation

FROM: Bill Neimes, P.E. II *BN*  
Hazardous Waste Regulation

DATE: December 7, 1989

SUBJECT: Safety Kleen - Tallahassee; FLD 982 133 159; H037-171747; Tank Certification Included with Permit Application.

I have reviewed the tank certification section of the permit application for the subject permit and offer one comment. On page 2 of the Project Observation Report No. 4 done by Wishmeirer & Associates under the heading Dirty Solvent Line from Dirty Pump to Dumpsters, the pressure test results indicate the dumpster connection hoses could not hold the 85 psi test pressure. The engineer ended up testing only the hard piping and not the flexible piping. The Department will need to know, before accepting the tank certification section, if all piping (flexible and hard) passed the pressure tests.

BN/do