DOCUMENT RECEIVED IN ELECTRONIC FORMAT FOLLOWS:

• FDEP RECEIVED DATE-STAMPED PAGE



13101 Telecom Drive, Suite 120 Tampa, FL 33637 PH 813-558-0990 FAX 813-558-9726 www.geosyntec.com

28 October 2011

Mr. Thomas Lubozynski, P.E. Waste Program Administrator Florida Department of Environmental Protection Central District Office 3319 Maguire Boulevard, Suite 232 Orlando, Florida 32803-3767 RECEIVED

OCT 3 | 2011

PER Central Plate

Subject: Minor Modification Permit Application

Phased Financial Assurance Cell 8 Construction

J.E.D. Solid Waste Management Facility (WACS #89544)

Osceola County, Florida

Dear Mr. Lubozynski:

Transmitted herein are four copies of the J.E.D. Solid Waste Management Facility (JED facility) Minor Modification Permit Application (Application). This application is submitted on behalf of Omni Waste of Osceola County, LLC (Omni) for the JED facility located in St. Cloud, Florida. This Application package contains three (3) hard-copies and one (1) electronic copy of the Application, and one check in the amount of \$250 (in accordance with Rule 62-701.315(4), F.A.C.).

If you have any questions or need additional information, please do not hesitate to contact the undersigned.

Sincerely,

Victor M. Damasceno, Ph.D., P.E.

Project Engineer

Florida P.E. No. 72966

Attachment

Copies to: Michael Kaiser, WSI

Prepared for



Omni Waste of Osceola County, LLC

1501 Omni Way St. Cloud, Florida 34773

RECEIVED
OCT 3 1 2011
OEP Central Dist.

MINOR MODIFICATION APPLICATION FOR PHASED FINANCIAL ASSURANCE CELL 8 CONSTRUCTION

J.E.D. Solid Waste Management Facility Osceola County, Florida

Prepared by

Geosyntec^D

consultants

13101 Telecom Drive, Suite 120 Tampa, Florida 33637

Project No. FL1985

October 2011



Omni Waste of Osceola County, LLC

1501 Omni Way St. Cloud, Florida 34773

MINOR MODIFICATION APPLICATION FOR PHASED FINANCIAL ASSURANCE CELL 8 CONSTRUCTION

J.E.D. Solid Waste Management Facility Osceola County, Florida

Prepared by



consultants

13101 Telecom Drive, Suite 120 Tampa, Florida 33637

Project No. FL1985

October 2011

Attachment 3 – Notes and Calculations



TABLE OF CONTENTS

1 INTROD	UCTION	1
2 PROJEC	Γ BACKGROUND	1
3 FINANCI	AL ASSURANCE COST ESTIMATE FOR CELL 8	2
ATTACHMI	ENTS	
Attachment 1	– FDEP Form 62-701.900(1)	
Attachment 2	- FDEP Form 62-701.900(28)	



MINOR MODIFICATION APPLICATION FOR CELL 8 FINANCIAL ASSURANCE J.E.D. SOLID WASTE MANAGEMENT FACILITY OSCEOLA COUNTY, FLORIDA

1 INTRODUCTION

Geosyntec Consultants (Geosyntec) has prepared this minor permit modification application (application) to provide the closure and long-term care cost estimates for Cell 8 at the J.E.D. Solid Waste Management (JED) facility, located in Osceola County, Florida. The closure and long-term care cost estimates for the JED facility are being updated to include Cell 8, the first cell to be constructed as part of Phase 3 development. Phase 3 development at the JED facility consists of three cells – Cells 8 through 10. To date, Cells 1 through 7 have been constructed. Cell 8 construction is scheduled to begin in October 2011 and is expected to be completed in the first quarter of 2012.

The JED facility is owned and operated by Omni Waste of Osceola County, LLC (Omni), which is a wholly owned subsidiary of Waste Services, Inc. (WSI). This minor modification application is being submitted to the Florida Department of Environmental Protection (FDEP), Central District on behalf of Omni.

Furthermore, this application is being submitted to comply with the requirements of Specific Condition No. 66 of FDEP Solid Waste Permit No. SC49-0199726-015 and provides updated closure and long-term care cost estimates for Cell 8. Attachment 1 includes the FDEP Form 62-701.900(1) – Application for a Permit to Construct, Operate, Modify or Close a Solid Waste Management Facility – which has been completed for this minor modification for phased financial assurance for Cell 8.

2 PROJECT BACKGROUND

The current 5-year construction and operation permit authorizes the development of Phases 1 through 3 of the JED facility. Phase 1 consists of four cells, Cells 1 through 4, and has a footprint of approximately 53 acres. Phase 2 consists of three cells, Cells 5 through 7, and has a footprint of approximately 36 acres. Phase 3 consists of three cells, Cells 8 through 10, and has a footprint of approximately 37 acres. The combined footprint of Phases 1 through 3 is approximately 126 acres. To date, Cells 1 through 7 have been constructed at the JED facility.

Since the remaining cells in Phase 3 will be constructed at different times, the financial assurance requirements for each new cell to be constructed will be submitted to FDEP as a minor permit modification for each new cell constructed. Annual financial assurance updates



will consider only the cells containing waste during the period covered by the financial assurance. The current financial assurance approved by FDEP for the JED facility includes the closure cost for the remaining portion of Phase 1, Cells 1 through 4 areas (not closed as part of the Phase 1 partial closure completed in 2009), Cells 5 through 7, and the long-term care costs for Cells 1 through 7. The currently approved and financially assured closure costs are \$5,950,241.32 and long-term care costs are \$7,404,650.74.


3 FINANCIAL ASSURANCE COST ESTIMATE FOR CELL 8

This minor permit modification application is being submitted to update the financial assurance cost estimate for the JED facility to include Cell 8. FDEP Form 62-701.900(28) – Closure Cost Estimating Form for Solid Waste Facilities – is included as Attachment 2; and the notes and calculations presented in Attachment 3. The closure and long-term care costs for Cell 8 were estimated using the FDEP approved unit rate costs from the financial assurance cost estimate revision associated with the addition of Cell 7, completed and approved in 24 February 2011. The unit rate costs used to calculate the closure and long-term care costs for Cell 8 have been inflated by 1% to account for the 2011 inflation adjustment issued by FDEP on 19 July 2011. The unit rates used herein will be verified and/or adjusted after completion of the next partial closure activities – expected to occur on or around spring of 2011. Note that the financial assurance cost estimate presented in Attachment 2 includes the closure and long-term care costs for Cell 8 only.

The closure and long-term care cost estimates for Cells 1 through 7, and Cell 8 at the JED facility are presented in the table below.

Cell Identification	Closure Cost Estimate	Long-Term Care Cost Estimate	Financial Assurance Cost Estimate
Cells 1 – 7	\$5,950,241.32	\$7,404,650.74	\$13,354,892.06
Cell 8	\$988,711.78	\$538,887.69	\$1,527,599.47
Total	\$6,938,953.10	\$7,943,538.43	\$14,882,491.53

Omni will provide FDEP with an insurance certificate for the revised financial assurance cost estimate of **\$14,882,491.53** upon verbal or written approval of this revised closure cost estimate.





Florida Department of Environmental Protection

Bob Martinez Center 2600 Blair Stone Road Tallahassee, Florida 32399-2400 DEP Form #: 62-701.900(1), F.A.C.

Form Title: Application to Construct, Operate, Modify, or Close a Solid Waste Management Facility

Effective Date: January 6, 2010

Incorporated in Rule: 62-701.330(3), F.A.C.

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION

APPLICATION TO CONSTRUCT, OPERATE, MODIFY, OR CLOSE A SOLID WASTE MANAGEMENT FACILITY

APPLICATION INSTRUCTIONS AND FORMS

INSTRUCTIONS TO APPLY FOR A SOLID WASTE MANAGEMENT FACILITY PERMIT

I. General

Solid Waste Management Facilities shall be permitted pursuant to Section 403.707, Florida Statutes,(FS) and in accordance with Florida Administrative Code (FAC) Chapter 62-701. A minimum of four copies of the application shall be submitted to the Department's District Office having jurisdiction over the facility. The appropriate fee in accordance with Rule 62-701.315, FAC, shall be submitted with the application by check made payable to the Department of Environmental Protection (DEP).

Complete appropriate sections for the type of facility for which application is made. Entries shall be typed or printed in ink. All blanks shall be filled in or marked "not applicable" or "no substantial change". Information provided in support of the application shall be marked "submitted" and the location of this information in the application package indicated. The application shall include all information, drawings, and reports necessary to evaluate the facility. Information required to complete the application is listed on the attached pages of this form.

II. Application Parts Required for Construction and Operation Permits

- A. Landfills and Ash Monofills Submit Parts A through S
- B. Asbestos Monofills Submit Parts A,B,C,D,E,F,I,K,M, O through S
- C. Industrial Solid Waste Disposal Facilities Submit Parts A through S

NOTE: Portions of some Parts may not be applicable.

NOTE: For facilities that have been satisfactorily constructed in accordance with their construction permit, the information required for A, B and C type facilities does not have to be resubmitted for an operation permit if the information has not substantially changed during the construction period. The appropriate portion of the form should be marked "no substantial change".

III. Application Parts Required for Closure Permits

- A. Landfills and Ash Monofills Submit Parts A,B,L, N through S
- B. Asbestos Monofills Submit Parts A,B,M, O through S
- C. Industrial Solid Waste Disposal Facilities Submit Parts A,B, L through S

NOTE: Portions of some Parts may not be applicable.

IV. Permit Renewals

The above information shall be submitted at time of permit renewal in support of the new permit. However, facility information that was submitted to the Department to support the expiring permit, and which is still valid, does not need to be re-submitted for permit renewal. Portions of the application not re-submitted shall be marked "no substantial change" on the application form.

V. Application Codes

S - Submitted

LOCATION - Physical location of information in application

N/A - Not Applicable

N/C - No Substantial Change

VI. LISTING OF APPLICATION PARTS

PART A: GENERAL INFORMATION

PART B: DISPOSAL FACILITY GENERAL INFORMATION

PART C: PROHIBITIONS

PART D: SOLID WASTE MANAGEMENT FACILITY PERMIT REQUIREMENTS, GENERAL

PART E: LANDFILL PERMIT REQUIREMENTS

PART F: GENERAL CRITERIA FOR LANDFILLS

PART G: LANDFILL CONSTRUCTION REQUIREMENTS

PART H: HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS

PART I: GEOTECHNICAL INVESTIGATION REQUIREMENTS

PART J: VERTICAL EXPANSION OF LANDFILLS

PART K: LANDFILL OPERATION REQUIREMENTS

PART L: WATER QUALITY AND LEACHATE MONITORING REQUIREMENTS

PART M: SPECIAL WASTE HANDLING REQUIREMENTS

PART N: GAS MANAGEMENT SYSTEM REQUIREMENTS

PART O: LANDFILL CLOSURE REQUIREMENTS

PART P: OTHER CLOSURE PROCEDURES

PART Q: LONG-TERM CARE

PART R: FINANCIAL ASSURANCE

PART S: CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION APPLICATION FOR A PERMIT TO CONSTRUCT, OPERATE, MODIFY OR CLOSE A SOLID WASTE MANAGEMENT FACILITY

Please Type or Print

PART	A. GENERAL INFORMATION								
1.	Type of disposal facility (check all that	at apply):							
	☑ Class I Landfill	☐ Ash Monofill							
	☐ Class III Landfill	☐ Asbestos Monofill							
	☐ Industrial Solid Waste								
	☐ Other Describe:								
NOTE:	Waste Processing Facilities should a Land Clearing Disposal Facilities sho Compost Facilities should apply on F C&D Disposal Facilities should apply	ould notify on Form 62-701.900(3), FAC; Form 62-701.900(10), FAC; and							
2.	Type of application:								
	□ Construction								
	☑ Operation								
	□ Construction/Operation								
	□ Closure								
	☐ Long-term Care Only								
3.	Classification of application:								
	□ New	□ Substantial Modification							
	□ Renewal	☐ Intermediate Modification							
4.	Facility name:J.E.D. Solid Waste	☑ Minor Modification a Management Facility							
5.	DEP ID number: 89544 (WACS	SID) County: Osceola							
6.	Facility location (main entrance):								
	1501 Omni Way, Saint Cloud, Flor	ida 34773							
7.	Location coordinates:								
	Section: <u>11,13,14,17,18</u> Townsh	nip:28S Range:32E & 33E							
	Latitude: 28° 3	<u>32</u> " Longitude: <u>81</u> ° <u>5</u> '	46						
	Datum: WGS84 Co	ordinate Method: DGPS							
	Collected by: Johnston's Surveying	Company/Affiliation: Johnston's Surveying							

8.	Applicant name (operating authority): Omni Waste of O	sceola County, LLC (O	mni)
	Mailing address: _1501 Omni Way	Saint Cloud	Florida 34773
	Street or P.O. Box	City	State Zip
	Contact person: Mike Kaiser	Telephone: (<u>904</u>	673-0446
	Title: Regional Engineer		
		MKaiser@Was	teservicesinc.com
9.	Authorized agent/Consultant: Geosyntec Consultants	E-Mail addre	ess (if available)
Э.	•	Tamania Tamana	FI 22027
	Mailing address: 13101 Telecom Drive, Suite 120 Street or P.O. Box	Temple Terrace City	FL 33637 State Zip
	Contact person: Victor M. Damasceno	Telephone: (813) 558-0990
	Title: Engineer	1010p110110. (<u></u>	
	Title. Engineer	1/0	
			Geosyntec.com ss (if available)
10.	Landowner (if different than applicant): N/A		,
10.	, , , , , , , , , , , , , , , , , , , ,		
	Mailing address:Street or P.O. Box	City	State Zip
	Contact person:	Telephone: ()
	,	. \	
4.4	Cities towns and speed to be seened.	E-Mail add	dress (if available)
11.	Cities, towns and areas to be served: Primarily Osceola, Brevard, Indian River, Okeechobee		
	Pasco, Hillsborough, Hardee, and Highlands Counties streams are available.	s. Other Florida countie	es are served as waste
40	Bookston to be accord		
12.	Population to be served: Five-Y	ear (appro	ovimato)
		etion: 6,239,688 (appro	
13.	Date site will be ready to be inspected for completion: A	nticipated Cell 8 comple	etion: Spring 2012
14.	Expected life of the facility:5years (Phases 1 - 3)		
15.	Estimated costs: (Estimated costs correspond to construction and correspond	onding closing for the 272.7-acre Ce	ells 8 through 23 area)
	Total Construction: \$_N/AC	Closing Costs: \$ 988,711	1.78
16.	Anticipated construction starting and completion dates:		
	From: N/A	o∙ N/A	
47		J. <u> </u>	
17.	Expected volume or weight of waste to be received:		
	yds³/day6,000 tons/d	lay	gallons/day

PART B. DISPOSAL FACILITY GENERAL INFORMATION

	s being submitted to upda		assurance for the J.E.D.
Facility to include the closure and lo	ng-term care costs estima	ate for Cell 8.	
-			
Facility site supervisor: Matt Orr			
Title: District Manager	Telephone:	· /407 \ 891 - 371	20
Title. District Warrager	releptione.	, ,	
			Vasteservicesinc.com
		E-Mail a	address (if available)
Disposal area: Total36	<u>60</u> acres; Used	88.2 acres;	Available 271.8 a
		88.2 acres;	Available271.8 a
Disposal area: Total36 Weighing scales used: ☑ Yes □ No		88.2 acres;	Available <u>271.8</u> a
)	88.2 acres;	Available <u>271.8</u> a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use	e: ☑ Yes □ No		Available <u>271.8</u> a
Weighing scales used: ☑ Yes ☐ No	e: ☑ Yes □ No		Available <u>271.8</u> a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use	e: ☑ Yes □ No		Available <u>271.8</u> a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:Surrounding land use, zoning:	o e: ☑ Yes □ No \$/yds³		Available <u>271.8</u> a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received: Surrounding land use, zoning: ☐ Residential	o e: ☑ Yes □ No \$/yds³ □ Industrial		Available 271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available 271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received: Surrounding land use, zoning: ☐ Residential	o e: ☑ Yes □ No \$/yds³ □ Industrial	<u>35</u> \$/ton	Available 271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available 271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available 271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized use Charge for waste received:	o e: ☑ Yes □ No \$/yds³ □ Industrial □ None	<u>35</u> \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized used: ☐ Charge for waste received: ☐ Surrounding land use, zoning: ☐ Residential ☐ Agricultural ☐ Commercial ☐ Commercial ☐ Types of waste received:	e: ☑ Yes □ No\$/yds³ □ Industrial □ None □ Other Describe	35 \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized used: ☐ Charge for waste received: ☐ Surrounding land use, zoning: ☐ Residential ☐ Agricultural ☐ Commercial ☐ ☐ Types of waste received: ☐ Household	e: ☑ Yes □ No\$/yds³ □ Industrial □ None □ Other Describe	35 \$/ton	Available271.8 a
Weighing scales used: ☑ Yes ☐ Not Security to prevent unauthorized used: ☐ Charge for waste received: ☐ Surrounding land use, zoning: ☐ Residential ☐ Agricultural ☐ Commercial ☐ United Description ☐ Commercial ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐ ☐	© Yes □ No\$/yds³ □ Industrial □ None □ Other Describe □ C & D debris □ Shredded/cut t	35 \$/ton	Available271.8 a

☐ Agricultural	☑ Domestic sludge
Asbestos waste tires, auto shredder waste	 ☑ Other Describe: e, and industrial liquid waste for solidification
Salvaging permitted: □ Yes ☑ No	
Attendant: ☑ Yes ☐ No	Trained operator: ☑ Yes ☐ No
Frained spotters: ☑ Yes ☐ No	Number of spotters used: 1 (minimum per work face)
Site located in: ☑ Floodplain	□ Wetlands □ Other:
Days of operation: Monday through S	aturday
ays of operation. Monday through c	aturday
	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m.
Hours of operation: Monday-Friday:	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m.
Hours of operation: Monday-Friday: Oays Working Face covered: Each w	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m.
Hours of operation: Monday-Friday: Oays Working Face covered: Each wellevation of water table: 79	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m.
Hours of operation: Monday-Friday: Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929
Hours of operation: Monday-Friday: Oays Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points:	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929
Hours of operation: Monday-Friday: © Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: ☑ Yes □ No	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929
Hours of operation: Monday-Friday: Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: Yes □ No Gas flaring: Yes □ No	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 2 Type controls: ☑ Active □ Passive
Hours of operation: Monday-Friday: Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: Yes No Gas flaring: Yes No Landfill unit liner type:	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 2 Type controls: ☑ Active □ Passive
Hours of operation: Monday-Friday: Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: Yes No Gas flaring: Yes No Landfill unit liner type: Natural soils	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 Type controls: Active Passive Gas recovery: Yes No
Hours of operation: Monday-Friday: Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: 63 Sas controls used: Yes No Sas flaring: Yes No andfill unit liner type: Natural soils Single clay liner	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 Type controls: ☑ Active □ Passive Gas recovery: □ Yes ☑ No □ Double geomembrane
Hours of operation: Monday-Friday: © Days Working Face covered: Each wellevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: ✓ Yes □ No Gas flaring: ✓ Yes □ No Landfill unit liner type: □ Natural soils □ Single clay liner □ Single geomembrane	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 Type controls: ☑ Active □ Passive Gas recovery: □ Yes ☑ No □ Double geomembrane □ Geomembrane & composite
Hours of operation: Monday-Friday: Days Working Face covered: Each well- Elevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: Yes No Gas flaring: Yes No Landfill unit liner type: Natural soils Single clay liner Single geomembrane Single composite Slurry wall	6 a.m. to 5 p.m.; Saturday 6 a.m. to 2 p.m. orking day ft. Datum Used: NGVD 1929 2 Type controls: ☑ Active □ Passive Gas recovery: □ Yes ☑ No □ Double geomembrane □ Geomembrane & composite ☑ Double composite
Hours of operation: Monday-Friday: Days Working Face covered: Each well- Elevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: Yes No Gas flaring: Yes No Landfill unit liner type: Natural soils Single clay liner Single geomembrane Single composite Slurry wall	orking day ft. Datum Used: NGVD 1929 Type controls: ☑ Active □ Passive Gas recovery: □ Yes ☑ No □ Double geomembrane □ Geomembrane & composite ☑ Double composite □ None ☑ Other Describe:
Hours of operation: Monday-Friday: © Days Working Face covered: Each well Elevation of water table: 79 Number of monitoring wells: 63 Number of surface monitoring points: Gas controls used: ☑ Yes ☐ No Gas flaring: ☑ Yes ☐ No Landfill unit liner type: ☐ Natural soils ☐ Single clay liner ☐ Single geomembrane ☐ Single composite ☐ Slurry wall	orking day ft. Datum Used: NGVD 1929 Type controls: ☑ Active □ Passive Gas recovery: □ Yes ☑ No □ Double geomembrane □ Geomembrane & composite ☑ Double composite □ None ☑ Other Describe:

Leachate collection method:	
☑ Collection pipes	☑ Sand layer
☑ Geonets (geocomposite)	☐ Gravel layer
□ Well points	☐ Interceptor trench
☐ Perimeter ditch	□ None
☐ Other Describe:	
Leachate storage method:	
□ Tanks	☑ Surface impoundments
☐ Other Describe:	
Leachate treatment method:	
✓ Oxidation	☐ Chemical treatment
□ Secondary	□ Settling
☐ Advanced	☑ None
☐ Other	LI NOTIC
Oxidation achieved through aer	ration in the uncovered Cell 2 of the leachate storage area. Cells 1, 3, and
4 are covered with no oxidation	activity.
Leachate disposal method:	
☑ Recirculated	□ Pumped to WWTP
☑ Transported to WWTP	☐ Discharged to surface water/wetland
☐ Injection well	☐ Percolation ponds
☑ Evaporation	☐ Spray Irrigation
□ Other	□ opray imgalion

Name and Class of receiving water: N/A Storm Water: Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-005-EI (Conceptual).	Storm Water: Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	For I	eachate discharged to surface waters:
Storm Water: Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3	Storm Water: Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3	Nam	ne and Class of receiving water:
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	N/A	<u>. </u>
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.	Collected: ☑ Yes ☐ No Type of treatment: Dry and wet retention for landfill and dry retention for access road.		
Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Indivi	Type of treatment: Dry and wet retention for landfill and dry retention for access road. Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002-EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Stori	m Water:
Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Colle	ected: ☑ Yes □ No
Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Name and Class of receiving water: Bull Creek, Class III Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Туре	e of treatment:
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	ыу	and wet retention for landing and dry retention for access road.
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Environmental Resources Permit (ERP) number or status: Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Nam	le and Class of receiving water:
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Bui	Cleek, Class III
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Current ERP numbers are ERP49-0199752-001-EI (Phase 1 Individual), ERP49-0199752-002EI (Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)		
(Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	(Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	Envi	ronmental Resources Permit (ERP) number or status:
(Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	(Conceptual), ERP49-0199752-003 (Phase 2 Individual), ERP49-0199752-004-EM (Phase 3 Individual)	0.	
and Ent. 40 0100/02 000 Et (Oundeplual).	and Ent. 40 0100702 000 ET (Ouroepidal).		
		and	LIN -40-0133132-000-LI (Conceptual).

PART C. **PROHIBITIONS** (62-701.300, FAC) <u>S</u> **LOCATION** N/A N/C **√** П 1. Provide documentation that each of the siting criteria will be satisfied for the facility; (62-701.300(2), FAC) **√** П 2. If the facility qualifies for any of the exemptions contained in Rules 62-701.300(12) through (18), FAC, then document this qualification(s). \checkmark 3. Provide documentation that the facility will be in compliance with the burning restrictions; (62-701.300(3), FAC) **√** 4. Provide documentation that the facility will be in compliance with the hazardous waste restrictions; (62-701.300(4), FAC) **√** 5. Provide documentation that the facility will be in compliance with the PCB disposal restrictions; (62-701.300(5), FAC) \checkmark 6. Provide documentation that the facility will be in compliance with the biomedical waste restrictions; (62-701.300(6), FAC) \checkmark 7. Provide documentation that the facility will be in compliance with the Class I surface water restrictions: (62-701.300(7), FAC) \checkmark 8. Provide documentation that the facility will be in compliance with the special waste for landfills restrictions; (62-701.300(8), FAC) **√** 9. Provide documentation that the facility will be in compliance with the liquid restrictions: (62-701.300(10), FAC) \checkmark 10. Provide documentation that the facility will be in compliance with the used oil and oily waste restrictions; (62-701.300(11), FAC) PART D. SOLID WASTE MANAGEMENT FACILITY PERMIT REQUIREMENTS, GENERAL (62-701.320, FAC) **LOCATION** N/A N/C <u>S</u>

Submittal

1. Four copies, at minimum, of the completed application form, all supporting data and reports; (62-701.320(5)(a),FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C	PART D CONTINUED
V	Attachment 1, Sheet 40 Attachment 2, Sheet 9			2. Engineering and/or professional certification (signature, date and seal) provided on the applications and all engineering plans, reports and supporting information for the application; (62-701.320(6),FAC)
✓	Attached to Report Cover			3. A letter of transmittal to the Department; (62-701.320(7)(a),FAC)
V	Attachment 1			4. A completed application form dated and signed by the applicant; (62-701.320(7)(b),FAC)
V	Attached to Report Cover			5. Permit fee specified in Rule 62-701.315, FAC in check or money order, payable to the Department; (62-701.320(7)(c),FAC)
				6. An engineering report addressing the requirements of this rule and with the following format: a cover sheet, text printed on 8 1/2 inch by 11 inch consecutively numbered pages, a table of contents or index, the body of the report and all appendices including an operation plan, contingency plan, illustrative charts and graphs, records or logs of tests and investigations, engineering calculations; (62-701.320(7)(d),FAC)
		V		7. Operation Plan and Closure Plan; (62-701.320(7)(e)1,FAC)
		V		8. Contingency Plan; (62-701.320(7)(e)2,FAC)
				9. Plans or drawings for the solid waste management facilities in appropriate format (including sheet size restrictions, cover sheet, legends, north arrow, horizontal and vertical scales, elevations referenced to NGVD 1929) showing; (62-701.320(7)(f),FAC)
				 a. A regional map or plan with the project location in relation to major roadways and population centers;
		7		b. A vicinity map or aerial photograph no more than 1 year old showing the facility site and relevant surface features located within 1000 feet of the facility;
		√		c. A site plan showing all property boundaries certified by a Florida Licensed Professional Surveyor and Mapper; and
				d. Other necessary details to support the engineering report, including referencing elevations to a consistent, nationally recognized datum and identifying the method used for collecting latitude and longitude data.

<u>S</u>	<u>LOCATION</u>	N/A	N/C	PART D CONTINUED
<u> </u>		_ 🗸		10. Documentation that the applicant either owns the property or has legal authority from the property owner to use the site; (62-701.320(7)(g),FAC)
□ <u> </u>		_ 🗸		11. For facilities owned or operated by a county, provide a description of how, if any, the facilities covered in this application will contribute to the county's achievement of the waste reduction and recycling goals contained in Section 403.706,FS; (62-701.320(7)(h),FAC)
□ <u> </u>		_ 🗸		12. Provide a history and description of any enforcement actions taken by the Department against the applicant for violations of applicable statutes, rules, orders or permit conditions relating to the operation of any solid waste management facility in this state; (62-701.320(7)(i),FAC)
<u> </u>		_ 🗸		13. Proof of publication in a newspaper of general circulation of notice of application for a permit to construct or substantially modify a solid waste management facility; (62-702.320(8),FAC)
<u> </u>		_ 🗸		14. Provide a description of how the requirements for airport safety will be achieved including proof of required notices if applicable. If exempt, explain how the exemption applies; (62-701.320(13),FAC)
<u> </u>		_ ✓		15. Explain how the operator and spotter training requirements and special criteria will be satisfied for the facility; (62-701.320(15), FAC)
PART	E. LANDFILL	PERMIT F	REQUIRE	EMENTS (62-701.330, FAC)
<u>s</u>	LOCATION	N/A	N/C	
<u> </u>		_ 🗸		1. Regional map or aerial photograph no more than 5 years old showing all airports that are located within five miles of the proposed landfill; (62-701.330(3)(a),FAC)
<u> </u>		_ ✓		2. Plot plan with a scale not greater than 200 feet to the inch showing; (62-701.330(3)(b),FAC)
<u> </u>		_ ✓		a. Dimensions;
<u> </u>		_		b. Locations of proposed and existing water quality monitoring wells;
П		7	П	c. Locations of soil borings:

<u>S</u>	LOCATION	<u>N/A</u>	N/C	PART E CONTINUED
		_ 		d. Proposed plan of trenching or disposal areas;
<u> </u>		_ 🗸		e. Cross sections showing original elevations and proposed final contours which shall be included either on the plot plan or on separate sheets;
□ <u> </u>		_ ✓		f. Any previously filled waste disposal areas;
□ <u> </u>		✓		g. Fencing or other measures to restrict access.
□ <u> </u>		_ 🗸		3. Topographic maps with a scale not greater than 200 feet to the inch with 5-foot contour intervals showing; (62-701.330(3)(c),FAC):
□ <u> </u>		_ 🗸		a. Proposed fill areas;
□ <u> </u>		✓		b. Borrow areas;
□ <u> </u>		<u> </u>		c. Access roads;
<u> </u>		_ ✓		d. Grades required for proper drainage;
<u> </u>		_ ✓		e. Cross sections of lifts;
□ <u> </u>		_ ✓		f. Special drainage devices if necessary;
□ <u> </u>		_ ✓		g. Fencing;
<pre></pre>		_ ✓		h. Equipment facilities.
□ <u> </u>		_		4. A report on the landfill describing the following; (62-701.330(3)(d),FAC)
<u> </u>		_ ✓		a. The current and projected population and area to be served by the proposed site;
□ <u> </u>		_		b. The anticipated type, annual quantity, and source of solid waste expressed in tons;
<u> </u>		_ ✓		c. Planned active life of the facility, the final design height of the facility and the maximum height of the facility during its operation;

<u>S</u>	LOCATION	N/A	N/C	PART E CONTINUED
□ <u> </u>		<u> </u>		d. The source and type of cover material used for the landfill.
□ <u> </u>	ection 3 of Report and	_ 🗸		5. Provide evidence that an approved laboratory shall conduct water quality monitoring for the facility in accordance with Chapter 62-160,FAC; (62-701.330(3)(g),FAC)
	ttachment 2, Section II	_ 🗆		6. Provide a statement of how the applicant will demonstrate financial responsibility for the closing and long-term care of the landfill; (62-701.330(3)(h),FAC)
PART	F. GENERAL (CRITERIA	A FOR LA	ANDFILLS (62-701.340,FAC)
<u>s</u>	<u>LOCATION</u>	<u>N/A</u>	N/C	
□ <u> </u>		_ 🗷		1. Describe (and show on a Federal Insurance Administration flood map, if available) how the landfill or solid waste disposal unit shall not be located in the 100-year floodplain where it will restrict the flow of the 100-year flood, reduce the temporary water storage capacity of the floodplain unless compensating storage is provided, or result in a washout of solid waste; (62-701.340(3)(b),FAC)
□ <u> </u>		_ 🗸		2. Describe how the minimum horizontal separation between waste deposits in the landfill and the landfill property boundary shall be 100 feet, measured from the toe of the proposed final cover slope; (62-701.340(3)(c),FAC)
PART	G. LANDFILL (CONSTR	UCTION	REQUIREMENTS (62-701.400,FAC)
<u>s</u>	LOCATION	N/A	N/C	
□ <u> </u>		_ 🗹		1. Describe how the landfill shall be designed so that solid waste disposal units will be constructed and closed at planned intervals throughout the design period of the landfill and shall be designed to achieve a minimum factor of safety of 1.5 using peak strength values to prevent failures of side slopes and deep-seated failures; (62-701.400(2),FAC)
□ _		_ ✓		2. Landfill liner requirements; (62-701.400(3),FAC)
□ _		_ ✓		a. General construction requirements; (62-701.400(3)(a),FAC):
□ <u> </u>		_ 🗸		(1) Provide test information and documentation to ensure the liner will be constructed of materials that have appropriate physical, chemical, and mechanical properties to prevent failure;

<u>s</u>	<u>LOCATION</u>	N/A	N/C		PART G CONTINUED
□ <u> </u>		V		(2)	Document foundation is adequate to prevent liner failure;
<u> </u>		V		(3)	Constructed so bottom liner will not be adversely impacted by fluctuations of the ground water;
_		V		(4)	Designed to resist hydrostatic uplift if bottom liner located below seasonal high ground water table;
_		V		(5)	Installed to cover all surrounding earth which could come into contact with the waste or leachate.
□ <u> </u>		V		b. Cor	mposite liners; (62-701.400(3)(b),FAC)
□ <u> </u>		✓		(1)	Upper geomembrane thickness and properties;
□ <u> </u>		V		(2)	Design leachate head for primary LCRS including leachate recirculation if appropriate;
□ <u> </u>		/		(3)	Design thickness in accordance with Table A and number of lifts planned for lower soil component.
		✓		c. Dou	uble liners; (62-701.400(3)(c),FAC)
<u> </u>		V		(1)	Upper and lower geomembrane thicknesses and properties;
<u> </u>		V		(2)	Design leachate head for primary LCRS to limit the head to one foot above the liner;
□ <u> </u>		V		(3)	Lower geomembrane sub-base design;
□ _		√		(4)	Leak detection and secondary leachate collection system minimum design criteria (k ≥ 10 cm/sec, head on lower liner ≤ 1 inch, head not to exceed thickness of drainage layer);
□ _		V			andards for geosynthetic components; (62-00(3)(d),FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C		PART G CONTINUED
□ <u> </u>		7		(1)	Factory and field seam test methods to ensure all geomembrane seams achieve the minimum specifications;
<u> </u>		7		(2)	Geomembranes to be used shall pass a continuous spark test by the manufacturer;
□ <u> </u>		7		(3)	Design of 24-inch-thick protective layer above upper geomembrane liner;
		√		(4)	Describe operational plans to protect the liner and leachate collection system when placing the first layer of waste above 24-inch-thick protective layer.
□ <u> </u>		V		(5)	HDPE geomembranes, if used, meet the specifications in GRI GM13 and LLDPE geomembranes, if used, meet the specifications in GRI GM17;
□ <u> </u>		V		(6)	PVC geomembranes, if used, meet the specifications in PGI 1104;
□ <u> </u>		V		(7)	Interface shear strength testing results of the actual components which will be used in the liner system;
□ <u> </u>		V		(8)	Transmissivity testing results of geonets if they are used in the liner system;
<u> </u>		V		(9)	Hydraulic conductivity testing results of geosynthetic clay liners if they are used in the liner system;
□ <u> </u>		7			osynthetic specification requirements; (62-00(3)(e),FAC)
□ <u> </u>		V		(1)	Definition and qualifications of the designer, manufacturer, installer, QA consultant and laboratory, and QA program;
_		V		(2)	Material specifications for geomembranes, geocomposites, geotextiles, geogrids, and geonets;

<u>S</u>	LOCATION	<u>N/A</u>	N/C		PART G CONTINUED
□ <u> </u>		7		(3)	Manufacturing and fabrication specifications including geomembrane raw material and roll QA, fabrication personnel qualifications, seaming equipment and procedures, overlaps, trial seams, destructive and nondestructive seam testing, seam testing location, frequency, procedure, sample size and geomembrane repairs;
□ <u> </u>		Ø		(4)	Geomembrane installation specifications including earthwork, conformance testing, geomembrane placement, installation personnel qualifications, field seaming and testing, overlapping and repairs, materials in contact with geomembrane and procedures for lining system acceptance;
□ <u> </u>		√		(5)	Geotextile and geogrid specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil materials and any overlying materials;
□ <u> </u>		√		(6)	Geonet and geocomposite specifications including handling and placement, conformance testing, stacking and joining, repair, and placement of soil materials and any overlying materials;
□ <u> </u>		✓		(7)	Geosynthetic clay liner specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil material and any overlying materials;
□ _		V		f. Star	ndards for soil liner components (62-710.400(3)(f),FAC):
□ <u> </u>		V		(1)	Description of construction procedures including overexcavation and backfilling to preclude structural inconsistencies and procedures for placing and compacting soil component in layers;
□ <u> </u>		7		(2)	Demonstration of compatibility of the soil component with actual or simulated leachate in accordance with EPA Test Method 9100 or an equivalent test method;
		V		(3)	Procedures for testing in-situ soils to demonstrate they meet the specifications for soil liners:

<u>s</u>	<u>LOCATION</u>	N/A	N/C		PART	G CONTINUED
		√		(4)	Specit minim	fications for soil component of liner including at a um:
		√			(a)	Allowable particle size distribution, Atterberg limits, shrinkage limit;
□ <u></u>		/			(b)	Placement moisture and dry density criteria;
□ <u> </u>		√			(c)	Maximum laboratory-determined saturated hydraulic conductivity using simulated leachate;
□ <u></u>		/			(d)	Minimum thickness of soil liner;
□ _		V			(e)	Lift thickness;
□ <u></u>		/			(f)	Surface preparation (scarification);
		√			(g)	Type and percentage of clay mineral within the soil component;
□ <u> </u>		V		(5)	to doc	dures for constructing and using a field test section ument the desired saturated hydraulic conductivity lickness can be achieved in the field.
□ <u>-</u>		V		syster	n, provid	landfill is to be constructed with a bottom liner le a description of how the minimum requirements I be achieved.
		√		3. Leachate co (62-701.400(4		and removal system (LCRS);
		√			e primary 00(4)(a),	and secondary LCRS requirements; (62-FAC)
		7		(1)		ructed of materials chemically resistant to the waste achate;
□ _		/		(2)		sufficient mechanical properties to prevent collapse pressure;

<u>S</u>	LOCATION	N/A	N/C		PART G CONTINUED
<u> </u>		V		(3)	Have granular material or synthetic geotextile to prevent clogging;
<u> </u>		√		(4)	Have method for testing and cleaning clogged pipes or contingent designs for rerouting leachate around failed areas;
□ <u> </u>		V		b. Oth	er LCRS requirements; (62-701.400(4)(b) and (c),FAC)
□ <u> </u>		√		(1)	Bottom 12 inches having hydraulic conductivity ≥ 1 x 10 ⁻³ cm/sec;
□ <u> </u>		√		(2)	Total thickness of 24 inches of material chemically resistant to the waste and leachate;
<u> </u>		✓		(3)	Bottom slope design to accommodate for predicted settlement and still meet minimum slope requirements;
□ <u> </u>		✓		(4)	Demonstration that synthetic drainage material, if used, is equivalent or better than granular material in chemical compatibility, flow under load and protection of geomembrane liner.
□ <u> </u>		V		4. Leachate re	circulation; (62-701.400(5),FAC)
□ <u> </u>		V		a. Des	cribe general procedures for recirculating leachate;
□ <u> </u>		V			cribe procedures for controlling leachate runoff and zing mixing of leachate runoff with storm water;
□ <u> </u>		✓			cribe procedures for preventing perched water conditions as buildup;
□ <u> </u>		V		canno	cribe alternate methods for leachate management when it t be recirculated due to weather or runoff conditions, surface wind-blown spray, or elevated levels of leachate head on er;
□ <u> </u>		V			cribe methods of gas management in accordance with Rule 1.530, FAC;

<u>s</u>	<u>LOCATION</u>	<u>N/A</u>	N/C		PART (CONTINUED
<u> </u>		V		and sta cover a	andards and prov	igation is proposed, describe treatment methods for leachate treatment prior to irrigation over final ride documentation that irrigation does not ificantly to leachate generation.
		V		5.Leachate stor 701.400(6),FA0	-	ks and leachate surface impoundments; (62-
□ <u> </u>		V		a. Surf	ace imp	oundment requirements; (62-701.400(6)(b),FAC)
		V		(1)		nentation that the design of the bottom liner will not versely impacted by fluctuations of the ground water;
		√		(2)	_	ned in segments to allow for inspection and repair eded without interruption of service;
□ <u> </u>		V		(3)	Gener	al design requirements;
		√			(a)	Double liner system consisting of an upper and lower 60-mil minimum thickness geomembrane;
<u> </u>		✓			(b)	Leak detection and collection system with hydraulic conductivity ≥ 1 cm/sec;
<u> </u>		7			(c)	Lower geomembrane placed on subbase ≥ 6 inches thick with $k \leq 1 \times 10^{-5}$ cm/sec or on an approved geosynthetic clay liner with $k \leq 1 \times 10^{-7}$ cm/sec;
<u> </u>		√			(d)	Design calculation to predict potential leakage through the upper liner;
_		V			(e)	Daily inspection requirements and notification and corrective action requirements if leakage rates exceed that predicted by design calculations;
<u> </u>		✓		(4)	Descri	ption of procedures to prevent uplift, if applicable;
_		V		(5)	_	n calculations to demonstrate minimum two feet of ard will be maintained;
		V		(6)	Proced	dures for controlling vectors and off-site odors.

<u>s</u>	<u>LOCATION</u>	<u>N/A</u>	<u>N/C</u>		PART G CONTINUED
		V		b. Abo	ove-ground leachate storage tanks; (62-701.400(6)(c),FAC)
□ <u> </u>		✓		(1)	Describe tank materials of construction and ensure foundation is sufficient to support tank;
□ <u> </u>				(2)	Describe procedures for cathodic protection if needed for the tank;
□ <u> </u>		V		(3)	Describe exterior painting and interior lining of the tank to protect it from the weather and the leachate stored;
<u> </u>		V		(4)	Describe secondary containment design to ensure adequate capacity will be provided and compatibility of materials of construction;
□ <u> </u>		√		(5)	Describe design to remove and dispose of stormwater from the secondary containment system;
<u> </u>		√		(6)	Describe an overfill prevention system such as level sensors, gauges, alarms and shutoff controls to prevent overfilling;
□ <u> </u>		V		(7)	Inspections, corrective action and reporting requirements
□ _		√			(a) Overfill prevention system weekly;
□ <u> </u>		√			(b) Exposed tank exteriors weekly;
□ <u> </u>		V			(c) Tank interiors when tank is drained or at least every three years;
□ <u> </u>		/			(d) Procedures for immediate corrective action if failures detected;
□ _		✓			(e) Inspection reports available for department review.
□ <u> </u>		V		c. Und	iderground leachate storage tanks; (62-701.400(6)(d),FAC)

<u>S</u>	LOCATION	N/A	N/C		ART G CONTINUED	
		√		(1)	Describe materials of con	struction;
_		V		(2)	A double-walled tank desi ollowing requirements;	ign system to be used with the
□ <u> </u>		7			a) Interstitial space	monitoring at least weekly;
_		V				ion provided for primary tank nal surface of outer shell;
<u> </u>		/			c) Interior tank coati leachate;	ngs compatible with stored
<u> </u>		/			d) Cathodic protecti repaired as need	on inspected weekly and ed;
		V		(3)		ntion system such as level and shutoff controls to prevent weekly inspections;
□ <u> </u>		✓		(4)	nspection reports availab	le for department review.
_		V			ile provided for routine m 6)(e),FAC)	aintenance of LCRS; (62-
		/		6.Liner systems 701.400(7),FAC	onstruction quality assur	ance (CQA); (62-
□ <u> </u>		✓		a. Prov	e CQA Plan including:	
_		V		(1)	Specifications and construystem;	uction requirements for liner
□ <u> </u>		/		(2)	Detailed description of quund frequencies;	ality control testing procedures
<u> </u>		✓		(3)	dentification of supervisir	ng professional engineer;
<u> </u>		✓		(4)	dentify responsibility and organizations and key per construction project;	authority of all appropriate rsonnel involved in the

<u>s</u>	LOCATION	N/A	N/C	PART G CONTINUED
		V		(5) State qualifications of CQA professional engineer and support personnel;
□ <u> </u>		✓		(6) Description of CQA reporting forms and documents;
		V		b. An independent laboratory experienced in the testing of geosynthetics to perform required testing;
□ <u>-</u>		V		7. Soil Liner CQA (62-701.400(8)FAC)
□ <u>-</u>		√		a. Documentation that an adequate borrow source has been located with test results or description of the field exploration and laboratory testing program to define a suitable borrow source;
□ <u></u>		V		b. Description of field test section construction and test methods to be implemented prior to liner installation;
		V		c. Description of field test methods including rejection criteria and corrective measures to insure proper liner installation.
□ <u> </u>		✓		8. Surface water management systems; (62-701.400(9),FAC)
		V		a. Provide a copy of a Department permit for stormwater control or documentation that no such permit is required;
		V		b. Design of surface water management system to isolate surface water from waste filled areas and to control stormwater run-off;
		V		c. Details of stormwater control design including retention ponds, detention ponds, and drainage ways;
		✓		9. Gas control systems; (62-701.400(10),FAC)
□ <u> </u>		√		a. Provide documentation that if the landfill is receiving degradable wastes, it will have a gas control system complying with the requirements of Rule 62-701.530, FAC;
		V		10. For landfills designed in ground water, provide documentation that the landfill will provide a degree of protection equivalent to landfills designed with bottom liners not in contact with ground water: (62-701 400(11) FAC)

PART H. HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS (62-701.410(1), FAC)

<u>s</u>	LOCATION	N/A	N/C	
<u> </u>		_ ✓		Submit a hydrogeological investigation and site report including at least the following information:
		<u> </u>		a. Regional and site specific geology and hydrogeology;
_		_		b. Direction and rate of ground water and surface water flow including seasonal variations;
		<u> </u>		c. Background quality of ground water and surface water;
<pre></pre>		<u> </u>		d. Any on-site hydraulic connections between aquifers;
		_		e. Site stratigraphy and aquifer characteristics for confining layers, semi-confining layers, and all aquifers below the landfill site that may be affected by the landfill;
<u> </u>		_		f. Description of topography, soil types and surface water drainage systems;
		_ 🗸		g. Inventory of all public and private water wells within a one-mile radius of the landfill including, where available, well top of casing and bottom elevations, name of owner, age and usage of each well, stratigraphic unit screened, well construction technique and static water level;
□ <u> </u>		<u> </u>		h. Identify and locate any existing contaminated areas on the site;
_		_		 i. Include a map showing the locations of all potable wells within 500 feet of the waste storage and disposal areas;
		~		Report signed, sealed and dated by PE and/or PG.

PART I. GEOTECHNICAL INVESTIGATION REQUIREMENTS (62-701.410(2),FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C	
<u> </u>		√		Submit a geotechnical site investigation report defining the engineering properties of the site including at least the following:
		V		a. Description of subsurface conditions including soil stratigraphy and ground water table conditions;
<u> </u>		✓		b. Investigate for the presence of muck, previously filled areas, soft ground, lineaments and sink holes;
		V		c. Estimates of average and maximum high water table across the site;
□ <u> </u>		✓		d. Foundation analysis including:
		V		(1) Foundation bearing capacity analysis;
		V		(2) Total and differential subgrade settlement analysis;
	_	V		(3) Slope stability analysis;
<u> </u>		V		e. Description of methods used in the investigation and includes soil boring logs, laboratory results, analytical calculations, cross sections, interpretations and conclusions;
<u> </u>		V		f. An evaluation of fault areas, seismic impact zones, and unstable areas as described in 40 CFR 258.13, 40 CFR 258.14 and 40 CFR 258.15.
		✓		2. Report signed, sealed and dated by PE and/or PG.

PART J. VERTICAL EXPANSION OF LANDFILLS (62-701.430,FAC)

<u>S</u>	LOCATION	<u>N/A</u>	N/C	
<u> </u>		V		1. Describe how the vertical expansion shall not cause or contribute to leachate leakage from the existing landfill, shall not cause objectionable odors, or adversely affect the closure design of the existing landfill;
<u> </u>		V		2. Describe how the vertical expansion over unlined landfills will meet the requirements of Rule 62-701.400, FAC with the exceptions of Rule 62-701.430(1)(c),FAC;
		✓		3. Provide foundation and settlement analysis for the vertical expansion;
<u> </u>		✓		4. Provide total settlement calculations demonstrating that the final elevations of the lining system, that gravity drainage, and that no other component of the design will be adversely affected;
<u> </u>		V		5. Minimum stability safety factor of 1.5 for the lining system component interface stability and deep stability;
<u> </u>		V		6. Provide documentation to show the surface water management system will not be adversely affected by the vertical expansion;
<u> </u>		7		7. Provide gas control designs to prevent accumulation of gas under the new liner for the vertical expansion.

PART K. LANDFILL OPERATION REQUIREMENTS (62-701.500,FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C	
		V		Provide documentation that landfill will have at least one trained operator during operation and at least one trained spotter at each working face; (62-701.500(1),FAC)
_		✓		2. Provide a landfill operation plan including procedures for: (62-701.500(2), FAC)
		V		a. Designating responsible operating and maintenance personnel
		✓		b. Emergency preparedness and response, as required in subsection 62-701.320(16), FAC;
		V		c. Controlling types of waste received at the landfill;
				d. Weighing incoming waste;
		V		e. Vehicle traffic control and unloading;
		V		f. Method and sequence of filling waste;
		7		g. Waste compaction and application of cover;
		V		h. Operations of gas, leachate, and stormwater controls;
		✓		i. Water quality monitoring.
		V		j. Maintaining and cleaning the leachate collection system;
		V		3. Provide a description of the landfill operation record to be used at the landfill; details as to location of where various operational records will be kept (i.e. FDEP permit, engineering drawings, water quality records, etc.) (62-701.500(3),FAC)
		V		4. Describe the waste records that will be compiled monthly and provided to the Department annually; (62-701.500(4),FAC)
		V		5. Describe methods of access control; (62-701.500(5),FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C	PART K CONTINUED
_		V		6. Describe load checking program to be implemented at the landfill to discourage disposal of unauthorized wastes at the landfill; (62-701.500(6),FAC)
		7		7. Describe procedures for spreading and compacting waste at the landfill that include: (62-701.500(7),FAC)
		√		a. Waste layer thickness and compaction frequencies;
□ <u> </u>		√		 b. Special considerations for first layer of waste placed above liner and leachate collection system;
□ <u> </u>		V		c. Slopes of cell working face and side grades above land surface, planned lift depths during operation;
		V		d. Maximum width of working face;
		7		e. Description of type of initial cover to be used at the facility that controls:
		V		(1) Vector breeding/animal attraction
□ <u> </u>		V		(2) Fires
		V		(3) Odors
□ <u> </u>		V		(4) Blowing litter
□ <u> </u>	_	V		(5) Moisture infiltration
		✓		f. Procedures for applying initial cover including minimum cover frequencies;
□ <u> </u>		√		g. Procedures for applying intermediate cover;
□ <u> </u>		V		h. Time frames for applying final cover;
		V		i. Procedures for controlling scavenging and salvaging.

<u>s</u>	LOCATION	N/A	N/C	PART K CONTINUED
<pre>_</pre>		V		j. Description of litter policing methods;
□ <u> </u>		7		k. Erosion control procedures.
		V		8. Describe operational procedures for leachate management including; (62-701.500(8),FAC)
		V		a. Leachate level monitoring, sampling, analysis and data results submitted to the Department;
		V		b. Operation and maintenance of leachate collection and removal system, and treatment as required;
		V		c. Procedures for managing leachate if it becomes regulated as a hazardous waste;
		V		d. Identification of treatment or disposal facilities that may be used for off-site discharge and treatment of leachate;
<u> </u>		V		e. Contingency plan for managing leachate during emergencies or equipment problems;
		V		f. Procedures for recording quantities of leachate generated in gal/day and including this in the operating record;
		V		g. Procedures for comparing precipitation experienced at the landfill with leachate generation rates and including this information in the operating record;
□ <u> </u>		V		h. Procedures for water pressure cleaning or video inspecting leachate collection systems.
		7		9. Describe how the landfill receiving degradable wastes shall implement a gas management system meeting the requirements of Rule 62-701.530, FAC; (62-701.500(9),FAC)
		V		10. Describe procedures for operating and maintaining the landfill stormwater management system to comply with the requirements of Rule 62-701.400(9); (62-701.500(10),FAC)

<u>s</u>	LOCATION	<u>N/A</u>	N/C	PART K CONTINUED
		_ 🗸		11. Equipment and operation feature requirements; (62-701.500(11),FAC)
		_ 🗸		 a. Sufficient equipment for excavating, spreading, compacting and covering waste;
<u> </u>		/		b. Reserve equipment or arrangements to obtain additional equipment within 24 hours of breakdown;
□ _		V		c. Communications equipment;
		_		d. Dust control methods;
		V		e. Fire protection capabilities and procedures for notifying local fire department authorities in emergencies;
□ <u> </u>		V		f. Litter control devices;
<u> </u>		/		g. Signs indicating operating authority, traffic flow, hours of operation, disposal restrictions.
		_ 🗸		12. Provide a description of all-weather access road, inside perimeter road and other roads necessary for access which shall be provided at the landfill; (62-701.500(12),FAC)
<u> </u>		_ 🗸		13. Additional record keeping and reporting requirements; (62-701.500(13),FAC)
		_ 🗸		a. Records used for developing permit applications and supplemental information maintained for the design period of the landfill;
_		_		b. Monitoring information, calibration and maintenance records, copies of reports required by permit maintained for at least 10 years;
<u> </u>		<u> </u>		c. Maintain annual estimates of the remaining life of constructed landfills and of other permitted areas not yet constructed and submit this estimate annually to the Department;
		_		d. Procedures for archiving and retrieving records which are more than five year old.

PART L. WATER QUALITY AND LEACHATE MONITORING REQUIREMENTS (62-701.510, FAC) S **LOCATION** N/A N/C **√** 1. Water quality and leachate monitoring plan shall be submitted describing the proposed ground water, surface water and leachate monitoring systems and shall meet at least the following requirements; \checkmark a. Based on the information obtained in the hydrogeological investigation and signed, dated and sealed by the PG or PE who prepared it; (62-701.510(2)(a),FAC) **√** b. All sampling and analysis preformed in accordance with Chapter 62-160, FAC; (62-701.510(2)(b),FAC) **V** c. Ground water monitoring requirements; (62-701.510(3),FAC) **V** П (1) Detection wells located downgradient from and within 50 feet of disposal units; **√** (2)Downgradient compliance wells as required: (3)Background wells screened in all aquifers below the landfill that may be affected by the landfill; ✓ Location information for each monitoring well; (4) \checkmark Well spacing no greater than 500 feet apart for (5)downgradient wells and no greater than 1500 feet apart for upgradient wells unless site specific conditions justify alternate well spacings; \checkmark (6)Well screen locations properly selected; \checkmark Monitoring wells constructed to provide representative (7)ground water samples: \checkmark Procedures for properly abandoning monitoring wells: (8) \checkmark (9)Detailed description of detection sensors if proposed.

✓

d. Surface water monitoring requirements; (62-701.510(4),FAC)

<u>s</u>	<u>LOCATION</u>	<u>N/A</u>	<u>N/C</u>		PART L CONTINUED
				(1)	Location of and justification for all proposed surface water monitoring points;
<u> </u>		V		(2)	Each monitoring location to be marked and its position determined by a registered Florida land surveyor;
		✓		e. Lea	chate sampling locations proposed; (62-701.510(5),FAC)
		. 🗸			al and routine sampling frequency and requirements; (62-10(6),FAC)
		. 🗸		(1)	Initial background ground water and surface water sampling and analysis requirements;
		. ✓		(2)	Routine leachate sampling and analysis requirements;
		. 🗸		(3)	Routine monitoring well sampling and analysis requirements;
<u> </u>		V		(4)	Routine surface water sampling and analysis requirements.
<u> </u>				prever	scribe procedures for implementing evaluation monitoring, nation measures and corrective action as required; (62-10(7),FAC)
		. 🗹			ter quality monitoring report requirements;(62-10(9),FAC)
		. 🗸		(1)	Semi-annual report requirements (see paragraphs 62 701.510(6)(c),(d)and (e) for sampling frequencies);
□ <u> </u>				(2)	Documentation that the water quality data shall be provided to the Department in an electronic format consistent with requirements for importing into Department databases, unless an alternate form of submittal is specified in the permit.
<u> </u>		✓		(3)	Two and one-half year report requirements, or every five years if in long-term care, signed, dated and sealed by PG or PE.

PART M. SPECIAL WASTE HANDLING REQUIREMENTS (62-701.520, FAC) S **LOCATION** N/A N/C **√** П 1. Describe procedures for managing motor vehicles; (62-701.520(1),FAC) **√** П 2. Describe procedures for landfilling shredded waste; (62-701.520(2),FAC) **√** 3. Describe procedures for asbestos waste disposal; (62-701.520(3),FAC) **√** 4. Describe procedures for disposal or management of contaminated soil; (62-701.520(4), FAC) **1** 5. Describe procedures for disposal of biological wastes; (62-701.520(5), FAC) PART N. GAS MANAGEMENT SYSTEM REQUIREMENTS (62-701.530,FAC) <u>S</u> LOCATION N/A N/C ✓ 1. Provide the design for a gas management system that will (62-701.530(1), FAC): **V** П a. Be designed to prevent concentrations of combustible gases from exceeding 25% the LEL in structures and 100% the LEL at the property boundary; **√** b. Be designed for site-specific conditions; ✓ c. Be designed to reduce gas pressure in the interior of the landfill; ✓ d. Be designed to not interfere with the liner, leachate control system or final cover. **√** П 2. Provide documentation that will describe locations, construction details and procedures for monitoring gas at ambient monitoring points and with soil monitoring probes; (62-701.530(2), FAC): \checkmark 3. Provide documentation describing how the gas remediation plan and odor remediation plan will be implemented; (62-701.530(3), FAC): ✓ 4. Landfill gas recovery facilities; (62-701.530(5), FAC):

<u>s</u>	LOCATION	<u>N/A</u>	N/C	PART N CONTINUED
□ <u> </u>		√		a. Information required in Rules 62-701.320(7) and 62-701.330(3) FAC supplied;
□ <u> </u>		V		b. Information required in Rule 62-701.600(4), FAC supplied where relevant and practical;
□ <u> </u>		V		c. Estimate of current and expected gas generation rates and description of condensate disposal methods provided;
<u> </u>		Ø		d. Description of procedures for condensate sampling, analyzing and data reporting provided;
□ <u> </u>		7		e. Closure plan provided describing methods to control gas after recovery facility ceases operation and any other requirements contained in Rule 62-701.400(10), FAC;
_		V		f. Performance bond provided to cover closure costs if not already included in other landfill closure costs.
PART	O. LANDFILL F	INAL CL	OSURE	REQUIREMENTS (62-701.600,FAC)
<u>s</u>	LOCATION	<u>N/A</u>	N/C	
□ <u> </u>		V		1. Closure permit requirements; (62-701.600(2),FAC)
		✓		a. Application submitted to Department at least 90 days prior to final receipt of wastes;
□ <u> </u>		V		b. Closure plan shall include the following:
□ <u> </u>		✓		(1) Closure design plan;
□ <u> </u>		V		(2) Closure operation plan;
		✓		(3) Plan for long-term care;
	ection 3 of Report and stachment 2, Section II			(4) A demonstration that proof of financial responsibility for long-term care will be provided.

<u>S</u>	<u>LOCATION</u>	N/A	N/C	PART O CONTINUED
				2. Closure design plan including the following requirements: (62-701.600(3),FAC)
		V		a. Plan sheet showing phases of site closing;
		V		b. Drawings showing existing topography and proposed final grades;
		V		c. Provisions to close units when they reach approved design dimensions;
		V		d. Final elevations before settlement;
		√		e. Side slope design including benches, terraces, down slope drainage ways, energy dissipaters and discussion of expected precipitation effects;
		V		f. Final cover installation plans including:
		V		(1) CQA plan for installing and testing final cover;
		✓		(2) Schedule for installing final cover after final receipt of waste;
		V		(3) Description of drought-resistant species to be used in the vegetative cover;
		V		(4) Top gradient design to maximize runoff and minimize erosion;
		✓		(5) Provisions for cover material to be used for final cover maintenance.
		V		g. Final cover design requirements:
□ <u> </u>		V		(1) Protective soil layer design;
		/		(2) Barrier soil layer design;

<u>S</u>	LOCATION	<u>N/A</u>	N/C	PART O CONTINUED
		V		(3) Erosion control vegetation;
		✓		(4) Geomembrane barrier layer design;
		V		(5) Geosynthetic clay liner design if used;
		V		(6) Stability analysis of the cover system and the disposed waste.
		✓		h. Proposed method of stormwater control;
		V		i. Proposed method of access control;
		V		j. Description of the proposed or existing gas management system which complies with Rule 62-701.530, FAC.
		V		3. Closure operation plan shall include:(62-701.600(4),FAC)
		V		a. Detailed description of actions which will be taken to close the landfill;
		✓		b. Time schedule for completion of closing and long-term care;
V	Section 3 of Report and Attachment 2, Section II			c. Describe proposed method for demonstrating financial assurance for long-term care;
		√		d. Operation of the water quality monitoring plan required in Rule 62-701.510, FAC.
		✓		e. Development and implementation of gas management system required in Rule 62-701.530, FAC.
		V		4. Certification of closure construction completion including: (62-701.600(6),FAC)
		√		a. Survey monuments; (62-701.600(6)(a),FAC)
		√		b. Final survey report; (62-701.600(6)(b),FAC)

<u>s</u>	<u>LOCATION</u>	N/A	N/C	PART O CONTINUED
		_ 🗹		5. Declaration to the public; (62-701.600(7),FAC)
		_ 🗸		6. Official date of closing; (62-701.600(8),FAC)
<u> </u>		_		7. Justification for and detailed description of procedures to be followed for temporary closure of the landfill, if desired; (62-701.600(9),FAC)
PART F	P. OTHER CL	OSURE P	ROCEDI	URES (62-701.610,FAC)
<u>s</u>	LOCATION	N/A	N/C	
<u> </u>		_ 🗸		1. Describe how the requirements for use of closed solid waste disposal areas will be achieved;(62-701.610(1),FAC)
<u> </u>		_ 🗸		2. Describe how the requirements for relocation of wastes will be achieved (62-701.610(2), FAC)
PART (Q. LONG-TER	M CARE	(62-701.6	S20,FAC)
<u>s</u>	LOCATION	<u>N/A</u>	N/C	
□ <u> </u>		_ 🗸		Maintaining the gas collection and monitoring system; (62-701.620(5), FAC)
□ <u> </u>		_ ✓		2. Stabilization report requirements; (62-701.620(6),FAC)
<pre></pre>		_ ✓		3. Right of access;(62-701.620(7),FAC)
□ <u> </u>		_		4. Requirements for replacement of monitoring devices; (62-701.620(8),FAC)
<u> </u>		_ 🗸		5. Completion of long-term care signed and sealed by professional engineer (62-701.620(9), FAC).

PART R. FINANCIAL ASSURANCE (62-701.630,FAC)

<u>S</u>	LOCATION	<u>N/A</u>	N/C	
√	Attachment 2			1. Provide cost estimates for closing, long-term care, and corrective action costs estimated by a PE for a third party performing the work, on a per unit basis, with the source of estimates indicated; (62-701.630(3)&(7), FAC).
		V		2. Describe procedures for providing annual cost adjustments to the Department based on inflation and changes in the closing, long-term care, and corrective action plans; (62-701.630(4)&(8), FAC).
√	Attachment 2, Section II			3. Describe funding mechanisms for providing proof of financial assurance and include appropriate financial assurance forms; (62-701.630(5),(6),&(9) FAC).
		7		4. Provide documentation and the appropriate forms for delaying submitting proof of financial assurance for solid waste disposal units that qualify; (62-701.630(2)(c), FAC).

PART S. CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

The undersigned applicant or authorized represer	ntative of Omni Waste of Osecola County, LLC (Omni)
is awar	e that statements made in this form and attached
Environmental Protection and certifies that the inf of his/her knowledge and belief. Further, the und	odification Permit from the Florida Department of formation in this application is true, correct and complete ersigned agrees to comply with the provisions of Chapter the Department. It is understood that the Permit is not traile or legal transfer of the permitted facility.
	1501 Omni Way
Signature of Applicant or Agent	Mailing Address
Mike Kaiser, Regional Engineer	Saint Cloud, Florida 34773
	City, State, Zip Code
MKaiser@Wasteservicesinc.com	(904) 673-0446
E-Mail address (if available)	Telephone Number
Professional Engineer registered in Florida (or Pu	
Florida Statutes): This is to certify that the engineering features of the sy me and found to conform to engineering princicacility, when properly maintained and operated, values of the Department. It is agreed that the und	
Professional Engineer registered in Florida (or Pu Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princi acility, when properly maintained and operated, we ules of the Department. It is agreed that the und	ernmental official, owner, or corporate officer. ublic Officer if authorized under Sections 403.707 and 403 his solid waste management facility have been designed/ iples applicable to such facilities. In my professional judg will comply with all applicable statutes of the State of Flori lersigned will provide the applicant with a set of instruction
Professional Engineer registered in Florida (or Purforida Statutes): This is to certify that the engineering features of the py me and found to conform to engineering principacility, when properly maintained and operated, when properly maintained and operated, when proper maintenance and operation of the facility.	ernmental official, owner, or corporate officer. Ablic Officer if authorized under Sections 403.707 and 403 his solid waste management facility have been designed/ ples applicable to such facilities. In my professional judg will comply with all applicable statutes of the State of Flor lersigned will provide the applicant with a set of instruction 13101 Telecom Drive, Suite 120
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, when become acility, when properly maintained and operated, when proper maintenance and operation of the facility. Signature	ernmental official, owner, or corporate officer. Ablic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed ples applicable to such facilities. In my professional judg will comply with all applicable statutes of the State of Flor lersigned will provide the applicant with a set of instruction management. 13101 Telecom Drive, Suite 120 Mailing Address
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, while sof the Department. It is agreed that the underoper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E.	ernmental official, owner, or corporate officer. sublic Officer if authorized under Sections 403.707 and 403
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, when proper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E.	ernmental official, owner, or corporate officer. Sublic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed/ In ples applicable to such facilities. In my professional judg Will comply with all applicable statutes of the State of Flori I lersigned will provide the applicant with a set of instruction Mailing Address Temple Terrace, FL, 33637 City, State, Zip Code
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, when proper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E.	ernmental official, owner, or corporate officer. Jublic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed/ Juples applicable to such facilities. In my professional judg Will comply with all applicable statutes of the State of Florical dersigned will provide the applicant with a set of instruction Temple Terrace, FL, 33637 City, State, Zip Code VDamasceno@Geosyntec.com
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, when proper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E.	ernmental official, owner, or corporate officer. Jublic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed/ Juples applicable to such facilities. In my professional judg July will comply with all applicable statutes of the State of Florical dersigned will provide the applicant with a set of instruction Temple Terrace, FL, 33637 City, State, Zip Code Juple VDamasceno@Geosyntec.com E-Mail address (if available)
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, when proper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E. Name and Title (please type)	ernmental official, owner, or corporate officer. Jublic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed/ Juples applicable to such facilities. In my professional judg July will comply with all applicable statutes of the State of Flore July Indiana Indiana Indiana Indiana July Indiana Indian
Professional Engineer registered in Florida (or Purflorida Statutes): This is to certify that the engineering features of the part of the properly maintained and operated, when properly maintained and operated, while sof the Department. It is agreed that the underoper maintenance and operation of the facility. Signature Victor M. Damasceno, Ph.D., P.E.	ernmental official, owner, or corporate officer. Jublic Officer if authorized under Sections 403.707 and 403 This solid waste management facility have been designed/ Juples applicable to such facilities. In my professional judg July will comply with all applicable statutes of the State of Florical dersigned will provide the applicant with a set of instruction Temple Terrace, FL, 33637 City, State, Zip Code Juple VDamasceno@Geosyntec.com E-Mail address (if available)

PART S. CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

The undersigned applicant or authorized represen	ntative of Omni Waste of Osecola County, LLC (Omni)
is aware	e that statements made in this form and attached
Environmental Protection and certifies that the info	podification Permit from the Florida Department of commation in this application is true, correct and complete to the best ersigned agrees to comply with the provisions of Chapter 403, the Department. It is understood that the Permit is not transferable e or legal transfer of the permitted facility.
Mile Kun	1501 Omni Way
Signature of Applicant or Agent	Mailing Address
Mike Kaiser, Regional Engineer	Saint Cloud, Florida 34773
Name and Title (please type)	City, State, Zip Code
MKaiser@Wasteservicesinc.com	(904) 673-0446
E-Mail address (if available)	Telephone Number
	Date: 10/25/11
Attach letter of authorization if agent is not a gove	rnmental official, owner, or corporate officer.
Professional Engineer registered in Florida (or Pu	ernmental official, owner, or corporate officer. ublic Officer if authorized under Sections 403.707 and 403.7075,
Professional Engineer registered in Florida (or Pu Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, we	
Professional Engineer registered in Florida (or Pu Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering principle facility, when properly maintained and operated, we rules of the Department. It is agreed that the und	ablic Officer if authorized under Sections 403.707 and 403.7075, his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, thi will comply with all applicable statutes of the State of Florida and ersigned will provide the applicant with a set of instructions of
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering principle facility, when properly maintained and operated, we rules of the Department. It is agreed that the und	ablic Officer if authorized under Sections 403.707 and 403.7075, his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, thi will comply with all applicable statutes of the State of Florida and
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, when proper maintenance and operation of the facility.	ablic Officer if authorized under Sections 403.707 and 403.7075, this solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, this will comply with all applicable statutes of the State of Florida and tersigned will provide the applicant with a set of instructions of 13101 Telecom Drive, Suite 120 Mailing Address Temple Terrace, FL, 33637
Professional Engineer registered in Florida (or Pu Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princi facility, when properly maintained and operated, we rules of the Department. It is agreed that the und	ablic Officer if authorized under Sections 403.707 and 403.7075, this solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, this will comply with all applicable statutes of the State of Florida and tersigned will provide the applicant with a set of instructions of the Mailing Address
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, when proper maintenance and operation of the facility. Victor M. Damasceno, Ph.D., P.	his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, this will comply with all applicable statutes of the State of Florida and tersigned will provide the applicant with a set of instructions of 13101 Telecom Drive, Suite 120 Mailing Address Temple Terrace, FL, 33637 City, State, Zip Code
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, when proper maintained and operated, by the Department. It is agreed that the undiproper maintenance and operation of the facility. Victor M. Damasceno, Ph.D., P. Name and Title (please type)	blic Officer if authorized under Sections 403.707 and 403.7075, his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, this will comply with all applicable statutes of the State of Florida and tersigned will provide the applicant with a set of instructions of 13101 Telecom Drive, Suite 120 Mailing Address Temple Terrace, FL, 33637
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, worden of the Department. It is agreed that the und proper maintenance and operation of the facility. Victor M. Darnasceno, Ph.D., P.	his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, thi will comply with all applicable statutes of the State of Florida and ersigned will provide the applicant with a set of instructions of 13101 Telecom Drive, Suite 120 Mailing Address Temple Terrace, FL, 33637 City, State, Zip Code VDamasceno@Geosyntec.com E-Mail address (if available)
Professional Engineer registered in Florida (or Pur Florida Statutes): This is to certify that the engineering features of the by me and found to conform to engineering princifacility, when properly maintained and operated, when proper maintained and operated, when proper maintenance and operation of the facility. Victor M. Damasceno, Ph.D., P. Name and Title (please type)	blic Officer if authorized under Sections 403.707 and 403.7075, his solid waste management facility have been designed/examine ples applicable to such facilities. In my professional judgment, this will comply with all applicable statutes of the State of Florida and lersigned will provide the applicant with a set of instructions of 13101 Telecom Drive, Suite 120 Mailing Address Temple Terrace, FL, 33637 City, State, Zip Code VDamasceno@Geosyntec.com

1.

2.



2893 Executive Park Drive, Suite 305, Weston, Florida 33331

February 6, 2009

RE: Omni Waste of Osceola County, LLC

To Whom It May Concern:

This is to confirm that Mike Kaiser is an authorized signatory of Omni Waste of Osceola County, LLC (the "Corporation"), with authority to execute and deliver all documents and instruments required in connection with environmental matters for the Corporation, including without limitation, permit applications, modifications and financial assurances for permits issued to the Corporation.

Waste Services, Inc.


Edwin D. Johnson

Executive Vice President & Chief Financial Officer

Omni Waste of Osceola County, LLC

Edwin D. Johnson

Manager





Florida Department of Environmental Protection

Bob Martinez Center 2600 Blair Stone Road Tallahassee, Florida 32399-2400 DEP Form # 62-701.900(28), F.A.C.

Form Title: Closure Cost Estimating Form For Solid Waste Facilities

Effective Date: January 6, 2010

Incorporated in Rule 62-701.630(3), F.A.C.

CLOSURE COST ESTIMATING FORM FOR SOLID WASTE FACILITIES

Date of DEP Approval:

I. GENERAL INF	ORMATION:						
Facility Name:	J.E.D. Solid V	Vaste Mana	agement Facili	ity	\	NACS ID: 89544	
Permit Application	n or Consent C	Order No.:	SC49 & SO4	49-199726-017 & 0	05 Expira	tion Date: <u>8/16</u>	<u>6/2016-1/</u> 11/201
Facility Address:	1501 Omni	Way, Sain	Cloud, Florid	a 34773			
Permittee or Owr	ner/Operator:	Omni Wa	aste of Osceol	la County, LLC (a w	vholly owned s	ubsidiary of W	'SI, Inc.)
Mailing Address:	1501 Omni	Way, Sain	Cloud, Florid	a 34773			
Latitude:	28 °	03'	32 "	Longitude:	81°	05'	46 "
Coordinate Metho	od: DGPS			atum: WGS84			
Collected by: J	ohnston's Surv	eying	C	company/Affiliation:	Johnston's Su	ırveying	
_							
Solid Waste Disp	osal Units Incl	uded in Es	timate:				
			Date Unit	Active Life of		If closed:	If closed:
			Began	Unit From Date	If active:	Date last	Official
Dhaaa	/ Call	A	Accepting	of Initial Receipt		waste	date of
Phase A		Acres	Waste	of Waste	life of unit	received	closing
Phase 3/	Cell 8	11.3	NA	1 to 2 years			
							
							
							
							
Total disposal un				Closure: 11.3		ng-Term Care:	11.3
area - used in the				Class III	COD Dobrio	Dianagal	
Facility (Check all the	iype: at apply) □			Jass III 🗆	C&D Debris	Disposai	
(Oneok all ti	ат арргу) 📋	Other:					
II. TYPE OF FIN	IANCIAL ASSI	JRANCE [OCUMENT (C	Check type)			
□ Lette	er of Credit*			ce Certificate	□ Esc	row Account	
□ Perf	ormance Bond	*	□ Financi	al Test	□ For	m 29 (FA Defe	erral)
□ Gua	rantee Bond*		□ Trust F	und Agreement			
* - Ind	licates mechanisms	that require t	he use of a Standt	by Trust Fund Agreemen	t		
Northwest District	Northeas	t Dietrict	Central District	Southwest District	South Dictric	rt Sau	utheast District

III. ESTIMATE ADJUSTMENT

40 CFR Part 264 Subpart H as adopted by reference in Rule 62-701.630, Florida Administrative Code, (F.A.C.) sets forth the method of annual cost estimate adjustment. Cost estimates may be adjusted by using an inflation factor or by recalculating the maximum costs of closure in current dollars. Select one of the methods of cost estimate ajustment below.

	(a)	Inflation	Factor	Adjustment	
--	-----	-----------	---------------	------------	--

(b) Recalculated or New Cost Estimates

Inflation adjustment using an inflation factor may only be made when a Department approved closure cost estimate exists and no changes have occurred in the facility operation which would necessitate modification to the closure plan. The inflation factor is derived from the most recent Implicit Price Deflator for Gross National Product published by the U.S. Department of Commerce in its survey of Current Business. The inflation factor is the result of dividing the latest published annual Deflatory by the Deflator for the previous year. The inflation factor may also be obtained from the Solid Waste website www.dep.state.fl.us/waste/categories/swfr or call the Financial Coordinator at (850) 245-8706.

This adjustment is based on t	he Department approved cl	osing cost estimate dat	ed:	
Latest Department Approved Closing Cost Estimate:	Current Year Infla Factor, e.g. 1.0			Inflation Adjusted Closing Cost Estimate:
	_ ×		=	
This adjustment is based on the	he Department approved lo	ng-term care cost estin	nate dated:	
Latest Department Approved Annual Long-Term Care Cost Estimate:	Current Year Infla Factor, e.g. 1.0			Inflation Adjusted Annual Long-Term Care Cost Estimate:
	_ ×		=	
Number of Years	of Long Term Care Remaini	ing:	×	
Inflation Adjusted	d Long-Term Care Cost Es	stimate:	=	
Signature by:	□ Owner/Operator	Ճ Engineer	(check what ap	oplies)
Ciar	nature		Δ.	ddress
Sigi	lature		A	uuless
Name	e & Title		City, Sta	ate, Zip Code
D	Pate		E-Ma	il Address
912.5	558-0990			
	ne Number			
: отортто				

IV. ESTIMATED CLOSING COST (check what applies)

Notes: 1. Cost estimates for the time period when the extent and manner of landfill operation makes closing most exp

- 2. Cost estimate must be certified by a professional engineer.
- 3. Cost estimates based on third party suppliers of material, equipment and labor at fair market value.
- 4. In some cases, a price quote in support of individual item estimates may be required.

Description			Number		
Subtotal Proposed Monitoring Wells:	Description	Unit	of Units	Cost / Unit	Total Cost
Subtotal Proposed Monitoring Wells: Excavation CY	1. Proposed Monitoring Wells	(Do not incl	ude wells alread	y in existence.)	
2. Slope and Fill (bedding layer between waste and barrier layer): Excavation CY Placement and Spreading CY 18.876 \$1.91 \$36.053.16 Compaction CY Off-Site Material CY Delivery CY Subtotal Slope and Fill: \$36.053.16 3. Cover Material (Barrier Layer): Off-Site Clay Synthetics - 40 mil SY 56.628 \$2.41 \$136.473.48 Synthetics - GCL SY Synthetics - Goenet SY Synthetics - Other (explain) SY 39.204 \$3.11 \$121,924.44 Geocomposite Drainage Layer 4. Top Soil Cover: Off-Site Material CY Delivery CY Spread CY 28.314 \$2.06 \$58.326.84 Subtotal Top Soil Cover: 5. Vegetative Layer Sodding SY 56.628 \$1.81 \$102.496.68 Hydroseeding AC Fertilizer AC 11.7 \$1,010.00 \$11,817.00 Mulch AC Other (explain) SY 9,438 \$3.09 \$29,163.42 Vegetative soil cover (6-in thick layer) 6. Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6.489.00 Starting Sy 9,56.62 \$9.50 Starting Sy 9,50 Startin		EA			
Excavation			Subtotal	Proposed Monitoring Wells:	
Placement and Spreading	2. Slope and Fill (bedding layer	between was	te and barrier lay	/er):	
Compaction CY	Excavation	CY			
Off-Site Material Delivery CY Subtotal Slope and Fill: \$36,053.16 3. Cover Material (Barrier Layer): Off-Site Clay CY Synthetics - 40 mil SY \$56,628 \$2.41 \$136,473.48 \$121,924.44 \$136,473.48 \$121,924.44 \$121,924.	Placement and Spreading	CY	18,876	\$1.91	\$36,053.16
Delivery CY Subtotal Slope and Fill: \$36,053.16	Compaction	CY			
Subtotal Slope and Fill: \$36,053.16	Off-Site Material	CY			
3. Cover Material (Barrier Layer): Off-Site Clay Synthetics - 40 mil SY Synthetics - GCL SY Synthetics - Geonet SY Synthetics - Other (explain) Geocomposite Drainage Layer 4. Top Soil Cover: Off-Site Material CY Delivery Spread CY Spread CY Synthetical SY Synthetics - Other (explain) SY Subtotal Cover Material: S258,397,92 4. Top Soil Cover: Off-Site Material CY Delivery Spread CY Spread CY Spread Subtotal Top Soil Cover: Sodding SY Sodding SY Sodding SY Fertilizer AC Hydroseeding AC Fertilizer AC Other (explain) SY 9,438 S3.09 S29,163.42 Vegetative Layer: Subtotal Vegetative	Delivery	CY			
Off-Site Clay CY 56,628 \$2.41 \$136,473.48 Synthetics - 40 mil SY 56,628 \$2.41 \$136,473.48 Synthetics - GCL SY Synthetics - Geonet SY Synthetics - Other (explain) SY 39,204 \$3.11 \$121,924.44 Geocomposite Drainage Layer Subtotal Cover Material: \$258,397.92 4. Top Soil Cover: Off-Site Material CY Subtotal Top Soil Cover: \$58,326.84 Subtotal Top Soil Cover: \$58,326.84 Subtotal Top Soil Cover: \$58,326.84 5. Vegetative Layer Southotal Top Soil Cover: \$58,326.84 Subtotal Vegetative Layer: \$11,817.00 Mulch AC 11.7 \$1,010.00 \$11,817.00 Mulch AC 11.7 \$1,010.00 \$11,817.00 Vegetative soil cover (6-in thick layer) Subtotal Vegetative Layer: \$143,4				Subtotal Slope and Fill:	\$36,053.16
Synthetics - 40 mil	3. Cover Material (Barrier Layer)	:			
Synthetics - GCL SY Synthetics - Geonet SY Synthetics - Other (explain) SY 39,204 \$3,11 \$121,924.44 \$258,397.92	Off-Site Clay	CY			
Synthetics - Geonet Synthetics - Other (explain) SY Synthetics - Other (explain) Synthetics - Other (explain) Synthetics - Other (explain) Synthetics - Other (explain) Synthetic - Other (explain) Syntheti	Synthetics - 40 mil	SY	56,628	\$2.41	\$136,473.48
Synthetics - Other (explain) SY 39,204 \$3.11 \$121,924.44 Geocomposite Drainage Layer Subtotal Cover Material: \$258,397.92 4. Top Soil Cover: Off-Site Material CY	Synthetics - GCL	SY			
Subtotal Cover Material: \$258,397.92	Synthetics - Geonet	SY			
4. Top Soil Cover: Off-Site Material CY	Synthetics - Other (explain)	SY	39,204	\$3.11	\$121,924.44
Off-Site Material CY	Geocomposite Drainage Layer	_		Subtotal Cover Material:	\$258,397.92
Delivery CY 28,314 \$2.06 \$58,326.84 Subtotal Top Soil Cover: \$58,326.84 Subtotal Soil Cover: \$102,496.68 Subtotal Soil Cover: \$11,817.00 Subtotal Soil Cover: \$11,817.00 Subtotal Soil Cover: \$143,477.10 Subtotal Soil Cover: \$14	4. Top Soil Cover:	_			
Spread CY 28,314 \$2.06 \$58,326.84 Subtotal Top Soil Cover: \$58,326.84 \$58,326.84 Subtotal Top Soil Cover: \$58,326.84 \$102,496.68 Hydroseeding AC Fertilizer AC 11.7 \$1,010.00 \$11,817.00 Mulch AC 11.7 \$1,010.00 \$11,817.00 Mulch AC 11.7 \$1,010.00 \$11,817.00 Mulch AC 11.7 \$1,010.00 \$11,817.00 Sty estative Explain \$29,163.42 \$29,163.42 \$29,163.42 \$143,477.10 Stormwater Control System: Subtotal Vegetative Layer: \$143,477.10 Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY \$3,650 \$9	Off-Site Material	CY			
Subtotal Top Soil Cover: \$58,326.84 5. Vegetative Layer Sodding SY 56,628 \$1.81 \$102,496.68 Hydroseeding AC	Delivery	CY			
5. Vegetative Layer Sodding SY 56,628 \$1.81 \$102,496.68 Hydroseeding AC	Spread	CY	28,314	\$2.06	\$58,326.84
Sodding SY 56,628 \$1.81 \$102,496.68				Subtotal Top Soil Cover:	\$58,326.84
Hydroseeding AC	5. Vegetative Layer			_	
Fertilizer AC 11.7 \$1,010.00 \$11,817.00 Mulch AC Other (explain) SY 9,438 \$3.09 \$29,163.42 Vegetative soil cover (6-in thick layer) 6. Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY Fiping LF 3,650 \$9.50 \$34,675.00 Ditches LF Berms LF Control Structures EA 1 \$876.00 \$876.00 Other (explain) "Wye" connection SY 62.5 \$50.00 \$3,125.00	Sodding	SY	56,628	\$1.81	\$102,496.68
Mulch AC Other (explain) SY 9,438 \$3.09 \$29,163.42 Vegetative soil cover (6-in thick layer) Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY Piping LF 3,650 \$9.50 \$34,675.00 Ditches LF Berms LF Control Structures EA 1 \$876.00 \$876.00 Other (explain) "Wye" connection SY 62.5 \$50.00 \$33,125.00	Hydroseeding	AC			
Other (explain) SY 9,438 \$3.09 \$29,163.42 Vegetative soil cover (6-in thick layer) Subtotal Vegetative Layer: \$143,477.10 6. Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY	Fertilizer	AC	11.7	\$1,010.00	\$11,817.00
Vegetative soil cover (6-in thick layer) Subtotal Vegetative Layer: \$143,477.10 6. Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY	Mulch	AC			
6. Stormwater Control System: Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY	Other (explain)	SY	9,438	\$3.09	\$29,163.42
Earthwork CY 2,100 \$3.09 \$6,489.00 Grading SY	Vegetative soil cover (6-in thick layer)		Subtotal Vegetative Layer:	\$143,477.10
Grading SY Piping LF 3,650 \$9.50 \$34,675.00 Ditches LF	6. Stormwater Control System:	_		_	
Piping LF 3,650 \$9.50 \$34,675.00 Ditches LF	Earthwork	CY	2,100	\$3.09	\$6,489.00
Ditches LF Berms LF Control Structures EA 1 \$876.00 \$876.00 Other (explain) "Wye" connection SY 62.5 \$50.00 \$3,125.00	Grading	SY			
Berms LF	Piping	LF	3,650	\$9.50	\$34,675.00
Control Structures EA 1 \$876.00 \$876.00 Other (explain) "Wye" connection SY 62.5 \$50.00 \$3,125.00	Ditches	LF			
Other (explain) "Wye" connection SY 62.5 \$50.00 \$3,125.00	Berms	LF			
	Control Structures	EA	1	\$876.00	\$876.00
inlet structures Subtotal Stormwater Control System: \$45,165,00	Other (explain) "Wye" connection	<u>SY</u>	62.5	\$50.00	\$3,125.00
, 410,100.00	inlet structures	_	Subtotal	Stormwater Control System:	\$45,165.00

Description	Unit	Number of Units	Cost / Unit	Total Cos
7. Passive Gas Control:				
Wells	EA	13	\$9,849.00	\$128,037.00
Pipe and Fittings	LF	2,890	\$25.40	\$73,406.00
Monitoring Probes	EA			
NSPS/Title V requirements	s LS	1		
·		Su	ıbtotal Passive Gas Con	trol: \$201,443.00
8. Active Gas Extraction Cont				
Traps	EA	1	\$6,700.00	\$6,700.00
Sumps	EA			
Flare Assembly	EA			
Flame Arrestor	EA			
Mist Eliminator	EA			
Flow Meter	EA			
Blowers	EA			
Collection System	LF			
Other (explain)		- <u></u> -		
		Subtotal Ac	tive Gas Extraction Con	trol: \$6,700.00
9. Security System:				
Fencing	LF			
Gate(s)	EA			
Sign(s)	EA			
			Subtotal Security Syst	em:
10. Engineering:				
Closure Plan Report	LS	1	\$5,000.00	\$5,000.00
Certified Engineering Drawing	gs LS	1		
NSPS/Title V Air Permit	LS	1		
Final Survey	LS	1	\$14,040.00	\$14,040.00
Certification of Closure	LS	1	\$10,000.00	\$10,000.00
Other (explain)				
			Subtotal Engineer	ing: \$29,040.00
Description Hour	c Cost	/ Hour H	ours Cost / Hou	r Total Cost
11. Professional Services	s Cost	/ HOUI H	ours Cost / Hour	Total Cos
	ract Management	t	Quality Assurance	
P.E. Supervisor		-		
On-Site Engineer				
Office Engineer				
On-Site Technician				
Other (explain)1		 3,658	1 \$55,202	ф 7 0,000,00
Other (explain)		,658	\$55,202	\$78,860.00
		Numbar		
		Number		
Description	Unit	of Units	Cost / Unit	Total Cos
Description Quality Assurance Testing	Unit LS	of Units	\$5,520.23	Total Cos \$5,520.23

	Subtotal of 1-11 Above:	\$862,983.25
12. Contingency 10 % o	Subtotal of 1-11 Above	\$86,298.32
	Subtotal Contingency:	\$86,298.32
	Estimated Closing Cost Subtotal:	\$949,281.57
Description		Total Cost
13. Site Specific Costs		
Mobilization	_	\$39,430.20
Waste Tire Facility	_	
Materials Recovery Facility	_	
Special Wastes	_	
Leachate Management System	Modification	
Other (explain)		
	Subtotal Site Specific Costs:	\$39,430.20
	TOTAL ESTIMATED CLOSING COSTS (\$):	\$988,711.78

V. ANNUAL COST FOR				
See 62-701.600(1)a.1., 62-70 certified closed and Department				
(Check Term Length) ☐ 5 Ye	ears □ 20 Years □ X 30	Years □ Other, _	Years	
Notes: 1. Cost e	estimates must be certified by	a professional enginee	r.	
2. Cost e	estimates based on third party	suppliers of material, e	quipment and labor at fair n	narket value.
3. In som	ne cases, a price quote in sup	port of individual item e	stimates may be required.	
All items must be address	ssed. Attach a detailed ex	planation for all entrie	es left blank.	
Description	Sampling Frequency (Events / Year)	Number of Wells	(Cost / Well) / Event	Annual Cost
1. Groundwater Monitori	ng [62-701.510(6), and (8	3)(a)]		
Monthly	12			
Quarterly	4			
Semi-Annually	2			
Annually	1			
		Subtotal (Groundwater Monitoring:	
2. Surface Water Monito	oring [62-701.510(4), and	(8)(b)]		
Monthly	12			
Quarterly	4			
Semi-Annually	2			
Annually	1			
		Subtotal Su	urface Water Monitoring:	
3. Gas Monitoring [62-70	1.400(10)]			
Monthly	12			
Quarterly	4			
Semi-Annually	2			
Annually	1			
		;	Subtotal Gas Monitoring:	
4. Leachate Monitoring	[62-701.510(5), (6)(b) and	62-701.510(8)c]		
Monthly	12			
Quarterly	4			
Semi-Annually	2			
Annually	1	1	\$1,061.11	\$1,061.11
Other (explain)				
		Subto	tal Leachate Monitoring:	\$1,061.11
		Number of		
Description	Unit	Units / Year	Cost / Unit	Annual Cost
5. Leachate Collection/T	reatment Systems Maint	enance		
<u>Maintenance</u>				
Collection Pines	l F			

Sumps, Traps

Lift Stations

Cleaning

Tanks

\$514.08

\$1,209.58

\$514.08

\$1,209.58

EΑ

EΑ

LS

EΑ

		Number of	_	
Description	Unit	Units / Year	Cost / Unit	Annual Cos
5. (continued)				
<u>mpoundments</u>				
Liner Repair	SY	1	\$106.11	\$106.11
Sludge Removal	CY			
Aeration Systems				
Floating Aerators	EA			
Spray Aerators	EA		<u> </u>	
<u>Disposal</u>				
Off-site (Includes	1000 gallon	1	\$123.00	\$123.00
ransportation and disposal)		Subtotal Leacha	te Collection / Treatment	
	. II. B.A Co. Co		Systems Maintenance:	\$1,952.77
6. Groundwater Monitoring W				
Monitoring Wells	LF			
Replacement	EA			
Abandonment	EA			
	Subto	otal Groundwater Moni	toring Well Maintenance:	
7. Gas System Maintenance				
Piping, Vents	LF	25	\$26.02	\$650.50
Blowers	EA			
Flaring Units	EA		·	
Meters, Valves	EA		·	
Compressors	EA		·	
Flame Arrestors	EA		·	
Operation	LS	_1_	\$650.00	\$650.00
		Subtotal G	as System Maintenance:	\$1,300.50
B. Landscape Maintenance				
Mowing	AC	_46.8	\$127.00	\$5,943.60
Fertilizer	AC		 .	
		Subtotal I	_andscape Maintenance:	\$5,943.60
). Erosion Control and Cover				
Sodding	SY	100	\$1.81	\$181.00
Regrading	AC			
Liner Repair	SY	10	\$21.21	\$212.10
Clay	CY		 .	
			and Cover Maintenance:	\$393.10
10. Storm Water Management	•	ance		
Conveyance Maintenance	LS	1	\$1,010.00	\$1,010.00
		orm Water Manageme	ent System Maintenance:	\$1,010.00
1. Security System Mainten				
Fences	LS	1		
Gate(s)	EA			
Sign(s)	EA		·	
		Subtotal Secur	rity System Maintenance:	

		Number of		
Description	Unit	Units / Year	Cost / Unit	Annual Cost
12. Utilities	LS	1	\$2,546.65	\$2,546.65
			Subtotal Utilities:	\$2,546.65
Leachate Collection/Treatr	nent Systems	Operation		
<u>Operation</u>				
P.E. Supervisor	HR			
On-Site Engineer	HR			
Office Engineer	HR			
OnSite Technician	HR			
Materials	LS	1		
	Subtotal L	eachate Collection/Treatn	nent Systems Operation:	
14. Administrative				
P.E. Supervisor	HR			
On-Site Engineer	HR			
Office Engineer	HR			
OnSite Technician	HR			
Other See notes	_LS	1	\$2,122.20	\$2,122.20
			Subtotal Administrative:	\$2,122.20
		S	Subtotal of 1-14 Above:	\$16,329.93
1E Contingonou	10	% of Subtotal of 1-14 A	hovo	
15. Contingency	10	% 01 Subtotal 01 1-14 A	-	\$1,632.99
			Subtotal Contingency:	\$1,632.99
		Number of		
Description	Unit	Units / Year	Cost / Unit	Annual Cost
16. Site Specific Costs				
_				
_				
		Sub	ototal Site Specific Costs:	
			· -	
		ANNUAL LONG-TERM C	CARE COST (\$ / YEAR):	\$17,962.92
		Number of Ye	ears of Long-Term Care:	30
		TOTAL LONG-	TERM CARE COST (\$):	\$538,887.69

VI. CERTIFICATION BY ENGINEER

This is to certify that the Cost Estimates pertaining to the engineering features of this solid waste management facility have been examined by me and found to conform to engineering principles applicable to such facilities. In my professional judgment, the Cost Estimates are a true, correct and complete representation of the financial liabilities for closing and/or long-term care of the facility and comply with the requirements of Rule 62-701.630 F.A.C. and all other Department of Environmental Protection rules, and statutes of the State of Florida. It is understood that the Cost Estimates shall be submitted to the Department annually, revised or adjusted as required by Rule 62-701.630(4), F.A.C.

	13101 Telecom Drive, Suite 120
Signature	Mailing Address
Victor M. Damasceno, Ph.D.,P.E.	Temple Terrace, Florida 33637
Name and Title (please type)	City, State, Zip Code
	VDamasceno@Geosyntec.com
Date	E-Mail address (if available)
	813-558-0990
Florida Registration Number	Telephone Number
(please affix seal)	
VII. SIGNATURE BY OWNER/OPERATOR	
	1501 Omni Way
Signature of Applicant	Mailing Address
Mike Kaiser, Regional Engineer	Saint Cloud, Florida 34773
Name and Title (please type)	City, State, Zip Code
MKaiser@Wasteservicesinc.com	(904)673-0446
E-Mail address (if available)	Telephone Number

VI. CERTIFICATION BY ENGINEER

This is to certify that the Cost Estimates pertaining to the engineering features of this solid waste management facility have been examined by me and found to conform to engineering principles applicable to such facilities. In my professional judgment, the Cost Estimates are a true, correct and complete representation of the financial liabilities for closing and/or long-term care of the facility and comply with the requirements of Rule 62-701.630 F.A.C. and all other Department of Environmental Protection rules, and statutes of the State of Florida. It is understood that the Cost Estimates shall be submitted to the Department annually, revised or adjusted as required by Rule 62-701.630(4), F.A.C.

No 72966 Victor M. Damasceno, Ph.D., P.E.
STATE OF STATE OF ON AL
Florida Registration Number
(please affix seal)

13101 Telecom Drive, Suite 120
Mailing Address
Temple Terrace, Florida 33637
City, State, Zip Code
VDamasceno@Geosyntec.com
E-Mail address (if available)
813-558-0990
Telephone Number

VII. SIGNATURE BY OWNER/OPERATOR

Signature of Applicant


1501 Omni Way Mailing Address

Mike Kaiser, Regional Engineer
Name and Title (please type)

Saint Cloud, Florida 34773 City, State, Zip Code

MKaiser@Wasteservicesinc.com
E-Mail address (if available)

(904)673-0446 Telephone Number



FINANCIAL ASSURANCE COST ESTIMATE FOR CLOSURE OF CELL 8: NOTES AND CALCULATIONS J.E.D. SOLID WASTE MANAGEMENT FACILITY

The information provided below presents the methods and assumptions used to estimate the cost for the items listed on the FDEP Form 62-701.900(28), F.A.C., "Closure Cost Estimating Form for Solid Waste Facilities" (January 6, 2010). The closure and long-term care costs were estimated for Cell 8 using the FDEP approved unit rate costs from the financial assurance cost estimate revision associated with the addition of Cell 7 completed and approved in 24 February 2011. The unit rate costs used to calculate of the closure and long-term care costs for Cell 8 have been inflated by 1% to account for the 2011 inflation adjustment issued by the FDEP on 19 July 2011. It is noted that the financial assurance cost estimate presented in Attachment 2 includes the closure and long-term care costs for Cell 8 only. The section numbers noted below correspond to the item numbers on FDEP Form 62-701.900(28), F.A.C.

I. GENERAL INFORMATION

The financial assurance cost estimate presented on the FDEP Form 62-701.900(28) provides the closure and long-term care costs for the Cell 8 at the J.E.D. Solid Waste Management facility in Osceola County, Florida.

IV. ESTIMATED CLOSING COST

1. Proposed Monitoring Wells

The groundwater monitoring well system for Phases 1 through 3 (Cells 1 through 10) has already been completed. Therefore, no costs have been included as part of this financial assurance revision.

2. Slope and Fill (bedding layer)

On-site soils will be used for intermediate cover. The total estimated volume is 18,876 cubic yards (yd³) for the 1-ft thick intermediate cover layer over the waste surface. The cost per yd³ includes excavation, hauling, placement, spreading, grading, and compaction. The estimated cost for slope and fill material is as follows:

As presented in Figure 1, the Cell 8 top deck area covers 3.6 acres and the 3:1 side slope area is equal to 7.7 acres resulting in a total Cell area of approximately 11.3 acres. To account for the additional area attributed to the 3:1 side slopes the plan areas are multiplied by 1.05. Therefore, the 3:1 side slope area for Cell 8 is 7.7 acres \times 1.05 = 8.1 acres plus the 3.6 acre top deck area equals a total corrected area of approximately **11.7 acres**.

• $(11.7 \text{ acres} \times 43,560 \text{ ft}^2/\text{acre} \times 1 \text{ ft cover thickness}) \div 27 \text{ ft}^3/\text{ yd}^3 = 18,876 \text{ yd}^3$

• $18,876 \text{ yd}^3 \text{ @ } \$1.91/\text{ yd}^3 = \$36,053.16$

3. Cover Material (Barrier Layer)

The final cover system for the JED facility is comprised of (from bottom to top):

- 12 inch intermediate cover soil layer (Item No.2 above)
- 40-mil PE smooth geomembrane
- geocomposite drainage layer (on 3:1 side slopes only)
- 18-inch cover protective soil layer
- 6-inch vegetative soil layer (Item No. 4 below)

Cost for geosynthetics includes material and installation costs. The estimated quantities are:

40-mil PE smooth geomembrane:

- 11.7 acres \times 43,560 ft²/acre \div 9 ft²/yd² = 56,628 yd²
- $56,628 \text{ yd}^2 60\text{-mil PE}$ textured geomembrane @ $2.41/\text{yd}^2 = 136,473.48$

Geocomposite Drainage Layer (on 3:1 side slopes only):

- 11.7 acres 3.6 acres (top deck of Cell 8) = 8.1 acres
- $8.1 \text{ acres} \times 43,560 \text{ ft}^2/\text{acre} \div 9 \text{ ft}^2/\text{yd}^2 = 39,204 \text{ yd}^2$
- $39,204 \text{ yd}^2$ geocomposite drainage layer @ $\$3.11/\text{yd}^2 = \$121,924.44$

The total cost for final cover materials (excluding the intermediate and vegetative soil layers) is \$258,397.92.

4. Top Soil Cover

Cover protective soil will consist of material obtained from on-site. Cost for the 18-inch cover protective soil layer includes excavation, hauling, placement, spreading, grading, and compaction.

- $(11.7 \text{ acres} \times 43,560 \text{ ft}^2/\text{acre} \times 1.5 \text{ ft cover thickness}) \div 27 \text{ ft}^3/\text{ yd}^3 = 28,314 \text{ yd}^3$
- $28,314 \text{ yd}^3 \text{ cover soils } @ $2.06/ \text{ yd}^3 = $58,326.84$

5. Vegetative Layer

The vegetative soil layer consists of a 6 inch layer over the cover protective soil. The estimated volume is 9,438 yd³. The vegetative soil will consist of material obtained from onsite sources. The cost per cubic yard includes hauling, placing, spreading, and grading.

The final cover area will be sodded. Sodding costs include all labor and materials.

- 11.7 acres \times 43,560 ft²/acre \div 9 ft²/yd² = 56,628 yd²
- 56,628 yd² Bahia sod @ \$1.81/yd²= **\$ 102,496.68**

Fertilizer (Amendments) for the vegetative soil layer is \$1,010 per acre.

• $11.7 \text{ acres} \times \$1,010/\text{acre} = \$11,817.00$

The estimated cost for the vegetative soil layer is as follows:

- $(11.7 \text{ acres} \times 43,560 \text{ ft}^2/\text{acre} \times 0.5 \text{ ft cover thickness}) \div 27 \text{ ft}^3/\text{ yd}^3 = 9,438 \text{ yd}^3$
- $9,438 \text{ yd}^3 \text{ } @ \$3.09/ \text{ yd}^3 = \$ 29,163.42$

The total cost for the vegetative layer (vegetative soil cover and sod) is \$143,477.10.

6. Stormwater Control System

Storm water control components that will be installed during closure consist of side slope drainage swales, inlet structures on the side slope swales, seepage header piping, and HDPE corrugated down chute pipes. The earthwork estimate includes excavation, hauling, placement, spreading, grading, and compaction of the additional soils required on the drainage benches for sloping and cover over the down chute piping.

Based on the ERP Lateral Expansion Permit Drawings (Sheet 37 of 40), approximately 2,750 feet of side slope drainage swales, 750 feet of 24-inch down chute pipes, 2,900 feet of 4-in seepage header pipe, and ten (10) wye-connection inlet structures will be installed to convey the storm water from the proposed side slope swales to the dry retention area located at the toe of the landfill perimeter berm. Costs associated with the additional storm water structure installed as part of the Cell 8 construction has also been included.

The total cost for the storm water control system is estimated to be \$45,165.00 as indicated below.

- Earthwork: Additional soil to construct drainage swales is calculated based on the typical cross-section detail for the drainage swale from the ERP Lateral Expansion Permit Drawings and using the average depth of the swale = 20.6 ft2 per linear foot of swale. 20.6 ft2 × 2,750 ft = 56,650 ft3 ÷ 27 ft3/yd3 = 2,100 yd3
 - \circ 2,100 yd³ @ \$3.09/yd³ = **\$6,489.00**
- Piping (material and installation):
 - \circ 750 ft of 24-inch HDPE corrugated pipe @ \$29.88/ft = \$22,410.00.
 - o 2,900 ft of 4-inch HDPE corrugated pipe @ 4.22/ft = \$12,238.00 (the cost of the 4-inch drainage pipe includes the cost of the pipe and a 3-ft wide strip of geomembrane used to wrap the pipe).

To calculate an average cost per foot of pipe for the FDEP form, the total pipe cost above has been divided by the total length of pipe to be installed:

- \circ (\$22,410 + \$12,238) = \$34,648 \div (750 ft + 2,900 ft) = \$9.50/ft.
- A concrete pad will be installed with each "wye" connection which joins the swale pipes to the main side slope downchute to hold the piping in place and reduce erosion. Ten (10) concrete pads are proposed for the Cell 8 closure. Each concrete pad will be 6-inches thick with dimensions of approximately 7.5-ft x 7.5-ft, for a total pad area of 6.25 yd². The price of 6-in thick concrete material and placement is 6.25 yd² x 10 structures = 62.5 yd² @ \$50/yd² = \$3,125.00.

• Drainage inlet structures: 1 @ \$876 each = **\$876.00**.

7. Passive Gas Control

The JED facility has an active gas collection and control system (GCCS) within the Phase 1 development area (i.e., Cells 1-4), which will be expanded upon with the closure of subsequent cells. The costs associated with the installation of the passive gas control elements were calculated utilizing the proposed GCCS design as provided in the Lateral Expansion Solid Waste Permit Drawings (Sheet 29 of 40). Costs include materials and installation.

Gas Wells [drilling, perforated pipe section (including gravel), solid pipe section (including soil backfill), and well head]: Drilling @ \$27.82/ft, perforated pipe section @ \$53.06/ft, solid pipe section @ \$35.03/ft, and well heads @ \$1,236.24 each. Well depths shown are average depths for shallow, medium, and deep wells within the Cell 8 footprint.

- 3-30 ft gas well @ \$3,254.64/gas well = \$9,763.92
- 2-80 ft gas well @ \$7,298.64/gas well = \$14,597.28
- 8 150 ft gas well @ \$12,960.24/gas well = **\$103,681.92**

To calculate an average cost per gas well for the FDEP form, the total well costs above have been divided by the proposed number of gas wells:

• $(\$9,763.92 + \$14,597.28 + 103,681.92) \div 13 \text{ wells} = \$128,043.12 \div 13 \text{ wells} = \$9,849.47 \text{ per well}$

Lateral piping (6-inch SDR-17 HDPE Pipe):

• 2,430ft @ \$18.54/ft = **\$45,052.20**

Header piping (12-inch SDR-17 HDPE Pipe):

• 460 ft @ \$35.03/ft = **\$16,113.80**

To calculate the cost per foot of gas system piping, the total pipe cost has been divided by the total estimated length of pipe:

•
$$(\$45,052.20 + \$16,113.80) = \$61,166 \div (2,430 + 460)$$
 ft = $\$21.17/\text{ft}$

It is assumed that an additional 20% of the pipe cost is needed for fittings.

• $(\$21.17 \times 20\%) + \$21.17 = \$25.40/\text{ft}$

The total cost for the lateral and header piping and fittings is:

• $$25.40/\text{ft} \times 2,890\text{ft} = $73,406.00$

Perimeter gas monitoring probes have been installed for Phases 1 through 3 (i.e., Cells 1-10) therefore, no costs have been included in this closure cost estimate.

The total cost for passive gas controls is \$201,443.00

8. Active Gas Control

Based on the proposed GCCS design, two gas flare stations will be installed as part of the GCCS for Phases 1 through 3. One gas flare station was already installed as part of the Phase 1, Sequence 1 and 2 GCCS installation (for Cells 1 through 4). The cost of the second gas flare was included as part of the Revised Financial Assurance for the remaining Phase 1 Closure Area; therefore, no additional costs have been included with the Cell 8 closure financial assurance.

One condensate trap will be installed as part of the GCCS system within the footprint of Cell 8. The cost per condensate trap is $\$6,700 \times 1 = \$6,700$.

The total cost for active gas extraction control is \$6,700.

9. Security System

The perimeter fencing and gates were installed as part of the Phase 1 construction and therefore have not been included as part of this closure cost estimate.

10. Engineering

Closure Plan Report – The closure plan is included as part of the permit renewal application. Geosyntec has estimated \$5,000 to update this plan.

Final Survey – It was estimated in the previously approved Financial Assurance (Cell 7 Closure) that surveying costs were approximately \$1,200/acre. This estimate was based on a survey cost for the partial closure of Phase 1 (\$30,000 / 25 acres = \$1,200/acre). This cost per acre estimate has been applied to the closure of Cell 8; therefore, costs associated with the final survey of Cell 8 are \$1,200/acre \times 11.7 acres = \$14,040.

Certification of Closure – Geosyntec has estimated \$10,000 to prepare the closure certification report.

11. Professional Services

These costs are based on Geosyntec estimates and labor rates. It is estimated that approximately 3 percent of construction cost will be needed for contract/construction management, which equates to $0.03 \times \$788,604.02 = \$23,658$.

It is estimated that approximately 7 percent of construction cost will be needed for construction quality assurance (CQA), which equates to:

• $0.07 \times \$788,604.02 = \$55,202.$

Quality assurance testing is estimated to be 10 percent of the CQA cost estimate and is based on the requirements of the CQA Plan, estimated quantities, and Geosyntec's experience. This equates to:

• $0.10 \times \$55,202.28 = \$5,520.23$.

12. Contingency

A contingency factor for closure costs of 10 percent is estimated.

13. Site Specific Costs

It is estimated that approximately 5 percent of construction cost will be needed for mobilization and demobilization of equipment which equates to

• $0.05 \times \$788,604.02 = \$39,430.20$.

V. ANNUAL COST FOR LONG TERM CARE

The unit costs for calculation of the long-term care costs were extracted from the Cell 7 Financial Assurance Minor Modification Application. The unit rate costs used in the calculation of the long-term care costs for Cell 8 have been inflated by 1% to account for the 2011 inflation adjustment issued by the FDEP on July 19, 2011.

1. Ground Water Monitoring

Currently, the groundwater monitoring well network for Phases 1 through 3 (Cells 1-10) has been installed. The long-term care cost for groundwater monitoring wells was included in the previously approved financial assurance cost estimate. Therefore, no additional monitoring cost has been included as part of the long-term care cost estimate for Cell 8.

2. Surface Water Monitoring

The long-term care cost for surface water monitoring was included in the previously approved financial assurance cost estimate. Therefore, no additional monitoring cost has been included as part of the long-term care cost estimate for Cell 8.

3. Landfill Gas Monitoring

The long-term care cost for gas monitoring probes was included in the previously approved financial assurance cost estimate which included gas monitoring for Phases 1 through 3. Therefore, no additional monitoring cost has included as part of the long-term care cost estimate for Cell 8.

4. Leachate Monitoring

A leachate sample would be collected annually from Cell 8. The leachate sampling cost includes all labor, equipment, and laboratory analyses required by the regulations.

• Annual leachate monitoring cost: \$1,061.11/year

5. Leachate Collection/Treatment System Maintenance

For the long term care cost estimate, the following maintenance activities have been assumed:

Leachate pumps: Assumed that pumps require annual maintenance and Cell 8 will require a replacement pump during the 30-year monitoring period:

- Annual maintenance = \$301.85/year
- Leachate pump replacement cost = \$6,367/30years = \$212.23/year

• Total estimated annual cost for pumps = \$514.08/year

Leachate collection pipes: Assumed that one cleaning <u>every 10 years</u> within the 30-year monitoring period will be required for Cell 8 (total of 3 cleanings).

• $(\$12,095.76 \times 3) / 30 \text{ years} = \$1,209.58/\text{year}.$

Leachate storage containers: Long term care for the leachate storage containers assumes that three of the four bladders will require replacement over the 30-year monitoring period. Replacement cost has been assumed to be \$10,611 per flexible bladder. Total long-term care cost for the three bladder replacement was split based on number of cells (i.e. 10 cells) to estimate the Cell 8 long-term care cost for leachate storage containers.

• 3 bladders \times \$10,611/bladder /30 years x (1/10) = **\$106.11/year**

Leachate disposal: Leachate generation rate after closure was assumed to be 20 percent of the annual average leachate generation rate for maximum waste height that was obtained from the HELP model Analysis (see Case 4 analyzed for maximum waste thickness of 220 ft in the calculation package entitled *Leachate Management System*).

• 24.63 ft³/ac/year or 184.3 gal/ac/year × 12 acres × 20 percent = 442 gal/year → use minimum unit of 1,000 gallons as shown on FDEP form 1,000 gallons/year × \$0.123/gallon for transportation and treatment = \$123/year.

Therefore, total long-term care cost for leachate system maintenance = \$1,952.77/year.

6. Maintenance of Groundwater Monitoring Wells

The long-term care cost for maintenance of groundwater monitoring wells was included in the previously approved financial assurance cost estimate. Therefore, no additional cost is included as part of the long-term care cost estimate for Cell 8.

7. Gas System Maintenance

Thirteen (13) gas wells will eventually be installed within the footprint of Cell 8. It is estimated that an additional \$50 per well/year will be needed for operation ($$50 \times 13$ wells = 650). It is also assumed that 25 ft piping will require replacement. The remainder of the long-term care cost for gas system maintenance was included in the previously approved financial assurance cost estimate.

8. Landscape

The long-term care cost estimate assumes that for the 11.7-acre area, the grass will be moved four times per year at a cost of \$127.00 per acre. Moving/maintenance:

• $4 \text{ times/year} \times 11.7 \text{ acres} \times \$127/\text{acre} = \$5,943.60/\text{year}$

9. Erosion Control and Cover Maintenance

As indicated on FDEP form.

10. Storm Water Management System Maintenance

As indicated on FDEP form.

11. Security System Maintenance

The long-term care cost for security system maintenance was included in the previously approved financial assurance cost estimate. Therefore, no additional cost is included as part of the long-term care cost estimate for Cell 8.

12. Utilities

The long-term care cost estimate for Phases 1 through 3 assumes that the power requirements for site equipment (i.e., pumps, lights, blowers, etc.) will cost \$2,101.20 per month. The total utility cost for Phases 1 through 3 is split based on number of cells (i.e. 10 cells) to estimate the utility cost for Cell 8:

• $\$2,101.20/\text{month} \times 12 \text{ months } x (1/10) = \$2,521.44/\text{year.}$

13. Leachate Collection/Treatment Systems Operation

The long-term care costs for the leachate collection/treatment system operation was included in the previously approved financial assurance cost estimate. Therefore, no additional cost is included as part of the long-term care cost for Cell 8.

14. Administrative

The long-term care cost estimate assumes that the administrative costs for Phases 1 through 3 to be \$21,222/year. The total administrative cost for Phases 1 through 3 is split based on number of cells (i.e. 10 cells) to estimate the administrative cost for Cell 8:

• $\$21,222/\text{year} \times (1/10) = \$2,122.20/\text{year}$

15. Contingency

A contingency factor for long-term care costs of 10 percent is estimated.

16. Site Specific Costs

No additional site specific costs are estimated.

