STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 1	EXTEND PIPE THRU BERM	---	---	265.00 (18" W)
S 2	MOD. FDOT TYPE 'E' INLET (DETAIL A)	146.50	143.76 (S)	141.76 (18" E) 141.76 (42" W)
S 3	CONST. MITERED END INTO CONC. PAVING	---	---	141.76 (42" E)
S 4	EXTEND PIPE THRU BERM	---	---	265.00 (18" W)
S 5	MOD. FDOT TYPE 'E' INLET (DETAIL A)	146.50	143.76 (S)	141.76 (18" E) 141.30 (42" W)
S 6	CONST. MITERED END INTO CONC. PAVING	---	---	141.30 (42" E)
S 7	FDOT TYPE 'E' INLET	145.09	142.35 (S)	139.85 (24" N)
S 8	CONST. MITERED END INTO CONC. PAVING	---	---	139.85 (24" S)
S 9	EXTEND PIPE THRU BERM	---	---	265.00 (18" N)
S 10	MOD. FDOT TYPE 'E' INLET (DETAIL A)	138.91	136.17 (W)	134.17 (18" S) 134.17 (42" N)
S 11	CONST. MITERED END INTO CONC. PAVING	---	---	134.17 (42" S)
S 12	EXTEND PIPE THRU BERM	---	---	265.00 (18" N)
S 13	MOD. FDOT TYPE 'E' INLET (DETAIL A)	134.91	132.17 (W)	130.17 (18" S) 130.17 (42" N)
S 14	CONST. MITERED END INTO CONC. PAVING	---	---	130.17 (42" S)
S 15	EXTEND PIPE THRU BERM	---	---	265.00 (18" N)
S 16	MOD. FDOT TYPE 'E' INLET (DETAIL A)	131.81	129.07 (W)	127.07 (18" S) 127.07 (42" N)
S 17	CONST. MITERED END INTO CONC. PAVING	---	---	127.07 (42" S)

STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 18	EXTEND PIPE THRU BERM	---	---	265.00 (18" N)
S 19	MOD. FDOT TYPE 'E' INLET (DETAIL A)	126.23	123.49 (W)	121.49 (18" S) 121.49 (42" N)
S 20	CONST. MITERED END INTO CONC. PAVING	---	---	121.49 (42" S)
S 21	FDOT TYPE 'E' INLET	122.65	119.91 (NW)	115.45 (24" NE)
S 22	CONST. MITERED END INTO CONC. PAVING	---	---	115.45 (24" SW)
S 23	EXTEND PIPE THRU BERM	---	---	265.00 (18" E)
S 24	MOD. FDOT TYPE 'E' INLET (DETAIL B)	121.50	118.76 (S)	116.76 (18" W) 116.76 (42" E)
S 25	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	121.50	118.76 (S)	116.76 (42" W) 113.76 (42" N)
S 26	EXTEND PIPE THRU BERM	---	---	265.00 (18" E)
S 27	MOD. FDOT TYPE 'E' INLET (DETAIL A)	121.50	118.76 (N)	116.76 (18" W) 116.76 (42" E)
S 28	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	121.50	118.76 (N)	116.76 (42" W) 113.76 (42" S)
S 29	FDOT TYPE 'E' INLET	121.50	118.76 (N) 118.76 (S)	116.76 (24" E)
S 30	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	121.50	118.76 (N) 118.76 (S)	116.76 (24" W) 110.96 (42" N) 110.46 (48" SE)
S 31	INLET STRUCTURE	115.00	107.80 (SW)	109.16 (48" NW) 102.89 (DBL. 48" SE)
S 32	EXTEND PIPE THRU BERM	---	---	265.00 (18" SE)
S 33	MOD. FDOT TYPE 'E' INLET (DETAIL B)	121.77	119.03 (SW)	117.03 (18" NW) 109.85 (42" SE)

STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 34	CONST. MITERED END INTO CONC. PAVING	---	---	109.85 (42" NW)
S 35	FDOT TYPE 'E' INLET	123.02	120.28 (SW)	115.85 (24" SE)
S 36	CONST. MITERED END INTO CONC. PAVING	---	---	115.85 (24" NW)
S 37	EXTEND PIPE THRU BERM	---	---	265.00 (18" S)
S 38	MOD. FDOT TYPE 'E' INLET (DETAIL B)	126.80	124.06 (W)	122.06 (18" N) 122.06 (42" S)
S 39	CONST. MITERED END INTO CONC. PAVING	---	---	122.06 (42" N)
S 40	EXTEND PIPE THRU BERM	---	---	265.00 (18" S)
S 41	MOD. FDOT TYPE 'E' INLET (DETAIL B)	131.94	129.20 (W)	127.20 (18" N) 127.20 (42" S)
S 42	CONST. MITERED END INTO CONC. PAVING	---	---	127.20 (42" N)
S 43	EXTEND PIPE THRU BERM	---	---	265.00 (18" S)
S 44	MOD. FDOT TYPE 'E' INLET (DETAIL B)	135.04	132.30 (W)	130.30 (18" N) 130.30 (42" S)
S 45	CONST. MITERED END INTO CONC. PAVING	---	---	130.30 (42" N)
S 46	EXTEND PIPE THRU BERM	---	---	265.00 (18" S)
S 47	MOD. FDOT TYPE 'E' INLET (DETAIL B)	139.03	136.29 (W)	134.29 (18" N) 134.29 (42" S)
S 48	CONST. MITERED END INTO CONC. PAVING	---	---	134.29 (42" N)
S 49	FDOT TYPE 'E' INLET	144.76	142.02 (N)	139.85 (24" S)
S 50	CONST. MITERED END INTO CONC. PAVING	---	---	139.85 (24" N)

STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 51	EXTEND PIPE THRU BERM	---	---	265.00 (18" W)
S 52	MOD. FDOT TYPE 'E' INLET (DETAIL B)	146.50	143.76 (N)	141.76 (18" E) 141.30 (42" W)
S 53	CONST. MITERED END INTO CONC. PAVING	---	---	141.30 (42" E)
S 54	EXTEND PIPE THRU BERM	---	---	265.00 (18" W)
S 55	MOD. FDOT TYPE 'E' INLET (DETAIL B)	146.50	143.76 (N)	141.76 (18" E) 141.76 (42" W)
S 56	CONST. MITERED END INTO CONC. PAVING	---	---	141.76 (42" E)
S 57	FDOT TYPE 'E' INLET	134.50	131.76 (W)	130.76 (30" N)
S 58	CONST. MITERED END INTO CONC. PAVING	---	---	130.76 (30" S)
S 59	FDOT TYPE 'E' INLET	130.27	127.53 (NW)	126.53 (30" NE)
S 60	CONST. MITERED END INTO CONC. PAVING	---	---	126.53 (30" SW)
S 61	FDOT TYPE 'E' INLET	128.15	125.41 (NW)	124.41 (30" NE)
S 62	CONST. MITERED END INTO CONC. PAVING	---	---	124.41 (30" SW)
S 63	FDOT TYPE 'E' INLET	124.50	121.76 (NW)	120.00 (24" NE)
S 64	CONST. MITERED END INTO CONC. PAVING	---	---	120.00 (24" SW)
S 65	FDOT TYPE 'E' INLET	123.50	120.76 (NW) 120.76 (SE)	117.41 (30" NE)
S 66	CONST. MITERED END INTO CONC. PAVING	---	---	117.41 (30" SW)
S 67	FDOT TYPE 'E' INLET	ERR	ERR (SW)	ERR (30" NW)

STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 68	CONST. MITERED END INTO CONC. PAVING	---	---	125.35 (30" NW)
S 69	FDOT TYPE 'E' INLET	135.72	132.98 (NW)	131.98 (30" SW)
S 70	CONST. MITERED END INTO CONC. PAVING	---	---	131.98 (30" NE)
S 71	FDOT TYPE 'E' INLET	139.91	137.17 (NW)	136.17 (30" SW)
S 72	CONST. MITERED END INTO CONC. PAVING	---	---	136.17 (30" NE)
S 73	CONCRETE ENDWALL DOUBLE 48" RCP	---	---	118.00 (DBL. 48" E)
S 74	CONCRETE ENDWALL DOUBLE 48" RCP	---	---	117.16 (DBL. 48" W)
S 75	INLET STRUCTURE	115.70	110.70 (NW)	106.13 (DBL. 48" S)
S 76	JUNCTION BOX	120.00	---	102.89 (DBL 48" N & S) 108.26 (48" SW)
S 77	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	106.40 (DBL. 48" E)
S 78	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	105.48 (DBL. 48" W)
S 79	CONCRETE ENDWALL 48" CMP	---	---	115.80 (48" NE)
S 80	CONST. MITERED END INTO CONC. PAVING	---	---	114.60 (48" SW)
S 81	4:1 MITERED END SECTION	---	---	101.65 (QUAD 24" NE)
S 82	4:1 MITERED END SECTION	---	---	101.00 (QUAD 24" SW)
S 83	FDOT TYPE 'E' INLET	121.50	118.76 (S)	116.76 (24" E)
S 84	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	121.50	118.76 (S)	116.76 (24" W) 111.56 (42" S) 111.06 (48" N)

STRUCTURE NUMBER	STRUCTURE DESCRIPTION	TOP ELEVATION	SLOT ELEVATION	INVERT ELEVATION
S 85	FDOT TYPE 'E' INLET	121.50	118.76 (N) 118.76 (S)	116.76 (24" E)
S 86	FDOT TYPE 'E' INLET W/ 7' TYPE J BOTTOM (ALTERNATE A)	121.50	118.76 (S)	116.76 (24" W) 109.01 (42" S) 109.01 (48" NE)
S 87	FDOT TYPE 'E' INLET	116.65	115.90 (N) 115.90 (S)	114.44 (15" E)
S 88	FDOT TYPE 'E' INLET	116.65	115.90 (N) 115.90 (S)	114.16 (15" W) 114.16 (15" NE)
S 89	FDOT TYPE 'E' INLET	114.65	113.90 (N) 113.90 (S)	112.96 (15" NE)
S 90	FDOT TYPE 'E' INLET	114.65	113.90 (N) 113.90 (S)	112.68 (15" SW) 112.68 (15" N)
S 91	CONST. MITERED END INTO CONC. PAVING	---	---	111.77 (15" S)
S 92	4:1 MITERED END SECTION	---	---	105.49 (TRIP. 54" NE)
S 93	4:1 MITERED END SECTION	---	---	105.49 (TRIP. 54" SW)
S 94	4:1 MITERED END SECTION	---	---	114.00 (15" SW)
S 95	FDOT TYPE 'E' INLET	116.00	114.70 (W)	111.50 (15" E)
S 96	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	112.80 (DBL. 48" E)
S 97	CONCRETE ENDWALL DOUBLE 48" CMP	---	---	112.25 (DBL. 48" W)
S 98	CONST. MITERED END INTO CONC. PAVING	---	---	129.00 (36" NE)
S 99	FDOT TYPE 'E' INLET	120.00	---	113.67 (36" NW) 113.67 (36" NE)
S 100	CONST. MITERED END INTO CONC. PAVING	---	---	111.50 (36" SW)
S 101	4:1 MITERED END SECTION	---	---	111.00 (15" W)
S 102	4:1 MITERED END SECTION	---	---	101.33 (DBL. 48" SW)
S 103	4:1 MITERED END SECTION	---	---	101.33 (DBL. 48" NW)

5-27-80

REVISIONS

ENG PROJ NO. E87.113.9
DRAWN BY PWH
CHECKED BY SLW
DATE JUNE 18,1990

SCHEDULE OF DRAINAGE STRUCTURES

TRAIL RIDGE LANDFILL (PLAN A)

England-Thims & Miller, Inc.
Consulting & Design Engineers
JACKSONVILLE, FLORIDA

DRAWING NO
35

PROJ NO E87.113-9