




The engineer expressly reserves the exclusive common law copyright and property rights to these drawings which may not be reproduced, changed or copied in any form or manner, nor are they to be assigned to any party without the engineers written consent.



FINISH FLOOR ELEV. 72.0'




NOTE:
PROVIDE 3" CLEAR COVER AROUND REINFORCEMENT
IN CONCRETE EXPOSED TO EARTH.



FOUNDATION NOTES:

1. ALL CONCRETE TO BE 3000 P.S.I. AT 28 DAY STRENGTH.
2. BILLET STEEL BARS FOR REINFORCING SHALL CONFORM TO THE REQUIREMENTS OF ASTM A-615, GRADE 60.
3. FOUNDATION DESIGN IS BASED ON A SOIL BEARING CAPACITY OF 3000 PSF AS INDICATED IN SOILS REPORT BY CENTRAL TESTING LABORATORIES.
4. SOIL SHALL BE TREATED FOR TERMITES BY A LICENSED EXTERMINATOR.
5. COMPACTION OF SOIL UNDER ALL CONCRETE TO BE 95% MAXIMUM DRY DENSITY BY MODIFIED PROCTOR.
6. FINAL FOUNDATION DESIGN SUBJECT TO BUILDING DESIGN BY MANUFACTURER.
7. STEEL REINFORCING TO HAVE 3" COVER FOR FACES OF FOUNDATION PERMANENTLY EXPOSED TO EARTH AND 2" FOR CONCRETE EXPOSED TO WEATHER, 1-1 1/2" ELSEWHERE.
8. 6 MIL VAPOR BARRIER REQUIRED BENEATH FOUNDATIONS AND SLAB.
9. FLOOR SLAB THICKNESS WILL BE 6" WITH #4 REBAR @ 12" O.C., BOTH WAYS.
10. FILL MATERIAL, IF NECESSARY, WILL BE AVAILABLE ON SITE.

DAVID W. SPRINGSTEAD, P.E.
FLORIDA REGISTRATION NO. 48229



REV. BY:	DESCRIPTION	DATE:	DRAWN

CLIENT: **SUMTER COUNTY BOARD OF COUNTY COMMISSIONERS**
 PROJECT: **COMPOST FINISHING BUILDING SECOND DIGESTER BAY ADDITION**
 DRAWING: **DETAILS** 2 of 2

Springstead Engineering, Inc.



Consulting Engineers
Architects, Planners
Surveyors
EB-0001723
LB-0001723 AA-0002820
727 South 14th Street
Leesburg, FL 34748
(352) 787-1414

SCALE: 1/8"=1'-0"	FILE: FLOOR	DATE: 4/03/02
DESIGN: [Signature]	DRAWN: [Signature]	CHECKED: [Signature]
DRAWING: DETAILS		
CLIENT: S.C.B.C.C.		
JOB NO.: 921100.005	SHEET: 2	OF: 2