



- Notes:
- 1) LEACHATE POND CONSTRUCTED AND LINED IN ACCORDANCE WITH THE PLANS. 40 MIL. HDPE LINER INSTALLED.
  - 2) EARTHWORK ON NEW LINED CELL COMPLETED. CELL IS NOT LINED AS OF AUGUST 23, 1988

I CERTIFY THAT, WITH THE EXCEPTIONS SHOWN AND NOTED, THIS PROJECT WAS CONSTRUCTED SUBSTANTIALLY IN ACCORDANCE WITH THE PLANS APPROVED BY THE STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION.

PAUL BRADLEY, P.E., REG. NO. 35481

SOUTHWEST DISTRICT  
TAMPA  
MAY 17 1988  
D.E.R.

3-31-88 APPROVED BY DER.

<b>SPRINGSTEAD ENGINEERING INC.</b>			
consulting engineers			
Leesburg — Bushnell			
DETAIL OF COMPOST PAD FOR SUMTER CO LANDFILL			
DATE	SCALE	FILE	JOB NO.
9-9-88	NONE	C-103	C-103
DESIGN	DRAWN	CHECKED	SHEET
PB	JAH	PB	5 OF 9