

From: [Butler, Linda](#)
To: ["John Arnold, P.E. \(john.phillip.arnold@gmail.com\)"; Chisolm, Jack; Bejnar, Tor; Solid Waste Financial Coordinator; Tedder, Richard; Pelz, Susan; Morgan, Steve; Commissioner Henry Wilson; Commissioner Jack Mariano; Commissioner Kathryn Starkey; Commissioner Pat Mulieri; Commissioner Ted Schrader; County Administrator John Gallagher; Pasco County Commissioners; Representative Mike Fasano; Representative Peter Nehr; Representative Richard Corcoran; Representative Will Weatherford; Senator Wilson Simpson](#)
Bcc: [SWD_Clerical](#)
Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Thursday, June 13, 2013 2:21:00 PM
Attachments: [Intent to Issue 177982-019-SCT3 & 177982-020-SOT3 \(87895\).pdf](#)

Attached is the official **Intent to Issue** documents for the above-subject project. This is the only copy you will receive, unless you request otherwise. Acrobat Reader 6.0 or greater is required to read the documents and is available for downloading at: <http://www.adobe.com/products/acrobat/readstep.html>. *The documents are being mailed today to Mr. Dominic Iafrate, Angelo's Aggregate Materials, Ltd., as there is no known email address for him.*

Please open and review the documents as soon as possible, and verify that they are accessible. Please send a "reply" message verifying receipt of the documents.

OCULUS Information:

Catalog: Solid Waste

Profile: Permit Authorization

County: Pasco

Facility ID: 87895

Document Type: Intent to Issue/Deny Related

Facility Type(s): Class III LF

Document Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III LF Intent & Draft Permits

The Southwest District Waste Management Program is issuing electronic documents for permits, notices, and other correspondence in lieu of hard copies through the United States Postal Service, to provide greater service to the applicant and the regulated community. You may access the attached documents and others in the Department's OCULUS document management system by clicking on the link <http://dwmedms.dep.state.fl.us/Oculus/servlet/login> and using the "Public OCULUS Log-in" button. Under the search feature, you may look through various documents, including permitting, compliance, fiscal, cleanup, and enforcement documents.

Documents addressed in this email may require immediate action within a specified time frame. Please advise this office of any changes to your email address. If you have any questions concerning the content of the attached documents, please contact the FDEP Engineering Specialist IV Steve Morgan at (813) 632-7600, ext. 329, or steve.morgan@dep.state.fl.us

Sincerely,

*Linda Butler, Administrative Secretary
FDEP - Southwest District Permitting
13051 North Telecom Parkway*

Temple Terrace, FL 33637-0926

(813) 632-7600, Ext 433

email: linda.butler@dep.state.fl.us



Florida Department of Environmental Protection

Southwest District
13051 North Telecom Parkway
Temple Terrace, Florida 33637-0926
Telephone: 813-632-7600

Rick Scott
Governor

Herschel T. Vinyard Jr.
Secretary

June 13, 2013

In the matter of an
Application for Permit by:

Permit Nos. 177982-019-SC/T3
177982-020-SO/T3
Pasco County
WACS ID #87895

Angelo's Aggregate Materials, Ltd.
Mr. Dominic Iafrate, VP
41111 Enterprise Road,
Dade City, Florida 33525

INTENT TO ISSUE

The Department of Environmental Protection hereby gives notice of its Intent to Issue permits (copies attached) for the proposed project as detailed in the application specified above, for the reasons stated below. The applicant, [Angelo's Aggregate Material, Ltd.](#), applied on [March 26, 2012](#) to the Department of Environmental Protection for renewal of existing permits to construct and operate [a Class III landfill and related appurtanances known as the Enterprise Class III Landfill at 41111 Enterprise Road, Dade City, Pasco County, Florida.](#)

The Department has permitting jurisdiction under 403.707 and 403.861, Florida Statutes, and Rules 62-4, and 62-701, Florida Administrative Code (F.A.C.). The project is not exempt from permitting procedures. The Department has determined that permits are required for the proposed work.

The Department intends to issue these permits based on its belief that reasonable assurances have been provided to indicate that the

proposed project will not adversely impact water quality and the proposed project will comply with appropriate provisions of Chapters 62-4, 62-301, 62-330, 62-520, 62-522, and 62-701, F.A.C., subject to the specific conditions attached in the permit. Pursuant to Section 403.815, Florida Statutes and Rule 62-110.106, F.A.C., **you (the applicant) are required to publish at your own expense the enclosed Notice of Proposed Agency Action on Permit Application.** The notice must be published one time only within thirty (30) days of receipt of this intent in the legal ad section of a newspaper of general circulation in the area affected. Proof of publication must be provided to the Department **within seven (7) days** of publication of the notice. Failure to publish the notice and provide proof of publication within the allotted time may result in the denial of the permit. The Department will issue the permits with the attached conditions unless petition for administrative proceeding (hearing) is filed pursuant to the provisions of Section 120.57, Florida Statutes.

The Department's proposed agency action shall become final unless a timely petition for an administrative hearing is filed under Sections 120.569 and 120.57, Florida Statutes (F.S.), before the deadline for filing a petition. The procedures for petitioning for a hearing are set forth below.

A person whose substantial interests are affected by the Department's proposed permitting decision may petition for an administrative proceeding (hearing) under Sections 120.569 and 120.57, F.S. The petition must contain the information set forth below and must be filed (received) in the Office of General Counsel of the

Department at 3900 Commonwealth Boulevard, Mail Station 35, Tallahassee, Florida 32399-3000.

Petitions by the applicant or any of the parties listed below must be filed within 14 days of receipt of this written notice. Petitions filed by other persons must be filed within 14 days of publication of the notice or receipt of the written notice, whichever occurs first. Under Section 120.60(3), F.S., however, any person who asked the Department for notice of agency action may file a petition within fourteen days of receipt of such notice, regardless of the date of publication. The petitioner shall mail a copy of the petition to the applicant at the address indicated above at the time of filing. The failure of any person to file a petition within the appropriate time period shall constitute a waiver of that person's right to request an administrative determination (hearing) under Sections 120.569 and 120.57, F.S., or to intervene in this proceeding and participate as a party to it. Any subsequent intervention (in a proceeding initiated by another party) will be only at the discretion of the presiding officer upon the filing of a motion in compliance with Rule 28-106.205, F.A.C.

A petition that disputes the material facts on which the Department's action is based must contain the following information:

(a) The name and address of each agency affected and each agency's file or identification number, if known;

(b) The name, address, and telephone number of the petitioner; the name, address, and telephone number of the petitioner's representative, if any, which shall be the address for service purposes during the course of the proceeding; and an explanation of how the petitioner's substantial interests will be affected by the agency determination;

(c) A statement of when and how the petitioner received notice of the agency decision;

(d) A statement of all disputed issues of material fact. If there are none, the petition must so indicate;

(e) A concise statement of the ultimate facts alleged, including the specific facts the petitioner contends warrant reversal or modification of the agency's proposed action;

(f) A statement of the specific rules or statutes the petitioner contends require reversal or modification of the agency's proposed action, including an explanation of how the alleged facts relate to the specific rules or statutes; and

(g) A statement of the relief sought by the petitioner, stating precisely the action petitioner wishes the agency to take with respect to the agency's proposed action.

A petition that does not dispute the material facts on which the Department's action is based shall state that no such facts are in dispute and otherwise shall contain the same information as set forth above, as required by Rule 28-106.301, F.A.C.

Because the administrative hearing process is designed to formulate final agency action, the filing of a petition means that the Department's final action may be different from the position taken by it in this notice. Persons whose substantial interests will be affected by any such final decision of the Department have the right to petition to become a party to the proceeding, in accordance with the requirements set forth above.

In accordance with Section 120.573, F.S., the Department advises that mediation is not available in this case under the provisions of that statute. This does not prevent any interested parties from agreeing to other forms of alternate dispute resolution.

Any party to this order has the right to seek judicial review of it under Section 120.68, F.S., by filing a notice of appeal under Rule 9.110, Florida Rules of Appellate Procedure, with the clerk of the Department in the Office of General Counsel, Mail Station 35, 3900 Commonwealth Boulevard, Tallahassee, Florida 32399-3000, and by filing a copy of the notice of appeal accompanied by the applicable filing fees with the appropriate district court of appeal. The notice of appeal must be filed within thirty days after this order is filed with the clerk of the Department.

Executed in Hillsborough County, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL PROTECTION



Jeffrey S. Greenwell
Waste Permitting Administrator

JG/sgm

Attachments

Pasco County Board of County Commissioners

Pasco County Notification List

John Arnold, P.E., john.phillip.arnold@gmail.com

Jack Chisolm, OGC Tallahassee (email)

Tor Bejnar, FDEP Tallahassee solid.waste.financial.coordinator@dep.state.fl.us

Richard Tedder, P.E., FDEP Tallahassee (email)

Susan Pelz, P.E., CAP Section, FDEP SWD (email)

CERTIFICATE OF SERVICE

This undersigned duly designated deputy clerk hereby certifies that this **INTENT to ISSUE** was transmitted electronically to the listed persons before the close of business on June 13, 2013.

FILING AND ACKNOWLEDGMENT FILED,
on this date, pursuant to
Section 120.52(11), Florida
Statutes, with the designated
Department Clerk, receipt of which
is hereby acknowledged.

 June 13, 2013
(Clerk) (Date)

State of Florida
Department of Environmental Protection
Notice of Proposed Agency Action on Permit Application

The Department gives notice of its intent to issue a permit to Angelo's Aggregate Material, Ltd., applied on March 26, 2012 to the Department of Environmental Protection for renewal of existing permits to construct and operate a Class III landfill and related appurtenances known as the Enterprise Class III Landfill at 41111 Enterprise Road, Dade City, Pasco County, Florida.

Persons whose substantial interests are affected by the Department's proposed permitting decision may petition for an administrative proceeding (hearing) in accordance with Section 120.57, Florida Statutes. The petition must contain the information set forth below, and must be filed (received) in the Office of General Counsel of the Department at 3900 Commonwealth Blvd., MS#35, Tallahassee, Florida 32399-3000, within fourteen (14) days of publication of this notice. Failure to file a request for hearing within this time period shall constitute a waiver any right such person may have to request an administrative determination (hearing) under Section 120.57, Florida Statutes.

The petition shall contain the following information:

- (a) The name, address, and telephone number of each petitioner, the applicant's name and address, the Department Permit File Number and the county in which the project is proposed;
- (b) A statement of how and when each petitioner received notice of Department's action, or proposed action;
- (c) A statement of how each petitioner's substantial interests are affected by the Department's action or proposed action;
- (d) A statement of the material facts disputed by Petitioner, if any;
- (e) A statement of facts which petitioner contends warrant reversal or modification of the Department's action or proposed action;
- (f) A statement of which rules or statutes petitioner contends require reversal or modification of the Department's action or proposed action; and
- (g) A statement of the relief sought by petitioner, stating precisely the action petitioner wants the Department to take with respect to the Department's action or proposed action.

Because the administrative hearing process is designed to formulate final agency action, the filing of a petition means that the Department's final action may be different from the position taken by it in this notice of intent. Persons whose substantial interests will be affected by any such final decision of the Department on the application have the right to petition to become a party to the

proceeding, in accordance with the requirements set forth above. Mediation is not available in this proceeding.

Failure to petition within the allowed time frame constitutes a waiver of any right such person has to request a hearing under Section 120.57, Florida Statutes, and to participate as a party to this proceeding. Any subsequent intervention will only be at the approval of the presiding officer upon motion filed pursuant to Rules 62-110.106, 28-106.201, and 28-106.301 F.A.C.

The application is available for public inspection during normal business hours, 8:00 a.m. to 5:00 p.m., Monday through Friday, except legal holidays, at [13051 N. Telecom Parkway, Temple Terrace, Fl. 33637-0926](#).



Florida Department of Environmental Protection

Southwest District
13051 North Telecom Parkway
Temple Terrace, Florida 33637-0926
Telephone: 813-632-7600

Rick Scott
Governor

Herschel T. Vinyard Jr.
Secretary

Permit Issued to:

Angelo's Aggregate Materials, LTD
Post Office Box 1493
Largo, Florida 33779
(813) 477-1719

WACS Facility ID No.: 87895
Facility Name: Enterprise Class III Landfill
41111 Enterprise Road
Dade City, Florida 33525

Contact Person:

John Arnold, P.E., Engineer
Post Office Box 1493
Largo, Florida 33779
John.phillip.arnold@gmail.com
(813) 477-1719

Solid Waste Construction Renewal Permit – Class III Landfill

Permit No.: 177982-019-SC/T3
Replaces Permit No.: 177982-008-SC/T3

Permit Issued: **June XX, 2013**
Permit Renewal Application Due Date: **(61 days prior to expiration date)**
Permit Expires: **June XX, 2018**

Permitting Authority

Florida Department of Environmental Protection
Southwest District Office
13051 N. Telecom Parkway
Temple Terrace, Florida 33637
Phone: (813)632-7600
Fax: (813)632-7664

SECTION 1 - SUMMARY INFORMATION

A. Authorization

The permittee is hereby authorized to construct the facility described below in accordance with the specific and general conditions of this permit and any documents attached to this permit or specifically referenced in this permit and made a part of this permit.

This solid waste construction permit is issued under the provisions of Chapter 403, Florida Statutes, Florida Administrative Code Chapters 62-4 and 62-701.

This permit does not relieve the permittee from complying with any other appropriate local zoning or land use ordinances or with any other laws, rules or ordinances. Receipt of any permits from the Department does not relieve the applicant from obtaining other federal, state, and local permits and/or modifications required by law, including those from other Sections within the Department or of the Water Management District.

B. Facility Location

The facility location is latitude 28° 19' 53" Latitude and Longitude 82° 08' 06" and the physical address is 41111 Enterprise Road, Dade City, Pasco County, Florida.

C. Facility Description

This facility is classified as a **Class III Landfill and related facilities**, and shall be constructed in accordance with all applicable requirements of Chapters 62-4, 62-302, 62-330, 62-520, 62-522 and 62-701, Florida Administrative Code. This permit authorizes construction of Cell 6B and Cell 7 of the Enterprise Class III landfill. The primary design features of the landfill is described in the "General Information" table provided in [APPENDIX 4](#).

D. Appendices Made Part of This Permit

APPENDIX 1 - General Conditions

APPENDIX 2 - Approved Application Documents

APPENDIX 3 - Project Specific Closure Construction Conditions

APPENDIX 4 - General Information

E. Attachments for Informational Purposes Only

ATTACHMENT 1 - Time Sensitive Action Chart

If any of the time deadlines in the Time Sensitive Action Chart are inconsistent with the time deadlines in the permit conditions, the time deadline in the permit condition shall be followed.

ATTACHMENT 2 - Facility Permit History

SECTION 2 - SPECIFIC CONDITIONS

A. Administrative Requirements

1. Documents Part of This Permit. The permit application **as revised in final form replaced or amended** in response to the Department's Request(s) for Additional Information are contained in the Department's files and are made a part of this permit. Those documents that make up the complete permit application are listed in [APPENDIX 2. \[APP-2\]](#)
2. Permit Modification. Any change to construction, operation, monitoring, or closure requirements of this permit may require a modification to this permit, in accordance with the provisions of Rule 62-701.320(4), F.A.C.
3. Permit Renewal. In order to ensure uninterrupted construction of this facility, a timely and sufficient permit renewal application must be submitted to the Department in accordance with Rule 62-701.320(10), F.A.C. A permit application submitted at least 61 days prior to the expiration of this permit is considered timely and sufficient.
4. Transfer of Permit or Name Change. In accordance with Rule 62-701.320(11), F.A.C., the Department must be notified by submitting Form 62-701.900(8) within 30 days: (a) of any sale or conveyance of the facility; (b) if a new or different person takes ownership or control of the facility; or (c) if the facility name or permittee's legal name is changed.
5. Air Construction Permit Requirements
 - a. The landfill owner or operator is not required to obtain an air construction permit, unless landfill construction or any modification is subject to the prevention of significant deterioration (PSD) requirements of Chapter 62-212, F.A.C. A landfill for which construction or modification is subject to PSD requirements must make application to the Bureau of Air Regulation, Department of Environmental Protection, Mail Station 5505, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400, for an air construction permit and must obtain such permit prior to beginning any construction or modification.
 - b. The landfill owner or operator is not required to obtain an air operating permit, unless the landfill is required to obtain a Title V Air Operating Permit (Title V Permit) pursuant to Section 403.0872, F.S. A landfill is required to obtain a Title V Permit if the landfill (or the total facility, if the landfill is contiguous to or part of a larger facility) has the potential to emit 10 tons per year (TPY) or more of any hazardous air pollutant, 25 TPY or more of any combination of hazardous air pollutants, or 100 TPY or more of any other regulated air pollutant. A landfill is also required to obtain a Title V Permit if the maximum design capacity, as defined in 40 CFR 60, Subpart WWW, is equal to or greater than 2.5 million Megagrams or 2.5 million cubic meters. Title V Permits must be applied for in accordance with the timing and content requirements of Rule 62-204.800, F.A.C., and Chapter 62-213, F.A.C. Title V applications shall be submitted the Southwest District Air Program Administrator at 13051 N. Telecom Parkway, Temple Terrace, Florida 33637-0926.

A. Administrative Requirements (cont.)

- c. The Permittee is required to comply with the requirements of 40 CFR 60, Subpart WWW and CC as adopted by reference in Rule 62-204.800, F.A.C. The Permittee may have to submit to the Division of Air Resource Management, Department of Environmental Protection, Mail Station 5500, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400, any amended design capacity report and any Non-Methane Organic Compound (NMOC) emission rate report, as applicable, pursuant to 40 CFR 6-.757(a)(3) and (b).

B. Construction Requirements

1. Construction Authorized. This Permit is valid for construction of Cell 6B and Cell 7 of the Enterprise Class III Landfill and related appurtenances, only. Construction of future Cells 9 through 14 and Cell 16 is not authorized by this permit.
2. General Construction Requirements. All construction shall be done in accordance with the approved design, drawings, CQA plan, and specifications and the project specific conditions provided in [APPENDIX 3](#). The Department shall be notified before any changes, other than minor deviations, to the approved design are implemented in order to determine whether a permit modification is required.
3. Certification of Construction Completion. Upon completion of construction, the engineer of record shall certify to the Department in accordance with Rule 62-701.320(9)(b), F.A.C., that the permitted construction is complete and was done in substantial conformance with the approved construction plans except where minor deviations were necessary. All deviations shall be described in detail and the reasons therefore enumerated. The following documents shall be submitted along with the Certification:
 - a. The final report and record drawings showing that the liner system has been installed in substantial conformance with the plans and specifications for the liner system. The record drawings must include the results of the surveys of the base grade and top of clay grade slopes, and the location of all occurrences of limerock.
 - b. Results of testing of soil components of the liner system.
 - c. Revised closing and long-term care estimates for Cell 7 of the Class III facility in accordance with Rule 62-701.630(3) & (7), F.A.C.
 - d. Construction details for ground water wells associated with Cell 7 as required by [APPENDIX 3, Conditions #3, #5.b., and #5.d.](#) of Operation Permit #177982-020-SO/T3; results of ground water "initial sampling event" for ground water wells associated with Cell 7 as required by [APPENDIX 3, Condition #4.b.](#) of Permit #177982-020-SO/T3.
4. Construction Quality Assurance. The Construction Quality Assurance (CQA) Plan submitted with the permit application shall be followed for preparing the subgrade and installing and testing the liner system and related components. The CQA engineer or the engineer's designee shall be on-site at all times during construction of the liner system to monitor the construction activities including preparation of the subbase, placement of the liner components.

B. Construction Requirements (cont)

5. Approval of Certification. The permittee shall not begin using Cell 6B or Cell 7 at the facility until one of the following has occurred: (1) the Department has stated in writing that it has no objection to the certification of construction completion; or (2) at least 30 days have passed since the certification was submitted and the Department has not responded in writing to the certification.

C. Operation Requirements

1. General Operating Requirements. Operation of the Enterprise Class III Landfill is not authorized under this permit. The Permittee shall operate the landfill in accordance with Operation Permit #177982-020-SO/T3, or its successors.
2. Contingency Plan and Notification of Emergencies. The Permittee shall notify the Department in accordance with the approved Contingency Plan. Notification shall be made to the DEP's Southwest District Office Compliance Assistance Program at (813) 632-7600 or SWD_Waste@dep.state.fl.us.
- 3.

D. Water Quality Monitoring Requirements

4. Water Quality Monitoring Plan. The Water Quality Monitoring Plan for this permit is included in APPENDIX 3 of Operation Permit #177982-020-SO/T3, or its successors.

E. Gas Management System Requirements

1. Landfill Gas Management Requirements. The landfill gas management requirements for this permit are included in [Specific Condition #2.E.](#), of Operations Permit #177982-020-SO/T3.

F. Financial Assurance and Cost Estimates

1. Financial Assurance Mechanism. The permittee may not receive waste for disposal or storage in any disposal unit for which financial assurance has not been approved. Proof that the financial mechanisms are established and funded in accordance with Rule 62-701.630, F.A.C. shall be submitted to the Department at least sixty (60) days prior to the planned acceptance of solid waste in any disposal unit. When established, the permittee shall maintain, in good standing, the financial assurance mechanisms. Supporting documentation and evidence of increases associated with cost estimate increases shall be submitted within the time frames specified in Rule 62-701.630, F.A.C.

All submittals in response to this specific condition shall be sent to:

Florida Department of Environmental Protection
Financial Coordinator - Solid Waste Section
2600 Blair Stone Road, MS 4565
Tallahassee, Florida 32399-2400
Solid.Waste.Financial.Coordinator@dep.state.fl.us.

2. Cost Estimates.
 - a. The permittee shall submit closure cost estimates, including annual adjustments for inflation, in accordance with the requirements of Rule 62-701.630(3) and (4), F.A.C., and 40 CFR Part 264.142(a) and .144(a) using Form 62-701.900(28).
 - b. An owner or operator using an escrow account shall submit the annual inflation adjusted estimate(s) between July 1 and September 1. An owner or operator using a letter of credit, guarantee bond, performance bond, financial test, corporate guarantee, trust fund or insurance shall submit the inflation adjusted cost estimate(s) between January 1 and March 1.
 - c. A cost estimate covering disposal units not previously covered by financial assurance mechanisms must be submitted prior to submitting financial assurance for such disposal units.
 - d. All submittals in response to this specific condition shall be sent to the District Office and a copy to the address identified in Specific Condition F.1.

G. Closure Requirements

1. Closure Permit Requirements. Closure of the Enterprise Class III Landfill is not authorized under this permit. Prior to initiating closure of a solid waste disposal unit, or part of a solid waste disposal unit, the Permittee must receive authorization from the Department in one of the following manners. The Permittee may submit an application to the Department for a closure permit on Form 62-701.900(1), which application shall include a closure plan. If the landfill is operating under a Department permit, the Permittee may request a modification of the permit to address substantive changes in the closure plan, or the Permittee may demonstrate that the closure plan in the existing operation permit includes sufficient detail to provide reasonable assurance of compliance with the provisions for closure. The application or request for modification shall include an updated closure plan which is made up of the following:
 - a. A closure design plan;
 - b. A closure operation plan;
 - c. A plan for long-term care; and,
 - d. A demonstration that proof of financial assurance for long-term care will be provided.
2. Closure Design. All closure construction shall be done in accordance with an approved closure design plan. The Department shall be notified before any changes, other than minor deviations, to the approved closure design are implemented in order to determine whether a permit modification is required.
3. Closure Operation Plan. All closure shall be done in accordance with an approved closure operation plan.
4. Certification of closure construction completion. After closure construction has been completed, the engineer of record shall certify to the Department on Form 62-701.900(2) that the closure is complete and that it was done in accordance with the plans submitted to the Department except where minor deviation was necessary. All deviations shall be described in detail and the reasons therefore enumerated.
5. List of Closed Units Not in Long-Term Care. No cells at the Enterprise Class III landfill have been closed as of the issuance date of this permit.

H. Long-Term Care Requirements

1. No portion of the Enterprise Class III Landfill is closed and in the long-term period for the facility.

Executed in Hillsborough County, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL PROTECTION

Jeffry S. Greenwell
Waste Permitting Administrator
Southwest District

FILED, on this date, pursuant to Section 120.52, F.S. with the designated Department Clerk, receipt of which is hereby acknowledged.

Clerk

Date

APPENDIX 1 - General Conditions

1. The terms, conditions, requirements, limitations and restrictions set forth in this permit, are "permit conditions" and are binding and enforceable pursuant to Sections 403.141, 403.161, 403.727, or 403.861, Florida Statutes. The permittee is placed on notice that the Department will review this permit periodically and may initiate enforcement action for any violation of these conditions.
2. This permit is valid only for the specific processes and operations applied for and indicated in the approved drawings or exhibits. Any unauthorized deviation from the approved drawings, exhibits, specifications, or conditions of this permit may constitute grounds for revocation and enforcement action by the Department.
3. As provided in subsections 403.087(6) and 403.722(5), F.S., the issuance of this permit does not convey any vested rights or any exclusive privileges. Neither does it authorize any injury to public or private property or any invasion of rights, nor any infringement of federal, State, or local laws or regulations. This permit is not a waiver of or approval of any other Department permit that may be required for other aspects of the total project which are not addressed in this permit.
4. This permit conveys no title to land or water, does not constitute State recognition or acknowledgment of title, and does not constitute authority for the use of submerged lands unless herein provided and the necessary title or leasehold interests have been obtained from the State. Only the Trustees of the Internal Improvement Trust Fund may express State opinion as to title.
5. This permit does not relieve the permittee from liability for harm or injury to human health or welfare, animal, or plant life, or property caused by the construction or operation of this permitted source, or from penalties therefore; nor does it allow the permittee to cause pollution in contravention of Florida Statutes and Department rules, unless specifically authorized by an order from the Department.
6. The permittee shall properly operate and maintain the facility and systems of treatment and control (and related appurtenances) that are installed and used by the permittee to achieve compliance with the conditions of this permit, are required by Department rules. This provision includes the operation of backup or auxiliary facilities or similar systems when necessary to achieve compliance with the conditions of the permit and when required by Department rules.

GENERAL CONDITIONS: (cont.)

7. The permittee, by accepting this permit, specifically agrees to allow authorized Department personnel, upon presentation of credentials or other documents as may be required by law and at reasonable times, access to the premises where the permitted activity is located or conducted to:

- (a) Have access to and copy any records that must be kept under conditions of the permit;
- (b) Inspect the facility, equipment, practices, or operations regulated or required under this permit; and
- (c) Sample or monitor any substances or parameters at any location reasonably necessary to assure compliance with this permit or Department rules.

Reasonable time may depend on the nature of the concern being investigated.

8. If, for any reason, the permittee does not comply with or will be unable to comply with any condition or limitation specified in this permit, the permittee shall immediately provide the Department with the following information:

- (a) A description of and cause of noncompliance; and
- (b) The period of noncompliance, including dates and times; or, if not corrected, the anticipated time the noncompliance is expected to continue, and steps being taken to reduce, eliminate, and prevent recurrence of the noncompliance.

The permittee shall be responsible for any and all damages which may result and may be subject to enforcement action by the Department for penalties or for revocation of this permit.

9. In accepting this permit, the permittee understands and agrees that all records, notes, monitoring data and other information relating to the construction or operation of this permitted source which are submitted to the Department may be used by the Department as evidence in any enforcement case involving the permitted source arising under the Florida Statutes or Department rules, except where such use is prescribed by Sections 403.111 and 403.73, F.S. Such evidence shall only be used to the extent it is consistent with the Florida Rules of Civil Procedure and appropriate evidentiary rules.
10. The permittee agrees to comply with changes in Department rules and Florida Statutes after a reasonable time for compliance; provided, however, the permittee does not waive any other rights granted by Florida Statutes or Department rules.
11. This permit is transferable only upon Department approval in accordance with Rule 62-4.120 and 62-730.300, Florida Administrative Code, as applicable. The permittee shall be liable for any non-compliance of the permitted activity until the transfer is approved by the Department.

GENERAL CONDITIONS: (cont.)

12. This permit or a copy thereof shall be kept at the work site of the permitted activity.
13. This permit also constitutes:
 - (a) Determination of Best Available Control Technology (BACT)
 - (b) Determination of Prevention of Significant Deterioration (PSD)
 - (c) Certification of compliance with State Water Quality Standards (Section 401, PL 92-500)
 - (d) Compliance with New Source Performance Standards
14. The permittee shall comply with the following:
 - (a) Upon request, the permittee shall furnish all records and plans required under Department rules. During enforcement actions, the retention period for all records will be extended automatically unless otherwise stipulated by the Department.
 - (b) The permittee shall hold at the facility or other location designated by this permit records of all monitoring information (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) required by the permit, copies of all reports required by this permit, and records of all data used to complete the application for this permit. These materials shall be retained at least three years from the date of the sample, measurement, report, or application unless otherwise specified by Department rule.
 - (c) Records of monitoring information shall include:
 1. the date, exact place, and time of sampling or measurements;
 2. the person responsible for performing the sampling or measurements;
 3. the dates analyses were performed;
 4. the person responsible for performing the analyses;
 5. the analytical techniques or methods used;
 6. the results of such analyses.
15. When requested by the Department, the permittee shall within a reasonable time furnish any information required by law which is needed to determine compliance with the permit. If the permittee becomes aware the relevant facts were not submitted or were incorrect in the permit application or in any report to the Department, such facts or information shall be corrected promptly.

APPENDIX 2 - Approved Application Documents

1. Enterprise Class III Landfill, Pasco County Florida, Operations Permit Renewal Application, (3-ring binder and plan set) dated March 23, 2012 (received March 26, 2012), prepared by Kelner Engineering, as revised, replaced or amended (information inserted into original) received, March 20, 2013, April 17, 2013, and April 18, 2013). This information includes, but is not limited to:
 - a. Landfill Engineering Report [Section 3], revised March 2013 (rcvd March 20, 2013),
 - b. 11"x17" Plan Set titled Angelo's Aggregate Materials Enterprise Recycling and Disposal Facility 2012 Permit Renewal Application (18 Sheets) {Section 4}, signed and sealed dated March 18, 2013.
 - c. Groundwater Monitoring Plan [Section 5], dated March 2013 (rcvd March 20, 2013), prepared by Locklear & Associates, as revised, replaced or amended by information received April 17, 2013, including but not limited to the following:
 - 1) Figure 2 [Proposed Surficial Aquifer Monitor Well Detail], revised April 2013,
 - 2) Figure 3 [Proposed Floridan Aquifer Monitor Well Detail], revised April 2013.

APPENDIX 3 – Project Specific Construction Conditions

1. Limerock Encountered During Site Mining or Cell Excavation. If limerock is encountered during site mining operations with 10 ft of the design cell clay layer elevation or during cell construction, the vertical and lateral extent of the limerock shall be investigated and the limerock area over-excavated and backfilled in accordance with the procedures in Section 3.7 of the Engineering Report.
2. Soil Liner Installation.
 - a. Each cell shall be over-excavated to approximately 3 feet below the approved cell bottom grades shown on the permit drawings [ref. APP- 2, Para. 1.b, Sheets C-5 & C-7]. A minimum thickness of 3 feet of clayey material, shall be compacted in the bottom and perimeter slopes of each cell. Thickness tests of the clay liner shall be taken at a minimum frequency of two tests per acre per lift [ref. APP-2, Para. 1.a, §3.15]. The clayey material shall have a maximum hydraulic conductivity of 1×10^{-8} cm/sec [ref. APP-2, Para. 1.a, §3.7, 3.10.2]. Hydraulic conductivity tests for the low permeability soil layer shall be conducted in accordance with ASTM D5084.
 - b. The low permeability soil shall be free from organics, roots, rubbish, debris or rocks greater than $\frac{1}{4}$ inch in any dimension, sticks greater than $\frac{1}{4}$ inch in diameter, calcareous deposits or any other deleterious material.
 - c. Hydraulic conductivity and % fines tests shall be taken at a frequency of one per acre per lift [ref. APP-2, Para. 1.a, §3.15]. All hydraulic conductivity tests shall have a maximum value of 1×10^{-8} cm/sec. Locations which do not meet this requirement shall be reworked and retested to confirm that the area passes. Permeability test locations shall not be covered by subsequent lifts until passing hydraulic conductivity test results are received by the CQA representative.
5. Leachate collection and removal system. The facility does not have a leachate collection and removal system that meets the design criteria of Rule 62-701.400(4), F.A.C. The bottom clay liner is sloped toward the northeast corner of the site (future disposal Cells 14/16). The system is designed such that leachate that does not percolate through the 3 foot-thick clay liner will seep toward the northeast portion of the site and discharge into Cells 14 and 16, where it will be commingled with stormwater runoff. Cells 14/16 are clay-lined on the bottoms. In the event that groundwater monitoring in the vicinity of Cells 14 or 16 indicate impacts to groundwater in this area, the Permittee shall sample the stormwater/leachate stored in temporary pond/Cells 14/16 in accordance with APPENDIX 3, Condition #8.c. of Operation Permit #177982-020-SO/T3, or its successors.

APPENDIX 4 - General Information

General Information:	Class III Landfill
Disposal acres	Approx. 60.9 acres (Cells 1-7 and 15) [ref. APP-2, Para. 1.b., Sheet C-4]
Lowest bottom elevation of cells.	+80 ft. NGVD (Cell 15)
Top elevation at final buildout (including cover)	max. +175 feet NGVD [ref. APP-2, Para. 1.b., Sheet C-8]
Side slopes max.	3H:1V below elevation +125 ft. NGVD; 4H:1V between el. +125 ft. and +150 ft NGVD; 20H:1V between el. +150 ft. and +170 ft NGVD; 30H:1V above +170 ft NGVD [ref. APP-2, Para. 1.b., Sheet C-8]
Liner system	3 foot-thick clay (bottom only Cells 1-5, and 15; bottom & sides of Cells 6A, 6B, & 7), max. permeability= 1×10^{-8} cm/sec [ref. APP-2, Para. 1.a., §3.7.]
LCS drainage system	None
Design Life	11.4 years (Cells 1-7 and 15) [ref. APP-2, Para. 1.a., §3.8.3.]
Closure slopes	3H:1V below elevation +125 ft. NGVD; 4H:1V between el. +125 ft. and +150 ft NGVD; 20H:1V between el. +150 ft. and +170 ft NGVD; 30H:1V above +170 ft NGVD [ref. APP-2, Para. 1.b., Sheet C-8]

ATTACHMENT 1 - Time Sensitive Action Chart		
Specific Condition	Submittal Due Date	Required Item
Cover page	No later than 61 day prior to expiration date of permit.	Submit permit renewal application
F.2.b.	Annually, between January 1 st and March 1 st each year	Submit revised cost estimates
	Annually	Submit proof of funding

ATTACHMENT 2 - Facility Permit History

Replaces Permit No.: **177982-008-SC/T3, issued 05/31/2007**
Including Modification No.:
177982-017-SC/MM, dated 01/07/2010;

DRAFT



Florida Department of Environmental Protection

Southwest District
13051 North Telecom Parkway
Temple Terrace, Florida 33637-0926
Telephone: 813-632-7600

Rick Scott
Governor

Herschel T. Vinyard Jr.
Secretary

Permit Issued to:

Angelo's Aggregate Materials, LTD
Post Office Box 1493
Largo, Florida 33779
(813) 477-1719

WACS Facility ID No.: 87895
Facility Name: Enterprise Class III Landfill
41111 Enterprise Road
Dade City, Florida 33525

Contact Person:

John Arnold, P.E., Engineer
Post Office Box 1493
Largo, Florida 33779
John.phillip.arnold@gmail.com
(813) 477-1719

Solid Waste Operation Renewal Permit - Class III Landfill

Permit No.: 177982-020-SO/T3
Replaces Permit No.: 177982-007-SO/T3

Permit Issued: **June XX, 2013**
Permit Renewal Application Due Date: **(61 days prior to expiration date)**
Permit Expires: **June XX, 2018**

Permitting Authority

Florida Department of Environmental Protection
Southwest District Office
13051 N. Telecom Parkway
Temple Terrace, Florida 33637
Phone: (813)632-7600
Fax: (813)632-7664

SECTION 1 - SUMMARY INFORMATION

A. Authorization

The permittee is hereby authorized to operate the facility described below in accordance with the specific and general conditions of this permit and any documents attached to this permit or specifically referenced in this permit and made a part of this permit.

This solid waste operation permit is issued under the provisions of Chapter 403, Florida Statutes, Florida Administrative Code Chapters 62-4 and 62-701.

This permit does not relieve the permittee from complying with any other appropriate local zoning or land use ordinances or with any other laws, rules or ordinances. Receipt of any permits from the Department does not relieve the applicant from obtaining other federal, state, and local permits and/or modifications required by law, including those from other Sections within the Department or of the Water Management District.

B. Facility Location

The facility location is latitude 28° 19' 53" Latitude and Longitude 82° 08' 06" and the physical address is 41111 Enterprise Road, Dade City, Pasco County, Florida.

C. Facility Description

This facility is classified as a **Class III Landfill and related facilities**, and shall be operated in accordance with all applicable requirements of Chapters 62-4, 62-302, 62-330, 62-520, 62-522 and 62-701, Florida Administrative Code. This permit authorizes operation of Cells 1-7 and 15 of the Enterprise Class III Landfill. The primary design features of the landfill are described in the "General Information" table provided in [APPENDIX 4](#).

D. Appendices Made Part of This Permit

APPENDIX 1 - General Conditions

APPENDIX 2 - Approved Application Documents

APPENDIX 3 - Water Quality Monitoring Plan

APPENDIX 4 - General Information

E. Attachments for Informational Purposes Only

ATTACHMENT 1 - Time Sensitive Action Chart

If any of the time deadlines in the Time Sensitive Action Chart are inconsistent with the time deadlines in the permit conditions, the time deadline in the permit condition shall be followed.

ATTACHMENT 2 - Facility Permit History

SECTION 2 - SPECIFIC CONDITIONS

A. Administrative Requirements

1. Documents Part of This Permit. The permit application **as revised in final form replaced or amended** in response to the Department's Request(s) for Additional Information are contained in the Department's files and are made a part of this permit. Those documents that make up the complete permit application are listed in [APPENDIX 2. \[APP-2\]](#)
2. Permit Modification. Any change to construction, operation, monitoring, or closure requirements of this permit may require a modification to this permit, in accordance with the provisions of Rule 62-701.320(4), F.A.C.
3. Permit Renewal. In order to ensure uninterrupted operation of this facility, a timely and sufficient permit renewal application must be submitted to the Department in accordance with Rule 62-701.320(10), F.A.C. A permit application submitted at least 61 days prior to the expiration of this permit is considered timely and sufficient.
4. Transfer of Permit or Name Change. In accordance with Rule 62-701.320(11), F.A.C., the Department must be notified by submitting Form 62-701.900(8) within 30 days: (a) of any sale or conveyance of the facility; (b) if a new or different person takes ownership or control of the facility; or (c) if the facility name or permittee's legal name is changed.
5. Air Construction Permit Requirements
 - a. The landfill owner or operator is not required to obtain an air construction permit, unless landfill construction or any modification is subject to the prevention of significant deterioration (PSD) requirements of Chapter 62-212, F.A.C. A landfill for which construction or modification is subject to PSD requirements must make application to the Bureau of Air Regulation, Department of Environmental Protection, Mail Station 5505, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400, for an air construction permit and must obtain such permit prior to beginning any construction or modification.
 - b. The landfill owner or operator is not required to obtain an air operating permit, unless the landfill is required to obtain a Title V Air Operating Permit (Title V Permit) pursuant to Section 403.0872, F.S. A landfill is required to obtain a Title V Permit if the landfill (or the total facility, if the landfill is contiguous to or part of a larger facility) has the potential to emit 10 tons per year (TPY) or more of any hazardous air pollutant, 25 TPY or more of any combination of hazardous air pollutants, or 100 TPY or more of any other regulated air pollutant. A landfill is also required to obtain a Title V Permit if the maximum design capacity, as defined in 40 CFR 60, Subpart WWW, is equal to or greater than 2.5 million Megagrams or 2.5 million cubic meters. Title V Permits must be applied for in accordance with the timing and content requirements of Rule 62-204.800, F.A.C., and Chapter 62-213, F.A.C. Title V applications shall be submitted the Southwest District Air Program Administrator at 13051 N. Telecom Parkway, Temple Terrace, Florida 33637-0926.

A. Administrative Requirements (cont.)

- c. The Permittee is required to comply with the requirements of 40 CFR 60, Subpart WWW and CC as adopted by reference in Rule 62-204.800, F.A.C. The Permittee may have to submit to the Division of Air Resource Management, Department of Environmental Protection, Mail Station 5500, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400, any amended design capacity report and any Non-Methane Organic Compound (NMOC) emission rate report, as applicable, pursuant to 40 CFR 6-.757(a)(3) and (b).

B. Construction Requirements

1. Construction authorized. This Permit does not authorize any construction activities.
2. General Construction Requirements. All construction shall be done in accordance with the approved design, drawings, CQA plan, and specifications proved in Construction Permit #177982-019-SC/T3, or its successors. The Department shall be notified before any changes, other than minor deviations, to the approved design are implemented in order to determine whether a permit modification is required.

C. Operation Requirements

1. General Operating Requirements. The Permittee shall operate the landfill in accordance with the approved permit application documents as listed in APPENDIX 2 [APP-2]; such as the, Operation, Monitoring, and Closure Plans, Permit Drawings, and associated documents. The Department shall be notified before any changes, other than minor deviations, to the approved Operation Plan are implemented in order to determine whether a permit modification is required.
2. Operation Plan. A copy of the approved Operation Plan [ref. APP-2, Para.1.c.] , including the operating record as defined in Rule 62-701.500(3), F.A.C., shall be kept at the facility office and shall be accessible to landfill operators.
3. Authorized Waste Types. The facility is authorized to manage only the following waste types:
 - a. Waste types defined in Rule 62-701.200, F.A.C.:
 - 1) Class III waste [ref. Op. Plan, §5.4]
 - 2) Processed Tires [ref. Op. Plan, §5.4]
 - 3) Asbestos Containing Materials [ref. Op. Plan, §5.6]
 - 4) Yard Trash & Clean Wood [ref. Op. Plan, §5.8]
 - 5) Waste Tires [In accordance with Waste Tire Processing Facility Permit #303741-001-WT/02 or its successors]
 - b. Other Wastes Specifically Authorized:
 - 1) Incidental Recyclable Materials [ref. Op. Plan, §5.7]

C. Operation Requirements (cont.)

4. Unauthorized Waste Types. The facility is not authorized to accept, process, or dispose any waste types not listed in C.3. above and those listed in Section 5.4 of the facility Operations Plan. Any unauthorized waste inadvertently received by the facility shall be managed in accordance with the approved Operations Plan [\[Op. Plan, § 5.3\]](#). Weekly random load checking of incoming waste shall be conducted in accordance with Rule 62-701.500(6)(a), F.A.C. [\[ref. Op. Plan, §5.5\]](#).
5. Waste Management and Handling
 - a. Solid waste shall be formed into cells to construct horizontal lifts. The working face of the cell, and side grades above land surface, shall be at a slope no greater than three feet horizontal to one-foot vertical rise or as authorized by this permit in accordance with the approved operation plan [\[Op. Plan, § 8.1\]](#).
 - b. No solid waste shall be disposed of outside of the permitted footprint of the solid waste disposal units.
 - c. The sequence of waste filling shall be as specified in the approved Operation Plan and Sequencing Plans [\[APP-2, Para 1.a. & 1.b.\]](#).
6. Landfill Elevation. The final (maximum) elevation of the Class III Landfill, shall not exceed +175 feet NGVD feet as shown on [Sheet C-8 of the Permit Drawings \[APP-2, Para. 1.b.\]](#).
7. Initial Waste Placement. The first layer of waste placed above the liner system shall consist of wastes containing no large rigid objects that may damage the liner system.
8. Cover Requirements:
 - a. Initial Cover: Initial cover of weekly cover consisting of six inches of a compacted soil shall be applied at the end of each work week. The facility may also use a 50/50 soil/mulch mix as initial cover in accordance with Policy Memo #SWM-05-4, dated April 25, 2001. [\[ref. Op. Plan, § 8.1 & 9.0\]](#).
 - b. Intermediate Cover: Intermediate cover shall be applied and maintained in accordance with Rules 62-701.500(7)(a) and (f), F.A.C. Intermediate shall be applied to areas not expected to receive wastes within 180 days. Soil and mulch mixed in a 50/50 ratio may also be applied as intermediate cover [\[ref. Op. Plan, § 8.1\]](#).
9. Erosion Control: Erosion control measures shall be employed to correct any erosion which exposes waste or causes malfunction of the storm water management system. Such measures shall be implemented within three days of occurrence. If the erosion cannot be corrected within seven days of occurrence, the landfill operator shall notify the Department and propose a correction schedule [\[ref. Op. Plan, § 8.2\]](#).
10. Contingency Plan and Notification of Emergencies. The Permittee shall notify the Department in accordance with the approved Contingency Plan. Notification shall be made to the DEP's Southwest District Office Compliance Assistance Program at (813) 632-7600 or SWD_Waste@dep.state.fl.us.

C. Operation Requirements (cont.)

11. Housekeeping. The facility shall be operated to control dust (and other fugitive particulate), vectors, litter and objectionable odors. If objectionable odors are confirmed beyond the landfill property boundary, the owner or operator shall comply with the gas management requirement in Section 2, Part E and the facility Operations Plan [ref. [Op. Plan, § 10.1](#)].
12. Leachate Management. The facility does not have a leachate collection and removal system that meets the design criteria of Rule 62-701.400(4), F.A.C. The bottom clay liner is sloped toward the northeast corner of the site (future disposal Cells 14/16). The system is designed such that leachate that does not percolate through the 3 foot-thick clay liner will seep toward the northeast portion of the site and discharge into Cells 14 and 16, where it will be commingled with stormwater runoff. Cells 14/16 are clay-lined on the bottoms. In the event that groundwater monitoring in the vicinity of Cells 14 or 16 indicate impacts to groundwater in this area, the Permittee shall sample the stormwater/leachate stored in temporary pond/Cells 14/16 in accordance with [APPENDIX 3, Condition #8.c.](#) of Operation Permit #177982-020-SO/T3, or its successors.
13. Spotters and Operators. This facility shall have the minimum number of spotters present when waste is accepted as specified in the operation plan, to be located as specified in the operation plan [ref. [Op. Plan, §5.1 & 15.0](#)]. A trained operator shall be on duty at the facility at all times the facility is operating [ref. [Op. Plan, §15.0](#)]. Approved training courses can be found at the following web site: <http://www.treeo.ufl.edu/sw/>
14. Record Keeping Requirements.
 - a. Waste Quantity Records. Waste records shall be compiled monthly, and copies shall be provided to the Department no less than annually by [April 15th](#). This information shall be reported to the Department through the DEP Business Portal located at: <http://www.fldepportal.com/go>. [ref. [Op. Plan, §19.0](#)].
 - b. Estimate of Remaining Life. The permittee shall submit the annual estimate of the remaining life and capacity by [April 15th](#). [ref. [Op. Plan, §19.0](#)]. The report is required by Rule 62-701.500(13) (c), F.A.C. and must be submitted to the District Office at SWD_Waste@dep.state.fl.us and to:
Florida Department of Environmental Protection
Solid Waste Section, MS 4565
2600 Blair Stone Road
Tallahassee, Florida, 32399-2400

C. Operation Requirements (cont.)

15. Hazardous Waste. If any regulated hazardous wastes are discovered to be deposited at the facility, the facility operator shall promptly notify the Department, the person responsible for shipping the wastes to the facility, and the generator of the wastes, if known. The area where the wastes are deposited shall immediately be cordoned off from public access. If the generator or hauler cannot be identified, the facility operator shall assure the cleanup, transportation, and disposal of the waste at a permitted hazardous waste management facility. In the event that hazardous wastes are discovered they shall be managed in accordance with the procedures provided in facility Contingency Plan [APP-2, Para 1.d.].
16. Stormwater. Leachate shall not be discharged into the stormwater management system. Stormwater or other surface water which comes into contact with or mixes with the solid waste or leachate shall be considered leachate and is subject to the requirements of Rule 62-701.500(8), F.A.C.

D. Water Quality Monitoring Requirements

1. Water Quality Monitoring Plan. The Water Quality Monitoring Plan for this permit is included in APPENDIX 3.

E. Gas Management System Requirements

1. Construction Requirements. The gas management system constructed at the Enterprise Class III Landfill is described in §3.10 of the Landfill Engineering Report [ref. APPENDIX 2, Para. 1.a.]. The Department shall be notified before any changes, other than minor deviations, to the approved Gas Monitoring Plan are implemented in order to determine whether a permit modification is required.
 - a. One ambient monitoring point is specified for the Enterprise Class III Landfill at the following location:

<u>Ambient Monitoring Point</u>	<u>Location Description</u>
Scale House	Landfill Entrance
 - b. Existing soil monitoring probes are specified for the Enterprise Class III Landfill at the following locations as depicted on Figure 1 ["Groundwater Monitoring Network"], prepared by Locklear & Associates, received March 20, 2013 [presented in APPENDIX 3]:

<u>Probe Number</u>	<u>Location Description</u>	<u>Scheduling Notes</u>
GP-6	Along north boundary (perimeter)	Existing/currently monitored
GP-7	Near northeast corner (perimeter)	Existing/currently monitored
GP-8	Near northeast corner (perimeter)	Existing/currently monitored
GP-9R	Along east boundary (perimeter)	Existing/currently monitored
GP-10R	Along east boundary (perimeter)	Existing/currently monitored
GP-11	Near southeast corner (perimeter)	Existing/currently monitored
GP-12R	Near southeast corner (perimeter)	Existing/currently monitored
GP-13R	Along south boundary (perimeter)	Existing/currently monitored
GP-14	Along south boundary (perimeter)	Existing/currently monitored
GP-15	Near southwest corner (perimeter)	Existing/currently monitored

E. Gas Management System Requirements (cont.)

2. Certification of Construction Completion. After construction is completed the engineer of record shall certify to the Department in accordance with Rule 62-701.320(9)(b), F.A.C., that the permitted construction is complete and was performed in substantial conformance with the approved construction plans except where minor deviations were necessary. All deviations shall be described and the reasons therefore enumerated.
3. Operational Requirements. Gas controls shall be operated and maintained so that they function as designed.
4. Monitoring Requirements. Monitoring for methane gas at the above-listed ambient monitoring point and soil monitoring probes shall be performed quarterly to determine the effectiveness of the gas migration controls. The gas monitoring results shall be reported as a percent of the lower explosive limit (LEL), calibrated to methane. The report shall be submitted to the Department under separate cover no later than 15 days after the end of the period in which the monitoring occurred.
5. Gas Remediation Plan. The facility landfill gas management system shall be operated to prevent the concentration of combustible gases from exceeding 25% of the lower explosive limit in structures, excluding gas control or recovery components, and from exceeding the lower explosive limit at or beyond the property boundary (as measured in the above-listed perimeter soil monitoring probe locations). If either of these limits is exceeded then a gas remediation plan shall be designed and implemented in accordance with Rule 62-701.530(3)(a), F.A.C., including:
 - a. Immediately take all necessary steps to ensure protection of human health and notify the Department,
 - b. Within seven (7) days of detection, submit to the Department for approval a gas remediation plan for the gas releases. The plan shall describe the nature and extent of the problem and the proposed remedy. The remedy may include some or all of the gas management system design contained in Rule 62-701.530(1)(a), F.A.C.,
 - c. The remedy shall be completed within 60 days of detection unless otherwise approved by the Department.
6. Odor Remediation Plan. The facility shall be operated to control objectionable odors. If objectionable odors are confirmed beyond the property boundary then upon notification by the Department the permittee shall develop and implement an odor remediation plan in accordance with the requirements of Rule 62-701.530(3)(b), F.A.C.

F. Financial Assurance and Cost Estimates

1. Financial Assurance Mechanism. The permittee may not receive waste for disposal or storage in any disposal unit for which financial assurance has not been approved. Proof that the financial mechanisms are established and funded in accordance with Rule 62-701.630, F.A.C. shall be submitted to the Department at least sixty (60) days prior to the planned acceptance of solid waste in any disposal unit. When established, the permittee shall maintain, in good standing, the financial assurance mechanisms. Supporting documentation and evidence of increases associated with cost estimate increases shall be submitted within the time frames specified in Rule 62-701.630, F.A.C.

All submittals in response to this specific condition shall be sent to:

Florida Department of Environmental Protection
Financial Coordinator - Solid Waste Section
2600 Blair Stone Road, MS 4565
Tallahassee, Florida 32399-2400

Solid.Waste.Financial.Coordinator@dep.state.fl.us.

2. Cost Estimates.
 - a. The permittee shall submit closure cost estimates, including annual adjustments for inflation, in accordance with the requirements of Rule 62-701.630(3) and (4), F.A.C., and 40 CFR Part 264.142(a) and .144(a) using Form 62-701.900(28).
 - b. An owner or operator using an escrow account shall submit the annual inflation adjusted estimate(s) between July 1 and September 1. An owner or operator using a letter of credit, guarantee bond, performance bond, financial test, corporate guarantee, trust fund or insurance shall submit the inflation adjusted cost estimate(s) between January 1 and March 1.
 - c. A cost estimate covering disposal units not previously covered by financial assurance mechanisms must be submitted prior to submitting financial assurance for such disposal units.
 - d. All submittals in response to this specific condition shall be sent to the District Office at SWD_Waste@dep.state.fl.us and a copy to the address identified in Specific Condition F.1.

G. Closure Requirements

1. Closure Permit Requirements. Closure of the Enterprise Class III Landfill is not authorized under this permit. Prior to initiating closure of a solid waste disposal unit, or part of a solid waste disposal unit, the Permittee must receive authorization from the Department in one of the following manners. The Permittee may submit an application to the Department for a closure permit on Form 62-701.900(1), which application shall include a closure plan. If the landfill is operating under a Department permit, the Permittee may request a modification of the permit to address substantive changes in the closure plan, or the Permittee may demonstrate that the closure plan in the existing operation permit [ref. APP-2, Para 1, Sec. 7] includes sufficient detail to provide reasonable assurance of compliance with the provisions for closure. The application or request for modification shall include an updated closure plan which is made up of the following:
 - a. A closure design plan;
 - b. A closure operation plan;
 - c. A plan for long-term care; and,
 - d. A demonstration that proof of financial assurance for long-term care will be provided.
2. Closure Design. All closure construction shall be done in accordance with the approved closure design plan. The Department shall be notified before any changes, other than minor deviations, to the approved closure design are implemented in order to determine whether a permit modification is required.
3. Closure Operation Plan. All closure shall be done in accordance with the approved closure operation plan.
4. Certification of closure construction completion. After closure construction has been completed, the engineer of record shall certify to the Department on Form 62-701.900(2) that the closure is complete and that it was done in accordance with the plans submitted to the Department except where minor deviation was necessary. All deviations shall be described in detail and the reasons therefore enumerated.
5. List of Closed Units Not in Long-Term Care. No cells at the Enterprise Class III landfill have been closed as of the issuance date of this permit.

H. Long-Term Care Requirements

1. No portion of the Enterprise Class III Landfill is closed and in the long-term period for the facility.

Executed in Hillsborough County, Florida.

STATE OF FLORIDA DEPARTMENT
OF ENVIRONMENTAL PROTECTION

Jeffry S. Greenwell
Waste Permitting Administrator
Southwest District

FILED, on this date, pursuant to Section 120.52, F.S. with the designated Department Clerk, receipt of which is hereby acknowledged.

Clerk

Date

APPENDIX 1 - General Conditions

1. The terms, conditions, requirements, limitations and restrictions set forth in this permit, are "permit conditions" and are binding and enforceable pursuant to Sections 403.141, 403.161, 403.727, or 403.861, Florida Statutes. The permittee is placed on notice that the Department will review this permit periodically and may initiate enforcement action for any violation of these conditions.
2. This permit is valid only for the specific processes and operations applied for and indicated in the approved drawings or exhibits. Any unauthorized deviation from the approved drawings, exhibits, specifications, or conditions of this permit may constitute grounds for revocation and enforcement action by the Department.
3. As provided in subsections 403.087(6) and 403.722(5), F.S., the issuance of this permit does not convey any vested rights or any exclusive privileges. Neither does it authorize any injury to public or private property or any invasion of rights, nor any infringement of federal, State, or local laws or regulations. This permit is not a waiver of or approval of any other Department permit that may be required for other aspects of the total project which are not addressed in this permit.
4. This permit conveys no title to land or water, does not constitute State recognition or acknowledgment of title, and does not constitute authority for the use of submerged lands unless herein provided and the necessary title or leasehold interests have been obtained from the State. Only the Trustees of the Internal Improvement Trust Fund may express State opinion as to title.
5. This permit does not relieve the permittee from liability for harm or injury to human health or welfare, animal, or plant life, or property caused by the construction or operation of this permitted source, or from penalties therefore; nor does it allow the permittee to cause pollution in contravention of Florida Statutes and Department rules, unless specifically authorized by an order from the Department.
6. The permittee shall properly operate and maintain the facility and systems of treatment and control (and related appurtenances) that are installed and used by the permittee to achieve compliance with the conditions of this permit, are required by Department rules. This provision includes the operation of backup or auxiliary facilities or similar systems when necessary to achieve compliance with the conditions of the permit and when required by Department rules.

GENERAL CONDITIONS: (cont.)

7. The permittee, by accepting this permit, specifically agrees to allow authorized Department personnel, upon presentation of credentials or other documents as may be required by law and at reasonable times, access to the premises where the permitted activity is located or conducted to:

- (a) Have access to and copy any records that must be kept under conditions of the permit;
- (b) Inspect the facility, equipment, practices, or operations regulated or required under this permit; and
- (c) Sample or monitor any substances or parameters at any location reasonably necessary to assure compliance with this permit or Department rules.

Reasonable time may depend on the nature of the concern being investigated.

8. If, for any reason, the permittee does not comply with or will be unable to comply with any condition or limitation specified in this permit, the permittee shall immediately provide the Department with the following information:

- (a) A description of and cause of noncompliance; and
- (b) The period of noncompliance, including dates and times; or, if not corrected, the anticipated time the noncompliance is expected to continue, and steps being taken to reduce, eliminate, and prevent recurrence of the noncompliance.

The permittee shall be responsible for any and all damages which may result and may be subject to enforcement action by the Department for penalties or for revocation of this permit.

9. In accepting this permit, the permittee understands and agrees that all records, notes, monitoring data and other information relating to the construction or operation of this permitted source which are submitted to the Department may be used by the Department as evidence in any enforcement case involving the permitted source arising under the Florida Statutes or Department rules, except where such use is prescribed by Sections 403.111 and 403.73, F.S. Such evidence shall only be used to the extent it is consistent with the Florida Rules of Civil Procedure and appropriate evidentiary rules.
10. The permittee agrees to comply with changes in Department rules and Florida Statutes after a reasonable time for compliance; provided, however, the permittee does not waive any other rights granted by Florida Statutes or Department rules.
11. This permit is transferable only upon Department approval in accordance with Rule 62-4.120 and 62-730.300, Florida Administrative Code, as applicable. The permittee shall be liable for any non-compliance of the permitted activity until the transfer is approved by the Department.

GENERAL CONDITIONS: (cont.)

12. This permit or a copy thereof shall be kept at the work site of the permitted activity.
13. This permit also constitutes:
 - (a) Determination of Best Available Control Technology (BACT)
 - (b) Determination of Prevention of Significant Deterioration (PSD)
 - (c) Certification of compliance with State Water Quality Standards (Section 401, PL 92-500)
 - (d) Compliance with New Source Performance Standards
14. The permittee shall comply with the following:
 - (a) Upon request, the permittee shall furnish all records and plans required under Department rules. During enforcement actions, the retention period for all records will be extended automatically unless otherwise stipulated by the Department.
 - (b) The permittee shall hold at the facility or other location designated by this permit records of all monitoring information (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) required by the permit, copies of all reports required by this permit, and records of all data used to complete the application for this permit. These materials shall be retained at least three years from the date of the sample, measurement, report, or application unless otherwise specified by Department rule.
 - (c) Records of monitoring information shall include:
 1. the date, exact place, and time of sampling or measurements;
 2. the person responsible for performing the sampling or measurements;
 3. the dates analyses were performed;
 4. the person responsible for performing the analyses;
 5. the analytical techniques or methods used;
 6. the results of such analyses.
15. When requested by the Department, the permittee shall within a reasonable time furnish any information required by law which is needed to determine compliance with the permit. If the permittee becomes aware the relevant facts were not submitted or were incorrect in the permit application or in any report to the Department, such facts or information shall be corrected promptly.

APPENDIX 2 - Approved Application Documents

1. Enterprise Class III Landfill, Pasco County Florida, Operations Permit Renewal Application, (3-ring binder and plan set) dated March 23, 2012 (received March 26, 2012), prepared by Kelner Engineering, as revised, replaced or amended (information inserted into original) received March 20, 2013, April 17, 2013, and April 18, 2013). This information includes, but is not limited to:
 - a. Landfill Engineering Report [Section 3], revised March 2013 (rcvd March 20, 2013),
 - b. 11"x17" Plan Set titled Angelo's Aggregate Materials Enterprise Recycling and Disposal Facility 2012 Permit Renewal Application (18 Sheets) {Section 4}, signed and sealed dated March 18, 2013.
 - c. Operations Plan [Section 3, Appendix 3-A] [[ref. Op. Plan](#)] dated March 2013 (rcvd March 20, 2013),
 - d. Contingency Plan [Section 3, Appendix 3-B] dated March 2013 (rcvd March 20, 2013),
 - e. Groundwater Monitoring Plan [Section 5], dated March 2013 (rcvd March 20, 2013), prepared by Locklear & Associates, as revised, replaced or amended by information received April 17, 2013, including but not limited to the following:
 - 1) Figure 2 [Proposed Surficial Aquifer Monitor Well Detail], revised April 2013,
 - 2) Figure 3 [Proposed Floridan Aquifer Monitor Well Detail], revised April 2013.

APPENDIX 3 – Water Quality Monitoring Plan

1. Water Quality Monitoring Quality Assurance.

- a. All field work done in connection with the facility's Water Quality Monitoring Plan shall be conducted in accordance with the Standard Operating Procedures (SOPs) described in DEP-SOP-001/01 (March 31, 2008) [or as replaced by successor SOPs], as referenced in Rule 62-160.210(1), F.A.C. All laboratory analyses done in connection with the facility's Water Quality Monitoring Plan shall be conducted by firms that hold certificates from the Department of Health Environmental Laboratory Certification Program under Chapter 64E-1, F.A.C., as referenced in Rule 62-160.300(1), F.A.C. The SOPs utilized and the laboratory's list of certified test methods and analytes must specifically address the types of sampling and analytical work that are required by the permit and shall be implemented by all persons performing sample collection or analysis related to this permit. Alternate field procedures and laboratory methods may be used if approved according to the requirements of Rules 62-160.220 and 62-160.330, F.A.C., respectively.
- b. The field testing, sample collection and preservation, and laboratory testing, including the collection of quality control samples, shall be in accordance with the requirements of and methods approved by the Department in accordance with Rule 62-4.246 and Chapter 62-160, F.A.C. Approved methods published by the Department or as published in Standard Methods, or by A.S.T.M., or EPA methods shall be used.

2. Zone of Discharge.

- a. The zone of discharge for this facility shall extend horizontally 100 feet from the limits of the landfill disposal areas or to the property boundary, whichever is less, and shall extend vertically to the bottom of the surficial aquifer.
- b. The permittee shall ensure that the water quality standards for Class G-II ground waters will not be exceeded at the boundary of the zone of discharge according to Rule 62-520.420, F.A.C., and that the ground water minimum criteria referenced in Rule 62-520.400, F.A.C., will not be exceeded outside the footprint of the landfill disposal areas.

- 3. Ground Water Monitor Well Locations.** The ground water monitor system constructed at the [Enterprise Class III Landfill](#) is described in Section 5 ["Groundwater Monitoring Plan"] of the Engineering Report [ref. [APPENDIX 2, Para. 1.e.](#)], and the monitor well locations are shown on Figure 1 [titled "Groundwater Monitoring Network"], prepared by Locklear & Associates, received March 20, 2013 [\[attached\]](#), as follow:

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

3. Ground Water Monitor Well Locations. [continued]

Wells associated with existing disposal areas: [Cells 1 through 6, Cell 15, temporary stormwater pond]:

<u>Well #</u>	<u>Scheduling Notes</u>	<u>WACS Testsite #</u>	<u>Aquifer</u>	<u>Well Designation</u>	<u>Location</u>
MW-3	A	19571	Surficial	Detection	See Figure 1
MW-3B	A	21964	Floridan	Detection	↓
MW-4	A	19572	Surficial	Detection	↓
MW-4B	A	21965	Floridan	Detection	↓
MW-5A	A	19573	Surficial	Detection	↓
MW-5B	A	19574	Floridan	Detection	↓
MW-6	A	19575	Surficial	Detection	See Figure 1
MW-7A	A	19576	Surficial	Detection	↓
MW-7BR	A	22592	Floridan	Detection	↓
MW-8	A	19578	Surficial	Detection	↓
MW-8B	A	21323	Floridan	Detection	↓
MW-9	A	19579	Surficial	Detection	↓
MW-9B	A	21324	Floridan	Detection	↓
MW-10	A	19580	Surficial	Detection	See Figure 1
MW-10B	A	21325	Floridan	Detection	↓
MW-15B	A, Z	28682	Floridan	Detection	↓
MW-16B	A, Z	28683	Floridan	Detection	↓
MW-17B	A	28684	Floridan	Detection	↓
Supply Well	A	21326	Floridan	Supply	↓
BW-1A	B, X	XXXXX	Surficial	Background	See Figure 1
BW-1B	B, X	XXXXX	Floridan	Background	↓
MW-6B	B, X	XXXXX	Floridan	Detection	↓
MW-1A	A	19566	Surficial	Piezometer	See Figure 1
MW-1B	A	19568	Floridan	Piezometer	↓
MW-11	A	19581	Surficial	Piezometer	↓
MW-11B	A	22593	Floridan	Piezometer	↓
MW-12A	A	19582	Surficial	Piezometer	↓
MW-12B	A	19583	Floridan	Piezometer	↓
P-4	A	N/A	Surficial	Piezometer	See Figure 1
P-6	A	N/A	Surficial	Piezometer	↓
P-8	A	N/A	Floridan	Piezometer	↓
P-10	A	N/A	Floridan	Piezometer	↓
P-11	A	N/A	Surficial	Piezometer	↓

Wells associated with future disposal areas [Cell 7]:

<u>Well #</u>	<u>Scheduling Notes</u>	<u>WACS Testsite #</u>	<u>Aquifer</u>	<u>Well Designation</u>	<u>Location</u>
MW-18A	C, Y	XXXXX	Surficial	Detection	See Figure 1
MW-18B	C, Y	XXXXX	Floridan	Detection	↓
MW-19A	C, Y	XXXXX	Surficial	Detection	↓
MW-19B	C, Y	XXXXX	Floridan	Detection	↓
MW-20A	C, Y	XXXXX	Surficial	Detection	↓
MW-20B	C, Y	XXXXX	Floridan	Detection	↓

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

3. Ground Water Monitor Well Locations. [continued]

Scheduling Notes:

A = existing well/piezometer; construction details previously provided; results of initial sampling event previously provided [excluding piezometers P-4, P-6, P-8, P-10 and P-11]

B = proposed monitor well **to be installed within 45 days of issuance of permit #177982-020-SO/T3** in accordance with the construction details presented in Table 2 [proposed surficial aquifer wells] or Table 3 [proposed Floridan aquifer wells] in Section 5 ["Groundwater Monitoring Plan"] of the Engineering Report [ref. [APPENDIX 2, Para. 1.e.\(1\) and Para. 1.e.\(2\)](#)]

C = proposed monitor well **to be installed at least 30 days prior to disposal of waste in Cell 7** in accordance with the construction details presented in Table 2 [proposed surficial aquifer wells] or Table 3 [proposed Floridan aquifer wells] in Section 5 ["Groundwater Monitoring Plan"] of the Engineering Report [ref. [APPENDIX 2, Para. 1.e.\(1\) and Para. 1.e.\(2\)](#)]

X = documentation of well construction details in accordance with [APPENDIX 3, Conditions #5.b., and #5.d.](#), shall be submitted to the Department **within 30 days of completion**; a ground water "initial sampling event" shall be conducted **within 7 days of well installation and development** for analysis of the parameters referenced in [APPENDIX 3, Condition #4.b.](#); the results of the "initial sampling event" shall be submitted to the Department **within 60 days of receipt from the laboratory**.

Y = documentation of well construction details shall be submitted in accordance with [APPENDIX 3, Conditions #5.b., and #5.d.](#); a ground water "initial sampling event" shall be conducted **within 7 days of well installation and development** for the parameters listed in [APPENDIX 3, Condition #4.b.](#); well construction details and results of the ground water "initial sampling event" shall be submitted as part of the certification of construction completion prepared for **Cell 7 [Specific Condition #2.B.3., of permit #177982-019-SC/T3]**.

Z = to be abandoned **at least 30 days prior to the construction of Cell 7**; documentation of well abandonment shall be submitted in accordance with [APPENDIX 3, Condition #6.](#)

All wells and piezometers are to be clearly labeled and easily visible at all times. Bollards or other devices shall be installed to protect the monitor wells located in areas of high traffic flow within the facility. The permittee shall keep all wells and piezometers locked to minimize unauthorized access.

4. **Ground Water Sampling.** The locations, parameters, and frequencies specified herein represent the minimum requirements for ground water monitoring. Additional samples, wells, and parameters may be required based upon subsequent analysis. Method Detection Limits must be reported at or below the Maximum Contaminant Levels established for the individual parameters to demonstrate compliance with the Class G-II ground water standards referenced in Chapter 62-520.420, F.A.C., and with the ground water minimum criteria referenced in Chapter 62-520.400, F.A.C. Compliance with ground water standards will be based on analysis of unfiltered samples.

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

4. Ground Water Sampling. [continued]

- a. Ground water levels shall be measured **semi-annually** (during the periods from Jan. 1 - June 30, and July 1 - Dec. 31 of each year) at a minimum, including all sampling events described in [APPENDIX 3, Conditions #4.b., and #4.c., below](#), at all active monitor wells and piezometers, as listed in [APPENDIX 3, Condition #3., above](#), to a precision of 0.01 foot. Ground water surface contour maps shall be prepared for each sampling event to include water elevations (using an industry approved datum) calculated for each monitor well and piezometer.
- b. An “initial sampling event” shall be conducted **within 7 days of installation and development** of all new monitor wells for analysis of the following parameters:

<u>Field Parameters</u>	<u>Laboratory Parameters</u>	
Static Water Level	Total Ammonia - N	Iron
before purging	Chlorides	Mercury
Specific Conductivity	Nitrate	Sodium
pH	Total Dissolved Solids (TDS)	
Dissolved Oxygen	<u>Those parameters listed in</u>	
Turbidity	<u>40 CFR Part 258, Appendix II</u>	
Temperature		
Color/sheen (by obs.)		

Results of initial sampling shall be submitted **within 60 days of receipt from the analytical laboratory**. Following the completion of the “initial sampling event” at the proposed monitor wells in accordance with the schedule presented in [APPENDIX 3, Condition #3., above](#), these new wells shall be included in subsequent routine ground water sampling events.

- c. The background wells, detection wells, and the supply well listed in [APPENDIX 3, Condition #3., above](#), shall be sampled **semi-annually** for analysis of the following parameters:

<u>Field Parameters</u>	<u>Laboratory Parameters</u>	
Static Water Level	Total Ammonia - N	Iron
before purging	Chlorides	Mercury
Specific Conductivity	Nitrate	Sodium
pH	Total Dissolved Solids (TDS)	
Dissolved Oxygen	<u>Those parameters listed in</u>	
Turbidity	<u>40 CFR Part 258, Appendix I</u>	
Temperature		
Color/sheen (by obs.)		

5. Ground Water Monitor Well Construction. The following information is required to be submitted **within 90 days of installation** of all new or replacement monitor wells and piezometers, or as stated below:

- a. Prior to construction of all new or replacement monitor wells or piezometers, the permittee shall request and receive Department approval of a minor permit modification in accordance with [Specific Condition #2.A.2., of this permit](#).

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

5. **Ground Water Monitor Well Construction.** [continued]
 - b. Construction details for all new or replacement wells and piezometers shall be provided to the Department's Southwest District Office on Department Form # 62-701.900(30), Monitoring Well Completion Report [\[attached\]](#).
 - c. **Within one week of well completion and development**, each new monitor well shall be sampled for the parameters listed in [APPENDIX 3, Condition #4.b., above](#), to comply with the requirements of Rules 62-701.510(7)(a), and 62-701.510(7)(c), F.A.C.
 - d. A surveyed drawing shall be submitted in accordance with Rule 62-701.510(3)(d)(1), F.A.C., showing the location of all monitor wells and piezometers (active and abandoned) horizontally located in degrees, minutes and seconds of latitude and longitude, and the elevation of the top of the well casing to the nearest 0.01 foot, using an industry approved datum. The surveyed drawing shall include the monitor well identification number, locations and elevations of all permanent benchmarks and/or corner monument markers at the site. The survey shall be conducted by Florida Licensed Professional Surveyor and Mapper.
6. **Well Abandonment.** All monitor wells and piezometers not listed in [APPENDIX 3, Condition #3., above](#), and not a part of the approved Water Quality Monitoring Plan shall be plugged and abandoned in accordance with Rule 62-532.500(5), F.A.C., and the rules of the Southwest Florida Water Management District. The permittee shall submit a written report to the Department **within 30 days of well/piezometer abandonment** verifying proper abandonment. A written request for exemption to the abandonment of a well/piezometer must be submitted to the Department's Solid Waste Section for approval.
7. **Verification/Evaluation Monitoring.** If at any time monitoring parameters are detected at concentrations significantly above background water quality, or exceed the Department's ground water quality standards or minimum criteria specified in Chapter 62-520, F.A.C., in any detection well, the permittee has 30 days from receipt of the sampling results to resample the monitor well(s) to verify the original analysis. Should the permittee choose not to resample, the Department will consider the water quality analysis as representative of current ground water conditions at the facility. If the data is confirmed, or if the permittee chooses not to resample, the permittee shall notify the Department in writing within 14 days of this finding. Upon notification by the Department, the permittee shall initiate evaluation monitoring as described in Rules 62-701.510(6)(a) and 62-701.510(6)(b), F.A.C. If monitoring parameters are detected and confirmed at concentrations significantly above background water quality, and exceed the Department's water quality standards or minimum criteria in any compliance well, the Permittee shall notify the Department in writing within 14 days of this finding and shall initiate corrective actions as described in Rule 62-701.510(6)(c), F.A.C.

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

8. **Surface Water Sampling.** All surface water bodies that may be affected by a contaminant release at the facility shall be monitored, except bodies of water contained completely within the property boundaries of the site which do not discharge from the site to surface waters (Rule 62-701.510(4), F.A.C.). It is not anticipated that the existing stormwater management system will discharge from the property. However, in the event that surface water discharge occurs from the stormwater management system, representative samples of each discharge event shall be collected for analysis of the parameters listed in [APPENDIX 3, Condition #8.b., below](#). In the event that any modifications to the stormwater management system associated with future uses of the facility result in periodic surface water discharges from the property, the Department may require the implementation of routine surface water monitoring.

- a. The locations, parameters, and frequencies specified herein represent the minimum requirements for surface water monitoring. Additional sampling locations and parameters may be required based upon subsequent analysis. Method Detection Limits must be less than or equal to the surface water criteria established for the individual parameters to demonstrate compliance with Class III surface water (predominantly freshwater) referenced in Chapter 62-302, F.A.C. Compliance with surface water criteria will be based on analysis of unfiltered samples.
- b. Surface water sampling shall be conducted **per discharge event** in accordance with the Department's SOPs to comply with the requirements of Rule 62-701.510(4), F.A.C. The Department's Southwest District office, [Compliance Assurance Program](#) shall be notified of the occurrence of each discharge event **within 24 hours of discovery**. Surface water samples shall be collected at the point of discharge from the property and shall be analyzed for the following parameters:

Field Parameters

Specific conductivity
pH
Dissolved oxygen
Turbidity
Temperature
Colors and sheens
(by observation)

Laboratory Parameters

Unionized ammonia	Total organic carbon (TOC)
Total hardness (as mg/L CaCO ₃)	Total nitrogen
Total phosphorus (as mg/L P)	Chemical oxygen demand (COD)
Chlorophyll A	Fecal coliform
Nitrate	Biochemical oxygen demand (BOD ₅)
Iron	Total dissolved solids (TDS)
Mercury	Total suspended solids (TSS)

Those parameters listed in
40 CFR Part 258, Appendix I

- c. Sampling of the temporary stormwater pond (located in Cells 14/16) shall be required in the event that the routine ground water sampling events conducted at the detection wells located in proximity to the temporary stormwater pond (MW-3, MW-3B, MW-4, MW-4B, MW-5A, MW-5B, MW-6 or MW-6B) indicate monitoring parameters are detected at concentrations significantly above background water quality, or exceed the Department's ground water quality standards or minimum criteria. In this case, surface water sampling in the temporary stormwater pond shall be conducted **within 30 days of receipt of ground water results** in accordance with the Department's SOPs for analysis of the parameters listed in [APPENDIX 3, Condition #8.b., above](#).

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

9. **Leachate Sampling.** In accordance with the amendments to Chapter 62-701, F.A.C., that are effective on August 12, 2012, the collection of leachate samples for laboratory analyses is not required.
10. **Water Quality Reporting Requirements.** Required water quality monitoring reports and all ground water and surface water analytical results for sampling events conducted at the [Enterprise Class III Landfill](#) shall be submitted electronically (via e-mail, CD, DVD, etc.). Water quality monitoring reports shall be submitted in Adobe pdf format.
- a. The water quality data Electronic Data Deliverable (EDD) shall be provided to the Department in an electronic format consistent with requirements for importing the data into the Department's databases as summarized on the Department's web site at: <http://www.dep.state.fl.us/waste/categories/shw/pages/ADaPT.htm>.
- Water quality monitoring reports shall be signed and sealed by a Florida registered professional geologist or professional engineer with experience in hydrogeological investigations and shall include the following:
- 1) Cover letter;
 - 2) Summary of exceedances and sampling problems, if any (e.g., variation from SOP field criteria);
 - 3) Conclusions and recommendations;
 - 4) Ground water contour maps;
 - 5) Chain of custody forms;
 - 6) Water levels, water elevation table;
 - 7) Ground Water Monitoring Certification, using Department Form #62-701.900(31);
 - 8) Appropriate sampling information on Form #FD 9000-24 (DEP-SOP-001/01); and,
 - 9) Laboratory and Field EDDs and error logs, as applicable.

All water quality reports shall be submitted to:

Florida Department of Environmental Protection
Southwest District Office, [Compliance Assurance Program](#)
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926
SWD_Waste@dep.state.fl.us

and to,

Florida Department of Environmental Protection
Solid Waste Section, MS 4565
2600 Blair Stone Road
Tallahassee, Florida, 32399-2400

APPENDIX 3 – Water Quality Monitoring Plan (cont.)

10. Water Quality Reporting Requirements. [continued]

- b. The permittee shall submit to the Department the results of analyses reported for each sampling event conducted at the facility by the following due dates:
- 1) [APPENDIX 3, Condition #4.b.](#) – results of ground water “initial sampling events” shall be submitted **within 60 days from completion of laboratory analyses**;
 - 2) [APPENDIX 3, Condition #4.c.](#) – results of ground water routine semi-annual sampling events shall be submitted **within 60 days from completion of laboratory analyses and no later than Jan. 15th, and July 15th of each year for the time periods July 1-Dec. 31, and Jan. 1-June 30, respectively**;
 - 3) [APPENDIX 3, Condition #7](#) – results of ground water verification events shall be submitted **within 60 days from completion of laboratory analyses**;
 - 4) [APPENDIX 3, Condition #8.b.](#) – results of surface water “discharge sampling events” shall be submitted **within 60 days from completion of laboratory analyses**; and,
 - 5) [APPENDIX 3, Condition #8.c.](#) – results of surface water sampling events conducted within the temporary storm water pond (Cells 14/16) shall be submitted **within 60 days from completion of laboratory analyses**.


- 11. Monitoring Plan Evaluation.** The permittee shall submit an evaluation of the water quality monitoring data (ground water analyses, ground water flow direction and velocity, and surface water analyses) every two and one-half years as required by Rule 62-701.510(8)(b), F.A.C. The due dates and time periods to be covered by the evaluations are summarized below:

<u>Monitoring Plan Evaluation Due Date</u>	<u>Starting Sampling Event</u>	<u>Ending Sampling Event</u>
Dec. 1, 2015	Second half 2011	First half 2015
Apr. 1, 2018	Second half 2015	Second half 2017

The evaluations shall include the applicable information as listed in Rule 62-701.510(8)(b), F.A.C., and shall include assessment of the effectiveness of the landfill closure design as related to the prevention of ground water and surface water contamination. Any ground water contamination that may exist shall be addressed as part of evaluation monitoring conducted at the facility in accordance with Rule 62-701.510(6), F.A.C. The monitoring plan evaluations shall be sent to:

Florida Department of Environmental Protection
Southwest District Office, [Waste Permitting Section](#)
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926

APPENDIX 3 - Water Quality Monitoring Plan (cont.)



APPENDIX 3 - Water Quality Monitoring Plan (cont.)



**Department of
Environmental Protection**

Bob Martinez Center
2600 Blair Stone Road
Tallahassee, Florida 32399-2400

DEP Form # 62-701.900(30)

Form Title: Monitoring Well Completion Report

Effective Date: January 6, 2010

Incorporated in Rule 62-701.510(3)

MONITORING WELL COMPLETION REPORT

DATE: _____

FACILITY NAME: _____

DEP PERMIT NO.: _____ WACS_FACILITY: _____

WACS MONITORING SITE_NUM.: _____ WACS_WELL: _____

WELL_TYPE: BACKGROUND _____ DETECTION _____ COMPLIANCE _____

LATITUDE AND LONGITUDE (see back for requirements): _____

Coordinate Accuracy _____ Datum _____ Elevation Datum _____

Collection Method _____ Collection Date _____

Collector Name _____ Collector Affiliation _____

AQUIFER MONITORED: _____

DRILLING METHOD: _____ DATE INSTALLED: _____

INSTALLED BY: _____

BORE HOLE DIAMETER: _____ TOTAL DEPTH: _____ (BLS)

CASING TYPE: _____ CASING DIAMETER: _____ CASING LENGTH: _____

SCREEN TYPE: _____ SCREEN SLOT SIZE: _____ SCREEN LENGTH: _____

SCREEN DIAMETER: _____ SCREEN INTERVAL: _____ TO _____
(BLS)

FILTER PACK TYPE: _____ FILTER PACK GRAIN SIZE: _____

INTERVAL COVERED: _____ TO _____ (BLS)

SEALANT TYPE: _____ SEALANT INTERVAL: _____ TO _____ (BLS)

GROUT TYPE: _____ GROUT INTERVAL: _____ TO _____ (BLS)

TOP OF CASING ELEVATION (NGVD): _____ GROUND SURFACE ELEVATION (NGVD): _____

DESCRIBE WELL DEVELOPMENT: _____

POST DEVELOPMENT WATER LEVEL ELEVATION (NGVD): _____

DATE AND TIME MEASURED: _____

REMARKS: _____

NAME OF PERSON PREPARING REPORT: _____

(Name, Organization, Phone No., E-mail)

NOTE: ATTACH AS-BUILT MW CONSTRUCTION DIAGRAM AND LITHOLOGIC LOG.(NGVD) NATIONAL GEODETIC
VERTICAL DATUM OF 1988 (BLS) = BELOW LAND SURFACE

APPENDIX 3 – Water Quality Monitoring Plan (cont)

Latitude must be measured in degrees, minutes and seconds, to at least two (2) decimal places.

Longitude must be measured in degrees, minutes and seconds, to at least two (2) decimal places.

Eastings and northings (State Plane Coordinates) **must** be converted to latitude and longitude.

Coordinate Accuracy: the measured, estimated degree of correctness of the measurement. An accuracy of 15 feet or 5 meters is preferred.

Datum: the horizontal reference for measuring locations on the Earth's surface. NAD83-North American Datum of 1983 is preferred.

Elevation Datum: the reference datum from which elevation measurements are made. NGVD88 (National Geodetic Vertical Datum of 1988) is preferred.

Collection Method: the method or mechanism used to derive the measurements, e.g. GPS, map, aerial photo, etc.

Collection Date: the date and time on which the measurements were taken.

Collector Name: the name of the person taking the measurement.

Collector Affiliation: the agency or company for whom the collector works.

APPENDIX 4 – General Information

<u>General Information:</u>	<u>Class III Landfill</u>
Disposal acres	Approx. 60.9 acres (Cells 1-7 and 15) [ref. APP-2, Para. 1.b., Sheet C-4]
Lowest bottom elevation of cells.	+80 ft. NGVD (Cell 15)
Top elevation at final buildout (including cover)	max. +175 feet NGVD [ref. APP-2, Para. 1.b., Sheet C-8]
Side slopes max.	3H:1V below elevation +125 ft. NGVD; 4H:1V between el. +125 ft. and +150 ft NGVD; 20H:1V between el. +150 ft. and +170 ft NGVD; 30H:1V above +170 ft NGVD [ref. APP- 2, Para. 1.b., Sheet C-8]
Liner system	3 foot-thick clay (bottom only Cells 1-5, and 15; bottom & sides of Cells 6A, 6B, & 7), max. permeability= 1 x10-8 cm/sec [ref. APP-2, Para. 1.a., §3.7.]
LCS drainage system	None
Design Life	11.4 years (Cells 1-7 and 15) [ref. APP-2, Para. 1.a., §3.8.3.]
Closure slopes	3H:1V below elevation +125 ft. NGVD; 4H:1V between el. +125 ft. and +150 ft NGVD; 20H:1V between el. +150 ft. and +170 ft NGVD; 30H:1V above +170 ft NGVD [ref. APP- 2, Para. 1.b., Sheet C-8]

ATTACHMENT 1 - Time Sensitive Action Chart		
Specific Condition	Submittal Due Date	Required Item
Cover page	No later than 61 days prior to expiration date of permit	Submit permit renewal application
E.4.	Quarterly, by January 15 th , April 15 th , July 15 th and October 15 th each year	Submit gas monitoring results
F.2	Annually, between January 1 st and March 1 st each year	Submit revised cost estimates
	Annually	Submit proof of funding
APP-3; 4.b.	Within 7 days of new well installation/development	Conduct ground water "initial sampling event."
APP-3; 4.c.	Semi-annually	Conduct ground water "routine sampling event."
APP-3; 5.b.	Within 90 days of installation	Submit well construction information.
APP-3; 5.d.	Within 90 days of new or replacement well installation	Submit survey drawing.
APP-3; 6.	Within 30 days of well abandonment	Submit documentation of well abandonment.
APP-3; 7.	Within 14 days of discovery	Submit notification of monitoring parameters significantly above background water quality, or exceeding ground water standards or minimum criteria.
APP-3; 8.b.	Per discharge event from the storm water management system	Conduct surface water sampling at the point of discharge from the property.
APP 3; 8.c.	Within 30 days of receipt of ground water results indicating exceedances	Conduct surface water sampling in the temporary storm water pond.
APP-3 10.b.1., 10.b.3., 10.b.4., 10.b.5.	Within 60 days from completion of laboratory analyses	Submit results of: <ul style="list-style-type: none"> - ground water initial sampling; - ground water verification sampling; - surface water discharge sampling; and, - surface water temporary storm water pond sampling.
APP-3 10.b.2.	Semi-annually by January 15 th and July 15 th of each year	Submit results of: <ul style="list-style-type: none"> - ground water routine sampling.
APP-3; 11.	By December 1, 2015 and by April 1, 2018	Submit monitoring plan evaluation report.

ATTACHMENT 2 - Facility Permit History

Replaces Permit No.: **177982-007-SO/T3, issued 05/31/2007**

Including Modification No.:

177982-012-SO/MM, dated 10/31/2007;
177982-013-SO/MM, dated 02/20/2008;
177982-014-SO/MM, dated 02/20/2008;
177982-015-SO/MM, dated 09/10/2008;
177982-016-SO/MM, dated 01/07/2010; and
177982-018-SO/MM, dated 04/06/2012;

From: [Tedder, Richard](#)
To: [Butler, Linda](#)
Subject: Out of Office: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Thursday, June 13, 2013 2:21:20 PM

I will be out of my office on 6/13 to 6/14. I expect to return on 6/17. I will try to respond to email if I can. If you need immediate help contact Derbra Owete (Administrative Assistant, 850/245-8732, derbra.owete@dep.state.fl.us) or Lee Martin (Professional Engineer III, 850/245-8734, lee.martin@dep.state.fl.us) or Mike Dunaway (Professional Engineer III, 850/245-8741, michael.dunaway@dep.state.fl.us). - RT

From: [Microsoft Exchange](#)
To: [Senator Wilson Simpson](#)
Subject: Undeliverable: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:16 AM
Attachments: [177982-019-SCT3 177982-020-SOT3 Enterprise Class III Landfill .msg](#)

Delivery has failed to these recipients or distribution lists:

HYPERLINK "mailto:simpson.wilson.web@flsenate.gov"Senator Wilson Simpson

Your message wasn't delivered because of security policies. Microsoft Exchange will not try to redeliver this message for you. Please provide the following diagnostic text to your system administrator.

The following organization rejected your message: leg.state.fl.us.

Sent by Microsoft Exchange Server 2007

Diagnostic information for administrators:

Generating server: ECHCAS1.floridadep.net

simpson.wilson.web@flsenate.gov

leg.state.fl.us #550 5.7.1 Unknown recipient <simpson.wilson.web@flsenate.gov> was submitted by host <199.73.152.10>. Sender address was <Linda.Butler@dep.state.fl.us>. ##

Original message headers:

Received: from ECHMBA.floridadep.net (::1) by ECHCAS1.floridadep.net (::1) with mapi; Thu, 13 Jun 2013 14:21:15 -0400

From: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

To: "John.phillip.arnold@gmail.com" <john.phillip.arnold@gmail.com> ,

"Chisolm, Jack" <Jack.Chisolm@dep.state.fl.us> , "Bejnar, Tor"

<Tor.Bejnar@dep.state.fl.us> , Solid Waste Financial Coordinator

<Solid.Waste.Financial.Coordinator@dep.state.fl.us> , "Tedder, Richard"

<Richard.Tedder@dep.state.fl.us> , "Pelz, Susan" <Susan.Pelz@dep.state.fl.us> ,

"Morgan, Steve" <Steve.Morgan@dep.state.fl.us> , Commissioner Henry Wilson

<hwilson@pascocountyfl.net> , Commissioner Jack Mariano

<jmariano@pascocountyfl.net> , Commissioner Kathryn Starkey

<kstarkey@pascocountyfl.net> , Commissioner Pat Mulieri

<pmulieri@pascocountyfl.net> , Commissioner Ted Schrader

<tschrader@pascocountyfl.net> , County Administrator John Gallagher

<pcadmin@pascocountyfl.net> , Pasco County Commissioners

<commissioners@pascocountyfl.net> , Representative Mike Fasano

<mike.fasano@myfloridahouse.gov> , Representative Peter Nehr

<peter.nehr@myfloridahouse.gov> , Representative Richard Corcoran

<richard.corcoran@myfloridahouse.gov> , Representative Will Weatherford

<will.weatherford@myfloridahouse.gov> , Senator Wilson Simpson

<simpson.wilson.web@flsenate.gov>

Disposition-Notification-To: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

Return-Receipt-To: <Linda.Butler@dep.state.fl.us>

Content-Class: urn:content-classes:message

Date: Thu, 13 Jun 2013 14:21:14 -0400

Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Thread-Topic: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Thread-Index: Ac5oYsoArUxymM03TUa1xwGIV/vD0g==

Message-ID: <4C1864BB14BF924DB761A4D9E8B2245B5DE6F88863@ECHMBA.floridadep.net>

Reply-To: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

Accept-Language: en-US

Content-Language: en-US

X-MS-Has-Attach: yes

X-MS-TNEF-Correlator:

acceptlanguage: en-US

Content-Type: multipart/mixed;

boundary="_004_4C1864BB14BF924DB761A4D9E8B2245B5DE6F88863ECHMBAflorida_"

MIME-Version: 1.0

From: [Microsoft Exchange](#)
To: ["John Arnold, P.E. \(john.phillip.arnold@gmail.com\)"](#)
Subject: Relayed: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:32 AM

Delivery to these recipients or distribution lists is complete, but delivery notification was not sent by the destination:
HYPERLINK "mailto:john.phillip.arnold@gmail.com""John Arnold, P.E. (john.phillip.arnold@gmail.com)"
Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Sent by Microsoft Exchange Server 2007

From: [Microsoft Exchange](#)
To: [Bejnar, Tor](#); [SWD_Clerical](#)
Subject: Delivered: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:32 AM

Your message has been delivered to the following recipients:
HYPERLINK "mailto:Tor.Bejnar@dep.state.fl.us"Bejnar, Tor
HYPERLINK "mailto:SWD_Clerical@dep.state.fl.us"SWD_Clerical
Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Sent by Microsoft Exchange Server 2007

From: [Microsoft Exchange](#)
To: [Chisolm, Jack](#); [Tedder, Richard](#); [Solid Waste Financial Coordinator](#); [Pelz, Susan](#); [Morgan, Steve](#)
Subject: Delivered: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:33 AM

Your message has been delivered to the following recipients:

HYPERLINK "mailto:Jack.Chisolm@dep.state.fl.us"Chisolm, Jack

HYPERLINK "mailto:Richard.Tedder@dep.state.fl.us"Tedder, Richard

HYPERLINK "mailto:Solid.Waste.Financial.Coordinator@dep.state.fl.us"Solid Waste Financial Coordinator

HYPERLINK "mailto:Susan.Pelz@dep.state.fl.us"Pelz, Susan

HYPERLINK "mailto:Steve.Morgan@dep.state.fl.us"Morgan, Steve

Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Sent by Microsoft Exchange Server 2007

From: [Pelz, Susan](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:33 AM

Your message was read on Thursday, June 13, 2013 2:21:25 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Microsoft Exchange](#)
To: [Representative Mike Fasano](#); [Representative Richard Corcoran](#); [Representative Will Weatherford](#)
Subject: Relayed: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:33 AM

Delivery to these recipients or distribution lists is complete, but delivery notification was not sent by the destination:

HYPERLINK "mailto:mike.fasano@myfloridahouse.gov"Representative Mike Fasano

HYPERLINK "mailto:richard.corcoran@myfloridahouse.gov"Representative Richard Corcoran

HYPERLINK "mailto:will.weatherford@myfloridahouse.gov"Representative Will Weatherford

Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Sent by Microsoft Exchange Server 2007

From: [Microsoft Exchange](#)
To: [Representative Peter Nehr](#)
Subject: Undeliverable: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:33 AM
Attachments: [177982-019-SCT3 177982-020-SOT3 Enterprise Class III Landfill .msg](#)

Delivery has failed to these recipients or distribution lists:

HYPERLINK "mailto:peter.nehr@myfloridahouse.gov"Representative Peter Nehr

An error occurred while trying to deliver this message to the recipient's e-mail address. Microsoft Exchange will not try to redeliver this message for you. Please try resending this message, or provide the following diagnostic text to your system administrator.

The following organization rejected your message: WG1.myfloridahouse.gov.

Sent by Microsoft Exchange Server 2007

Diagnostic information for administrators:

Generating server: ECHCAS1.floridadep.net

peter.nehr@myfloridahouse.gov

WG1.myfloridahouse.gov #550 <peter.nehr@myfloridahouse.gov>: Recipient address rejected: User unknown ##

Original message headers:

Received: from ECHMBA.floridadep.net (::1) by ECHCAS1.floridadep.net (::1) with mapi; Thu, 13 Jun 2013 14:21:15 -0400

From: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

To: "john.phillip.arnold@gmail.com" <john.phillip.arnold@gmail.com> ,

"Chisolm, Jack" <Jack.Chisolm@dep.state.fl.us> , "Bejnar, Tor"

<Tor.Bejnar@dep.state.fl.us> , Solid Waste Financial Coordinator

<Solid.Waste.Financial.Coordinator@dep.state.fl.us> , "Tedder, Richard"

<Richard.Tedder@dep.state.fl.us> , "Pelz, Susan" <Susan.Pelz@dep.state.fl.us> ,

"Morgan, Steve" <Steve.Morgan@dep.state.fl.us> , Commissioner Henry Wilson

<hwilson@pascocountyfl.net> , Commissioner Jack Mariano

<jmariano@pascocountyfl.net> , Commissioner Kathryn Starkey

<kstarkey@pascocountyfl.net> , Commissioner Pat Mulieri

<pmulieri@pascocountyfl.net> , Commissioner Ted Schrader

<tschrader@pascocountyfl.net> , County Administrator John Gallagher

<pcadmin@pascocountyfl.net> , Pasco County Commissioners

<commissioners@pascocountyfl.net> , Representative Mike Fasano

<mike.fasano@myfloridahouse.gov> , Representative Peter Nehr

<peter.nehr@myfloridahouse.gov> , Representative Richard Corcoran

<richard.corcoran@myfloridahouse.gov> , Representative Will Weatherford

<will.weatherford@myfloridahouse.gov> , Senator Wilson Simpson

<simpson.wilson.web@flsenate.gov>

Disposition-Notification-To: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

Return-Receipt-To: <Linda.Butler@dep.state.fl.us>

Content-Class: urn:content-classes:message

Date: Thu, 13 Jun 2013 14:21:14 -0400

Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Thread-Topic: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III
Landfill

Thread-Index: Ac5oYsoArUxymM03TUa1xwGIV/vD0g==

Message-ID: <4C1864BB14BF924DB761A4D9E8B2245B5DE6F88863@ECHMBA.floridadep.net>

Reply-To: "Butler, Linda" <Linda.Butler@dep.state.fl.us>

Accept-Language: en-US

Content-Language: en-US

X-MS-Has-Attach: yes

X-MS-TNEF-Correlator:

acceptlanguage: en-US

Content-Type: multipart/mixed;

boundary="_004_4C1864BB14BF924DB761A4D9E8B2245B5DE6F88863ECHMBAflorida_"

MIME-Version: 1.0

From: [John Arnold](#)
To: [Butler, Linda](#)
Subject: Out of office Re: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Thursday, June 13, 2013 2:21:33 PM

I'm out of the office and will be back on Tuesday the 18th. I'll get back with you then.

Take care

--

John Arnold, P.E.
Ph. (352) 339-1408

From: [Fasano, Mike](#)
To: [Butler, Linda](#)
Subject: Thank you for contacting State Representative Mike Fasano
Date: Thursday, June 13, 2013 2:22:17 PM

Thank you for contacting the office of Florida State Representative Mike Fasano. I receive many email messages each day and do my best to respond to each one personally. Your message is very important to us. However, if you need immediate assistance please contact our District office at 727-848-5885 or 800-948-5885.

Thanks again for contacting us.

Mike Fasano
Florida House District 36

From: [Microsoft Exchange](#)
To: [Commissioner Henry Wilson](#); [Commissioner Jack Mariano](#); [Commissioner Kathryn Starkey](#); [Commissioner Pat Mulieri](#); [Commissioner Ted Schrader](#); [County Administrator John Gallagher](#); [Pasco County Commissioners](#)
Subject: Relayed: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:50 AM

Delivery to these recipients or distribution lists is complete, but delivery notification was not sent by the destination:

HYPERLINK "mailto:hwilson@pascocountyfl.net"Commissioner Henry Wilson
HYPERLINK "mailto:jmariano@pascocountyfl.net"Commissioner Jack Mariano
HYPERLINK "mailto:kstarkey@pascocountyfl.net"Commissioner Kathryn Starkey
HYPERLINK "mailto:pmulieri@pascocountyfl.net"Commissioner Pat Mulieri
HYPERLINK "mailto:tschrader@pascocountyfl.net"Commissioner Ted Schrader
HYPERLINK "mailto:pcadmin@pascocountyfl.net"County Administrator John Gallagher
HYPERLINK "mailto:commissioners@pascocountyfl.net"Pasco County Commissioners
Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Sent by Microsoft Exchange Server 2007

From: [Morgan, Steve](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:50 AM

Your message was read on Thursday, June 13, 2013 2:31:37 PM (GMT-05:00) Eastern Time (US & Canada).

From: [SWD Clerical](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:51 AM

Your message was read on Thursday, June 13, 2013 2:31:40 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Fasano, Mike](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:53 AM

Your message was read on Thursday, June 13, 2013 2:52:40 PM (GMT-05:00) Eastern Time (US & Canada).

From: [PCAdmin](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:54 AM

Your message was read on Thursday, June 13, 2013 3:06:05 PM (GMT-05:00) Eastern Time (US & Canada).

From: Will.Weatherford@myfloridahouse.gov
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:54 AM

Your message was read on Thursday, June 13, 2013 3:11:20 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Henry O. Wilson, Jr.](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:54 AM

Your message was read on Thursday, June 13, 2013 3:24:46 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Pat Mulieri](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:55 AM

Your message was read on Thursday, June 13, 2013 5:14:41 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Kathryn Starkey](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:55 AM

Your message was read on Saturday, June 15, 2013 12:25:43 PM (GMT-05:00) Eastern Time (US & Canada).

From: [Solid Waste Financial Coordinator](#)
To: [Butler, Linda](#)
Subject: Read: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Monday, November 04, 2013 9:25:55 AM

Your message was read on Monday, June 17, 2013 8:05:33 AM (GMT-05:00) Eastern Time (US & Canada).

From: [John Arnold](#)
To: [Butler, Linda](#)
Subject: Re: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Tuesday, June 18, 2013 8:34:49 AM

Could you please provide the intent language in Word or a text format so that I can provide to the newspaper?

Thanks
John

On Thu, Jun 13, 2013 at 2:21 PM, Butler, Linda <Linda.Butler@dep.state.fl.us> wrote:

Attached is the official **Intent to Issue** documents for the above-subject project. This is the only copy you will receive, unless you request otherwise. Acrobat Reader 6.0 or greater is required to read the documents and is available for downloading at: <http://www.adobe.com/products/acrobat/readstep.html>. *The documents are being mailed today to Mr. Dominic Iafrate, Angelo's Aggregate Materials, Ltd., as there is no known email address for him.*

Please open and review the documents as soon as possible, and verify that they are accessible. Please send a "reply" message verifying receipt of the documents.

OCULUS Information:

Catalog: Solid Waste
Profile: Permit Authorization
County: Pasco
Facility ID: 87895
Document Type: Intent to Issue/Deny Related
Facility Type(s): Class III LF

Document Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III LF
Intent & Draft Permits

The Southwest District Waste Management Program is issuing electronic documents for permits, notices, and other correspondence in lieu of hard copies through the United States Postal Service, to provide greater service to the applicant and the regulated community. You may access the attached documents and others in the Department's OCULUS document management system by clicking on the link <http://dwmedms.dep.state.fl.us/Oculus/servlet/login> and using the "Public OCULUS Log-in" button. Under the search feature, you may look through various documents, including permitting, compliance, fiscal, cleanup, and enforcement documents.

Documents addressed in this email may require immediate action within a specified time frame. Please advise this office of any changes to your email address. If you have any questions concerning the content of the attached documents, please contact the FDEP Engineering Specialist IV Steve Morgan at [\(813\) 632-7600, ext. 329](tel:(813)632-7600), or steve.morgan@dep.state.fl.us

Sincerely,

Linda Butler, Administrative Secretary

FDEP - Southwest District Permitting

13051 North Telecom Parkway

Temple Terrace, FL 33637-0926

[\(813\) 632-7600, Ext 433](tel:(813)632-7600)

email: linda.butler@dep.state.fl.us

Please take a few minutes to share your comments on the service you received from the department by clicking on this link [DEP Customer Survey](#).

--

John Arnold, P.E.
Ph. (352) 339-1408

From: [Butler, Linda](#)
To: ["John Arnold"](#)
Subject: RE: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill
Date: Tuesday, June 18, 2013 9:03:00 AM
Attachments: [177982-019-SC-T3 & 11982-020-SO-T3 NAA \(87895\).doc](#)

Attached is the Word version of the "Notice". If I may be of any further assistance, please contact me.

*Linda Butler, Administrative Secretary
FDPEP - Southwest District Permitting
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926
(813) 632-7600, Ext 433
email: linda.butler@dep.state.fl.us*

From: John Arnold [mailto:john.phillip.arnold@gmail.com]
Sent: Tuesday, June 18, 2013 8:34 AM
To: Butler, Linda
Subject: Re: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III Landfill

Could you please provide the intent language in Word or a text format so that I can provide to the newspaper?

Thanks
John

On Thu, Jun 13, 2013 at 2:21 PM, Butler, Linda <Linda.Butler@dep.state.fl.us> wrote:
Attached is the official **Intent to Issue** documents for the above-subject project. This is the only copy you will receive, unless you request otherwise. Acrobat Reader 6.0 or greater is required to read the documents and is available for downloading at:
<http://www.adobe.com/products/acrobat/readstep.html>. *The documents are being mailed today to Mr. Dominic Iafrate, Angelo's Aggregate Materials, Ltd., as there is no known email address for him.*

Please open and review the documents as soon as possible, and verify that they are accessible. Please send a "reply" message verifying receipt of the documents.

OCULUS Information:

Catalog: Solid Waste
Profile: Permit Authorization
County: Pasco
Facility ID: 87895
Document Type: Intent to Issue/Deny Related
Facility Type(s): Class III LF
Document Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III LF
Intent & Draft Permits

The Southwest District Waste Management Program is issuing electronic documents for permits, notices, and other correspondence in lieu of hard copies through the United States Postal Service, to provide greater service to the applicant and the regulated community. You may access the attached documents and others in the Department's OCULUS document management system by clicking on the link <http://dwmedms.dep.state.fl.us/Oculus/servlet/login> and using the "Public OCULUS Log-in" button. Under the search feature, you may look through various documents, including permitting, compliance, fiscal, cleanup, and enforcement documents.

Documents addressed in this email may require immediate action within a specified time frame. Please advise this office of any changes to your email address. If you have any questions concerning the content of the attached documents, please contact the FDEP Engineering Specialist IV Steve Morgan at [\(813\) 632-7600, ext. 329](tel:(813)632-7600), or steve.morgan@dep.state.fl.us

Sincerely,

*Linda Butler, Administrative Secretary
FDEP - Southwest District Permitting
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926
 [\(813\) 632-7600, Ext 433](tel:(813)632-7600)
email: linda.butler@dep.state.fl.us*

Please take a few minutes to share your comments on the service you received from the department by clicking on this link [DEP Customer Survey](#).

--

John Arnold, P.E.
Ph. (352) 339-1408

From: Butler, Linda
To: Morgan, Steve; SWD_Clerical
Subject: FW: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits
Date: Thursday, June 13, 2013 2:27:00 PM
Attachments: image002.png
image003.png

Complete

Florida Department of Environmental Protection - Enterprise Applications

Help Legal Docs EBP Exit Window

ORACLE

Permitting Application - Events

Events Scheduled 35 of 90

Site # 0177982 Site Name ENTERPRISE CLASS III LANDFILL
Permit # Type/Subtype SC / T3 Received 03/26/2012
Project # 019 Project Name ENTERPRISE CLASS III LF

> STOP CLOCK: Done

Event	Begin Date	Period	Due Date	Rmn	Status	End Date
Receive Request	03/26/2012	1	03/27/2012		Done	03/26/2012
Fee Verification	03/26/2012	2	03/28/2012		Sufficient Fee	03/28/2012
Completeness Review	03/26/2012	30	04/25/2012		Incomplete	04/24/2012
RESET CLOCK	04/24/2012	1	04/25/2012		Done	04/24/2012
Awaiting Additional Information	04/24/2012	45	06/08/2012		Received	04/18/2013
Completeness Review	04/18/2013	30	05/18/2013		Complete	04/18/2013
Determine Agency Action	04/18/2013	90	07/17/2013		Issue	06/10/2013
Mail Public Notice of Intent to Applicant a	06/10/2013	10	06/20/2013		Done	06/13/2013
Date of Publication	06/13/2013	999	03/08/2016	999	Pending	
STOP CLOCK	06/13/2013	1	06/14/2013		Done	06/13/2013
Publish Notice of Application	03/28/2012	14	04/11/2012		Done	04/27/2012

Record: 10/12

Florida Department of Environmental Protection - Enterprise Applications

Help Legal Docs EBP Exit Window

ORACLE

Permitting Application - Events

Events Scheduled 35 of 90

Site # 0177982 Site Name ENTERPRISE CLASS III LANDFILL
Permit # Type/Subtype SO / T3 Received 03/26/2012
Project # 020 Project Name ENTERPRISE CLASS III LF

> STOP CLOCK: Done

Event	Begin Date	Period	Due Date	Rmn	Status	End Date
Receive Request	03/26/2012	1	03/27/2012		Done	03/26/2012
Fee Verification	03/26/2012	2	03/28/2012		Sufficient Fee	03/28/2012
Completeness Review	03/26/2012	30	04/25/2012		Incomplete	04/24/2012
RESET CLOCK	04/24/2012	1	04/25/2012		Done	04/24/2012
Awaiting Additional Information	04/24/2012	45	06/08/2012		Received	04/18/2013
Completeness Review	04/18/2013	30	05/18/2013		Complete	04/18/2013
Determine Agency Action	04/18/2013	90	07/17/2013		Issue	06/10/2013
Mail Public Notice of Intent to Applicant a	06/10/2013	10	06/20/2013		Done	06/13/2013
Date of Publication	06/13/2013	999	03/08/2016	999	Pending	
STOP CLOCK	06/13/2013	1	06/14/2013		Done	06/13/2013
Publish Notice of Application	03/28/2012	14	04/11/2012		Done	04/27/2012

Record: 10/12

From: Brantley, Anna On Behalf Of SWD_Clerical
Sent: Thursday, June 13, 2013 12:16 PM
To: Butler, Linda
Subject: FW: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

For review and process

From: Morgan, Steve
Sent: Thursday, June 13, 2013 12:02 PM
To: SWD_Clerical
Subject: FW: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

Please process as indicated below.

Please feel free to e-mail or call me if you have any further questions.

Steven G. Morgan, Waste Management Section
Florida Department of Environmental Protection
Southwest District Office
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926

phone - (813) 632-7600 **ext 329**
fax - (813) 632-7672
e-mail - steve.morgan@dep.state.fl.us

From: Greenwell, Jeff
Sent: Thursday, June 13, 2013 11:53 AM
To: Morgan, Steve
Subject: RE: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

I have signed the ITI. Please process accordingly.

Thanks,
jsjg

From: Morgan, Steve
Sent: Monday, June 10, 2013 9:35 AM
To: Greenwell, Jeff
Subject: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

Jeff:

Please review the hyperlinks for the Intent to Issue, Notice of Proposed Agency Action, and Draft Permit. Please electronically initial the intent to issue routing memo and sign the Intent to Issue. Once signed, forward to support staff for dating, clerking, scanning, e-mailing and Oculus & PA entry.

Intent to Issue Permit Cover Memo - [W:\SOLID WASTE - DO NOT DELETE\Permits_Backup-sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 intent.cvr \(87895\).doc](#)
Intent to Issue - [W:\SOLID WASTE - DO NOT DELETE\Permits_Backup-sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue \(87895\).doc](#)
Notice of Proposed Agency Action - [W:\SOLID WASTE - DO NOT DELETE\Permits_Backup-sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 NAA \(87895\).doc](#)
Draft Permit 177982-019-SC/T3 - [W:\SOLID WASTE - DO NOT DELETE\Permits_Backup-sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 permit \(87895\) \[DRAFT\].doc](#)
Draft Permit 177982-020-SO/T3 - [W:\SOLID WASTE - DO NOT DELETE\Permits_Backup-sgm\pasco\Enterprise\177982-020-SO-T3 \(87895\)\177982-020-SO-T3 permit \(87895\) \[DRAFT\].doc](#)

Day 90 is 7/17/13.

OCULUS Information:

Catalog: Solid Waste
Profile: Permit Authorization
County: Pasco
Facility ID: 87895
Document Type: Intent to Issue/Deny Related
Facility Type(s): Class III LF
Document Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III LF Intent & Draft Permits

PA Information:

Site #: 177982
Project #: 019
Expiration Date: TBD

Events

Mail Public Notice of Intent to Applicant Status: Done End Date: (date clerked)

Site #: 177982
Project #: 020
Expiration Date: TBD

Events

Mail Public Notice of Intent to Applicant Status: Done End Date: (date clerked)

Please feel free to e-mail or call me if you have any further questions.

Steven G. Morgan, Waste Management Section
Florida Department of Environmental Protection
Southwest District Office
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926

phone - (813) 632-7600 **ext 329**
fax - (813) 632-7672
e-mail - steve.morgan@dep.state.fl.us

From: [Brantley, Anna](#) on behalf of [SWD_Clerical](#)
To: [Butler, Linda](#)
Subject: FW: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits
Date: Thursday, June 13, 2013 12:16:28 PM

For review and process

From: Morgan, Steve
Sent: Thursday, June 13, 2013 12:02 PM
To: SWD_Clerical
Subject: FW: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

Please process as indicated below.

Please feel free to e-mail or call me if you have any further questions.

Steven G. Morgan, Waste Management Section
Florida Department of Environmental Protection
Southwest District Office
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926

phone - (813) 632-7600 **ext 329**
fax - (813) 632-7672
e-mail - steve.morgan@dep.state.fl.us

From: Greenwell, Jeff
Sent: Thursday, June 13, 2013 11:53 AM
To: Morgan, Steve
Subject: RE: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

I have signed the ITI. Please process accordingly.

Thanks,
jsg

From: Morgan, Steve
Sent: Monday, June 10, 2013 9:35 AM
To: Greenwell, Jeff
Subject: Enterprise Class III LF 177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue & Draft Permits

Jeff:

Please review the hyperlinks for the Intent to Issue, Notice of Proposed Agency Action, and Draft Permit. Please electronically initial the intent to issue routing memo and sign the Intent to Issue. Once signed, forward to support staff for dating, clerking, scanning, e-mailing and Oculus & PA entry.

Intent to Issue Permit Cover Memo – [W:\SOLID WASTE - DO NOT DELETE\Permits Backup-
sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 intent cvr
\(87895\).doc](#)

Intent to Issue – [W:\SOLID WASTE - DO NOT DELETE\Permits Backup-sgm\pasco\Enterprise\177982-019-SC-
T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 Intent to Issue \(87895\).doc](#)

Notice of Proposed Agency Action - [W:\SOLID WASTE - DO NOT DELETE\Permits Backup-
sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 & 11982-020-SO-T3 NAA \(87895\).doc](#)

Draft Permit 177982-019-SC/T3 - [W:\SOLID WASTE - DO NOT DELETE\Permits Backup-
sgm\pasco\Enterprise\177982-019-SC-T3 \(87895\)\177982-019-SC-T3 permit \(87895\) \[DRAFT\].doc](#)

Draft Permit 177982-020-SO/T3 - [W:\SOLID WASTE - DO NOT DELETE\Permits Backup-
sgm\pasco\Enterprise\177982-020-SO-T3 \(87895\)\177982-020-SO-T3 permit \(87895\) \[DRAFT\].doc](#)

Day 90 is 7/17/13.

OCULUS Information:

Catalog: Solid Waste

Profile: Permit Authorization

County: Pasco

Facility ID: 87895

Document Type: Intent to Issue/Deny Related

Facility Type(s): Class III LF

Document Subject: 177982-019-SC/T3 & 177982-020-SO/T3 Enterprise Class III LF Intent & Draft Permits

PA Information:

Site #: 177982

Project #: 019

Expiration Date: TBD

Events

Mail Public Notice of Intent to Applicant Status: Done End Date: (date clerked)

Site #: 177982

Project #: 020

Expiration Date: TBD

Events

Mail Public Notice of Intent to Applicant Status: Done End Date: (date clerked)

Please feel free to e-mail or call me if you have any further questions.

Steven G. Morgan, Waste Management Section
Florida Department of Environmental Protection
Southwest District Office
13051 North Telecom Parkway
Temple Terrace, FL 33637-0926

phone - (813) 632-7600 **ext 329**

fax - (813) 632-7672

e-mail - steve.morgan@dep.state.fl.us