Jacksonville Area Landfills 5110 U.S. Highway 301 P.O. Box 548 Baldwin, Florida 32234 904/289-9100 • FAX: 904/289-9013



A Waste Management Company

33628

September 26, 1994

Ms. Mary Nogas, P.E. Florida Department of Environmental Protection 7825 Bay Meadows Way, Suite B-200 Jacksonville, Florida 32256-7577

Re:

Trail Ridge Landfill, Inc.) Permit # SC16-184444

Application for Permit Modification

Dear Ms. Nogas:

Attached is a completed permit application requesting a modification to the above referenced permit. This modification is necessary in order to comply with recent changes made to Chapter 17-701.510 (Water Quality and Leachate Monitoring Requirements). More specifically, we request that all monitoring wells, surface water, and leachate sampling be conducted semi-annually in accordance with Chapter 17-701.510 (1) (a) F.A.C.

I am familiar with and have reviewed the hydrogeology and the historical analytical data of the site. Based on this information, it appears that there are no karst areas or other highly transmissive zones. Also, there is a predominant direction of ground water and surface water flow from west to east as documented by submittal of ground water elevation contour data. The current monitoring system is designed to intercept ground water flow in this direction or any minor deviations to the north or south. Considering these factors, and a composite double liner underlying the site, semi-annual monitoring is an appropriate monitoring frequency for this facility.

As we discussed, there are no fees associated with this modification since it is a result of changes made to Chapter 17-701 F.A.C.

If you have any questions or comments concerning this submittal, please give me a call at 289-9100.

Sincerely,

Scott W. McCallister, P.G. Senior Environmental Engineer

SWM:lh Enclosure

cc:

Greg Mathes Scott Kelly


(



Florida Department of Environmental Regulation

Twin Towers Office Bldg. • 2600 Blair Stone Road • Tallahassee, Florida 32399-2400

DER Form # 17-70	01.900(1)
Form Tide Solid W	aste Permit Application
Effective Date_Jane	uery 6, 1993
DER Application No	
	(Filled in by DER



STATE OF FLORIDA
DEPARTMENT OF ENVIRONMENTAL REGULATION

SOLID WASTE MANAGEMENT FACILITY PERMIT

APPLICATION INSTRUCTIONS AND FORMS

INSTRUCTIONS TO APPLY FOR A SOLID WASTE MANAGEMENT PERMIT

I. General

Solid Waste Management Facilities shall be permitted pursuant to Section 403.707, Florida Statutes, (FS) and in accordance with Florida Administrative Code (FAC) Rule 17-701. A minimum of six copies of the application shall be submitted to the Department District Office having jurisdiction over the facility. The appropriate fee in accordance with Chapter 17-4, FAC, and Rule 17-701.320(5)(c), FAC, shall be submitted with the application by check made payable to the Department of Environmental Regulation (DER).

Complete appropriate sections for the type of facility for which application is made. Entries shall be typed or printed in ink. All blanks shall be filled in or marked "not applicable" or "no substantial change". Information provided in support of the application shall be marked "submitted" and the location of this information in the application package indicated. The application shall include all information, drawings, and reports necessary to evaluate the facility. Information required to complete the application is listed on the attached pages of this form.

II. Application Parts Required for Construction and Operation Permits

- A. Landfills and Ash Monofills Submit parts A,B, D through Q, and S
- B. Asbestos Monofills Submit parts A,B,D,E,F,I,K, M through Q, and S
- C. Industrial Solid Waste Facilities Submit parts A,B, D through Q, and S
- D. Volume Reduction Facilities Submit parts A,C,D,R, and S

NOTE: Portions of some parts may not be applicable.

NOTE: For facilities that have been satisfactorily constructed in accordance with their construction permit, the information required for A,B,C and D type facilities does not have to be resubmitted for an operation permit if the information has not substantially changed during the construction period. The appropriate portion of the form should be marked "no substantial change".

III. Application Parts Required for Closure Permits

- A. Landfills and Ash Monofills Submit parts A,B, N through Q, and S
- B. Asbestos Monofills Submit parts A,B, M through Q, and S
- C. Industrial Solid Waste Facilities Submit parts A,B, N through Q, and S
- D. Volume Reduction Facilities Submit parts A,C,R, and S

NOTE: Portions of some parts may not be applicable.

IV. Permit Renewals

The above information shall be submitted at time of permit renewal in support of the new permit. However, facility information that was submitted to the Department to support the expiring permit, and which is still valid, does not need to be re-submitted for permit renewal. Portions of the application not re-submitted shall be marked "no substantial change" on the application form.

V. Application Codes

S - Submitted

LOCATION - Physical location of information in application

N/A - Not Applicable

N/C - No Substantial Change

VI. LISTING OF APPLICATION PARTS

PART A	4 -	GENERAL INFORMATION
PART E	3 -	DISPOSAL FACILITY GENERAL INFORMATION
PART (-	VOLUME REDUCTION FACILITY GENERAL INFORMATION
PART I	-	SOLID WASTE MANAGEMENT FACILITY PERMIT GENERAL REQUIREMENTS
PART E	-	LANDFILL PERMIT GENERAL REQUIREMENTS
PART F	-	GENERAL CRITERIA FOR LANDFILLS
PART G	; <u>-</u>	LANDFILL CONSTRUCTION REQUIREMENTS
PART H	· -	HYDROGEOLOGICAL INVESTIGATION REQUIREMENTS
PART I	-	GEOTECHNICAL INVESTIGATION REQUIREMENTS
PART J	-	VERTICAL EXPANSION OF LANDFILLS
PART K	_	LANDFILL OPERATION REQUIREMENTS
PART L	-	WATER QUALITY AND LEACHATE MONITORING REQUIREMENTS
PART M	-	SPECIAL WASTE HANDLING REQUIREMENTS
PART N	-	LANDFILL CLOSURE REQUIREMENTS
PART O	-	CLOSURE PROCEDURES
PART P	-	LONG TERM CARE REQUIREMENTS
PART Q	-	FINANCIAL RESPONSIBILITY REQUIREMENTS
PART R	-	VOLUME REDUCTION PLANT REQUIREMENTS
PART S	-	CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

STATE OF FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION

APPLICATION FOR PERMIT TO CONSTRUCT, OPERATE, MODIFY OR CLOSE A SOLID WASTE MANAGEMENT FACILITY

Please Type or Print

A.	GENERAL INFORMATIO	N		
1.	Type of facility:			
	Disposal [X]			
	Class I Land Class II Land Class III Land Other	dfill []	Ash Monofill Asbestos Monofill Industrial Solid Waste	[]
	Volume Reduction	[]		
	Incinerator Composting Materials Red Other	[] covery [] []	Pulverizer/Shredder Compactor/Baling Plant Energy Recovery	[]
! .	Type of application	1:		
	Construction Operation	(x)	Construction/Operation Closure	
	Classification of a	application:		
	New Renewal	[]	Substantial Modification Minor Modification	[X]
	racifity name:	ail Ridge Landfi		
	DER ID number:	S3116P03090	Duva County:	1
	Facility location (main entrance):	5110 U.S. Hwy 301	
			Baldwin, FL 32234	
•	Location coordinate	.s:		
-	Section: $20,21$ Tow		Range: 23E	
	UTMs: Zone	km E	km N	
	Latitude: 30 0	14 • 00 "	Longitude: 82 0 02 ·	30 •
•	Applicant name (ope	rating authorit	y): Trail Ridge Landfill,	Inc.
	Mailing address: 5.	110 US Hwy 301 treet or P.O. B		FL 32234 State Zip
	Contact person:	Scott McCalliste	er Telephone:	(⁹⁰⁴) 289-9100
	Title: Sr. Environ	mental Engineer		

9.	Authorized agent/Consultant: N/A
	Mailing address: Street or P.O. Box City State Zip
	Contact person: Telephone: ()
	Title:
10.	Landowner(if different than applicant): City of Jacksonville
	Mailing address: Street or P.O. Box City State Zip
	Contact person: Telephone: ()
11.	Cities, towns and areas to be served: Jacksonville and neighboring environs
12.	Population to be served: Current: approx. 660,000 Five-Year Projection: 2010 projection 781,000 Volume of solid waste to be received: Max. 3000 Yes 3/day tons/day gallons/day
14.	Date site will be ready to be inspected for completion: N/A
15.	Estimated life of facility: 18 years
16.	Estimated costs:
	Total Construction: \$ N/A Closing Costs: \$ N/C
17.	Anticipated construction starting and completion dates:
	From:N/A To:N/A

N/C
Facility site supervisor: • Greg Mathes
Title:Division President & Gen. Mgr. Telephone: (904) 289-9100
Disposal area: Total 176 acres; Used 46 acres; Available 130 acres
Weighing scales used: Yes [X] No []
Security to prevent unauthorized use: Yes $[X]$ No $[\]$
Charge for waste received:\$/yds ³ 59.00 \$/ton
Surrounding land use, zoning:
Residential [] Industrial [] Agricultural [X] None [] Commercial [] Other []
Types of waste received:
Residential [] C & D debris [] Commercial [] Shredded/cut tires [] Incinerator/WTE ash [] Yard trash [] Treated biohazardous [] Septic tank [] Water treatment sludge [] Industrial [] Air treatment sludge [] Industrial sludge [] Agricultural [] Domestic sludge [] Asbestos [] Other [] N/C
Salvaging permitted: Yes $[]$ No $[X]$
Attendant: Yes $[X]$ No $[X]$ Trained operator: Yes $[X]$ No $[X]$
Spotters: Yes [X] No [] Number of spotters used: N/C
Site located in: Floodplain [] Wetlands [] Other [] N/C
Property recorded as a Disposal Site in County Land Records: Yes [X] No
Days of operation: Monday - Saturday
Hours of operation: 6 a.m 7 p.m.
Days Working Face covered: <u>daily</u>
Elevation of water table: variesft. NGVD

19.	Number of surface monitoring points:	3
20.	Gas controls used: Yes $\{^X\}$ No $\{$ $\}$	Type controls: Active $\{\ \}$ Passive $\{\ ^X\}$
	Gas flaring: Yes $\{\ \}$ No $\{\ ^{ ext{X}}\}$	Gas recovery: Yes $\{\ \}$ No $\{^X\}$
21.	Leachate control method - liner type	: :
	Natural soils Single clay liner Single geomembrane Single composite Slurry wall Other []	Double geomembrane [] Geomembrane & composite [] Double composite [] None [] double geomembrane & composite
22.	Leachate collection method:	
	Collection pipes [X] Geonets [X] Well points [] Perimeter ditch [] Other []	Sand layer [X] Gravel layer [] Interceptor trench [] None []
23.	Leachate storage method:	
	Tanks [X] Other []	Surface impoundments []
24.	Leachate treatment method:	
	Oxidation [] Secondary [] Advanced [] Other []	Chemical treatment [] Settling [] None [X]
25.	Leachate disposal method:	
	Recirculated [] Transported to WWTP [X] Injection well [] Other []	Pumped to WWTP [] Discharged to surface water [] Evaporation (ie: Perc Pond) []
26.	For leachate discharged to surface wa	
	Name and Class of receiving wat	N/A ter:
27.	Storm Water:	
	Collected: Yes $\{{}^{X}\}$ No $\{{}^{T}\}$	Type of treatment: Retention
	Name and Class of receiving wat	ter: Headwaters of Deep Creek
28.	Management and Storage of Surface Wat	ters (MSSW) Permit number or status: N/A

Facility site supervisor:	
Citle:	Telephone: ()
Disposal area: Total acres; Use	ed acres; Available acres
Security to prevent unauthorized use:	Yes [] No []
Site located in: Floodplain [] We	etlands [] Other []
ays of operation:	
ours of operation:	·
umber of operating staff:	
xpected useful life: Years	
eighing scales used: Yes [] No []	
ormal processing rate: yd ³ /day	tons/day gal/day
aximum processing rate:yd ³ /day	tons/day gal/day
harge for waste received:	
ype of facility (check one or more):	
Pulverizer/shredder [] Compactor/baling []	Energy recovery []
aterial recovered, tons/week:	
Paper Ferrous metals Aluminum Other:	Glass Non-ferrous metals Plastics
nergy recovery, in units shown:	
High pressure steam, lb/h Low pressure steam, lb/hr Electricity, kw/hr Gas, ft /hr	Chilled water, gal/hr Oil, gal/hr Oil, BTU/hr

17.	Process water management:
	Recycled: Yes [] No []
	Treatment method used:
	Discharged to: Surface waters [] Underground [] Other []
	Name and Class of receiving water:
18.	Storm Water:
	Collected: Yes [] No [] Type of treatment:
	Name and Class of receiving water:
19.	MSSW Permit number or status:
20.	Final residue produced:
	% of normal processing rate
	% of maximum processing rate
	Disposed of at (Site name):
21.	Supplemental fuel used:
	Type: Quantity used/hour:
22.	Costs:
	Estimated operating costs (material-energy revenue): \$
	Total cost/ton: \$ Net cost/ton: \$
23.	State pollution control bond financing amount: \$
24.	Estimated amount of tax exemptions that will be requested: \$
	, -

D.	SOLID WASTE	MANAG	EMENT	FACILI:	TY FERMIT GENERAL REQUIREMENTS (17-701.320, FAC)
<u>s</u>	LOCATION	N/A	N/C		
<u>X</u>	Attached		_	1.	Six copies, at minimum, of the completed application form, all supporting data and reports; (17-701.320(5)(a),FAC)
<u>X</u>	Attached			2.	Engineering and/or professional certification (signature, date and seal) provided on the applications and all engineering plans, reports and supporting
<u>x</u>	Attached			3.	information for the application; (17-701.320(6),FAC) A letter of transmittal to the Department; (17-701.320(7)(a),FAC)
<u>X</u>	Attached			4.	A completed application form dated and signed by the applicant; (17-701.320(7)(b),FAC)
		<u>X</u>		5.	Permit fee specified in Rule 17-4.050, FAC and Rule 17-7-1.320(5)(c), FAC in check or money order, payable to the Department; (17-701.320(7)(c),FAC)
			<u>X</u>		An engineering report addressing the requirements of this rule and with the following format: a cover sheet, text printed on 8 1/2 inch by 11 inch consecutively numbered pages, a table of contents or index, the body of the report and all appendices including an operation plan, contingency plan, illustrative charts and graphs, records or logs of tests and investigations, engineering calculations; (17-701.320(7)(d),FAC))
			X	7.	Operation Plan; (17-701.320(7)(e)1,FAC)
			<u> </u>	8.	Contingency Plan; (17-701.320(7)(e)2,FAC)
					Plans or drawings for the solid waste management facilities in appropriate format (including sheet size restrictions, cover sheet, legends, north arrow, horizontal and vertical scales, elevations referenced to NGVD) showing; (17-702.320(7)(f),FAC)
			<u>X</u>		a. A regional map or plan with the project location;
			<u> </u>		 A vicinity map or aerial photograph no more than 1 year old;
			<u>X</u>		c. A site plan showing all property boundaries certified by a registered Florida land surveyor;
			X		d. Other necessary details to support the engineering report.
 .	····		<u>X</u>	i	Proof of property ownership or a copy of appropriate agreements between the facility operator and property owner authorizing use of property; (17-701.320(7)(g),FAC)

<u>s</u>	LOCATION	N/A	N/C		
		· _	<u> </u>	11.	For facilities owned or operated by a county, provide description of how, if any, the facilities covered in this application will contribute to the county's achievement of recycling goals contained in Section 403.706,FS; (17-701.320(7)(h),FAC)
			<u>X</u>	12.	Provide a history and description of any enforcement actions taken by the Department against the applicant for violations of applicable statutes, rules, orders or permit conditions relating to the operation of any solid waste management facility in this state; (17-701.320(7)(i),FAC)
			<u>X</u>	13.	Proof of publication in a newspaper of general circulation of notice of application for a permit to construct or substantially modify a solid waste management facility; (17-702.320(8),FAC)
			<u>X</u>	14.	Provide a description of how the requirements for airport safety will be achieved including proof of required notices if applicable; (17-701.320(12),FAC)
E.	LANDFILL PE	RMIT G	ENERAL	REQUI	REMENTS (17-701.330, FAC)
			<u>X</u>	1.	Vicinity map or aerial photograph no more than 1 year old and of appropriate scale showing land use and local zoning within one mile of the landfill and of sufficient scale to show all homes or other structures, water bodies, and roads other significant features of the vicinity. All significant features shall be labeled; (17-701.330(4)(a),FAC)
		·	<u>X</u>	2.	Vicinity map or aerial photograph no more than 1 year old showing all airports that are located within five miles of the proposed landfill; (17-701.330(4)(b),FAC)
			<u>X</u>	3.	Plot plan with a scale not greater than 200 feet to the inch showing; (17-701.330(4)(c),FAC)
			<u>X</u>		a. Dimensions;
 .			<u>_x</u>		b. Locations of proposed and existing water quality monitoring wells;
		•	<u>X</u>		c. Locations of soil borings;
			<u>X</u>		d. Proposed plan of trenching or disposal areas;
 -			<u> </u>	•	e. Cross sections showing original elevations and proposed final contours which shall be included either on the plot plan or on separate sheets;
		<u>X</u>			f. Any previously filled waste disposal areas;
			X		g. Fencing or other measures to restrict access.

<u>s</u>	LOCATION	N/A	N/C	4.	Topographic maps with a scale not greater than 200 feet to the inch with 5-foot contour intervals showing; (17-701.330(4)(d),FAC)
			<u>X</u>		a. Proposed fill areas;
			<u> </u>		b. Borrow areas;
· ——			<u>X</u>		c. Access roads;
			<u>X</u>		d. Grades required for proper drainage;
			<u>X</u>		e. Cross sections of lifts;
			<u>_x</u>		f. Special drainage devices if necessary;
			<u>X</u>		g. Fencing;
			<u>X</u>		h. Equipment facilities.
				5.	A report on the landfill describing the following; (17-701.330(4)(e),FAC)
			<u> </u>		a. The current and projected population and area to be served by the proposed site;
	····		<u>X</u>		b. The anticipated type, annual quanity, and source of solid waste, expressed in tons;
			<u>X</u>		c. The anticipated facility life;
_			<u>X</u>		d. The source and type of cover material used for the landfill.
			<u>X</u>	6.	Provide evidence that an approved laboratory shall conduct water quality monitoring for the facility in accordance with Rule 17-160, FAC; (17-701.330(4)(h), FAC)
			<u>X</u>	7.	Provide a statement of how the applicant will demonstrate financial responsibility for the closing and long-term care of the landfill; (17-701.330(4)(i),FAC)
F.	GENERAL CRII	ERIA	FOR LA	NDFILL	s (17-701.340,FAC)
			<u>X</u>	1.	Describe (and show on a Federal Insurance Administration flood map, if available) how the landfill or solid wasted disposal unit shall not be located in the 100-year floodplain where it will restrict the flow of the 100-year flood, reduce the temporary water storage capacity of the floodplain unless compensating storage is provided, or result is a washout of solid waste; (17-701.340(4)(b),FAC)
			<u>X</u>	2.	Describe how the minimum horizontal separation between waste deposits in the landfill and the landfill property boundary shall be 100 feet, measured from the toe of the proposed final cover slope; (17-701.340(4)(c),FAC)
			<u>X</u>	3.	Describe what methods shall be taken to screen the landfill from public view where such screening can practically be provided; (17-701.340(4)(d),FAC)

<u>s</u>	LOCATION	N/A	N/C				
G.	LANDFILL CO	NSTRUC	TION	REQUIR	EMENTS	(17-7	01.400,FAC)
_			<u>X</u>	1.	solid close	d wast	ow the landfill shall be designed so that e disposal units will be constructed and lanned intervals throughout the design period dfill; (17-701.400(2),FAC)
				2.	Landi	Eill 1.	iner requirements; (17-701.400(3),FAC)
					a.		ral construction requirements; 701.400(3)(a),FAC)
			<u>X</u>			(1)	Provide test information and documentation to ensure the liner will be constructed of materials that have appropriate physical, chemical, and mechanical properties to prevent failure;
			<u>X</u>			(2)	Document foundation is adequate to prevent liner failure;
			<u>_X</u>			(3)	Constructed so bottom liner will not be adversely impacted by fluctuations of the ground water;
		X				(4)	Designed to resist hydrostatic uplift if bottom liner located below seasonal high ground water table;
	· · · · · · · · · · · · · · · · · · ·	_	<u>X</u>			(5)	Installed to cover all surrounding ear+ which could come into contact with t waste or leachate.
	,				b.	Compo	site liners; (17-701.400(3)(b),FAC)
 .			<u>X</u>			(1)	Upper geomembrane thickness and properties;
 -			<u>X</u>			(2)	Design leachate head for primary LCRS including leachate recirculation if appropriate;
			<u>X</u>			(3)	Design thickness in accordance with Table A and number of lifts planned for lower soil component.
					c.	Doubl	e liners; (17-701.400(3)(c),FAC)
			<u>X</u>			(1)	Upper and lower geomembrane thicknesses and properties;
 -			<u>X</u>			(2)	Design leachate head for primary LCRS to limit the head to one foot above the liner;
			X			(3)	Lower geomembrane sub-base design;
			<u>X</u>			(4)	Leak detection and secondary leachate collection system minimum design criteria $(k \ge 1 \text{ cm/sec}, \text{ head on lower liner} \le 1 \text{ inch, head not to exceed thickness of drainage layer)}$:

-	TONNMINI	AT / PA	N/C			
<u>s</u>	LOCATION	N/A	<u>N/C</u>	d.		dards for geomembranes; 701.400(3)(d),FAC)
			<u>_X</u>		(1)	Field seam test methods to ensure all field seams are at least 90 percent of the yield strength for the lining material;
			<u>X</u>		(2)	Design of 24-inch-thick protective layer above upper geomembrane liner;
			X		(3)	Describe operational plans to protect the liner and leachate collection system when placing the first layer of waste above 24-inch-thick protective layer.
				e.		ynthetic specification requirements; 701.400(3)(e),FAC)
			<u>X</u>		(1)	Definition and qualifications of the designer, manufacturer, installer, QA consultant and laboratory, and QA program;
			<u>X</u>		(2)	Material specifications for geomembranes, geotextiles, geogrids, and geonets;
			X		(3)	Manufacturing and fabrication specifications including geomembrane raw material and roll QA, fabrication personnel qualifications, seaming equipment and procedures, overlaps, trial seams, destructive and nondestructive seam testing, seam testing location, frequency, procedure, sample size and geomembrane repairs;
			X		(4)	Geomembrane installation specifications including earthwork, conformance testing, geomembrane placement, installation personnel qualifications, field seaming and testing, overlapping and repairs, materials in contact with geomembrane and procedures for lining system acceptance;
		-	_X_		(5)	Geotextile and geogrid specifications including handling and placement, conformance testing, seams and overlaps, repair, and placement of soil materials;
			X		(6)	Geonet specifications including handling and placement, conformance testing, stacking and joining, repair, and placement of soil materials;
				f.		ards for soil components; 01.400(3)(f),FAC)
 ·			_X_		(1)	Description of construction procedures including overexcavation and backfilling to preclude structural inconsistencies and procedures for placing and compacting soil component in layers;

X (2) Demonstration of compatibility of component with actual or simulated in accordance with EPA Test Method an equivalent test method; X (3) Procedures for testing in-situ a demonstrate they meet the specific for soil liners; (4) Specifications for soil component including at a minimum: X (a) Allowable particle size distr. Atterberg limits, shrinkage. X (b) Placement moisture and dry criteria; X (c) Maximum laboratory-det. X (d) Minimum thickness of soil limits, shrinkage. X (d) Minimum thickness of soil limits, shrinkage. X (e) Lift thickness; X (f) Surface preparation (scarification of the status of the soil component; X (g) Type and percentage of clay within the soil component; X (f) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the fill thickness	S LOCAT	ION N/A N	<u>/c</u>				•	
demonstrate they meet the specif for soil liners; (4) Specifications for soil component including at a minimum: X (a) Allowable particle size distr. Atterberg limits, shrinkage. X (b) Placement moisture and dry criteria; X (c) Maximum laboratory-det. saturated hydraulic condusing simulated leachate; (d) Minimum thickness of soil linerates. X (e) Lift thickness; X (f) Surface preparation (scarification within the soil component; X (g) Type and percentage of clay within the soil component; X (s) Procedures for constructing and field test section to document the saturated hydraulic conductive thickness can be achieved in the file thickness can be achieved in the f		<u> </u>		(2)	component	: with actual or dance with EPA T	simulated lead Sest Method 910	chate
including at a minimum: X (a) Allowable particle size distr. Atterberg limits, shrinkage. X (b) Placement moisture and dry criteria; X (c) Maximum laboratory-dett. saturated hydraulic condusing simulated leachate; (d) Minimum thickness of soil limits. X (e) Lift thickness; X (f) Surface preparation (scarification of the soil component; X (g) Type and percentage of clay within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivit thickness can be achieved in the first section and removal system (LCRS); (17-701.400(4),FAC) 3. Leachate collection and removal system (LCRS); (17-701.400(4),FAC) X (1) Constructed of materials characterist of the waste and leachate present collapse under pressure; X (2) Have sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging;		<u> </u>	_	(3)	demonstra	ite they meet		
X (b) Placement moisture and dry criteria; X (c) Mainmum laboratory-dett saturated hydraulic condusing simulated leachate; X (d) Minimum thickness of soil link X (e) Lift thickness; X (f) Surface preparation (scarific saturated hydraulic conductivity within the soil component; X (g) Type and percentage of clay within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the fit saturated hydraulic achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be achieved in the fit of the saturated hydraulic conductivity thickness can be				(4)	Specification including	tions for soil at a minimum:	component of 1	iner
Criteria; (c) Maximum laboratory-dete saturated hydraulic condusing simulated leachate; (d) Minimum thickness of soil ling to be saturated hydraulic condusing simulated leachate; (d) Minimum thickness of soil ling to be saturated hydraulic conductivity thickness; (g) Type and percentage of clay within the soil component; (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section and removal system (LCRS); (17-701.400(4),FAC) a. The primary and secondary LCRS requirem (17-701.400(4)(a),FAC) X (1) Constructed of materials characteristation to the waste and leachated resistant to the waste and leachated for the strong and conductivity thickness can be achieved in the field test section and removal system (LCRS); (17-701.400(4)(a),FAC) A (1) Constructed of materials characteristation to the waste and leachated resistant to the waste and leachated for testing and conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document; and the field test section to document; and the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section to document the			<u> </u>					
Saturated hydraulic condusing simulated leachate; X			<u>.</u>				e and dry den	sity
X (e) Lift thickness; X (f) Surface preparation (scarific X) X (g) Type and percentage of clay within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the fit 3. Leachate collection and removal system (LCRS); (17-701.400(4),FAC) a. The primary and secondary LCRS requirem (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachate x and the collection and control of the collection and removal system (LCRS); (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachate x			<u>-</u>		sat	urated hydrau	lic conducti	
X (f) Surface preparation (scarific X (g) Type and percentage of clay within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the fit 3. Leachate collection and removal system (LCRS); (17-701.400(4),FAC) a. The primary and secondary LCRS requirem (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachate resistant to the waste and leachate (2) Have sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contents and secondary the same and the		<u>X</u>	<u>. </u>		(d) Min	imum thickness	of soil liner;	
(f) Surface preparation (starfied within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section and removal system (LCRS); (17-701.400(4),FAC) a. The primary and secondary LCRS requirem (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachated for the sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contact the sufficient mechanical proper prevent clogging;		<u> </u>	<u>-</u>		(e) Lif	t thickness;		
within the soil component; X (5) Procedures for constructing and field test section to document the saturated hydraulic conductivity thickness can be achieved in the field test section and removal system (LCRS); (17-701.400(4),FAC) a. The primary and secondary LCRS requirem (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachated fresistant to the waste and leachated proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contact the section of the sectio		X	<u>.</u>		(f) Sur	face preparatio	n (scarificati	on);
field test section to document the saturated hydraulic conductivit thickness can be achieved in the fit thickness can be a		<u>X</u>						eral
(17-701.400(4),FAC) a. The primary and secondary LCRS requiremediate (17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachate (1) and the waste and leachate (1) and the waste and leachate (2) have sufficient mechanical proper prevent collapse under pressure; X (2) Have sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contact (1) and the contact (1)		<u>x</u>	_	(5)	field tes	t section to do hydraulic	cument the des	ired and
(17-701.400(4)(a),FAC) X (1) Constructed of materials che resistant to the waste and leachate X (2) Have sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and or			3. Lead				em (LCRS);	
resistant to the waste and leachate X (2) Have sufficient mechanical proper prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contents.			a.				S requirements	;
prevent collapse under pressure; X (3) Have granular material or sy geotextile to prevent clogging; X (4) Have method for testing and contact the statement of the statement o		<u> </u>	-	(1)				ally
geotextile to prevent clogging; X (4) Have method for testing and continuous continuou		<u>X</u>	_	(2)				to
		<u>x</u>	-	(3)				etic
rerouting leachate around failed ar		<u> </u>	-	(4)	clogged p	ipes or contin	ngent designs	for

<u>s</u>	LOCATION	<u>N/A</u>	N/C		b.	Primary	LCRS requirements; (17-701.400(4)(b),FAC)
			<u>X</u>				ottom 12 inches having hydraulic onductivity $\geq 1 \times 10^{-3}$ cm/sec;
			<u>X</u>			Ċ	otal thickness of 24 inches of material hemically resistant to the waste and eachate;
			<u>x</u>				ottom slope design to accomodate for redicted settlement;
			X			m t	emonstration that synthetic drainage aterial, if used, is equivalent or better han granular material in chemical empatibility, flow under load and rotection of geomembrane liner.
				4.	Leach	ate reci	rculation; (17-701.400(5),FAC)
		X			a.	Describ leachat	e general procedures for recirculating
		<u>X</u>			b.	runoff	e procedures for controlling leachate and minimizing mixing of leachate runoff orm water;
		<u>X</u>			c.		e procedures for preventing perched water ons and gas buildup;
*		<u>X</u>			d.	weather wind-blo	alternate methods for leachate ent when it cannot be recirculated due to or runoff conditions, surface seeps, own spray, or elevated levels of leachate the liner;
		<u>X</u>			e.		e methods of gas management to control ad migration of methane;
		<u>X</u>			f.	treatment treatment and pro	hate irrigation is proposed, describe at methods and standards for leachate at prior to irrigation over final cover wide documentation that irrigation does natribute significantly to leachate on.
				5.			orage tanks and leachate surface (17-701.400(6),FAC)
					a.		<pre>impoundment requirements; 400(6)(b),FAC)</pre>
 .		<u>X</u>) bd	cumentation that the design of the tom liner will not be adversely impacted fluctuations of the ground water;
		<u> </u>				in	signed in segments to allow for spection and repair as needed without terruption of service:

<u>s</u>	LOCATION	<u>n/a</u>	N/C		(3)	Gener	al design requirements;
		X				(a)	Double liner system consisting of arupper and lower 60-mil minimum thickness geomembrane;
		<u>X</u>				(Þ)	Leak detection and collection system with hydraulic conductivity > 1 cm/sec;
		<u>X</u>				(c)	Lower geomembrane placed on subbase \geq 6 inches thick with $k \leq 1 \times 10^{-5}$ cm/sec;
		<u>X</u>				(d)	Design calculation to predict potential leakage through the upper liner;
		<u>X</u>				(e)	Daily inspection requirements and notification and corrective action requirements if leakage rates exceed that predicted by design calculations;
		<u>X</u>			(4)		iption of procedures to prevent c, if applicable;
		<u>X</u>			(5)		n calculations to demonstrate minimum et of freeboard will be maintained;
		<u>x</u>			(6)	Proced site o	dures for controlling vectors and off- odors.
				b.			d leachate storage tanks; (6)(c),FAC)
			<u>X</u>		(1)		be tank materials of construction and foundation is sufficient to support
			<u>X</u>		(2)		be procedures for cathodic protection eded for the tank;
			X		(3)	lining	be exterior painting and interior of the tank to protect it from the er and the leachate stored;
			X		(4)	ensure and	be secondary containment design to adequate capacity will be provided compatibility of materials of suction;
			X		(5)		be design to remove and dispose of rater from the secondary containment
			X		(6)	as le	be an overfill prevention system such evel sensors, gauges, alarms and f controls to prevent overfilling;

<u>s</u>	LOCATION	<u>N/A</u>	N/C			(7)	_	ctions, corrective action and ting requirements;
			X				(a)	Overfill prevention system weekly;
			X				(b)	Exposed tank exteriors weekly;
							(C)	Tank interiors when tank is drained
							` '	or at least every three years;
			<u> </u>				(d)	Procedures for immediate corrective action if failures detected;
			<u>_X</u>				(e)	Inspection reports available for department review.
					C.			leachate storage tanks; (6)(d),FAC)
		<u>x</u>				(1)	Descr	ibe materials of construction;
		<u>X</u>				(2)		ble-walled tank design system to be with the following requirements;
		<u>X</u>					(a)	Interstitial space monitoring at least weekly;
		<u>X</u> .					(p)	Corrosion protection provided for primary tank interior and external surface of outer shell;
 ·		<u>X</u>					(c)	Interior tank coatings compatible with stored leachate;
 -		<u>X</u>					(d)	Cathodic protection inspected weekly and repaired as needed;
-		<u>X</u>				(3)	as l shuto	ibe an overfill prevention system such evel sensors, gauges, alarms and ff controls to prevent overfilling and de for weekly inspections;
		<u>X</u>				(4)	Inspe	ction reports available for department
		<u>X</u>			d.			ovided for routine maintenance of 01.400(6)(e),FAC)
				6.		system 7-701.		struction quality assurance (CQA): FAC)
			<u>X</u>		a.	Provi	de CQA	Plan including:
	 		X			(1)		fications and construction ements for liner system;
	***************************************		_X_			(2)		ed description of quality control og procedures and frequencies;
			<u>X</u>			(3)	Ident:	fication of supervising professional eer;

<u>s</u>	LOCATION	N/A	N/C				
		 ,	<u> </u>			(4)	Identify responsibility and authority all appropriate organizations and key personnel involved in the construction project;
			<u> </u>			(5)	State qualifications of CQA professional engineer and support personnel;
			<u> X</u>			(6)	Description of CQA reporting forms and documents;
			<u>X</u>		b.		ndependent laboratory experienced in the ng of geosynthetics to perform required ng;
				7.	Surfa	ce wat	er management systems; (17-701.400(9),FAC)
			_X		a.	isola	n of surface water management system to te surface water from waste filled areas and ntrol stormwater run-off;
			<u>_x</u>		b.		ls of stormwater control design including tion ponds, detention ponds, and drainage
				8.	Gas c	ontrol	systems; (17-701.400(10),FAC)
			<u>x</u>		a.	colle	n details for gas control system including ction pipes and vents, and passive venting cuum extraction details;
			<u> </u>		b.		entation that the gas control system wingpact the liner or leachate control system;
			<u> X</u>		с.	flari	sed methods, of odor control including ng designs in accordance with er 17-210, FAC;
					d.	to e	iption of a routine gas monitoring program name gas control system is operating rly including:
			X			(1)	Location of monitoring points;
			<u>X</u>			(2)	Requirements for quarterly sampling of all monitoring points;
			<u>X</u>			(3)	Description of corrective measures to be completed within 60 days of detection of elevated levels of explosive gases;
			X		e.	Descri method	ption of condensate collection and disposal s.
				9.	Landfi	ill gas	recovery facilities; (17-701.400(11),FAC)
			X		a.		nation required in Rules 17-701.320(7) and .330(4), FAC supplied;

<u>s</u>	LOCATION	N/A	N/C			
_			<u>X</u>		b.	Information required in Rule 17-701.600(4), FAC supplied where relevant and practical;
_			<u>X</u>		c.	Estimate of current and expected gas generation rates and description of condensate disposal methods provided;
		_	<u>X</u>		d.	Description of procedures for condensate sampling, analyzing and data reporting provided;
			<u>X</u>		e.	Closure plan provided describing methods to control gas after recovery facility ceases operation;
			<u>X</u>		f.	Performance bond provided to cover closure costs if not already included in other landfill closure costs.
		<u>X</u>	_	10.	docum prote liner	landfills designed in ground water, provide entation that the landfill will provide a degree of ction equivalent to landfills designed with bottom s not in contact with ground water; 01.400(12),FAC)
н.	HYDROGEOLOGI	CAL II	WEST1	GATION	REQUI	REMENTS (17-701.410, FAC)
				1.		t a hydrogeological investigation and site report ding at least the following information:
			X		a.	Regional and site specific geology and hydrogeology;
			<u>X</u>		b.	Direction and rate of ground water and surface water flow including seasonal variations;
			<u>X</u>		c.	Background quality of ground water and surface water;
			<u>X</u>		d.	Any on-site hydraulic connections between aquifers;
····			<u>X</u>		e.	Site stratigraphy and aquifer characteristics for confining layers, semi-confining layers, and all aquifers below the landfill site that may be affected by the landfill;
			<u>X</u>		f.	Site topography and soil characteristics;
			<u>_x_</u>		g.	Inventory of all public and private water wells within a one-mile radius of the landfill including well top of casing and bottom elevations, name of owner, age and usage of each well, stratigraphic unit screened, well construction technique and static water level;
			X		h.	Existing contaminated areas on landfill site.
			X	2.	Report	signed, sealed and dated by PE or PG.

				1.	the eng	geotechnical site investigation report defini. ineering properties of the site including a ne following:
<u>s</u>	LOCATION	N/A	N/C			
			<u>X</u>		80	escription of subsurface conditions including oil stratigraphy and ground water table and tions;
		-,	<u>_x</u>		fi	evestigate for the presence of muck, previously lled areas, soft ground, lineaments and sindles;
			<u>X</u>			timates of average and maximum high water table ross the site;
					d. Fo	undation analysis including:
			X		(1) Foundation bearing capacity analysis;
			<u> </u>		(2) Total and differential subgrade settlement analysis;
			<u> X</u>		(3) Slope stability analysis;
			<u>_x</u>		an re	scription of methods used in the investigation d includes soil boring logs, laboratory sults, analytical calculations, cross sections, terpretations and conclusions;
			X		f. Re	port signed, sealed and dated by PE or PG.
J.	VERTICAL EXP	ANSIO	OF I	ANDFIL	LS (17-70)	1.430,FAC)
		X		1.	contribut landfill	how the vertical expansion shall not cause or te to leachate leakage from the existing or adversely affect the closure design of the landfill;
		<u>X</u>		2.	landfills	how the vertical expansion over unlined will meet the requirements of Rule 17-701.400, the exceptions of Rule 17-701.430(1)(c),FAC;
		<u>X</u>		3.		foundation and settlement analysis for the expansion;
		X	***	4.	the final drainage,	otal settlement calculations demonstrating that elevations of the lining system, that gravity and that no other component of the design will sely affected;
 .		<u>X</u>		5.		stability safety factor of 1.5 for the lining mponent interface stability and deep stability;
<u> </u>		<u>X</u>		6.	managemen	documentation to show the surface water at system will not be adversely affected by the expansion;

I. GEOTECHNICAL INVESTIGATION REQUIREMENTS (17-701.420, FAC)

<u>s</u>	<u>LOCATION</u>	<u>n/a</u>	N/C		
_		<u>X</u>		7.	Provide gas control designs to prevent accumulation of gas under the new liner for the vertical expansion.
ĸ.	LANDFILL OP	ERATIO	N REQ	UIREME	NTS (17-701.500,FAC)
	<u></u>		<u>X</u>	1.	Provide documentation that landfill will have at least one trained operator during operation and at least one trained spotter at each working face; (17-701.500(1),FAC)
				2.	Provide a landfill operation plan including procedures for: (17-701.500(2), FAC)
			<u>X</u>		 Designating responsible operating and maintenance personnel;
	<u></u>		<u>X</u>		b. Contingency operations for emergencies;
			<u>X</u>		c. Controlling types of waste received at the landfill;
			<u>X</u>		d. Weighing incoming waste;
			<u>X</u>		e. Vehicle traffic control and unloading;
			<u>X</u>		f. Method and sequence of filling waste;
		_	<u>-x</u>		g. Waste compaction and application of cover;
			<u>X</u>		 Operations of gas, leachate, and stormwater controls;
			<u>X</u>		i. Water quality monitoring.
			<u> X</u>	3.	Provide a description of the landfill operation record to be used at the landfill; (17-701.500(3),FAC)
	-		<u>X</u>	4.	Describe the waste records that will be compiled monthly and provided to the Department quarterly; (17-701.500(4),FAC)
			<u>X</u>	5.	Describe methods of access control; (17-701.500(5),FAC)
			<u>x</u>	6.	Describe load checking program to be implemented at the landfill to discourage disposal of unauthorized wastes at the landfill; (17-701.500(6),FAC)
				7.	Describe procedures for spreading and compacting waste at the landfill that include: (17-701.500(7),FAC)
			<u>X</u>		a. Waste layer thickness and compaction frequencies;
			<u>X</u>		b. Special considerations for first layer of waste placed above liner and leachate collection system;
			X		c. Slopes of cell working face and side grades above land surface, planned lift depths during operation:

<u>s</u>	LOCATION	N/A	N/C			-
			<u>X</u>		d.	Maximum width of working face;
<u>s</u>	LOCATION	<u>n/a</u>	N/C			
			X		e.	Procedures for applying initial cover including minimum cover frequencies;
			X		f.	Procedures for applying intermediate cover;
			X		g.	Time frames for applying final cover;
			<u>X</u>		i.	Description of litter policing methods;
			<u>X</u>		j.	Erosion control procedures.
				8.		ribe operational procedures for leachate management uding; (17-701.500(8),FAC)
			<u>X</u>		a.	Leachate level monitoring, sampling, analysis and data results submitted to the Department;
_		_	<u>X</u>		b.	Operation and maintenance of leachate collection and removal system, and treatment as required;
			<u> </u>		c.	Procedures for managing leachate if it becomes regulated as a hazardous waste;
			X		d.	Agreements for off-site discharge and treatmen+ of leachate;
			X		e.	Contingency plan for managing leachate during emergencies or equipment problems;
			X		f.	Procedures for recording quantities of leachate generated in gal/day;
			X		g.	Procedures for comparing precipitation experienced at the landfill with leachate generation rates.
			<u>X</u>	9.	as re	ibe routine gas monitoring program for the landfill quired by Rule 17-701.400(10), FAC; 01.500(9), FAC)
			<u>X</u>	10.	landf stand	ibe procedures for operating and maintaining the ill stormwater management system to comply with the ards of Chapters 17-3, 17-302 and 17-25, FAC; 01.500(10),FAC)
				11.		ment and operation feature requirements; 01.500(11),FAC)
			<u>X</u>		a.	Sufficient equipment for excavating, spreading, compacting and covering waste;
			<u>X</u>		b.	Reserve equipment or arrangements to obtain additional equipment within 24 hours of breakdown:

<u>_s</u> _	LOCATION	<u>N/A</u>	N/C			
			<u>X</u>		c.	Communications equipment;
_			<u>X</u>		d.	Personnel shelter and sanitary facilities, first aid equipment;
			Х		_	Duck control methods:
					e.	Dust control methods;
			<u>X</u>		f.	Fire protection capabilities and procedures for notifing local fire department authorities in emergencies;
			<u>X</u>		g.	Litter control devices;
			<u>X</u>		h.	Signs indicating operating authority, traffic flow, hours of operation, disposal restrictions.
			<u>X</u>	12.	perim- which	de a description of all-weather access road, inside eter road and other roads necessary for access shall be provided at the landfill; 01.500(12),FAC)
				13.		ional record keeping and reporting requirements; 01.500(13),FAC)
			_X		a.	Records used for developing permit applications and supplemental information maintained for the design period of the landfill;
			<u>_x</u>		b.	Monitoring information, calibration and maintenance records, copies of reports required by permit maintained for at least 10 years;
			<u>X</u>		c.	Background water quality records shall be maintained for the design period of the landfill;
	·		<u>X</u>		d.	Maintain annual estimates of the remaining life of constructed landfills and of other permitted areas not yet constructed and submit this estimate annually to the Department.
t.	WATER QUALITY	Z AND	LEACH	ATE MON	NITORIN	NG REQUIREMENTS (17-701.510, FAC)
X	See Attached Le	tter		1.	submit water	quality and leachate monitoring plan shall be ted describing the proposed ground water, surface and leachate monitoring systems and shall meet at the following requirements;
		_	<u>X</u>		a.	Based on the information obtained in the hydrogeological investigation and signed, dated and sealed by the PG or PE who prepared it; (17-701.510(2)(a),FAC)
			<u>X</u>			All sampling and analysis preformed by organizations having Department approved Comprehensive Quality Assurance Plans; (17-701.510(2)(b),FAC)

<u>s</u>	LOCATION	N/A	N/C			/**
				c.		nd water monitoring requirements; 701.510(3),FAC)
			<u> </u>		(1)	Detection wells located downgradient from and within 50 feet of disposal units;
			<u>X</u>		(2)	Downgradient compliance wells as required;
			X		(3)	Background wells screened in all aquifers below the landfill that may be affected by the landfill;
			<u>X</u>		(4)	Location information for each monitoring well;
			<u>X</u>		(5)	Well spacing no greater than 500 feet apart for downgradient wells and no greater than 1500 feet apart for upgradient wells unless site specific conditions justify alternate well spacings;
 ·			<u> </u>		(6)	Well screen locations properly selected;
			<u>_x</u>		(7)	Procedures for properly abandoning monitoring wells;
		<u>X</u>			(8)	Detailed description of detection sensors if proposed.
				d.		ace water monitoring requirements; 701.510(4),FAC)
 -			<u>X</u>		(1)	Location of and justification for all proposed surface water monitoring points;
 -			<u>X</u>		(2)	Each monitoring location to be marked and its position determined by a registered Florida land surveyor;
			X	e.		nate sampling locations proposed; 01.510(5),FAC)
				f.	Routi (17-7	ne sampling frequency and requirements; 01.510(6),FAC)
X See	Attached Let	ter	—		(1)	Background ground water and surface water sampling and analysis requirements;
X Sam	e as above	 .			(2)	Leachate quarterly and annual sampling and analysis requirements;
X Sam	e as above	<u> </u>			(3)	Detection well quarterly sampling and analysis requirements;
X_Sam	e as above				(4)	Compliance well sampling and analysis as requirements;
X_Sam	e as above				(5)	Surface water sampling and analysis requirements.

		N/C					
See attached	le <u>tte</u> r			g.	monit	ibe procedures for implementing assessment oring and corrective action as required; 01.510(7),FAC)	
				h.		quality monitoring report requirements; 01.510(9),FAC)	
	<u> </u>				(1)	Quarterly report requirements;	
	<u>X</u>				(2)	Annual report requirements including a report submitted to the Department which is signed, dated and sealed by PG or PE.	
SPECIAL WAST	E HAND	LING	REQUIR	EMENTS	(17-	701.520, FAC)	
		<u>X</u>	1.			ocedures for managing motor vehicles; (1),FAC)	
		<u>X</u>	2.			ocedures for landfilling shredded waste; (3),FAC)	
		<u>X</u>	3.			ocedures for asbestos waste disposal; (4),FAC)	
LANDFILL FINA	AL CLO	SURE 1	REQUIRI	EMENTS	(17-7	701.600,FAC)	
			1.	Closur	e sche	edule requirements; (17-701.600(2),FAC)	
		X		a.	schedu Depart	entation that a written notice including a ule for closure will be provided to the tment at least one year prior to final ot of wastes;	
		X		b.		e to user requirements within 120 days of receipt of wastes;	
		X		_			
				c.		e to public requirements within 10 days of receipt of wastes.	
-			2.		final		
-		X	2.	Closur	final e perm: Applic	receipt of wastes.	
	·	_X_		Closur a.	final e perm Applic days p	receipt of wastes. it general requirements; (17-701.600(3),FAC) tation submitted to Department at least 90	
		<u>X</u>		Closur a. b.	final e perm: Applic days p Closur	receipt of wastes. it general requirements; (17-701.600(3),FAC) cation submitted to Department at least 90 prior to final receipt of wastes;	
				Closur a. b.	final e perm. Applic days p Closur (1)	receipt of wastes. it general requirements; (17-701.600(3),FAC) cation submitted to Department at least 90 prior to final receipt of wastes; ce plan shall include the following:	
		X		Closur a. b.	final e perm. Applic days p Closur (1) (2)	receipt of wastes. it general requirements; (17-701.600(3),FAC) cation submitted to Department at least 90 prior to final receipt of wastes; ce plan shall include the following: Closure report;	
		X X		Closur a. b.	final e perm. Applic days p Closur (1) (2) (3)	receipt of wastes. it general requirements; (17-701.600(3),FAC) cation submitted to Department at least 90 prior to final receipt of wastes; ce plan shall include the following: Closure report; Closure design plan;	
		<u>x</u> <u>x</u> <u>x</u>		Closur a. b.	final e perm. Applic days p Closur (1) (2) (3) (4)	receipt of wastes. it general requirements; (17-701.600(3),FAC) cation submitted to Department at least 90 prior to final receipt of wastes; ce plan shall include the following: Closure report; Closure design plan; Closure operation plan;	

<u>_s</u>	LOCATION	N/A	N/C			
				3.	Clos	ure report requirements; (17-701.600(4),FAC)
					a.	General information requirements;
			<u>X</u>			(1) Identification of landfill;
			<u>X</u>			(2) Location, description and vicinity map;
			<u>_X</u>			(3) Total acres of disposal areas and landfill property;
			<u>X</u>			(4) Legal property description;
			<u>X</u>			(5) History of landfill;
			<u>X</u>			(6) Identification of types of waste disposed of at the landfill.
			<u>X</u>		b.	Geotechnical investigation report and water quality monitoring plan required by Rule 17-701.330(4),FAC;
			<u>X</u>		c.	Land use information report indicating identification of adjacent landowners; zoning; present land uses; and roads, highways right-of-way, or easements.
			<u>X</u>		d.	Report on actual or potential gas migration at landfills containing biodegradable wastes including detailed description of test and investigation methods used;
			X		e.	Report assessing the effectiveness of the landfill design and operation including results of geotechnical investigations, surface water and storm water management, gas migration and concentrations, condition of existing cover, and nature of waste disposed of at the landfill;
				4.		are design requirements to be included in the are design plan: (17-701.600(5),FAC)
			X		a.	Plan sheet showing phases of site closing;
			<u>X</u>		b.	Drawings showing existing topography and proposed final grades;
			<u>X</u>		c.	Provisions to close units when they reach approved design dimensions;
			<u>X</u>		d.	Final elevations before settlement;
			<u>X</u>		e.	Side slope design including benches, terraces, down slope drainage ways, energy dissipators and discussion of expected precipitation effects;
					f.	Final cover installation plans including:
			<u> </u>			(1) CQA plan for installing and testing final

<u>s</u>	LOCATION	<u>N/A</u>	N/C				
			<u>X</u>			(2)	Schedule for installing final cover after final receipt of waste;
			<u>X</u>			(3)	Description of drought-resistant species to be used in the vegetative cover;
			<u>X</u>			(4)	Top gradient design to maximize runoff and minimize erosion;
			<u>X</u>			(5)	Provisions for cover material to be used for final cover maintenance.
					g.	Final	cover design requirements:
			<u>X</u>			(1)	Protective soil layer design;
			<u>X</u>			(2)	Barrier soil layer design;
			х_			(3)	Erosion control vegetation;
		X				(4)	Geomembrane barrier layer design.
			<u>X</u>		h.	Propo	sed method of stormwater control;
			X		i.	Propo	sed method of access control;
			<u>X</u>		j.		iption of proposed final use of the closed ill, if any;
				5.			ration plan shall include: (6),FAC)
	<u> </u>		<u>X</u>		a.		led description of actions which will be to close the landfill;
			X		b.	Time s	schedule for completion of closing and long care;
			<u>X</u>		c.	Descri financ	ibe proposed method for demonstrating cial responsibility;
			<u>X</u>		d.		ate any additional equipment and personnel to complete closure.
		<u> </u>	<u>X</u>	6.	to be	follow	on for and detailed description of procedures ed for temporary closure of the landfill, if 7-701.600(7),FAC)
· .	CLOSURE PROCE	EDURES	(17	7-701.6	10,FAC)	
			<u>x</u>	1.	Surve	y monum	ments; (17-701.610(2),FAC)
			<u>X</u>	2.	Final	survey	report; (17-701.610(3),FAC)
			<u>X</u>	3.			on of closure construction completion;
_	· · · · · · · · · · · · · · · · · · ·		X	4.	Declar	ration	to the public; (17-701.610(5),FAC)
			X	5.	Offic	ial dat	e of closing; (17-701.610(6),FAC)

_	LOCATION	N/A	N/C			
_			<u>X</u>	6.	Use of closed	landfill areas; (17-701.610(7),FAC)
	LONG TERM	CARE RI	EQUIRE	MENTS	17-701.620,FAC)
-		_ —	<u>X</u>	1.	Right of prop (17-701.620(4	perty access requirements;),FAC)
-			_X_	2.	Successors of	interest requirements; (17-701.620(5),FAC)
_	·		_X_	3.	Requirements (17-701.620(7	for replacement of monitoring devices;),FAC)
	FINANCIAL	RESPONS	SIBILI	TY REQ	IREMENTS (17-	701.630,FAC)
_			<u>X</u>	1.	care costs of performing the	estimates for closure costs and long term estimated by a PE for a third party se work, on a per unit basis, with the imates indicated; (17-701.630(3),FAC)
			<u>X</u>	2.	adjustments t	ocedures for providing annual cost o the Department based on inflation and e closure and long-term care plans;),FAC)
			<u>X</u>	3.	financial re	ling mechanisms for providing proof of sponsibility and include appropriate consibility forms; (17-701.630(5)&(6),FAC)
,	VOLUME REDU	CTION	PLANT	REQUIF	EMENTS (17-70)	1.700,FAC)
_		<u>X</u>		1.	Proof of post	ing a performance bond payable to the cover closing costs, if required;
_		<u> </u>		2.	Materials reco	overy facility requirements;
		<u> </u>			a. Submit 17-701.3	information required in Rule 320,FAC
		<u> </u>			b. Submit following	an engineering report including the
_		<u> </u>			be	escription of the solid waste proposed to collected, stored, processed or sposed;
_		X			(2) Pr ar	ojection with assumptions for waste types of quantities expected in future years;
		X			al	scription of operation and functions of l processing equipment with design iteria and expected performance;
		<u>X</u>				scription of flow of solid waste, pected regular facility operations,

<u>_s_</u>	LOCATION	<u> N/A</u>	N/C			
_		_X_		(5)	Description of loading, unloading, and processing areas;
		<u>X</u>		(6)	Identification and capacity of temporary on-site storage areas for materials handled and provisions for solid waste and leachate containment;
		<u>X</u>		(7)	Identification of potential ground water and surface water contamination;
		<u>X</u>			8)	Plan for disposal of unmarketable recyclables and residue and contingencies for waste handling during breakdowns.
				c. s	ubmit	the following operational information:
		<u>X</u>		(1)	Operation and maintenance manual;
		<u>X</u>		(Waste control plan to manage unauthorized wastes;
		<u>X</u>		(3)	Contingency plan for emergencies;
		<u>X</u>		(4)	Closure plan including the following:
_		<u>X</u>				(a) Notification to Department 180 days prior to closure;
		<u>X</u>				(b) Procedures for removal of all waste within 30 days of receipt of final waste;
		<u>X</u>				(c) Completion of closure activities within 180 days of receipt of final waste and notification to the Department that closure is complete.

S. CERTIFICATION BY APPLICANT AND ENGINEER OR PUBLIC OFFICER

A. Applicant

The undersigned applicant or authorized representative of Trail Ridge Landfill, Inc. is aware that statements made in this form and attached information are an application for a modification to an operation permit from the Florida Department of Environmental Regulation and certifies that the information in this application is true, correct and complete to the best of his knowledge and belief. Further, the undersigned agrees to comply with the provisions of Chapter 403, Florida Statutes, and all rules and regulations of the Department. It is understood that the Permit is not transferable, and the Department will be notified prior to the sale or legal transfer of the permitted facility.

Signature of Applicant or Agent

Greg Mathes, Division President & General Mgr.

Name and Title

Date: 09/27/94

Attach letter of authorization if agent is not a governmental official, owner, or corporate officer.

B. Professional Engineer Registered in Florida or Public Officer as required in Secti 403.707 and 403.707(5), Florida Statutes.

This is to certify that the engineering features of this solid waste management facility have been designed/examined by me and found to conform to engineering principals applicable to such facilities. In my professional judgement, this facility, when properly maintained and operated, will comply with all applicable statutes of the State of Florida and rules of the Department. It is agreed that the undersigned will provide the applicant with a set of instructions of proper maintenance and operation of the facility.

Signature	Mailing Address
Name and Title (please type)	City, State, Zip Code
Florida Registration Number (please affix seal)	()Telephone Number
,	Date: