



# BOARD OF COUNTY COMMISSIONERS DEPARTMENT OF PUBLIC WORKS

September 1, 1999

REPLY TO:

Solid Waste Management  
P.O. Box 340  
Lecanto, Florida 34460

3600 W. SOVEREIGN PATH  
LECANTO, FLORIDA 34461

ADMINISTRATION OFFICE  
Suite 212  
352-527-5477 Phone  
352-527-5479 Fax

ENGINEERING DIVISION:  
Suite 241  
352-527-5446 Phone  
352-527-5476 Fax

- Land Section  
Suite 205  
352-527-5447 Phone  
352-527-5459 Fax
- Permits & Compliance Sec.  
Suite 204  
352-527-5448 Phone  
352-527-5319 Fax
- Project Management Sec.  
Suite 241  
352-527-5449 Phone  
352-527-5482 Fax
- Survey Section  
Suite 241  
352-527-5446 Phone  
352-527-5482 Fax

1300 S. LECANTO HIGHWAY  
LECANTO, FLORIDA 34461

- MAINTENANCE OPERATIONS:
- Facilities Maint. Section  
PO Box 143  
Lecanto, FL 34460  
352-527-0333 Phone  
352-527-0654 Fax
  - Fleet Management Section  
PO Box 215  
Lecanto, FL 34460  
352-746-6888 Phone  
352-746-5011 Fax

AQUATIC SERVICES  
PO Box 440  
Lecanto, FL 34460  
352-746-2694 Phone  
352-746-9189 Fax

ROAD MAINTENANCE  
PO Box 167  
Lecanto, FL 34460  
352-746-4107 Phone  
352-746-1203 Fax

UTILITIES DIVISION  
PO Box 440  
Lecanto, FL 34460  
352-746-2694 Phone  
352-746-1676 Fax

SOLID WASTE MANAGEMENT  
230 W. Gulf to Lake Highway  
PO Box 340  
Lecanto, FL 34460  
352-746-5000 Phone  
352-527-1204 Fax

D.E.P.  
SEP 07 1999  
Southeast District Tampa

Kim B. Ford, P.E.  
Solid Waste Section  
Department of Environmental Protection  
3804 Coconut Palm Drive  
Tampa, Florida 33619

Re: Citrus County Central Landfill,  
Permit No. 126601-002- SF

Dear Mr. Ford:

This is to update you on activities that have occurred in the past few months at our closed landfill.

## FIREARMS TRAINING FACILITY

The Citrus County School Board, Withlacoochee Technical Institute has completed construction of the firearms training facility according to the plans submitted last year.

## EXPLOSIVES DETONATION AREA

The Citrus County Sheriff's Office Bomb Squad has constructed an explosives detonation pit near the firearms training facility. The bottom of the pit is at grade (even with the new thicker cover over the closure cap). The walls of the pit are constructed with oversize tires, reinforced on the exterior with dirt. The top is open to direct the force of any blast upward.

## PERIMETER FENCING

Six-foot high chain-link fence was placed along the west and south sides of the closed site, the boundaries that separate the landfill from the state forest. This completes our perimeter fencing for the property.

## GAS WELL REPLACEMENT

Because of the alignment of the new fencing, access to three of the three-foot deep gas monitoring wells has been blocked. We intend to replace those wells, inside the fence line, next week. When the installation is complete, we will send a revised will location map for your files.

Kim Ford  
September 1, 1999  
Page 2

#### LEACHATE LIFT STATIONS

There have been two fire incidents at the east side lift station for the closed landfill in the past six months. Both involved the junction box/control panel area. There was damage to equipment but no loss of function. As a result, we have requested that the configuration of the exterior electrical equipment for both lift stations be changed to move it from the immediate vicinity and to allow for better sealing of conduit. A local electrical contractor and CH2M HILL, our engineering consultant will be working together to provide a safe workable design and installation. We expect this work to be completed within about six weeks.

Please contact me if you have any questions.

Sincerely,



Susan J. Metcalfe  
Director

CC: Kenneth Saunders, Director, Public Works Department  
Bob Butera, FDEP, Tampa