

Borderieux, Scott

From: Thompson, Madison <MThompson@scsengineers.com>
Sent: Wednesday, May 16, 2018 3:48 PM
To: Borderieux, Scott
Subject: RE: 2018 First Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795
Attachments: Final Lena Road LF - Q4 2017 Gas Probe Monitoring Report.pdf; 2017 Fourth Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795

Scott,

Attached is the fourth quarter gas probe monitoring report which was send to SWD_Waste@dep.state.fl.us on 1/7/2018 by Dan Cooper (dcooper@scsengineers.com).

As noted in the attached report:

“...The 2017 third quarter monitoring event that was scheduled to occur in September 2017 did not take place due to SCS and County involvement in the Hurricane Irma relief and debris management efforts in Manatee County. To ensure that a monitoring event is not missed in the future SCS has prepared a reoccurring calendar event for the first month of each monitoring period to allow for unforeseen circumstances such as those experienced during the third quarter of 2017. The readings for the 2017 second and fourth quarters indicate no gas in any of the probes or buildings before and after the missed event.”

Please let me know if you have any further questions or require additional information.

Thank you,

Madison Thompson
SCS ENGINEERS – Tampa, FL
(813) 804-6704 (W)
(602) 762-4545 (M)
MThompson@SCSEngineers.com

From: Borderieux, Scott <Scott.Borderieux@dep.state.fl.us>
Sent: Monday, May 14, 2018 10:23 AM
To: Thompson, Madison <MThompson@scsengineers.com>
Subject: FW: 2018 First Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795

Madison,

I do not seem to have received Q3 or Q4 gas reports from last year. Do you have these? Will you send me copies? Thanks.

Scott

From: Borderieux, Scott
Sent: Friday, April 13, 2018 4:15 PM
To: Borderieux, Scott <Scott.Borderieux@dep.state.fl.us>
Cc: Tafuni, Steven <Steven.Tafuni@dep.state.fl.us>
Subject: FW: 2018 First Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795

Due 5-13

Scott Borderieux

Engineering Specialist
Compliance Assurance
Florida Department of Environmental
Protection -- Southwest District
13051 N. Telecom Pkwy
Temple Terrace, FL 33637-0926
(813) 470-5758 (direct line)
(813) 470-5995 - fax
scott.borderieux@dep.state.fl.us

From: Thompson, Madison [<mailto:MThompson@scsengineers.com>]
Sent: Friday, April 13, 2018 2:25 PM
To: SWD_Waste <SWD_Waste@dep.state.fl.us>
Cc: 'bryan.white (bryan.white@mymanatee.org)' <bryan.white@mymanatee.org>; 'Anthony Detweiler (anthony.detweiler@mymanatee.org)' <anthony.detweiler@mymanatee.org>; 'Lynette Falkowski' <lynette.falkowski@mymanatee.org>; 'Mike Gore' <mike.gore@mymanatee.org>; Cooper, Dan <DCooper@SCSEngineers.com>
Subject: 2018 First Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795

Attached is the Landfill Gas Monitoring Report for the first quarter of 2018 for Lena Road Landfill in Manatee County (WACS # 44795).

Included is the methane perimeter probes and building sampling results.
There were no exceedances observed during this event.

Please let us know if you have any questions or require additional information.

Thank you,

Madison Thompson
Staff Professional
SCS ENGINEERS
3922 Coconut Palm Drive, Suite 102
Tampa, FL 33619
(813) 804-6704 (W)
(602) 762-4545 (M)
MThompson@SCSEngineers.com

SCSEngineers.com

Ownership Makes a Difference!



Borderieux, Scott

From: Cooper, Dan <DCooper@SCSEngineers.com>
Sent: Sunday, January 7, 2018 7:16 PM
To: SWD_Waste
Cc: 'bryan.white (bryan.white@mymanatee.org)'; 'Anthony Detweiler (anthony.detweiler@mymanatee.org)'; 'Lynette Falkowski'; 'Mike Gore'; Thompson, Madison
Subject: 2017 Fourth Quarter Probe/Perimeter Monitoring Report - Lena Road Landfill WACS # 44795
Attachments: Final Lena Road LF - Q4 2017 Gas Probe Monitoring Report.pdf

Attached is the Landfill Gas Monitoring Report for the fourth quarter of 2017 for Lena Road Landfill in Manatee County (WACS # 44795). Included is the methane perimeter probes and building sampling results. There were no exceedances observed during this event.

Please let us know if you have any questions or require additional information.

Dan

Daniel Cooper, PE
Project Director/Vice President
SCS ENGINEERS
3922 Coconut Palm Drive, Suite 102
Tampa, Florida 33619
(813) 804-6710 Direct
(813) 621-0080 Office
DCooper@SCSEngineers.com

SCSEngineers.com
Ownership Makes a Difference!

SCS ENGINEERS

January 5, 2018
File No. 09217088.05

Mr. John Morris, P.G.
Florida Department of Environmental Protection
Southwest District Office – Solid Waste Section
13051 N. Telecom Parkway
Temple Terrace, FL, 33737-0926

Subject: **Landfill Gas Monitoring Report, Fourth Quarter 2017
Methane Perimeter Probes and Buildings Sampling
Lena Road Landfill, Manatee County, Florida
Permit # 39884-018-SO/01**

Dear Mr. Morris:

SCS Engineers (SCS) is pleased to submit the results of the fourth quarter 2017 landfill gas (LFG) perimeter probe and building monitoring at Lena Road Landfill. Provided below is a description of our activities, summary of the monitoring results, and recommendations.

BACKGROUND

At Lena Road Landfill, Stage I and Stage III are currently not accepting waste and have intermediate cover, while Stage II contains the active area of the site. Currently, there is an active landfill gas (LFG) collection system encompassing both Stage I and Stage III, with vertical LFG extraction wells removing gas from the landfill. There is no gas collection system in Stage II.

Landfill gas probes are designed to monitor whether methane and other gases are migrating underground outside of the landfill area. There are 11 LFG monitoring probes located on site around the boundaries of the Lena Road Landfill. Attachment 1 is a site map showing the LFG monitoring probe locations. This quarterly monitoring was conducted in accordance with Rule 62-701.530(2)(c), F.A.C. per specific condition Part F-2 of the landfill's operations permit #39884-018-SO-01.

Additionally, rule 62-701.530(1)(a) of the Florida Administrative Code (F.A.C.) requires the following:

- The methane concentration may not exceed 25 percent of the lower explosive limit (LEL) in structures on- or off-site. The LEL for methane is five percent by volume in air. Therefore, the maximum allowable concentration in on-site or off-site structures is 1.25 percent methane by volume.
- The methane concentration at or beyond the landfill property boundary may not exceed the LEL (i.e., five percent (5.0%) methane by volume).

MONITORING RESULTS

On December 7, 2017, SCS personnel monitored the LFG monitoring probes and on-site structures. SCS used a Landtec GEM-5000 gas monitor to measure gas composition in the monitoring probes and on-site structures. The GEM-5000 measures gas by percent volume of methane, carbon dioxide, oxygen, and balance gas, which is considered to be composed primarily of nitrogen. The instrument was calibrated prior to use during the sampling event and the calibration sheets are included in Attachment 3.

LFG Monitoring Probes

Attachment 2 shows the readings obtained from the 11 probes along the property boundary, no methane was detected in the gas monitoring probes. A site plan showing the probe locations is included in Attachment 1.

Monitoring of On-Site Structures

No methane was detected in the scale house building, administration building, recycling (HHW) building/offices, or maintenance building/offices, as shown in Attachment 2. In the buildings, SCS monitored both restrooms, the offices, and common areas. Readings were taken while walking around the buildings and interior rooms in a continuous manner. The location of the buildings monitored can be seen in Attachment 1.

CONCLUSIONS

No methane was detected during this monitoring event in the 11 probes or within any of the buildings monitored on-site, which are the compliance points for migration. The facility is thus in compliance with its operations permit for gas migration and monitoring and no further tests are required until the first quarter of 2018.


It should be noted that the 2017 third quarter monitoring event that was scheduled to occur in September 2017 did not take place due to SCS and County involvement in the Hurricane Irma relief and debris management efforts in Manatee County. To ensure that a monitoring event is not missed in the future SCS has prepared a reoccurring calendar event for the first month of each monitoring period to allow for unforeseen circumstances such as those experienced during the third quarter of 2017. The readings for the 2017 second and fourth quarters indicate no gas in any of the probes or buildings before and after the missed event.

Please call us at (813) 621-0080 if you have any questions or would like additional information.

Sincerely,



Madison Thompson
Associate Staff Professional
SCS ENGINEERS




MJT/DRC: drc

Attachment

cc: C. Mike Gore – Utilities Department Director, Manatee County (electronic)
Bryan White – Landfill Superintendent, Manatee County (electronic)
Anthony Detweiler – Operations Supervisor, Manatee County (electronic)
Lynette Falkowski – Administration, Manatee County (electronic)

ATTACHMENT 1
GAS PROBE LOCATIONS



SCS ENGINEERS

Lena Road Landfill, Manatee County, Florida
Figure 1: Gas Monitoring Probes & Building Locations

ATTACHMENT 2

4th QUARTER PROBE/BUILDING MONITORING RESULTS

**ATTACHMENT 2
LANDFILL GAS MIGRATION MONITORING,
4th QUARTER 2017
LENA ROAD LANDFILL, MANATEE COUNTY, FLORIDA**

Probe No.	CH₄ (%)	CO₂ (%)	O₂ (%)	Balance (%)	Comments
GMW-1	0.0	1.3	19.5	79.2	N/A
GMW-2	0.0	0.4	20.0	79.6	N/A
GMW-3	0.0	1.8	19.6	78.6	N/A
GMW-4	0.0	1.8	19.5	78.7	N/A
GMW-5	0.0	2.7	18.8	78.5	N/A
GMW-6	0.0	1.4	19.1	79.5	N/A
GMW-7	0.0	0.6	19.7	79.7	N/A
GMW-8	0.0	0.1	20.0	79.9	N/A
GMW-9	0.0	3.6	16.1	80.1	N/A
GMW-10	0.0	0.2	19.8	80.1	N/A
GMW-11A	0.0	3.8	14.6	81.6	N/A

On Site	CH₄ (%)	% LEL
Recycling Area (HHW Bldg)	0.0	0.0
Recycling Office (HHW Bldg)	0.0	0.0
Scale House Bldg	0.0	0.0
Administration Bldg	0.0	0.0
Maintenance Office	0.0	0.0
Maintenance Bldg	0.0	0.0

Notes:

1. Monitoring performed by SCS Engineers on: 12/7/2017
2. Temperature: 74 °F
3. Barometric Pressure: 30.0 in-Hg
4. % LEL = % CH₄ above background / 5% Volume for CH₄ LEL * 100

ATTACHMENT 3
GEM CALIBRATION SHEETS

GEM-5000 Field Calibration Data Sheet

GEM-5000 Instrument Data

Instrument Serial No.: GM 500213
 Technician Name: Madison Thompson and Amit Gulati
 Date and Time: 12/7/17 10:30 AM
 Last Factory Calibration Date: _____

Calibration Gas Manufacturer's Data

Manufactured by: Landtec
 Manufactured date: Jan-16
 Lot Number: BAQ-399-1
 Expiration Date: 1/14/20

Prior to taking any measurements the instrument must undergo a full calibration according to manufacturer's instructions. This should then be followed by a calibration verification using ambient air and calibration gas to verify instrument performance prior to measurement.

Tabulated below are the acceptable gas concentrations that should be demonstrated when zeroing the instrument and calibrating the span gas concentrations.

Zero Gas Composition			
CH ₄ (%)	CO ₂ (%)	N ₂ (%)	O ₂ (%)
0.0	0.0	0.0	0.0 (Calibration Gas)

Span Gas Composition			
CH ₄ (%)	CO ₂ (%)	N ₂ (%)	O ₂ (%)
50.0	35.0	15.0	0.0

Calibration must be verified by conducting the following procedures:

- 1) Turn on the instrument and allow it to run and purge with ambient air for 3 minutes and then record the gas concentration readings.
- 2) Apply calibration gas to the instrument, wait 1 minute for the readings to stabilize and then record the gas concentration readings.
- 3) Determine if the reading is within 10% of calibration gas concentration. If so indicate that the instrument "Passes" the field calibration for that gas.
- 4) If any of the sensors display a reading outside of the acceptable range, then a full manufacturer's calibration must be performed.

Target Gas (%)	Ambient Air Purge Gas Readings (%)	Acceptable Ambient Air Range (%)	Calibration Gas Instrument Readings (%)	Acceptable Calibration Gas Range (%)	Pass/Fail
CH ₄	0.0	0.0 - 0.3	48.2	47.0 - 53.0	Pass
CO ₂	0.2	0.0 - 0.3	34.7	32.0 - 38.0	Pass
O ₂	20.9	19.9 - 21.9	0.4	0.0 - 1.0	Pass