

**FLORIDA DEPARTMENT OF
Environmental Protection**

Ron DeSantis
Governor

Bob Martinez Center
2600 Blair Stone Road
Tallahassee, Florida 32399-2400

Jeanette Nuñez
Lt. Governor

Noah Valenstein
Secretary

**Source-Separated Organics Processing Facility Registration
Confirmation of Submission**

07/30/2019

Waste Registration Section

SUMTER COUNTY SOLID WASTE

SUMTER COUNTY CITIZEN DROP-OFF AREA FACILITY

835 CR 529 SUMTERVILLE, FL 33585

Dear **SUMTER COUNTY SOLID WASTE**

You indicated that operation of your Source-Separated Organics Processing Facility known as SUMTER COUNTY CITIZEN DROP-OFF AREA FACILITY (located at 835 CR 529, SUMTERVILLE) in Sumter County is addressed under another Department permit, and that you were submitting only the required annual report. Thank you for your submittal, a copy of which is attached for your information. Please note that your facility identification number (WACS ID) is 53008.

You must comply with the requirements specified in Chapter 62-709, Florida Administrative Code (F.A.C.) in order to maintain qualification for the registration program. A summary of the operating requirements is attached.

If you have any questions or need further assistance, please contact Waste Registration Section at (850) 245-8707 or by e-mail at Waste.Registration@dep.state.fl.us.

Please retain a copy of this confirmation for your records.

Sincerely,

Waste Registration Section

cc: Gloria Depradine; Central District



Florida Department of Environmental Protection

Solid Waste Section, Mail Station 4565
2600 Blair Stone Road, Tallahassee, Florida 32399-2400

DEP Form # 62-709.901(3)
Appl for Reg. and Ann Rep for a YT Trans
Form Title <u>Station or SW Organic Recycling Facility</u>
Effective Date <u>February 15, 2010</u>
DEP Facility ID No. <u>53008</u>
(Filled in by DEP)
DEP WACS ID No: <u>53008</u>
(Filled in by DEP)
This form is adopted by reference in subsection 62-709.901(3), F.A.C.

Application for Registration and Annual Report for a Yard Trash Transfer Station or a Solid Waste Organics Recycling Facility

PART A - GENERAL INFORMATION

1. Type of Application: New Renewal (due July 1) Annual report only for facility operating under permit:
2. Type of Facility: Yard trash recycling Manure blending
Yard trash transfer station Vegetative, animal byproducts or manure composting
3. Type of Waste Processed: Yard trash Manure Animal byproducts Pre-consumer Vegetative
Vegetative (could/did come into contact with animal products or byproducts or end user)
4. Facility Name: SUMTER COUNTY CITIZEN DROP-OFF AREA FACILITY
5. Registrant Name (or Permittee if annual report only): SUMTER COUNTY CITIZEN DROP-OFF AREA FACILITY
6. Federal Employer Identification Number: 596000865
7. Mailing Address: 319 E Anderson Ave
City Bushnell State FL Zip 33513 6135
Street Mailing Address (if different): _____
City _____ State _____ Zip _____
8. Facility Location - Street Address or Property Number: 835 CR 529
City SUMTERVILLE County Sumter
9. Contact Person: Bryant, Michael Telephone: (352) 569-6700

PART B - ADDITIONAL INFORMATION REQUIRED FOR REGISTRATION APPLICATION

10. Records required by Rule 62-709.320, F.A.C., will be kept at the facility? Yes No
If no, please indicate where these records will be kept and made available upon Department request to review the records:

11. Does the registrant own the facility site? Yes No
If you answered no, please attach evidence that the facility owner or operator has permission from the landowner to operate a yard trash transfer station or a solid waste organics recycling facility at this site.
12. Has the organic recycling facility begun operations? Yes No
If this facility was operating in the previous calendar year, the annual report in Part C must be completed.
13. ~~Include a check or money order for the \$35.00 registration fee made payable to the Florida Department of Environmental Protection. Payment of \$35.00 for this registration was received via online transaction.~~

I affirm that I have read Rules 62-709.320, 62-709.330 and 62-709.350, F.A.C., and shall comply with the requirements specified in those rules. I also affirm that the information provided in the application is true, accurate, and correct to the best of my knowledge. I have attached all documents and/or authorizations that are required.

Print Name and Title of Registrant or Authorized Agent _____

Signature _____

Date _____

Email address (if available): _____

PART C - ANNUAL REPORT

14. Calendar Year (January 1 through December 31) Covered by this Report: 2018
15. Values used in this report are in (SELECT ONE): Tons Cubic Yards
16. **For Existing Facilities that have not reported this information in the past,** Amount of
- a. Unprocessed Material On Site at Beginning of Report Year: 0
- b. Processed Material On Site at Beginning of Report Year (total): 0
17. Total Quantity of Material Received During Report Year: 4785.00
18. Total Quantity of Material Lost Due to Processing (e.g. grinding, drying, shrinkage, fires, etc.) During Report Year: 0
19. Total Quantity of Material Removed from Site for:
- a. Use (e.g., landfill cover, fuel, mulch, compost, etc.): 0
- b. Disposal: 0
- c. Other (transfer stations) 4785.00
20. Total Quantity On Site at End of Report Year of:
- a. Unprocessed Material: 0
- b. Processed Material: 0

Note that the total sum of items 16 a and b plus 17 must equal to sum of items 18, plus 19 a, b and c, plus 20 a and b.

Total of items 16 and 17 Total of Items 18, 19 and 20

I affirm that the information provided in the annual report is true, accurate, and correct to the best of my knowledge.

Michael James Bryant, Assistant Public Works Director of Operatic

Michael James Bryant

07/30/2019

Print Name and Title of Registrant/Permittee or
Authorized Agent

Signature

Date

Email address (if available): Michael.Bryant@sumtercountyfl.gov

~~PART D - MAILING INSTRUCTIONS~~

This registration was completed and payment of \$35.00 (if applicable) was received via online transaction.

~~Remember to include the \$35.00 fee if this is also a registration application. Mail completed form to:~~

~~Department of Environmental Protection
Solid Waste Section, MS 4565
2600 Blair Stone Road
Tallahassee, Florida 32399-2400~~

Requirements for source-separated organics facilities qualifying for registration - Chapter 62-709, F.A.C.

Rule/Referenced Rule	Provision
Specific to all	
62-709.300(7)(a)	No person shall cause or allow objectionable odor in violation of Chapter 62-296, F.A.C.
62-709.300(7)(b)	Rule 62-701.300, and subsection 62-701.320(13) apply to facilities regulated under 62-709.
62-701.300(1)(b)	Stored or processed in a way or location that does not violate air quality or water quality standards.
62-701.300(2)(a)	Geological formations or subsurface features must provide support for the facility
62-701.300(2)(c)	Not in a dewatered pit unless permanent leachate containment and special design techniques used.
62-701.300(2)(d)	Not in any natural or artificial water body(e.g., ground water and wetlands within DEP jurisdiction).
62-701.300(2)(f)	Not be placed on the right of way of any public highway, road, or alley.
62-701.300(3)	No open burning in the recycling area of the facility and controlled burning complies with DEP rules.
62-701.300(14)	No CCA treated wood in material applied as a ground cover, soil or soil amendment.
62-701.300(15)	No unconfined emissions of particulate matter in violation of paragraph 62-296.320(4)(c), F.A.C.
62-709.320(2)(a)	Have the necessary operational features and equipment - unless otherwise specified, including
62-709.320(2)(a)1.	effective barrier to prevent unauthorized entry and dumping
62-709.320(2)(a)2.	Dust and litter control methods
62-709.320(2)(a)3.	Fire protection and control provisions to deal with accidental burning of solid waste, including
62-709.320(2)(a)3.a.	20-foot all-weather access road all around the perimeter
62-709.320(2)(a)3.b.	No material shall be mechanically compacted
62-709.320(2)(a)3.c.	No material shall be more than 50 feet from access by motorized firefighting equipment
62-709.320(2)(b)	Operate in a manner to control vectors
62-709.320(2)(c)	Operate in a manner to control objectionable odors per with Rule 62-296.320(2), F.A.C.
62-709.320(2)(d)	Keep any installed drains and leachate or condensate conveyances cleaned
62-709.320(2)(e)	Process received solid waste timely as follows
62-709.320(2)(e)1.	Size-reduce or remove yard trash within 6 months or time needed to receive 3,000 tons or 12,000 cubic yards, whichever is greater. Separated logs with 6 inch diameter or greater can be stored for up to 12 months before being size-reduced or removed.
62-709.320(2)(e)2.	Putrescible waste (e.g., vegetative wastes, animal byproducts or manure) shall be processed and incorporated into the composting material, or removed from the facility, within 48 hours.
62-709.320(2)(f)	Containerized and removed immediately any treated or untreated biomedical waste; hazardous waste; or any materials having (PCB) concentration of 50 ppm or greater.
62-709.320(2)(g)	All residuals, solid waste and recyclable materials removed and recycled or disposed upon ceasing operations. Any remaining processed material shall be properly used or disposed.
62-709.320(4)(a)	Keep monthly records of incoming and outgoing material for at least three years..
62-709.320(4)(b)	If temperature used to show disinfection or vector attraction achieved, keep records for 3 years.

Specific to yard trash only facilities	
62-709.300(7)(b)	Rule 62-701.300, and subsection 62-701.320(13) apply to facilities regulated under 62-709.
62-701.300(12)(a)	At least 100 feet from off-site potable water well that existed before facility registered.
62-701.300(12)(b)	At least 50 feet from any body of water, including wetlands. Not including parts of permitted stormwater system, or water bodies totally within facility with no discharge to surface waters.
62-709.330(2)	Processed material gone from facility within 18 months, unless longer storage authorized by permit.
62-709.330(3)	Accept only yard trash, and bags used to collect yard trash. Containerized any other material

Specific to composting of vegetative wastes, animal byproducts or manure, or blending manure	
62-709.300(7)(b)	Rule 62-701.300, and subsection 62-701.320(13) apply to facilities regulated under 62-709.
62-701.300(2)(b)	Be more than 500 feet off-site potable water well that existed before facility registered
62-701.300(2)(e)	Within 200 feet from any body of water, including wetlands. Not including parts of permitted stormwater system, or water bodies totally within facility with no discharge to surface waters.
62-701.320(13)(b)	Not within 10,000 feet of any licensed and operating airport runway used by turbine powered aircraft, or within 5,000 feet of any licensed and operating airport runway used only by piston engine aircraft, unless applicant demonstrates that the facility is designed and will be operated so that it does not pose a bird hazard to aircraft.
62-709.350(2)	Carbon:nitrogen ratio of the blended feedstocks shall be greater than 20.
62-709.350(3)	Piles do not exceed 12 feet in height.
62-709.350(5)	All material removed within 18 months, unless longer storage authorized by permit.
62-709.350(6)	Show that disinfection achieved. not required if made from only pre-consumer vegetative waste
62-709.350(7)	Vector attraction reduction controls shall include either (a) or (b) below:
62-709.350(7)(a)	Composted for at least 14 days, with temperature no lower than 40 degrees Celsius and average temperature of the material being composted higher than 45 degrees Celsius; or
62-709.350(7)(b)	Specific oxygen uptake rate (SOUR) for material being composted or blended shall be equal to or less than 1.5 milligrams of oxygen per hour per gram of total solids (dry weight basis) at a temperature of 20 degrees Celsius