



Florida Department of Environmental Protection

Central District
3319 Maguire Boulevard, Suite 232
Orlando, Florida 32803-3767

Charlie Crist
Governor

Jeff Kottkamp
Lt. Governor

Michael W. Sole
Secretary

ELECTONIC MAIL

Imarion@co.volusia.fl.us

Mr. Lenny Marion
Solid Waste Director
3151 East State Road 44
DeLand, FL 32724

OCD-SW-10-0056

Volusia County - SW
Tomoka Farms Road Landfill WACS # 27540
Class I - Permit # S064-0078767-023
Inspection Report Transmittal

Dear Mr. Marion:

On January 27 2010, representatives of the Florida Department of Environmental Protection conducted an inspection at the above referenced facility to determine the status of compliance with solid waste regulations.

At the time of the inspection, the following was noted:

1. On the south side of the Class I landfill, leachate continues to actively flow from an eroded area west of the haul road. The seepage appears to remain in the lined area of the landfill. This was the same problem that was observed during previous inspections.
2. There is exposed waste associated with the new haul road construction on the west side of the Class I landfill. This waste must be covered upon completion of the road. Please submit a schedule for the completion for the road and covering of the waste within 10 days of receipt of this letter.

If you have any questions or need further information, please contact Gloria-Jean DePradine at (407) 893-3328 or by e-mail at Gloria.Depradine@dep.state.fl.us.

Sincerely,

Gloria-Jean DePradine
Compliance and Enforcement Supervisor

Date: February 12, 2010

GD/bw

Attachment: Solid Waste Inspection Report

cc: Jennifer Stirk, Volusia County, jstirk@co.volusia.fl.us
Chet Purves, Volusia County, cpurves@co.volusia.fl.us



Florida Department of
Environmental Protection
Inspection Checklist

FACILITY INFORMATION:

Facility Name: TOMOKA FARMS ROAD LANDFILL

On-Site Inspection Start Date: 01/27/2010

On-Site Inspection End Date: 01/27/2010

WACS No.: 27540

Facility Street Address: 1990 TOMOKA FARMS ROAD

City: DAYTONA BEACH

County Name: VOLUSIA

Zip: 32114

INSPECTION PARTICIPANTS:

(Include ALL Landfill and Department Personnel with Corresponding Titles)

Principal Inspector: Brad Whidden, Inspector

Other Participants: Glorinda-Jean Depradine, Inspector; Chris Ellis, Site Operator

INSPECTION TYPE:

Routine Operation Inspection for Landfill - Class I facility

Routine Operation Inspection for Landfill - Class III facility

Routine Operation Inspection for Other Facilities - Yard Trash Processing Facility

ATTACHMENTS TO THE INSPECTION CHECK LIST:

This Cover Page to the Inspection Checklist may include any or all of the following attachments as appropriate.

SECTION 1.0 - FILE REVIEW

SECTION 2.0 - LANDFILL OPERATION AND MAINTENANCE

Inspection Date: 01/27/2010

SECTION 1.0 - FILE REVIEW

Requirements:

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

Item No.	FILE REVIEW (Pre- or Post-Inspection, as appropriate.) Completed	Ok	Not Ok	Unk	N/A
1.1	For landfills, is the method and sequence of filling wastes according to plans? 62-701.500(2)(f)	✓			
1.2	For landfills, are the following records being reported to the Department?(Check any that are Not OK.) <input type="checkbox"/> Waste reports (quarterly) 62-701.500(4) <input type="checkbox"/> Annual estimate of remaining life 62-701.500(13)(c)	✓			
1.3	Is leachate sampled, tested and disposed as required? 62-701.500(8)(a) & 62-701.510(6)(c)	✓			
1.4	Is gas monitoring being performed as required by the permit? 62-701.500(9) & 62-701.530(2)	✓			
1.5	Are the results of the gas sampling reported to the Department quarterly? 62-701.530(2)	✓			
1.6	Is water quality sampling and testing performed according to standard procedures and at the required frequencies? See 62-701.510(2) for landfills; 62-701.730(4)(b) & (10) for C&D debris sites; 62-713.400(3) for stationary soil treatment facilities.	✓			
1.7	Do the results of the water quality testing suggest there may be adverse impacts to water quality from the operation of the solid waste facility? 62-701.510(3) & (4)			✓	
1.8	For closed landfills and C&D disposal facilities with final elevations higher than 20 feet above grade, has a final survey report verifying the final elevations and contours of the facility been submitted to the Department? 62-701.610(3) & 62-701.730(9)(c)	✓			
1.9	Is financial assurance adequate? See 62-701.630 for landfills; 62-710(7)(a) & (10)(a) for WPFs; 62-701.730(11)(a) for C&D debris facilities; 62-713.600(6)(a) for stationary soil treatment facilities; 62-711.500(3) for waste tire facilities. NOTE: The Solid Waste Financial Coordinator in Tallahassee can assist with this information.	✓			
1.10	Are cost estimates current and adjusted every year? See 62-701.630(4) for landfills; 62-701.710(7)(b) & (10)(a) for WPFs; 62-701.730(11)(b) for C&D debris facilities; 62-713.600(6)(b) & (c) for stationary soil treatment facilities; 62-711.500(3) for waste tire facilities.	✓			
1.11	For C&D debris disposal and disposal with recycling facilities, is an Annual Report submitted to the Department for the disposal operation by April 1st of each year? 62-701.730(12)				✓
1.12	For C&D recycling facilities with no disposal, is an Annual Report for the recycling operation submitted to the Department by April 1st of each year? 62-701.710(9)(b)				✓
1.13	For compost facilities, has the compost product been sampled and analyzed every 20,000 tons or every 3 months (whichever is sooner)? 62-709.530(1)				✓
1.14	For compost facilities, has the annual report been submitted by June 1st? 62-709.530(3)				✓

Inspection Date: 01/27/2010

SECTION 2.0 - LANDFILL OPERATION AND MAINTENANCE

Requirements:

The requirements listed in this section provide an opportunity for the Department's inspector to indicate the conditions found at the time of the inspection. A "Not Ok" response to a requirement indicates either a potential violation of the corresponding rule or an area of concern that requires more attention. Both potential violations and areas of concern are discussed further at the end of this inspection report.

Item No.	SOLID WASTE PROHIBITIONS (unless "grandfathered" in, see 62-701.300(16)) Completed	Ok	Not Ok	Unk	N/A
2.1	Unauthorized disposal/storage prohibited, except yard trash, within 500' of a potable water well? 62-701.300(2)(b)	✓			
2.2	Unauthorized disposal/storage prohibited, except yard trash, within 1000' of a potable water well serving a community water system? 62-701.300(2)(h)	✓			
2.3	Unauthorized storage/disposal of yard trash prohibited within the minimum setbacks of (Check any that are Not OK) 62-701.300(12) <input type="checkbox"/> 100 feet for potable water wells (except on-site)? <input type="checkbox"/> 50 feet for water bodies? <input type="checkbox"/> 200 feet for community water supply wells?	✓			
2.4	Unauthorized disposal/storage prohibited in an area subject to frequent and periodic flooding unless flood protection measures in place? 62-701.300(2)(d)	✓			
2.5	Unauthorized disposal/storage prohibited in any natural or artificial body of water including ground water? 62-701.300(2)(e)	✓			
2.6	Unauthorized disposal/storage prohibited, except yard trash, within 200' of any natural or artificial body of water, including wetlands without permanent leachate controls, except impoundments or conveyances which are part of an on-site, permitted stormwater management system or on-site water bodies with no off-site discharge? 62-701.300(2)(f)	✓			
2.7	Unauthorized open burning of solid waste prohibited except in accordance with Department requirements? 62-701.300(3)	✓			
2.8	Are the following prohibited wastes or special wastes properly controlled, managed and disposed? (Check any that are Not OK) <input type="checkbox"/> Hazardous waste 62-701.300(4) <input type="checkbox"/> Biomedical waste 62-701.300(6) <input type="checkbox"/> Yard trash 62-701.300(8)(c) <input type="checkbox"/> Whole waste tires 62-701.300(8)(e) <input type="checkbox"/> Used oil, except as exempted 62-701.300(11) <input type="checkbox"/> Lead-acid batteries, mercury-containing switches and lamps in WTEs 62- <input type="checkbox"/> PCB wastes 62-701.300(5) <input type="checkbox"/> Lead-acid batteries 62-701.300(8)(a) <input type="checkbox"/> White goods 62-701.300(8)(d) <input type="checkbox"/> Liquids 62-701.300(10)	✓			
2.9	Are only permitted waste types disposed at facility? 62-701.340(3), 62-701.500(6)(a)&(2)(c)	✓			

Item No.	LANDFILL OPERATION AND MAINTENANCE Completed	Ok	Not Ok	Unk	N/A
2.10	Is there a trained operator on-site at Class I and III landfills when receiving wastes? 62-701.500(1)	✓			
2.11	Is there at least one spotter at each working face when receiving wastes at Class I and III landfills? 62-701.500(1)	✓			
2.12	Are the following records or plans current and available on-site? (Check any that are Not OK.) <input type="checkbox"/> Training Plan 62-701.320(15)(a) <input type="checkbox"/> Operating Plan 62-701.500(2) <input type="checkbox"/> Waste weight records 62-701.500(4) <input type="checkbox"/> Precipitation records 62-701.500(8)(g) <input type="checkbox"/> Load-checking program records 62-701.500(6)(a) <input type="checkbox"/> Training records 62-701.320(15)(a)	✓			

Inspection Date: 01/27/2010

Item No.	LANDFILL OPERATION AND MAINTENANCE Completed	Ok	Not Ok	Unk	N/A
2.12	<input type="checkbox"/> Operation record 62-701.500(3) <input type="checkbox"/> Quantity of leachate 62-701.500(8)(f)	✓			
2.13	Is the operation plan substantially followed? 62-701.500(2)	✓			
2.14	Is incoming waste weighed? 62-701.500(4)(a)&(2)(d)	✓			
2.15	Is the method and sequence of filling wastes according to plans? 62-701.500(2)(f)	✓			
2.16	Is access properly controlled to prevent unauthorized waste disposal? 62-701.500(5)	✓			
2.17	Is waste compacted as required? 62-701.500(7)(a)	✓			
2.18	Are the working face and side slopes above ground graded to a slope no greater than 3 ft. horizontal to 1 ft. vertical rise? 62-701.500(7)(c)	✓			
2.19	Is a narrow working face practiced? 62-701.500(7)(d)	✓			
2.20	Is the frequency, amount and quality of initial cover, as required? 62-701.500(7)(e)	✓			
2.21	Is the frequency, amount and quality of intermediate cover, as required? 62-701.500(7)(f)	✓			
2.22	Is litter controlled and are litter control devices maintained? 62-701.500(7)(i) and (11)(f)	✓			
2.23	Is erosion control adequate? 62-701.500(7)(j)	✓			
2.24	Is the leachate collection and removal system maintained and operated as required? 62-701.500(2)(j), 62-701.500(8)(b) & (h)		✓		
2.25	Is leachate disposed of or treated as required? 62-701.500(8)(b), (c) and (d)	✓			
2.26	If leachate recirculation is practiced at the facility, is it done in accordance with Department requirements and the Operation Plan? 62-701.400(5)				✓
2.27	Is gas controlled to not cause objectionable odors beyond the property boundary? 62-701.530(3)(b)	✓			
2.28	Is gas controlled to not allow combustible gas concentrations to exceed specified limits? 62-701.530(3)(a)	✓			
2.29	Are gas vents intact and functioning properly? 62-701.500(9) & 62-701.530(1)(a)3.	✓			
2.30	Is mixing of leachate and stormwater prevented or minimized? 62-701.500(10) & 62-701.400(9)(c)	✓			
2.31	Is stormwater management system maintained and operated as required? 62-701.500(10)	✓			
2.32	Is there sufficient operating equipment? 62-701.500(11)(a)	✓			
2.33	Is there sufficient reserve equipment (or other arrangements)? 62-701.500(11)(b)	✓			
2.34	Are communication facilities adequate? 62-701.500(11)(c)	✓			
2.35	Are approved dust control methods adequate? 62-701.500(11)(d)	✓			
2.36	Are fire protection and fire fighting capabilities adequate and operational? 62-701.500(11)(e)	✓			
2.37	Are there required signs for operational directions and public information? 62-701.500(11)(g)	✓			
2.38	Are all-weather access roads and inside perimeter roads properly maintained? 62-701.500(12)	✓			
2.39	Are ground water wells intact and properly maintained? 62-701.510(2)(b), 62-701.620(9)	✓			
2.40	Are all specific conditions in the permit being followed? 62-701.320(1)	✓			

Pre-existing Area Of Concern:

Area: South Side Slope

Rule: 62-701.500(8)(h), 62-701.500(8)(b), 62-701.500(2)(j)

Question Number: 2.24

Explanation: Leachate continues to actively flow on the south side slopes west of the haul road where it is directed into a trench and is then pumped into the leachate ponds. It appears that the leachate continues to remain within the lined area of

Inspection Date: 01/27/2010

the landfill.

Corrective Action: Continue efforts with the gas system expansion in combination with the sequence of fill modifications to alleviate leachate seepage in this area.

Area: South Side Slope

Rule: 62-701.500(8)(h), 62-701.500(8)(b), 62-701.500(2)(j)

Question Number: 2.24

Explanation: Leachate continues to actively flow on the south side slopes west of the haul road. As before the leachate flow is directed to an area at the toe of the east side of the active cell and remains in the lined area of the landfill.

Corrective Action: The facility is in the initial stages of implementing the approved sequence of fill plan. The facility believes that once the plan is in effect and the south side slopes are re-worked the leachate problems will cease. The facility is to continue these efforts.

COMMENTS:

01/27/2010

Class I Landfill:

Leachate risers 6,5,4, and 1 have all been replaced and repaired. This was part of the leachate collection repairs detailed in the completion report submitted on 12/31/2009 by SCS Engineers . A new type of cap is used with a connection on the side instead of the end. These risers are located on the north and west side slopes.

The working face is now on the SE side of the landfill. Intermediate cover is in place in the previous disposal area.

The new haul road's footprint is in place on the west side of the landfill. This process is producing large areas of exposed waste and should be covered as soon as possible. Chris Ellis said that the facility is planning to place roofing shingles over this area in the near future. Completion of the road should soon follow. It should be noted that record rainfall levels in the area have been contributing to delays on all of the facility's projects.

As in past inspections, leachate continues to flow just east of the current haul road (South side). An active flow is still observed originating on the side slopes near the surface. Flow continues to be diverted via a channel that wraps around the East side of the landfill into a trench. This leachate is pumped into riser number 5 via a portable pump. The trenched area continues to contain a large amount of waste from the above working face. This waste needs to be removed as soon as possible. As before, the leachate seepage appears to not mix with stormwater and remains within the lined area of the landfill.

According to Chris Ellis, the facility plans to fill in an area of the stormwater ditch on the southeast side of the landfill adjacent to the toe of the slope. This is the only area the stormwater ditch currently extends to the adjacent side of the current south side slopes. A divider has been constructed on the far end of the area to be filled. The facility plans to fill in the rest of the area in the coming days.

Class III Landfill and Yard Trash Area:

There were 2 areas of ponded water on the surface of the landfill at the bottom of the current working face and near the roofing shingles disposal area. Chris Ellis stated that the facility is planning to fill in these areas with cover material. The processed yard trash is currently arranged

Inspection Date: 01/27/2010

in windrows for compost on the south side of the class III surface. The roofing shingles area is currently being excavated for use in the class I haul road construction.

ATTACHMENTS:

Class I overview



Trenched Area on Class I East sid



New Haul Road Construction



Leachate Flow Near Haul Rd.



Class I Working Face



Stormwater Canal Construction



Inspection Date: 01/27/2010

Signed:

Brad Whidden

PRINCIPAL INSPECTOR NAME

Inspector

PRINCIPAL INSPECTOR TITLE*Brad Whidden***PRINCIPAL INSPECTOR SIGNATURE**

2/3/2010

DATE

Glorida-Jean Depradine

INSPECTOR NAME

Inspector

INSPECTOR TITLE

NO SIGNATURE

INSPECTOR SIGNATURE

FDEP

ORGANIZATION

Chris Ellis

REPRESENTATIVE NAME

Site Operator

REPRESENTATIVE TITLE

NO SIGNATURE

REPRESENTATIVE SIGNATURE

Volusia County

ORGANIZATION

NOTE: By signing this document, the Site Representative only acknowledges receipt of this Inspection Report and is not admitting to the accuracy of any of the items identified by the Department as "Not Ok" or areas of concern.