



NOTES:
 1. PERFORATIONS SPACED 90" APART HORIZONTALLY.
 2. PERFORATIONS SPACED 6" APART VERTICALLY.

NOTES:
 1. PIPE EXTENSION INSTALLED DURING CONSTRUCTION EXTENDS ABOVE GRADE. UPON FILLING IN THE AREA OF THE WELL, THIS EXTENSION CAN BE CUT AND CAPPED AT GRADE AS DESIRED.

NOTES:
 1. CONTRACTOR SUPPLIED A FULL SET OF ECCENTRIC POLYPROPYLENE ORIFICE PLATES FOR EACH HORIZONTAL COLLECTOR WELLHEAD. SIZES INCLUDED ARE 1/8", 1/4", 3/8", 1/2", 3/4", 1", 1-1/4", 1-1/2".
 2. TO AVOID AIR INFILTRATION, COLLECTORS SHALL BE CLOSELY MONITORED UNTIL THERE IS AT LEAST 20 FT OF OVERLYING REFUSE.
 3. HORIZONTAL COLLECTORS WERE INSTALLED WITH A MINIMUM OF 3% SLOPE FROM END OF COLLECTOR PIPE TO HEADER TIE-IN.

BY	DRG
DESCRIPTION	REVISED FOR THE RECORD
DATE	4/15/10
REV	1
DRAWING TITLE DETAILS - 6	
PROJECT TITLE SOUTHEAST COUNTY LANDFILL LANDFILL GAS COLLECTION AND CONTROL SYSTEM PROJECT	
CLIENT HILLSBOROUGH COUNTY SOLID WASTE MANAGEMENT DEPARTMENT TAMPA, FLORIDA	
SCS ENGINEERS STEARNS, CONRAD AND SCHMIDT CONSULTING ENGINEERS 601 PARK GARDEN BLVD., SUITE 100, TAMPA, FL 33610 FLORIDA CERTIFICATE OF AUTHORIZATION NO. 0004882 PLS. NO. 09207055.00 DWN: SDA/RDJ CRK: BTJ APP: BTJ RJD	
CADD FILE:	075500DET1
DATE:	OCTOBER 8, 2008
SCALE:	NOT TO SCALE
DRAWING NO.	
RECORD DRAWING DATE: APRIL 15, 2010	
13 of 30	