

November 1, 2010

Tom Lubozynski
District Waste Management Administrator
Florida Department of Environmental Protection (FDEP)
3319 Maguire Blvd., Suite 232
Orlando, Florida 23803-3767

**RE: Modification to Gas Collection and Control System
 Tomoka Farms Road Landfill – Volusia County, FL
 Facility ID 1270117**

Mr. Lubozynski:

On behalf of Volusia County, HDR Engineering, Inc. (HDR) is submitting a notification to the FDEP of two modifications to the existing landfill gas collection and control system (GCCS) at the Tomoka Farms Road Landfill (Landfill).

The first modification involves installing a new header line along the southern edge of the active Class I North Cell landfill outside of the waste and reconnecting the lateral pipes to this new header line. The existing header line that is located within the waste will be capped and abandoned. This modification will allow easier access to the header line, easier connection to future expansion of the GCCS, and be capable of handling future growth.

The second modification involves installing a “tee” before the utility flare. This provides a contingency plan in the event the existing utility flare becomes inoperable and a connection to an emergency back-up flare becomes necessary. By installing the “tee” to the GCCS piping just before the utility flare, a back-up flare can be connected in a quick and efficient manner.

The modifications being requested are strictly operational and will not result in an increase in emissions. These modifications are proposed to be scheduled to coincide with the closure activities expected to commence summer of 2011. The requested GCCS changes will be identified in the Landfill Gas Collection Master Plan, which will be completed by September 2011.

If you have any questions please feel free to contact me (904) 598-8928 at your convenience.

Sincerely,



Carlo Lebron, PE
Project Manager

cc: Lenny Marion, Volusia County